

Dames & Moore



6 Commerce Drive
Cranford, New Jersey 07016
(201) 272-8300

SDMS Document



67883

April 14, 1987

Ms. Janet Feldstein
SCP - Carlstadt Project Office
Emergency and Remedial Response Division
U.S. Environmental Protection Agency
26 Federal Plaza
New York, New York 10278

Re: Revision No. 1
Project Operations Plan
SCP Site Remedial Investigation
Carlstadt, New Jersey

Dear Ms. Feldstein:

The acceptable grout mixes listed at the end of Table 7-2 in the March 4, 1987 Project Operations Plan are incorrect. The New Jersey Department of Environmental Protection has provided the following as acceptable grout mixes:

1. Dry-mixed cement-bentonite:
 - 5 pounds bentonite (maximum)
 - 94 pounds cement (1 bag)
 - 8 gallons water (maximum)
2. Water-mixed cement-bentonite:
 - 8 pounds bentonite (maximum)
 - 94 pounds cement (1 bag)
 - 10 gallons water (maximum)
3. Neat cement:
 - 94 pounds cement (1 bag)
 - 6 gallons water (maximum)

Please distribute these revisions as appropriate.

Very truly yours,

DAMES & MOORE
(A Professional Limited Partnership)

Gerard M. Coscia, P.E.
Project Manager

GMC/jhm

cc: Mr. Thomas D. Morris, P.E.
IBM Corp. RECD

003581