

From: SAMUEL BORRIES
To: GUSTAFSON-MARY
Date: Monday, March 6, 1995 9:44 am
Subject: Delivery Orders

169786 [REDACTED]
Ltr. to 3/20/95
complete 9/28/95
Close - cost effective

Mary Elaine,

As we discussed last week I would like to put two delivery orders in place for Riedel at Sauget Site G, and EQM at [REDACTED]. The Riedel D.O. will be new but the EQM will just be a change in the scope of work.

Sauget, Site G - Riedel - \$100,000 if possible SB

- * Develop and implement a Health and Safety Plan to cover removal activities;
- * Develop and implement a sampling and analytical program designed to identify contaminated material;
- * Extinguish any remaining fires by an appropriate means;
- * Consolidate and/or remove non-hazardous waste and/or brush and debris;
- * Solidify/stabilize semi-solid material in tar pits;
- * Remove water in depression and treat if necessary;
- * Backfill on-site depressions and bring site surface up to grade;
- * Properly close/abandon any monitoring wells that interfere with cap placement;
- * Consolidate contaminated off-site soils and sediment on-site to be covered by the cap;
- * Level site to grade for cap placement;
- * Place a 2-foot soil cover or 2-foot clay impermeable layer below a frost zone layer with a 6-inch topsoil layer as determined by the OSC; and
- * Seed topsoil and implement necessary erosion control measures to prevent cap erosion and implement necessary site security controls for site operation and post site removal control.

[REDACTED]
[REDACTED]
Any questions please give me a call at 3-2886.

4 mo.

A-mend H & S
GW verification

Lynn P. [REDACTED]
1-800-617-1035