INITIAL SITE EVALUATION FOR
AMERICAN CHEMICAL SERVICE, INC.,
GRIFFITH, INDIANA
U.S. ENVIRONMENTAL PROTECTION AGENCY
REGION V

Work Assignment No.: 61-5LJ7.0

Document Number: 160-WP1-RT-AVJD-1

March 1985

COMPANY CONFIDENTIAL

Prepared by:

Roy F. Weston, Inc. Bannockburn, Illinois

This document has been prepared for the United States Environmental Protection Agency under Contract WA68-01-6939. The material contained herein is not to be disclosed to; discussed with, or made available to any person or persons for any reason without the prior expressed approval of a responsible official of the United States Environmental Protection Agency.



11 East Adams Street, Suite 1500 Chicago, Illinois 60603 312 786-0253

April 2, 1985

Mr. Richard Bartelt Regional Project Officer U.S. Environmental Protection Agency 230 South Dearborn Street Chicago, Illinois 60604

Mr. Rodney Gaither
Remedial Project Manager
U.S. Environmental Protection Agency
230 South Dearborn Street
Chicago, Illinois 60604

Subject:

Initial Site Evaluation (Site 160)

American Chemical Service, Griffith, Indiana

Work Assignment No.:

61-5LJ7.0

EPA Contract No.:

68-01-6939

Document No.:

160-WP1- -AWKW-1

Dear Messrs. Bartelt and Gaither:

Camp Dresser & Mc^{ν} ee Inc. is pleased to submit this Initial Site Evaluation for the American Chemical Service, Inc. site located in Griffith, Lake County, Indiana.

This report summarizes the existing conditions at the American Chemical Service, Inc. site including site visit, site description, contamination problem definition, contaminant migration, data gaps and initial remedial measures. Also included are existing site maps.

Mr. Richard Bartelt Mr. Rodney Gaither April 2, 1985 Document No.: Page Two

If you have any questions, please do not hesitate to call.

Very truly yours,

CAMP DRESSER & MCKEE INC.

ROY F. WESTON, INC.

John W. Hewthorne, P.E.

Region V/REM II Regional Manager

James M. Burton, P.E.

Site Manager

JWH/JMB:slr

Enclosure

cc: U.A. Joiner, Contracting Officer, U.S. EPA

W.M. Kaschak, Project Officer, U.S. EPA

N.M. Willis, Regional Coordinator, U.S. EPA

TABLE OF CONTENTS

INITIAL SITE EVALUATION AMERICAN CHEMICAL SERVICE, INC. GRIFFITH, INDIANA

| 1.0 | INTR | ODUCTIO | ı | | Page |
|-----|-------------------------|------------------|-------------|--|------|
| | | Purpos | e | | 1 |
| | 1.2 | Scope | | . | 1 |
| | | | ocation and | | 2 |
| | 1.4 | Site S | tatus and I | Project Type | 6 |
| 2.0 | INITIAL SITE EVALUATION | | | | 7 |
| | 2.1 | Site V | isit | | 7 |
| | 2.2 | Site D | escription | | 9 |
| | | 2.2.1 | Environmen | ntal Setting | 9 |
| | | | | ogy and Hydrogeology | 10 |
| | | 2.2.3 | Site Chron | nology | 10 |
| | | | 2.2.3.1 | Site Ownership Chronology | 11 |
| | | | 2.2.3.2 | ISBH Site Activity Chronology | 13 |
| | | | | U.S. EPA Region V Site Activity Chronology | 16 |
| | | | | American Chemical Service Correspondence Chronology | 20 |
| | | | 2.2.3.5 | Legislative Body Correpondence Chronology | 21 |
| | | | | Newspaper Article Chronology | 22 |
| | | | | Chronological Summary of American | 22 |
| | | | * (| Chemical Service, Inc. On-Site Event | ts . |
| | 2.3 | Contam | ination Pr | oblem Definition | 29 |
| | | 2.3.1 | Waste Dis | posed of at the Site | 29 |
| | | | | Site Contamination | 42 |
| | 2.4 | Contam Effect | _ | ation and Environmental/Health | 44 |
| | | 2.4.1 | Migration | Pathways | 44 |
| | | | _ | Receptors | 44 |
| | | | | ental and Public Health Effects | 53 |
| | 2.5 | Discus | ssion of Da | ata Gaps | 54 |
| | 2.6 | Initia | l Remodial | Maguras | E C |

TABLE OF CONTENTS (continued)

LIST OF FIGURES

| | | Page |
|---|--|----------------------|
| 1 | Site Location Map | 3 |
| 2 | Detailed Site Location Map | 4 |
| 3 | Waste Disposal Flow Chart | 43 |
| 4 | Location of Wells Sampled in Lake County Groundwater Survey | 49 |
| | | Pocket 1 Pocket 2 |
| | LIST OF TABLES | |
| 1 | Summary of On-Site Events at American Chemical Service, Inc. from 1971 to Present | 23 |
| 2 | Storage, Treatment and Disposal of Self Generated Waste At American Chemical Service, Inc. | 30 |
| 3 | Disposal Practices by American Chemical Service, Inc. and Kapica Drum, Inc. | 36 |
| 4 | American Chemical Service, Inc. Storage Process Prior to Reclamation | 41 |
| 5 | U.S. EPA Sampling Results Surveillance and Analysis Division Environmental Emergency and Investigations Branch at American Chemical Service, Inc. and Griffit City Landfill May 8-9, 1980 | 4 5 :h |
| 6 | U.S. EPA Sampling Results Surveillance and Analysis Division Environmental Emergency and Investigations Branch at American Chemical Service, Inc. and Griffit City Landfill May 8-9, 1980 | 47 ch |
| 7 | Ecology and Environment, Inc. Well Sampling Results Ecology and Environment, Inc.Well Sampling Data American Chemical Service, Inc. and Griffith City Landfill November 3, 1982 | 48 |
| 8 | Indiana State Board of Health 1981 Lake County Groundwater Survey Results | 50 |
| 9 | Private Wells Sampled by Lake County Health Department Lake County, Indiana | nt 52 |

SECTION 1

Page No.: 1

INTRODUCTION

1.1 PURPOSE

This report has been prepared in accordance with the requirements of the Work Plan Memorandum for the American Chemical Service, Inc. (ACS) site in Griffith, Indiana (Document No. 160-WP1-WM-ARLB-1), and the Work Assignment for that site (No. 61-5LJ7.0). Its purpose is to summarize the existing conditions and background data for the site, to focus the development and implementation of a RI/FS program.

1.2 SCOPE

This report includes summaries of six topic areas each discussed in separate sections:

- o Site visit
- o Site description
- o Contamination problem definition
- o Contamination migration and environmental/health effects
- o Discussion of data gaps
- o Initial remedial measures

The first section presents the observations made during the initial site visit (March 12, 1985) and discusses their implications for the RI/FS. The second section includes a review of the geographic, topographic, hydrologic, physiographic and geological setting of the American Chemical Service, Inc. site. It also includes a review of the site chronology including information concerning the site ownership, state and federal response/enforcement activities, correspondence and public concerns. The third section summarizes the wastes generated at the site and their ultimate disposal locations. This section also includes a discussion of the degree of site contamination. The fourth section discusses the contaminant migration pathways and potential contaminant receptors. Also discussed are potential environmental and public health effects. The fifth section discusses the data gaps that have been revealed based on a review of existing data as discussed in Section 2.1 through 2.4. Obtaining needed information will be one of the primary goals of the remedial investigation. The final section discusses any necessary initial remedial measures and need for a limited feasibility study.

Initial Site Evaluation
American Chemical Service, Inc.
Document No.: 160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No.: 2

The information used to prepare the Initial Site Evaluation came from five major sources. Those sources are:

- o Initial site visit
- o U.S. EPA Region V files
- o Indiana State Board of Health files
- o City of Griffith, Indiana Department of Public Works files
- o Response to the U.S. EPA Request for Information sent to American Chemical Service, Inc. (October 18, 1984).

All references and documents cited in this report are maintained in the project file located at the WESTON office, Bannockburn, Illinois. Copies of most of the documents are also maintained at U.S. EPA Region V offices, Chicago, Illinois.


1.3 SITE LOCATION AND HISTORY

For the purpose of this report the site is defined as American Chemical Service, Inc., Pazmey Corporation (formerly Kapica Drum, Inc. and Griffith City Landfill (see Figures 1 and 2)).

American Chemical Service, Inc. (ACS) is a solvent reclamation and chemical manufacturing facility located at 420 South Colfax Avenue, Griffith, Indiana. ACS began operations in May, 1955, solely as a solvent recovery firm. Later, the company also began limited chemical manufacturing. Mr. James Tarpo is president of ACS. Messrs. John and James Murphy are the firm's vice presidents.

The ACS solvent recovery process generates still bottom wastes which were originally deposited in the Still Bottoms Pond and Treatment Pond Number 1 located on the southern portion of the facility. In the 1960's, leaching and/or runoff from the pond area reportedly had caused vegetation kills in a marsh immediately to the west of the site. Operation of Still Bottoms Pond and Treatment Pond Number 1 was terminated in 1972. They were drained and filled in with partially full drums of sludge materials. A portion of Treatment Pond Number 1 may have been inundated when the present fire water pond was constructed in November, 1973. The fire pond is located at the southwestern corner of the facility and stores water for fire control purposes.

From 1958 to 1975, ACS operated a small landfill known as the Off-site Containment Area on a piece of property directly south of their plant. Throughout its operation, the Off-site Containment Area was utilized for the disposal of a variety of wastes generated at the ACS






FIGURE 2 DETAILED SITE LOCATION MAP AMERICAN CHEMICAL SERVICE, INC.

plant. Originally, the still bottoms from the aforementioned ponds were disposed of in this containment area. From 1968 to 1970, ACS operated an incinerator at their facility and wastes from the incinerator were also deposited in the containment area during this period. In addition to these wastes, general refuse and an estimated 20,000 to 30,000 drums were deposited in the containment area prior to its closure. These drums reportedly were either empty or partially full of unreclaimable wastes. A tank truck partially full of sludge material, was also buried in the containment area. ACS reports that leachate problems have been associated with the containment area since the 1960's, but have steadily decreased over the years.

In 1972, ACS discontinued use of its Off-site Containment Area and the site was capped with a reported two to three foot layer of soil. In 1980, a 31-acre portion of property owned by ACS to the west of the containment area was sold to the City of Griffith. The city used this property for an expansion of their municipal landfill, which had been operating to the southwest of the ACS property. This transaction reportedly included strip of the west edge of the containment area. As previously mentioned, ACS began operation of an incinerator at their plant in 1968. Mr. Tarpo has reported a rate of 2 million gallons of ACS and off-site waste per year were burned in this incinerator prior to its closure of 1970.

In October, 1971, ACS began a swine fat reprocessing operation. Due to its economic liability to the firm, it was terminated in April, 1973. In May, 1972, a production line was opened for the manufacturing of a gasoline additive for the American Oil Company, referred to as "Amotone." In early 1974, ACS began manufacturing a plasticizer called "Proxol" for the Swift Chemical Division. Both materials are currently being manufactured at the facility. Since 1983, "Epoxol" has been produced by ACS for its own distribution. The major operation at the site, however, remains solvent recovery. Aqueous wastes generated at the facility are reported to be disposed of off site.

The Griffith Landfill has been in operation since the 1950's. It has been included in the site because it has been reported (Reply to U.S. EPA Request For Information sent to ACS-10/18/84) that hazardous wastes from American Chemical Services, Inc. and Kapica Drum, Inc. were disposed of in the landfill prior to the implementation of RCRA.

Kapica Drum, Inc. (now Pazmey Corporation under new ownership) had been in operation since 1951. The business of Kapica Drum, Inc. was drum reconditioning which resulted in rinse water from drums that contained hazardous wastes. It has been included in the site because it has been reported (Reply to U.S. EPA Request For Information sent to ACS-10/18/840 that hazardous waste drum rinse water has been discharged on the Kapica Drum, Inc. property.

Initial Site Evaluation
American Chemical Service, Inc.

Document No.: 160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No.: 6

1.4 SITE STATUS AND PROJECT TYPE

American Chemical Service, Inc., is an actively operated facility. The 1983 notifier's listing notes treatment, storage and disposal activities at the site. American Chemical Service, Inc.'s EPA I.D. number is INDO16360265. The June, 1983 Hazard Ranking System scores were as follows:

| | | | | =0 00 |
|----|-------------|-------|-------|-------|
| T) | Groundwater | Route | score | 59.86 |

- 2) Surface Water Route Score 8.89
- 3) Air Route Score 0
- 4) Overall Average Score 34.98

American Chemical Service, Inc., is an enforcement lead site.

3

SECTION 2

INITIAL SITE EVALUATION

2.1 SITE VISIT

On March 12, 1985 members of the REM II project team (Jim Burton and Ed Need) met with representatives of the U.S. EPA (Rodney Gaither) and Indiana State Board of Health (Wallace Turner) to visit the American Chemical Service, Inc. site. The purpose of the visit was to become familiar with site topography, access routes and proximity of receptors to possible contamination, collect data for preparation of the site health and safety plan and verify information gathered during the review of existing data. In addition to visiting the American Chemical Service, Inc. site, two adjacent properties were visited and the owners interviewed. The schedule of events during the March 12 site visit was as follows:

8:30 AM-10:00 AM Meeting with Mr. Glen Reyome,
Director of Public Works, Griffith,
Indiana.

10:00 AM-2:00 PM Meeting with Mr. James Tarpo,
President of American Chemical
Service, Inc. and Mr. John Murphy,
Vice President of American Chemical
Service, Inc.

2:00 PM-2:30 PM Meeting with Mr. Bob Pazdro, owner of Pazmey Corporation.

2:30 PM-3:30 PM Out briefing between members of the REM II project team, Rodney Gaither and Wallace Turner to discuss the day's events and future activities.

During the meeting with Mr. Royome the topics of discussion included 1) property ownership, 2) soil information, 3) disposal of hazardous waste from American Chemical Service and Kapica Drum, Inc. Mr. Reyome was asked if he was aware of how much of the ACS Off-site Containment Area is on the property that the Town of Griffith purchased from ACS. He stated that he was not aware that any of the Off-site Containment Area is on Town of Griffith property. Mr. Reyome was able to provide information concerning soil borings conducted at the landfill. When asked if the landfill has ever disposed of hazardous wastes from American Chemical Service, Inc. or Kapica Drum, Mr. Reyome stated that he did not think the landfill had ever accepted hazardous waste. However he stated that he could not state they definitly had not accepted hazardous wastes it would be buried in the

earlier parts of the landfill and indicated that most likely area on a landfill map.

Following our discussion with Mr. Reyome, he drove us to the landfill so that we could get a feel for the area. While at the landfill Ed Need took the opportunity to observe the soils at the face of the open excavation.

After leaving the landfill we met with Mr. Tarpo and Mr. Murphy of American Chemical, Inc. We spent approximatley 1½ hours discussing questions that we had concerning information in the ACS response to the U.S. EPA Request for Information. During our meeting Mr. Tarpo discussed concern that he be allowed access to information gather as part of our investigations. Following our meeting Mr. Tarpo and Mr. Murphy took us on a site tour. During the tour we looked at each hazardous waste disposal site revealed during the reveiw of existing information. The Old Still Bottoms Pond, Old Treatment Pond Number 1 and the On-site Containment Area were easily located.

The Still Bottoms Pond and Old Treatment Pond Number 1 are raised areas due to their previous filling. Both of these sites are graveled over and portions of these areas had structures built on them. Nothing unusual (leachate, etc.) was observed at the sites. The On-site Containment Area is flush with the site grade, however, exposed rusted drums made the site easy to locate. Again, nothing unusual was noted at this site.

Finally we looked at the Off-site Containment Area. This area was also easily located. As we approached from the northeast the site appears as a mound approximately 12-15 feet high. We climbed the side of the mound and stood on top. The general overall dimensions of the fill area are discernable from the top but are not well defined. The site had a well established vegetation cover. There were no signs of leachate. One item of note was a wooden surveying stake located on top of the fill area. Mr. Tarpo stated that this was the Griffith Landfill property boundary. If this is true, approximately 30-40 feet of the Off-site Containment Area is located on Griffith Landfill property.

Finally we went to the Pazmey Corp. property (formerly Kapica Drum, Inc.) to speak to the owner, Mr. Bob Pazdo. Mr. Pazdo invited us in to look at whatever we wanted to. He seemed unsure about our purpose for the visit. While on the property we looked at the area that is suspected of being used to dispose of drum rinse water. Nothing unusual was noted except for scattered dried chunks of paint. Mr. Pazdro stated on several occassions that he does not have any first hand knowledge of any activites conducted by Kapica Drum Inc. and that he does not handle any drums that contained hazardous waste.

2.2 SITE DESCRIPTION

2.2.1 ENVIRONMENTAL SETTING

The American Chemical Service, Inc. facility is located 1 mile southeast of Griffith in the northeast 1/4 of the southeast 1/4, Section 2, Township 35 north, Range 9 west, Lake County, Indiana. It is bordered by the Griffith Landfill on the southwest and Pazmey Corporation (formerly Kapica Drum, Inc.) on the south. The Chesapeake and Ohio Railroad bisects the site. Elevations range from 635 feet to 650 feet, and bedrock elevations from 500 feet to 525 feet.

Griffith is located in the Calumet Lacustrine Plain, an area of high population and industrial use in extreme western Indiana. There are 40-250 feet of Wisconsinian Age Surficial deposits that comprised the bed of Glacial Lake Chicago. Calumet Lacustrine Plain is an area of low relief with three relict shorelines containing dunes (some up to 40 ft. high). Bedrock is 4000 feet of Cambrian to Devonian Age limestones, dolomite, sandstones, and shales overlying Pre-Cambrian Granitic basement rock. The Detroit River and Traverse Formations, comprised of limestone (some Karst) underly the town of Griffith.

The sedimentary rocks are gently flexed to form a saddle-like structure of part of the Kankakee Arch. Dip is 5-7 feet/mile to southeast. Drainage of surface waters in Griffith is to the north and the Little Calumet River is the major drainageway. The sediments of the Calumet Lacustrine Plain are fine lake silts and clays, paludal deposits of muck and peat, great expanses of beach and dune sand as out-wash and in till inclusions, and clay-rich tills. The three beach ridges in the area were formed as falling lake levels in Glacial Lake Chicago stabilized slightly after the Valparaiso Moraine was breached. Each beach ridge formation was accompanied by near-shore foredunes.

Three aquifers occur in the glacial deposits of Lake County and the depth to the potentiometric is about 15 feet. The uppermost is the Calumet Aquifer, a thin, unconfined layer of fine sand 5- to 75-ft. thick (averaging 20-feet thick). It is not used extensively because it cannot sustain high pumpage wells due to its usually thin saturated thickness. Under the Calumet Aquifer is a 50-foot thick layer of clay-rich till. Water in the Calumet Aquifer is potable and of good quality, but is susceptible to contamination.

The Valparaiso Aquifer, underlying the thick clay layer, is 10- to 90-feet thick and is confined. Pumping rates are 7×10^{-3} gal/day/ft². It is hydraulically connected to the Kankakee Aquifer to the south.

In general, the sediments underlying Griffith contain a great reservoir of fresh water in them and also have a great potential for contamination (Indiana DNR, 1975). Griffith is in an area that is considered not suitable for landfills and poor for settling ponds without severe preparatory and operational adjustments.

2.2.2 SITE GEOLOGY AND HYDROGEOLOGY

Surficial deposits at the site are 100 to 300 feet of unconsolidated glacial deposits. They are subdivided into four units.

Unit 1, the Calumet Aquifer, (uppermost), is 10 to 27 feet of medium to coarse silty sand with interbedded beach gravels. Hydraulic conductivities in Unit 1 range from 2.8 \times 10⁻³ cm/sec to 4.7 \times 10⁻² cm/sec with an average of 2.1 \times 10⁻² cm/sec. The transmissivity coefficient is 22 cm²/sec. The groundwater is unconfined and at a depth of 16 to 22 feet in the southern one-third of the site, and three feet in the northern two-thirds. Flow is to the northeast.

Unit 2 is a silty clay, 15- to 30-feet thick, with thin, discontinuous interbedded gravel and an average hydraulic conductivity of 3.3 \times 10⁻⁷ cm/sec. It is considered to be a semi-confining layer.

Unit 3, the Valparaiso Aquifer, is a sand layer at an average depth of 40 feet below ground surface. The hydraulic conductivity ranges from 9.4 x 10^{-3} cm/sec to 4.7 x 10^{-2} cm/sec and the transmissivity is 34.5 to 70 cm²/sec. It has a storage coefficient of 0.003 and is partially confined. Flow is to the northwest.

Unit four, which directly overlies the bedrock, is a confining layer of clay till. Borings on-site, however, indicate absence of Unit 4, with sand and gravel from 24 feet to 130 feet, the depth at which bedrock is encountered.

The two major soils in the area are the Plainfield fine sand and the Maumee loamy fine sand with average hydraulic conductivities of 1.42 x 10^{-2} cm/sec.

(All preceding text from an Office Memorandum from Jim King to Lake County, August 15, 1978.)

2.2.3 SITE CHRONOLOGY

The purpose of the site chronology is to present an overview of the site history and provide the reader with a sense of the site history.

For clarity, the site chronology has been divided into several categories, which in some cases run concurrent with one another. The site chronology categories are listed below:

- o American Chemical Service, Inc. Property Ownership History
- o Indiana State Board of Health Site Inspections/Activities and Correspondence Concerning American Chemical Service, Inc.
- o U.S. EPA Region V Site Inspections/Activities and Correspondence Concerning American Chemical Service, Inc.
- o Correspondence From and To American Chemical Service, Inc.
- o Correspondence From the Congress of the United States and Indiana State Legislature Concerning American Chemical Service, Inc.
- o Chronology of Newspaper Articles Concerning American Chemical Service, Inc.
- o Chronological Summary of American Chemical Service, Inc. On-site Events

The information found in each site chronology category came from one or more of the following sources:

o U.S. EPA Region V Files

---.

- o Indiana State Board of Health Files
- o City of Griffith, Indiana Department of Public Works Files
- o Response to the U.S. EPA Request for Information Sent to American Chemical Service, Inc. (October 18, 1984).

2.2.3.1 Site Ownership Chronology

The following chronology of property ownership is based on the American Chemical Service, Inc. reply to the October 18, 1984 United States Environmental Protection Agency, Region V Request For Information. Document numbers referenced in the following discussion are those of the attachments to the response to the U.S. EPA Region V request for information. Refer to Map 1 for relative property location.

| Location | Period | Ownership Status | Reference |
|---------------------------|----------------|---|---|
| Area 1 (8.74 acres) | 1955-Nov. 1967 | Leased by American Chemical Service From Chesapeake and Ohio Railway Company | Response to the U.S. EPA Request for Information to American Chemical Service, Inc. (October 18, 1984). |

| Location | Period | Ownership Status | Reference |
|--|-----------------------------------|--|---|
| Area 1 (8.74 acres) | 1967-Present | Colfax Chemical Sales Inc. purchased the 8.74 acres it had leased. (Colfax Chemical Sales Inc. merged with ACS on Sept. 3, 1978) (Document 3C) | Letter and attached Warranty Deed from M.L. Hawkins of the C&O Railway Company to G.R. Murphy, President of American Chemical Service, Inc. (September 18, 1967) (Document 3B) |
| Area lA (1.0 acre) | Oct. 22, 1973 to June 17, 1983 | Colfax Chemical Sales, Inc. sold 1.0 acre to Swift Chemical Co. | - |
| | June 17, 1983 to Present | American Chemical Service, Inc. repur- chases the 1.0 acre property from ESCHEM, Inc. | Bill of Sale (June 17, 1983) (Document 3F) |
| Area 2 (39.277 acres) | Aug. 25, 1955- 1961 | Entire area owned by Edgar F. Seifert. ACS paid the taxes and used the land. | Lake County Title Company revenue stamp receipt. (Aug. 27, 1955) Lake County Trust Company purchased statement. Letter from E.F. Seifert (Documents G & 3H) |
| Area 2A (2.0 acres sub- | 1961-Feb. 1, 1980 | John L. and Helen E. Kapica | (Document 3I) |
| divided from the 39.277 acro of Area 2) | Feb. 1, 1980- Present es | Robert Pazdro | Real Estate Contract (Document 3J) |
| Area 2Bl | July 1, 1969 to June 1979 | American Chemical Service, Inc. leased 16.284 acres to the Town of Griffith for use as a sanitary landfill. | Real Estate Lease (July 1, 1969) (Document 3L) |

Page No.: 13

| Location | Period | Ownership Status | Reference |
|-------------------------------|-------------------------------|---|--|
| Area 2B2 (31.277 acres) | Jan. 8, 1980 to Present | American Chemical Service, Inc. sold 14.993 acres (Area 2B2) in addition to the previously leased 16.284 acres (Area 2B1) to the Town of Griffith for use as a sanitary landfill Total acerage sold to Town of Griffith was 31.277 acres. | |
| Area 2C (6.0 acres) | August 25, 1955 to Present | Owned by American Chemical Service, Inc. through original Augus 25, 1955 purchase. The is the only remaining piece of the 39.277-act tract that ACS still of | st nis ere |
| Area 3 (4.03 acres) | July 1971 - Present | American Chemical Service, Inc. leased 4.03 acres from C&O Railway Company and B&O Railroad Company. | Letter and attached lease from Arthur C. Johnson of the C&O and B&O Railroads to J.T. Murphy of ACS (July 7, 1971) (Document 3D) |

The maximum amount of property that has ever been under American Chemical Services, Inc. control since the company was founded in 1955 was 52.05 acres. Over the years the amount of property under ACS control has decreased as discussed in the previous chronology. In summary, 2.0 acres of the 39.277-acre tract south of the C&O railroad were sold to Mr. John Kapica and subsequently resold by Mr. Kapica to Mr. Pazdro. An additional 31.277 acres of the 39.277-acre tract south of the C&O railroad were sold to the City of Griffith to be used as a sanitary landfill. At the present time American Chemical Service, Inc. owns 6.0 acres of the original 39.277-acre tract south of the C&O railroad and 8.74 acres north of the C&O railroad for a total of 14.74 acres. In addition, ACS leases 4.03 acres north of the C&O railroad from the C&O railway company.

2.2.3.2 Indiana State Board of Health Site Activity Chronology

April 13, 1972 is the earliest documentation concerning regulatory agency interest in the ACS site found during the review of existing

data. Indiana State Board of Health (ISBH) interest in the ACS site during the period April, 1972 to September, 1973 centered around improved waste handling, spill prevention and site maintenance. ISBH interest in the ACS site during the period September, 1974 to September, 1975 is related to a charge that the company was discharging chemicals to the sanitary sewer and dumping chemicals on-site. There was very little ISBH activity concerning ACS during the period September, 1975 to December, 1982. The first step to list American Chemical Service, Inc. as a NPL site was taken on December, 1982 and continued through April, 1984 when data was supplied by Techlaw. A detailed chronology based on available information is presented below.

| April 13, | 1972 | Mr. Richard Cleaton of ISBH made a routine site visit and observed a number of problems. ACS is installing a new chemical facility (amotone) for gasoline additives for American Oil |
|-----------|------|--|
| | | Company. |

| May 12, 1972 | Mr. Richard Cleaton of ISBH made a routine site |
|--------------|---|
| | visit and observed no dikes or pad provided for |
| | storage tanks in the incinerator area. ACS |
| | agreed to implement several measures |
| | recommended by ISBH. |

| June 20, 1972 | Mr. Richard Cleaton of ISBH made a follow-up on |
|---------------|---|
| | inspection made on May 12, 1972 and found that |
| | approaches agreed upon during May inspection |
| | had not been implemented. |

| July 19, 1972 | Mr. Richard Cleaton of ISBH made a routine visit for review of manufacturing process |
|---------------|--|
| | operations. ISBH sampled outfall from ACS to Turkey Creek marsh. |

| July 25, 1972 | Mr. Richard Cleaton of ISBH visited the ACS site for sampling and also made observations at |
|---------------|---|
| | the site. ACS to make connection to the Griffith sewer system. |

| August 2, 1972 | Mr. Richard Cleaton of ISBH visited ACS to |
|----------------|---|
| | collect samples. He also noticed that the old |
| | lagoon was filled with drums. The drums were |
| | not labeled. |

| March 13, 1973 | Routine visit to the ACS site by Mr. Cleaton of |
|----------------|---|
| | ISBH. ISBH found that ACS had cleaned up drum |
| | storage area, incinerator and gasoline additive |
| | areas. |

April 4, 1973 Mr. Cleaton of ISBH made a routine visit to ACS. Found clean-up work was in progress and ACS promised to clean up lagoon. ACS shut down lard operations due to financial loss.

April 25, 1973

ISBH visit to ACS site regarding the new construction of facilities (EPONOL for Swift Chemicals) planned by ACS.

August 21, 1973 Mr. Cleaton of ISBH attends a Town of Griffith board meeting regarding ACS sewer connection to the Griffith-Hammond sewer system.

September 10, 1973

ISBH's routine visit to ACS and determined that ACS has progressed very well on the clean-up of site such as disposal of unsightly barrels, diking of tanks, etc. Construction of epoxy plant had started.

September 10, 1974

ISBH conducts an inspection of ACS based on a communication from the city Superintendent of Sewers and Sanitary Landfill that ACS is dumping a red organic material into the ditches. Inspection revealed no evidence of dumping.

October 4, 1974 Mr. Stevens, Chief of Industrial Waste Disposal Section of ISBH informs president of town board of Griffith, Indiana that ISBH is unable to confirm the discharge of red organic material to the ditches.

September 22, 1975 Mr. Love, Director of Division of Sanitary
Engineering informs Mr. Galambos, Trustee, Town
of Griffith, that ACS is not dumping chemicals
on-site and would use on-site incineration or
approved sanitary landfill for hazardous
wastes.

April 12, 1976 Mr. Love, Director of Division of Sanitary
Engineering of ISBH grants permission to the
Gary Land Development Landfill to accept 25 cu.
yd./day of paint sludges from ACS.

December 10, 1982 ISBH prepares an office memorandum based on a site visit to ACS on November 22, 1982 regarding information on Hazard Ranking System.

May 27, 1983 ISBH submits information to Mr. Bartelt, Remedial Response Branch, U.S. EPA Region V for

Page No.: 16

inclusion of ACS in the first Superfund National Priorities List (NPL).

May 31, 1983

Mr. Lamm, Director of Division of Land Pollution Control, ISBH informs ACS that their facility has been submitted to the U.S. EPA for inclusion on the National Priority List under CERCIA.

June 9, 1983

Mr. Lamm, Director of Division of Land Pollution Control, ISBH informs Mr. Reyome, Director of Public Works, Griffith, Indiana that the State of Indiana has submitted ACS facility for inclusion on the National Priorities List.

August 1, 1983

State Health Commissioner of ISBH letter to Ms. Hall of U.S. Congress regarding ACS site's inclusion in the National Priorities List.

September 2, 1983

ISBH receives communication from U.S. EPA/Remedial Response Program regarding ACS site in the National Priorities List for Indiana.

September 15, 1983

ISBH's letter to Pazmey Corporation regarding inspection made on August 9, 1983. The inspection revealed that Pazmey Corp. is in violation of the Indiana Environmental Act ICl3-7-4-1 due to the runoff of caustic material onto the soil from their wash building. The letter requested that Pazmey Corp. submit within 35 days steps taken to achieve compliance.

April 21, 1984

Mr. Richard Cleaton of the ISBH sent slides taken in August, 1972 to Ms. Keefe of Techlaw, Inc. The slides depict landfilling of drums at the ACS site.

2.2.3.3 U.S. EPA Region V Site Activity Chronology

U.S. EPA activities concerning the American Chemical Service, Inc. site began in February, 1980 and continue to the present. During this period of time two on-site investigations were conducted in order to provide information for the Hazard Ranking System. During May of 1980, sampling was conducted at the ACS site by the U.S. EPA Environmental Emergency and Investigation Branch. Sampling was again conducted at the ACS site during November, 1982 when a U.S. EPA FIT

contractor (Ecology and Environment) installed four monitoring wells and collected water samples. A detailed chronology of U.S. EPA site activities is presented below.

February 22, 1980

Mr. Shandross of U.S. EPA Region V makes an Identification and Preliminary Assessment of ACS as potential hazardous site.

Page No.: 17

March 4, 1980

Mr. Shandross of U.S. EPA Region V makes a Site Inspection Report of ACS as a possible hazardous waste site.

March 7, 1980

Mr. Shandross of U.S. EPA Region V prepares a tentative disposition of ACS as a potential hazardous waste site and recommends investigative action by EPA and State because there is no information on types of wastes, volume and how wastes are buried.

May 8, 9, 1980

A Field Sampling Report was prepared by Surveillance and Analysis Division of Environmental Emergency & Investigations Branch of U.S. EPA. The report includes a discussion of four water and soil samples taken at ACS site and contains photographs taken at the site. The samples were analyzed for organic pollutants, metals and cyanide.

May 18, 1980

Mr. Shandross of U.S. EPA Region V prepares a trip report and submits it to Mr. Goldstein, Chief, Hazardous Waste Management Section, U.S. EPA. The report included discussions of the ACS waste disposal area, wastes disposed at site, problems with neighbors, local wells, geology and past incineration practices.

July 3, 1980

Central Regional Laboratory prepares a laboratory report based on sampling conducted at ACS site on May 8 and 9, 1980. Water and sediment samples collected at ACS indicated the presence of following priority pollutants: phenol, isophorone, napthalene, fluorene, phenathrene, anthracene, bis(2-chloroethyl) ether, and phthalates.

August 19, 1980

On-scene Coordinator for U.S. EPA Region V informs ACS to provide containment measures to prevent oily discharge from the ACS Off-site Containment Area entering the surface water. The containment measures to be completed by November 1, 1980.

December 12, 1980

U.S. EPA prepares a report based on an RCRA inspection of ACS facility on December 4, 1980. The inspection indicated the following violations: Lack of controlled entry, lack of evacuation plan, lack of maintenance of a complete operating record and failure to perform complete analysis of wastes to be incinerated.

April 7, 1981

Memorandum to file by EPA Region V based on a site visit to ACS by Mr. A.K. Baumann on March 13, 1981. Site inspection indicated that the landfill area has been covered with 12 inches of clay and seeded. An evacuation plan has been made as part of the contingency plan. ACS has implemented a new method for cross-referencing manifest document numbers. Fence has been installed and ACS would also fence the area to be purchased from the railroad. Regarding compliance order, only site security remains unresolved.

June 8, 1981

U.S. EPA Region V receives Notification of Hazardous Waste Site from Estech Specialty Chemicals Corp. regarding the epoxidized cotton seed and linseed oils process at ACS.

June 8, 1981

U.S. EPA Region V receives Notification of Hazardous Waste site from Mobil Chemical Co., regarding wastes handled by ACS.

June 8, 1981

U.S. EPA Region V receives Notification of Hazardous Waste Site from Ashland Chemical Co. regarding wastes handled by ACS.

August 12, 1981

U.S. EPA Region V sends Mr. Reyome, Dept. of Public Works, Griffith, Indiana, the following reports:

- 1. Findings of violation and compliance order.
- 2. Field sampling report, May 8, 9, 1980
- 3. Proposed closure plan for ACS prepared by Ecology and Environment, Inc. on September 16, 1980.

October 21, 1981

Mr. Shandross, State Implementation Officer, U.S. EPA Region V writes Mr.Reyonne, Director of Public Works, Griffith, Indiana providing clarification on items published by Hammond Times and Gary Post Tribune.

Initial Site Evaluation American Chemical Service, Inc. Document No.:160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No.: 20

2.2.3.4 American Chemical Service, Inc. Correpondence Chronology

The following chronology covers the period from June, 1972 to present.

June 29, 1972

Mr. George Murphy of ACS sent a letter to Mr. Miller, Technical Secretary of State of Indiana Stream Pollution Control Board regarding reactivation of oil skimmer on plant effluent to the treatment ponds, plans for provioing dike for storage tanks and plans for covering drains to eliminate stormwater discharges to the lagoon.

October 24, 1972

Mr. Sam Moore, Chief Industrial Waste Disposal Section of ISBH wrote a letter to Mr. George Murphy of ACS regarding satisfactory progress being made by ACS and informed that ACS should contact the Town of Griffith regarding extending sewer to ACS.

April 26, 1973

Letter to ISBH by Mr. George Murphy of ACS proposing installation of process to manufacture epoxidized linseed oil and soybean oil and estimates of volume of wastewater discharges from these processes. Requested permission from ISBH for installation of these processes.

May 10, 1973

ACS provides additional information on volume and characteristics of wastewater discharges and proposed treatment from new processes identified in their letter of 4/26/73.

June 19, 1973

ISBH approves plans for controlling wastes from the manufacture of epoxidized linseed and soybean oils.

September 26, 1980

ACS informs the on-scene coordinator that containment measures suggested in his letter to ACS on August 19, 1980 will be implemented as requested.

April 29, 1981

Director of Enforcement Division of U.S. EPA Region V sends a consent agreement and final order for ACS.

June 18, 1981

Chief of Litigation Unit V receives the signed consent agreement from ACS.

Amer smical Service, Inc.
Docume of 160-WP1-RT-AVJD-1
March 1985
Revision: 0
Page No. 24

TABLE 1 (continued)

| DATE | EVENT | SOURCE | COMMENTS |
|---------|--|---|--|
| 8/2/72 | ISBH inspection | Industrial Waste Dis- posal Section Report | Changes in lard oil process dried up one ditch, water in culvert on south side of railroad track was sampled, old lagoon was now filled with mostly unlabeled, full, partially full, or empty drums (owner said had been that way for a year, ISBH official said wasn't there 3 months before). |
| 3/13/73 | ISBH inspection | Industrial Waste Dis- posal Section Report | ACS had substantially cleaned up drum storage area, incinerator and gasoline additive area. Lard oil effluent to lagoons still "a mess". |
| 4/4/73 | ISBH inspection | Industrial Waste Dis- posal Section Report | Lard oil operation shut down |
| 8/15/78 | Discussion of inspection of Griffith Landfill on 6/15/78 | Memo to Lake Co. from Jim King | Conclusions: Landfill rated as marginal for hazardous waste disposal if sandy upper layer is removed and operations confined to clay layer, extensive volumes of water are migrating along sand/clay interface with discharge into pit in west-central part of property and leachate (black) was observed being pumped into a ditch leading off the Griffith Landfill property. Leachate flows NW. |

TABLE 1 (continued)

| DATE | EVENT | SOURCE | COMMENTS |
|----------|---|--|---|
| 5/8-9/80 | Field sampling of ACS and Griffith Landfill by U.S. EPA | Field Sampling Report | Leachate (black) was observed being pumped into a ditch leading off the Griffith Landfill property. |
| 5/18/80 | Report of trip to ACS | Letter from Richard Shandross to Jay Goldstein | Off-site Containment Area (Map 1/location C) 120'x250'x9'(10,000 yds') contains 25,000-30,000 1/3-full drums, sludge, buried tank truck (1/3-full). Leachingto east and north forming a black puddle 10'x20' which soaks in every year. |
| | | | Griffith Landfill has black (but different) leachate along N&E borders that flows to Turkey Creek. |
| | | | Waste in the Off-site Containment Area is characterized as 80% solvent distillation bottoms, 20% other (80%=1/4 solvents, 1/4 pigments, 1/2 resins incl. PCBs) |
| | | | Discharges to ditch killed vegetation |
| | | | 2 barrel fires have occurred |
| | | | There are four on-site wells at ACS, Inc.; three at Griffith Landfill (1 in use); and 1 at Kapica Drum, Inc. drum (now Pazmey Corp.) Total of 8 wells. |

Amer emical Service, Inc.
Document No.: 160-WP1-RT-AVJD-1
March 1985
Revision: 0
Page No. 26

TABLE 1 (continued)

| DATE | EVENT . | SOURCE | COMMENTS |
|---------|---------------------------------------|--|--|
| 5/18/80 | (continued) | , | Salisbury Engineering made 4 test borings at the Griffith Landfill and encountered (lhr after drilling) water levels at 4' in 3 borings and 16' in the fourth. Incinerator operated 1968-1978. Bottom ash (most went up stack) disposed of on-site for 2 yrs. |
| | | | 7-8 barrels of PCB burned during the period of incinerator operation. |
| 7/3/80 | Results of field sampling by U.S. EPA | Lab report from Curtis Ross, Central Regional Lab, to Richard Bartelt Environmental Emergency Invest- igation Branch | 2 soil samples: 15' north of ACS Off- site Containment Area and 36' east of ACS Off-site Containment Area 2 water samples: Leachate pool 10' north of ACS Off-site Containment Area and runoff from Griffith Landfill. |
| | | | Conclusions: Significant contamination by priority pollutants in soils and leachate (phenol, isophoron, naphtha- lene, fluorene, pthalates) |
| | | | Griffith Landfill runoff contains phenols, ketones, and alcohols. |

Ameri e hwatigation
Ameri emical Service, Inc.
Document No.: 160-WP1-RT-AVJD-1
March 1985
Revision: 0

Page No. 27

TABLE 1 (continued)

| DATE | EVENT | SOURCE | COMMENTS |
|---------|---|--|---|
| 9/9/80 | (Ecology & Environment) FIT inspection of ACS site. | | |
| 9/11/80 | Discussion of FIT Investigation | Letter to Rene Van Someren from Rod Bloese | Mr. Tarpo (President of ACS, Inc.) estimated 20,000 drums were disposed of in the ACS Off-site Containment Area and were punctured to prevent floating. |
| | | | Leachate spring observed (with stains of past leaching) along northeast face of Off-site Containment Area. |
| | | | Leachate ponded in low area adjacent to Off-site Containment Area, flora damaged to 1' from ponded area. |
| | | | Drums exposed along face of Off-site Containment Area. |
| | | | General refuse dump area envelopes the southern part of the Off-site Containment Area. |
| | | | Trench dug SW of ACS Off-site Contain- ment Area on the Griffith Landfill is 25' below grade, liquid is pumped into Griffith sewers. |

Amer emical Service, Inc.
Document No.: 160-WP1-RT-AVJD-1
March 1985

March 1985 Revision: 0 Page No. 28

TABLE 1 (continued)

| DATE | EVENT | SOURCE | COMMENTS |
|------------|--|--|--|
| 7/12-14/82 | Four monitoring wells | Boring logs | Drilled to depths of 15-25', encountered water, sand and gravel to 15-20', then silty clay. Water 4-10' below surface. |
| 8/18/82 | Water sampling by FIT team | E&E report to Tim O'Mara from Ellen J. Jurezak | |
| 11/3/82 | Results of water sampling by FIT team | ELE report to Tim O'Mara from Ellen Jurezak | Upgradient monitoring well most contam- inated (M.W. 2 near Off-site Contain- ment Area). Other monitoring wells have lower levels of contamination. |
| 9/83 | Summary of complaints against ACS since 1972 | Sheet headed "Conditions at Listing" | Shallow water aquifer contaminated by by pentachlorophenol, benzene, toluene, vinyl chloride, 1,1,1-trichloroethylene No contamination of drinking water wells as yet. |

2.3 CONTAMINATION PROBLEM DEFINITION

2.3.1 WASTE DISPOSAL AT SITE

The two primary activities of American Chemical Service, Inc. are chemical manufacturing and solvent reclamation. Table 2 summarizes the American Chemical Service, Inc. manufacturing processes with regard to hazardous wastes generated, quantity, storage, treatment and disposal practice. Based on a review of this data, the following conclusion can be drawn concerning site contamination with hazardous materials from manufacturing processes.

- 1. Hazardous wastes were generated. Examples are Benzene (P028), Toluene (U220), Maleic anhydride (U147), Methanol (U154), Formaldehyde (U122).
- Some hazardous wastes were stored in drums or large tanks on ACS property prior to disposal by incineration or recovery by distillation (Benzene, Toluene, Maleic Anhydride).
- 3. The following six manufacturing processes resulted in wastes being disposed of in the Off-site Containment Area (see Map 1 Map Location C).
 - o Imidization of 6D with Amine 1200 gal/yr (1971-1975) of filter cake. Hazard unknown.
 - o Mannich condensation calcium neutralized 600 gal/yr of filter cake (1973-1975). Hazard unknown.
 - o Copper-8-quino linate production unknown number of empty fiber drums and bags (1973-1975). Hazard unknown.
 - o Manufactured paints or laquers unknown number of empty tins and bags. Hazard unknown.
 - o Manufactured soldering flux unknown number of empty tins and boxes (1967-1975). Hazard unknown.
 - o Manufactured mold release agents unknown number of empty tins and boxes (1967-1975). Hazard unknown.
- 4. The following four manufacturing processes resulted in wastes passing through Treatment Pond #2 (see Map 2 Map Location B).

TABLE 2

STORMER, TREATMENT AND DISTORAL OF SELF CENTERINE WASTE AT MERICON CHERICAL SERVICE, INC.

| Disposal Fraction | | 1974-1977:incinerated 1977-present: blanded as fuel source | Discharged to FOTM | Mathemal resuld, water discharged to marsh. (Map l/Location A) | Incinerated | (1974-1977): Incinerated (1977-1982): Elended as fuel |
|--|------------------------------------|---|--|--|---|--|
| Treatment Practice | | | 1974-1981: passed through 2 settling tests | Separated by distillation | | |
| Storage Pratice | | Benema/Tolumner transported in drums to inclnerator storage tanks | Aqueous waste $+ H_2^0$ 2 | Aquatus waste plus metherol (1958-1967): collected in tanks | Agracus waste (1967-1974): collected in tank and pumped to incinerator storage tanks. | Agueous waste (1974-1982): collected in druss and pumped to incinerator storage tanks |
| Quantity Generated | | 12,000 gal/yr. | | 30,000 gml/yr | 37,000 gml/yr | |
| Hazardous Mastes, By-Products end/or Hazardous Substances Generated | Nane | Liquid waste: 50% bensene (1974-1976) or 50% tolumne and 50% epostidized linesed oil | | Aquecus waste: 50% methanol | Aquecus waste: mostly water | Aquecus waste, mostly water |
| Menufacturing Process | Berium Naphtha- late Production | | | Browinstion of vegetable oil | | Bromination of Vegetable Oil (continued) |
| Period of Operation | 1955-Present | | | 1958-Present | | 1958-Present |

Information contained in Table 2 is from the ACS response to U.S. EPA Request for Information (October 18, 1984).

TABLE 2 (continued)

STORAGE, TREATMENT AND DISPOSAL OF SELF GENERATED WASTE AT AMERICAN CHEMICAL SERVICE, INC.

| Period of Operation | Manufacturing Process | Hazardous Wastes, By-Products and/or Hazardous Substances Generated | Quantity Generated | Storage Pratice | Treatment Practice | Disposal Practice |
|---------------------------|--|--|-----------------------|--|---|--|
| | | Hexane | 2,000 gal/yr | Hemane (1976-present): collected in a tank | | Transported in drums, pumped to incinerator storage tanks. (1976-1977): incinerated (1977-present): blended as fuel source |
| 1969- presen t | Manufactured paints or laquers | Paint or laquer | 500 gal/yr. | Liquid consisting of 95% thinner and 5% paint or laquer collected in drums | Distilled and thinner recovered. | Residue pumped to incinerator storage tanks and incinerated |
| | | Empty tins and bags | Unknown | | | Off-site Containment Area (Map 1/Location C) |
| 1971-Present | Condensation of Maleic Anhydride and Polybutene | Liquid waste of 50% maleic anhydride and 50% polybutene | 6,000 gal/yr. | Maleic enhydride and polybutene (1971- present): collected in 1,500 gal. tank and pumped to incinerator storage tanks | | (1971-1977): incinerated (1971-present): blended as fuel source |
| 1971-Present | Imidization of (6D) with amine | Mater reaction waste | 10,000 gml/yr | | Passed through Trustment Pond #2 (1971-1974) Passed through Trustment Pond #2 (1974-1978) (Map 2/Location B) | Discharge to marsh (Map 1/Location A) Discharged to the POTW |
| | | | | (1978-present): col- lected in a 4,000 gal. tank | | Hauled by tank truck to commercial landfills |

TABLE 2 (continued)

STORAGE, TREATMENT AND DISPOSAL OF SELF GENERATED WASTE AT AMERICAN CHEMICAL SERVICE, INC.

| Period of Operation | Manufacturing Process | Hazardous Wastes, By-Products and/or Hazardous Substances Generated | Quantity Generated | Storage Pratice | Treatment Practice | Disposal Practice |
|------------------------|---|--|------------------------|--|---|---|
| | | Filter cake: 50% dia- tomaceous filter aid, 50% product | 1,200 gml/yr. | Filter cake solid (1971-present): collected in drums | | Disposed of at the Off- site Contairment Area (1971-1975)(Map 1/ Location C) |
| | | | | | | Disposed of at commerical landfills (1975-Present) |
| 1973-Present | Mannich Condensation Calcium | Aqueous waste: 10% methanol | 40,000 gal/yr | | Treatment Pond #2 (1973- 1974) | Discharge to marsh (Map 1/Location A) |
| | Neutralized | | | | Treatment Pond #2 (1974-1978) (Map 2/Location B) | Discharge to FOTM, |
| | | | | 1978-1984: collected in 4,000 gal. tank | | Hauled by tank truck to commercial landfills |
| | | | | 1984-present: | Methanol and water separated in distill- ation column | Methanol reused as fuel water discharged to POTW |
| | | Filter cake: diatomaceous filter (50%) and 50% product | 600 gal/yr | Pilter cake solid: (1973-present) collected in drums | | Disposed of at Off-site Containment Area (1973-1975) (Map 1/ Location C) Commercial landfills (1975-present) |
| | | Ca(CH) ₂ (solid) | 2,000 empty bags/yr | | | (1575-passaile) |
| 1972-1974 | Coplymerzation of Furfuryl Alcohol and Formaldehyde | Aqueous waste (mostly water) | 5,000 gal/yr. | Aqueous waste (1972- 1974): collected in 2,000 gal. tank | Treatment Pond #2 (Map 2/Location B) | Discharge to marsh (Map 1/Location A) |
| | | Maste (mostly furfuryl alcohol) | 10,000 gal/yr | Organic waste: col- lected in 2,000 gal. tank and pumped to incinerator storage | | 1974-1977: incinerated 1977-present: used as fuel source |

TABLE 2 (continued)

STORAGE, TREMINENT AND DISPOSAL OF SELF GENERATED WASTE AT AMERICAN CHEMICAL SERVICE, INC.

| Period of Operation | Manufacturing Process | Hazardous Wastes, By-Products and/or Hazardous Substances Generated | Quantity Generated | Storage Pratice | Treatment Practice | Disposal Practice |
|------------------------|--|--|-----------------------|---|--|--|
| 1973-1979 | Furan Resin | Nane | | tanks | | |
| 1973-Present | Catalyst Blend Copper-8-Quino- linate production | Dilute acetic acid | 400 gal/yr | Dilute acetic acid collected in drums | | 1973-1977: incinerated 1977-present: fuel source |
| | | Piber drums and bags (empty) | Unknown | | | Off-eite Containment Area (1973-1975) (Map 1/Location C) Commerical landfill (1975-Present) |
| 1974-Present | Homopolymersation of furfuryl alcohol | Aqueous waste (mostly) water) | 12,000 gml/yr. | Aqueous waste (1974- to 1978): collected in 2,000 gal. tank (1978-present): collected in 8,000 cal. tank | Treatment Fond #2 (Map 2/Location B) | FORM Hauled to commerical disposal locations |
| 1965-1975 | Manufactured soldering flux | No wastes Empty tins & Bomes | Unknown | • | | Griffith Sanitary Lendfill (1965-1967) Map 1/Location D. Off-site Containment Area (1967-1975) (Map 1/Location C. |
| 1974-Present | Epoxidation of Linseed Oil | Aqueous waste: 1.5% H ₂ O ₂ 1.2% formic acid, .3% NaOH | 40,000 gal/yr. | Aqueous waste + NaCH and soep of lineolic acid: collected in 4,000 gal tank (1979-1981) | | Hauled to Lend and Lakes III, Chicago |
| | | Aqueous waste: 2.3% NaCH and 15% soap of lineolic acid | 1,000,000 gal/yr | 1981-present: both aqueous wastes | Neutralization tank and 2 settling tanks | Discharged to POTW |

(

TABLE 2 (continued)

STORAGE, TREATMENT AND DISPOSAL OF SELF GENERATED WASTE AT AMERICAN CHEMICAL SERVICE, INC.

| Period of Operation | Manufacturing Process | Hazardous Wastes, By-Products and/or Hazardous Substances Generated | Quantity Generated | Storage Pratice | Treatment Practice | Disposal Practice |
|---------------------------|--|--|-----------------------|-----------------|--------------------------------------|--|
| 1967–P rese nt | Manufactured mold release agents | No wastes Empty tins & boxes | Unknown | | | Off-mite Containment Arem (1967-1975) Mmp 1/ Location C Commerical Lendfill (1975-present) |
| 10/71-3/73 | Processed animal oils | Water & small amounts of animal oils | 1,000,000 gal/yr | | Treatment Fond #2 (Map 2/Location B) | Skimmed, removed and and resold |
| 1962-1965 | Manufactured Ski Belts | None | | | | |
| 1955-1963 | Rope treatment | None | | | | |
| 1963-1975 | Manufactured cable flooding compound | None | | | | |

- o Imdization of 6D with Amine 10,000 gal/yr of water reaction/waste (1971-1978).
- o Mannich condensation calcium neutralized 40,000 gal/yr (10% methanol) (1973-1978).
- o Copolymerization of Furfuryl, Alcohol and Formaldehyde 5000 gal/yr (1972-1974). Mostly water.
- o Homopolymerization of Furfuryl Alcohol 12,000 gal/yr (1974-1978). Mostly water.

The manufacturing process wastes deposited in the Off-site Containment Area were primarily empty containers. The contents of the containers were probably raw materials used for the particular manufacturing process. The hazard potential of the manufacturing process wastes disposed of in the Off-site Containment Area is unknown based on the available information. Waste from manufacturing processes that passed through Treatment Pond Number 2 contained two listed hazardous wastes. These listed hazardous wastes are methanol and formaldehyde. Based on the available data, approximately 24,000 gallons of methanol and a small volume of formaldehyde were treated in Treatment Pond Number 2. It is unlikely that remnants of either of these wastes still remain in the treatment pond.

Table 3 summarizes the disposal practices of American Chemical Service, Inc., and Kapica Drum, Inc. from 1955 to the present. This table includes disposal practices for both the ACS manufacturing process wastes and solvent reclamation wastes; and Kapica Drum, Inc. drum reclamation wastes. Basically there are four locations on ACS property that contain buried hazardous wastes. These locations are:

- o Off-site Containment Area (Map 1 Location C)
- o On-site Containment Area (Map 2 Location E)
- o Old Still Bottom Pond (Map 2 Location F)
- o Old Treatment Pond Number 1 (Map 2 Location G)

In addition, it is suspected that wastes are located in the Griffith Landfill (Map l/Location D). These wastes were contributed by ACS and Kapica Drum, Inc. (now owned by Pazmey Corporation) This is based on information supplied by the reply to the U.S. EPA Request For Information sent to ACS (10/18/84)

The table is self-explanatory; however, in summary, the largest disposal area is the Off-site Containment Area. The Old Still Bottoms Pond and Old Treatment Pond Number 1 also contain significant amounts

TABLE 3
DISPOSAL PRACTICES BY AMERICAN CHEMICAL SERVICE, INC. AND KAPICA DRUM, INC.

| Disposal Practice | Period | Тура | Quantity | Location | Comments |
|----------------------|--------------------|--|-----------|---|--|
| AMERICAN CHEM | ICAL SERVICE, INC. | | | | |
| Landfilling | 1955-1977 | | | Off-site Containment Area (Mmp 1/Location C) | Containers punctured as they were landfilled |
| | | 55 gal. drums of PCB contaminated waste | 6 Drums | | |
| | | Non-reclaimable still bottoms | | | |
| | | Drums containing solidified materials Ex: Latex paint, solid resin | | | |
| | 1956-1975 | Distillation bottoms | 10,000 cy | | |
| | | Soilid material rec'd for reclamation | | | |
| | | Solid material rec'd for incineration | | | |
| | | Paper | | | |
| | | Incinerator ashes | 68 cy | | |
| | | Ignitable and corrosive hazardous wastes | | | |
| | | Chlorinated solvent, acetone and MEK bottoms | | | |

Information contained in Table 3 is from the ACS response to U.S. EPA Request For Information (October 18, 1984.

perio mice vice

Document No.: 160-MP1-RT-AWND-1
Narch 26, 1985
Revision: 0
Page No: 37

TABLE 3 (continued)

DISPOSAL PRACTICES BY AMERICAN CHEMICAL SERVICE, INC. AND KAPICA DRUM, INC.

| Disposal Practice | Period | Туре | Quantity | Location | Communits |
|----------------------|-----------|--|--|--|---|
| | | Spent cresylic acid, cyanide and chromium from plating | | | |
| | | Lead Pigments | | | |
| | | Empty bottles that had contained 2,4,D and 2,4,5-TP | Several 100 cases | • | |
| | | 1 tank truck containing 500 gallons solidified paint | | | |
| Landfilling | Mid 60's | Sludge and semi-solids of unknown type. | 400 drums | On-site Containment area (Map 2/Location E) | |
| Landfilling | 1969-1975 | Solids in drums-questionable as to content, but probably solvent solids of benzene, amylacetate, dimethyl aniline, diethylether | 200 drums | Treatment Pond #1 or Off-mite Containment Area | During this time the 2,4-D and 2,4,5-TP plus an unknown amount of DDT was incinerated |
| Landfilling | 1955-1967 | Trash | | City of Griffith | |
| | | Retained samples (contained hazardous substances) | 10 gal/wk | Indiana Landfill (Map 1/Location D) | |
| Pond disposal | 1955–1972 | Still bottoms sludges from reclamation processes sludges containing 1,1,1-trichlorosthane, trichlorosthylene, methylene chloride, toluene, benzene and other low toiling solvents. | 253,510 gal. still bottoms sludge and 2,000 partially filled drums | Old Still Bottoms Pond (Nep 2/Location F) (125° dia.x 4.5° deep) | |

(

TABLE 3 (continued) DISPOSAL PRACTICES BY AMERICAN CHEMICAL SERVICE, INC. AND KAPICA DRUM, INC.

| Disposal Practice | Period | Тура | Quantity | Location | Comments |
|----------------------------------|-----------|--|--|---|--|
| | | Partially filled drums of semi-solid paint, lacquer and ink waste | 41,612 gal. sludge 1,000 partially filled drums | Old Treatment Pond #1 (Mmp 2/Location G) (180'x70'x3' Deep) | Treatment Pond #1 and the still bottoms pond were filled and scaled in 1972. During closing the liquid portion of Treatment Pond #1 and the Still Bottom Pond were drained leaving the heavy sludges. Drums were placed on top of the pond, punctured and crushed. Ponds were "closed off" by sand fill and compacting |
| | 1968-1976 | Aqueous phase containing small quantities of organic (some hazardous) solvents | | Treatment Pond #2 (Nep 2/Location B) (180'x70'x10' Deep) | Supposedly biodegradable wastewater over- flow from Trentment Pond #1 and API oil decenter was discharged here. Overflow from Trentment Pond #2 went to the warsh from 1968-1974 and to the PONM from 1974 to Present. |
| Treatment Pond Inter-connecti | | | | | |
| API Oil Decanter | 1963-1967 | 1,1,1-trichloroethame, trich- loroethyleme, methyleme chloride, tolueme, benseme and other low boiling solvents | 1 | API oil decenter (Mep 2/Location H) | Dimensions are 15'x15'x5' 1963-1967- wastewater flowed directly to marsh 1967-1972-wastewater flowed to T.P. #1 then to marsh 1972-1974 wastewater flowed to T.P. #2 then to marsh |
| Trenches | 1955-1976 | Reclamation residues contain- ing above-mentioned compounds | | Trench #1 (1'x2'x125') (Map 2/Location I) | Conducted wastewater to Trench #2 |
| | 1955~1976 | Reclamation residues contain- ing above-mentioned compounds | | Trench #2 (1'x2'x110') (Map 2/Location J) | 1955-1963: Conducted wastewater from reclamation facility to marsh 1963-1976-to API oil december Replaced in 1976 by a close-pipe system |
| | 1963-1976 | Aqueous phase w/small quanti- ties of organic (some hazardous) solvents | | Trench #3 1'x2'x70' (Map 2/Location K) | (1963-1967): Conducted wastemater from API oil decenter to mersh All trenches are presently filled, and the area is used as a roadway |

TABLE 3 (continued)

DISPOSAL PRACTICES BY AMERICAN CHEMICAL SERVICES

| Disposal Practice | Period | Тура | Quentity | Location | Comments |
|------------------------|----------------------|--|---------------------|--|--|
| KAPICA DRUM, 1 | NC. (now Pazmey Corp | p.) | | | |
| DISPOSAL OF CO | NTENTS | | | | |
| | 1961-1971 | If drums sent to Kapica contained liquid, the contents were dumped on the ground OR | 330 yd ³ | Kapica Dump site (Map 1/Location L) | |
| | | Combined to generate full drums | 2,500 drums | Griffith Sanitary Landfill (Map 1/Location D) | |
| | 1978-1980 | Paint residue sludge from Kapica Drums,Inc. | 250 gal/wk | ACS sludge box | For disposal at Gary Development Lendfill |
| DISPOSAL OF RI | NSE WATER | | | | |
| | 1961-1971 | Unknown | Unknown | Mest end of Kapica property | |
| Drum Mashing | 1962-1983 | Liquid waste | | Flowed intermittently onto ACS property from Rapica Drums, Inc. and Passmay Corp. | |
| Drum Reconditioning | 1962¬July 1980 | Empty drums from ACS were picked up and reconditioned by Kapica | | Kepica Drume | After August, 1980, ACS bought new drums from Kapica (who sold out to Pagesy in 2/ |
| | 1962-1980 | 1,000 gal. H ₂ O containing 600 lbs. NaOI4(s) + 400 lbs Na ₃ PO ₄ (s) | 3 times/year | Unknown | Used for washing drums at Kapica |

of waste; however, the volume is less than the Off-site Containment Area. The smallest of the waste disposal sites is the On-site Containment Area. The small piece of property owned by ACS and reported to be used by Kapica Drum, Inc. to dispose of drum residue may have contaminated soil, however, there is no documentation of buried waste. In addition there were three trenches on ACS property that carried waste from the solvent reclamation facility to the storage and treatment ponds. These may be sites of contaminated soil.

Table 4 summarizes the locations of waste storage sites prior to reclamation. This data has been included to indicate areas in which the potential for spills and/or leaks during storage may have occurred. However, the only documented spills were dry solvent that was cleaned up, and a spill and subsequent fire.

In summary, the specific areas recommended for remedial investigation based on available data are as follows:

| Property | Location | Justification |
|---------------------------------|---|--|
| American Chemical Service, Inc. | Off-site Con- tainment Area (Map 1/ Location C) | Documented Haz- ardous Waste Disposal Site |
| | On-site Con- tainment Area (Map 2/ Location E) | Documented Haz- ardous Waste Disposal Site |
| | Old Still Bottoms Pond (Map 2/ Location F) | Documented Haz- ardous Waste Disposal Site |
| | Old Treatment Pond #1 (Map 2/ Location G) | Documented Haz- ardous Waste Disposal Site |
| | Kapical Drum, Inc. Draining Area (Map 1/ Location L) | Suspected Soil Contamination |
| | Old Drum Storage Area (Map 2/ Location M) | Suspected Soil Contamination |

In: 1 S Eva ior New Arch 1985
Revision: 0
Page No: 41

TABLE 4

AMERICAN CHEMICAL SERVICE, INC. HAZARDOUS WASTE STORAGE PRACTICE
PRIOR TO RECLAMATION

| PERIOD | WASTE | STORAGE PRACTICE | LOCATION |
|-----------|---|--|--|
| 1955-1968 | Incoming materials prior to reclamation | Drum storage direction ground. Occasional spillage. Dry solvent mass easily picked up Area was undiked. | Drum storage area (Map 2/Location M) |
| 1966 | Reclamation bottoms to be fed to the incineration | Bulk storage at tank farm. Finally diked in 1973. | Location of present waste fuel tank farm. (Map 2/Location N) |
| 1970-1975 | Reclamation Crude | Converted 75% from drum storage to bulk storage. Began picking up in bulk from customers in 1970. | Reclaim crude tank farm (Map 2/Location P) |
| Unknown | Chlorinated solvents | Drum storage | Unknown |
| Unknown | Unknown | Small fire in drum storage area several hundred gallons of material spilled. | Drum Storage Area (Map 2/Location M) |

Initial Site Evaluation American Chemical Service, Inc. Document No.:160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No.: 42

Old Wastewater Suspected Soil Trenches (Map 2/

Contamination

Location I,J,

K)

Kapica Drum, Inc. (now Pazmey, Corp.) West end of Kapica Drum property

Suspected Soil Contamination

(Map 2/ Location 0)

City of Griffith

Griffith Landfill (Map 1/

Location D)

Suspected Hazardous Waste Disposal Site

Figure 3 shows the relationship between the hazardous waste generated and processed by American Chemical Service, Inc. and their ultimate disposal.

2.3.2 DEGREE OF SITE CONTAMINATION

There are four locations on the American Chemical Service, Inc. property that are documented hazardous waste disposal sites. The most heavily contaminated areas are the Off-site Containment Area, Old Treatment Pond Number 1, Old Still Bottoms Pond and On-site Containment Area. This classification is due to the large quanitity and wide variety of waste buried at these locations. One other area of the property that can be classified as possibly contaminated is the old drum storage area (Map 1 - Location M). This statement is based on the fact that drums were stored in other areas prior to being reclaimed. These drums contained a wide variety of material and it is likely that spills occurred in the area.

In addition, there are two other areas on ACS property that are suspected of having contaminated soil of unknown degree. These are the Kapica Drum, Inc. drum draining area and, old wastewater trenches. The Kapica Drum, Inc. drum draining area is reported to have been used to dispose of drum residue prior to reclaimation. The old wastewater trenches are suspected of soil contamination because they were used to transport wastewater from the solvent reclaimation facility to the storage and treatment ponds.

Finally, there have been references to waste from ACS and Kapica being disposed of in the Griffith Landfill. The general location where these wastes, if they actually exist, were probably disposed of is shown on Map 1 - Location D. This location was provided by City of




FIGURE 3 WASTE DISPOSAL FLOWCHART

Griffith Department of Public Works personnel as the most likely location for wastes <u>if</u> they were disposed of in the landfill. The degree of contamination, if any, is unknown.

On-site soil and water sampling has been conducted twice at the ACS site. Tables 5 & 6 summarize the May, 1980 sampling results. Thirty-nine organic compounds were identified during the May, 1980 sampling along with a number of metals. Table 7 summarizes the November, 1982 sampling results. Ten organic compounds were identified in monitoring well water samples. The location of these wells in relation to the Off-site Containment Area is shown on Map 1. Monitoring Wells 1 & 2 are relatively close to the On-site Containment Area and the results indicate that waste constituents have migrated at least to these monitoring wells.

2.4 CONTAMINANT MIGRATION AND ENVIRONMENTAL/HEALTH EFFECTS

2.4.1 MIGRATION PATHWAYS

Contaminant migration from the ACS site can be in surface water or groundwater. Airborne contaminant migration is not likely at the ACS site. As noted in Section 2.3.2, documentation of contaminants in On-site surface and groundwater (upper aquifer) was obtained during the 1980 and 1982 sampling. Off-site surface water sampling has not been conducted.

Off-site groundwater sampling has been conducted on two occasions. The first is a Lake County Groundwater Survey conducted by the Indiana State Board of Health. This survey involved the sampling of 32 wells. Some of the well locations are shown on Figure 4. The results of the survey are shown on Table 8. The analysis was primarily to measure metals content. The data did not reveal any parameter beyond the levels set for the Safe Drinking Water Act (SDWA) for maximum contaminant levels. No organic compound data was collected.

Table 9 shows the results of water sampling at seven homes near ACS. Six of the wells did not show any contaminants. One of the wells (O'Neil) showed a Benzene concentration of 6.2 ppb and an acetone concentration of .9 ppm. Due to the lack of confirming data from the other six nearby wells the validity of the Benzene contamination is questionable. However, if the O'Neil well uses water from a different aquifer (perhaps the upper aquifer) than the other six wells, this could explain the difference in the findings. The available data is not sufficient to definitely state that contamination has moved outside ACS property.

2.4.2 POTENTIAL RECEPTORS

Groundwater is the primary receptor of concern. Surface water is a secondary receptor. Existing information indicates that there are two

_ial__e i___at_

American Chemical Service, Inc.
Document No.: 160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No: 45

Water

TABLE 5

U.S. EPA SAMPLING RESULTS SURVEILLANCE AND ANALYSIS DIVISION ENVIRONMENTAL EMERGENCY AND INVESTIGATIONS BRANCH AT AMERICAN CHEMICAL SERVICE AND GRIFFITH CITY LANDFILL MAY 8-9, 1980 (CONCENTRATION UNIT IN PPB)

| | Subsurface Soil Sample #1 15' N of ACS Off-Site Containment Area | Subsurface Soil Sample #2 36' E of ACS Off-Site Containment Area | Sample #1 from Leachate Pool 10' N of ACS Off-Site Containment Area | Water Sample #2 from Run Off From Griffith Landfill |
|------------------------------|--|--|---|---|
| Phenol | K1,400 | 26 | K13 | 350 |
| Isophorone | K700 | 6.2 | K240 | KO.7 |
| Naphthalene | 12,000 | 21 | 29 | KO.5 |
| Fluorene | 1,000 | 6.1 | K23 | KO.8 |
| Diethylphthalate | K7,400 | 2,500 | K240 | 10 |
| Phenanthrene and anthracene | 1,400 | 26 | K42 | K1.0 |
| Di-n-butylphthalate | 1,100 | ü | K240 | 21 |
| Bis(2-ethylhexyl)phthalate | 110,000 | 71 | 510 | 63 |
| Butylbenzylphthalate | 8,300 | 117 | K240 | KO.7 |
| Bis(2-chloroethyle)ether | K400 | K5.5 | 300 | 28 |
| Dimethylphthalate | K510 | K5.5 | 2,300 | KO.7 |
| Methylnaphthalenes(2) | 32,000 | - | _ | - |
| Dimethylnapthalenes(5) | 22,000 | - | - | - |
| Dephenylether | 3,800 | - | - | _ |
| Polychlorinated Unknown | 12,000 | - | - | - |
| Hydrocarbons(2) | 5,100 | - | - | - |
| (2-Ethoxy)Ethyl Acetate | - | 17,000 | ~ | - |
| 2-(Hydroxymethyl)-1-pentanol | - | 40,000 | - | - |
| Trimethyl-2-cyclohexen-1-one | - | 36,000 | - | - |
| N-methyl-2-pyrrolidone | - | 11,000 | - | |

American Chemical Service, Inc. Document No.: 160-WP1-RT-AVJD-1

March 26, 1985 Revision: 0 Page No: 46

TABLE 5 (continued)

| | Subsurface Soil Sample #1 15' N of ACS Off-Site Containment Area | Subsurface Soil Sample #2 36' E of ACS Off-Site Containment Area | Water Sample #1 from Leachate Pool 10' N of ACS Off-Site Containment Area | Water Sample #2 from Run Off From Griffith Landfill |
|--|--|--|---|---|
| 1-(2-butomyethoxy)ethanol | _ | 6,800 | _ | - |
| 2-ethylhexanoic acid | - | 4,100 | - | - |
| methylphenols (2) | . - | 57,000 | - | - |
| Ethylphenols (3) | - | 58,000 | _ | - |
| Dimethylphenopols (2) | - | 15,000 | - | - |
| Pentylphenol | _ | 4,100 | - | - |
| Methomytrimethylphenol | - | 11,000 | - | - |
| Dimethyl Benzenedicarboxylate | - | 5,300 | - | - |
| 2,2,4-Trimethyl-3-cyclohexen- | - | | | |
| 1-methanol | | 1,700 | _ | - |
| N-methyl-2-pyrrolidone | - | - | - | 180 |
| Methylphenol | - | - | - | 120 |
| Dimethylphenol | - | - | - | 52 |
| Pentylphenol | | _ | - | 81 |
| Trimethyl-cyclohexanone | - | - | - | 160 |
| 2-(2-Methoxy-1-methylethoxy) -1-propanol | - | - | - | 500 |
| 1-(2-Methoxy-1-methylethyl) 2-propanol | - | - | - | 43 |
| 1,1'-oxybis-2-chloroethane | - | - | _ | 53 |
| 3,3-5-trimethylcyclohexene | - | - | - | 460 |
| Unknown | - | 9,500 | 200 | 120 |

¹⁻Data obtained from U.S. EPA analytical resutls: Data set EEIB 280 and 281 samples collected at American Chemical Service, Inc. and Griffith Landfill July 3, 1980.

²⁻Compounds 1-11 are priority pollutants confirmed by mass spectra and gas chromalographic retention

³⁻Compounds 12-39 are non-priority pollutants confirmed by computer library search and quantified according to standards.
4-K indicates lower detection limit.

⁵⁻Parenthesis () indicates the number of isomers present.

Initial Site Evaluation American Chemical Service, Inc. Document No.: 160-WP1-RT-AVJD-1 March 1985

Revision: 0
Page No: 47

TABLE 6

U.S. EPA SAMPLING RESULTS SURVEILLANCE AND ANALYSIS DIVISION ENVIRONMENTAL EMERGENCY AND INVESTIGATIONS BRANCH AT AMERICAN CHEMICAL SERVICE, INC. AND GRIFFITH LANDFILL MAY 8-9, 1980 (CONCENTRATION UNIT IN PPB)

| | Soil Sample #1 (mg/g) | Soil Sample #2 (mg/g) | Water Sample #1 mg/l |
|----------|-----------------------|--------------------------|-------------------------|
| | | | |
| Ca | 3.8 | KO.5 | 381 |
| Mg | 2.8 | 0.9 | 74.6 |
| Na | KO.1 | KO.1 | 195 |
| Ag | KO.3 | KO.3 | \mathbf{n} |
| Al | 3,700 | 3 ,4 00 | 467 |
| В | K8 | K8 | 1,800 |
| Be | 0.2 | 0.2 | K1. |
| Ba | 11 | 13 | 335 |
| Cđ | KO.1 | K0.2 | 184 |
| ထ | 4 | 2 | 4 27 |
| Cr | 11 | 2 8 9 | 254 |
| Cu Cu | 13 | 9 | 117 |
| Fe | 9,100 | 7,600 | 10,400 |
| Min | 370 | 55 | 8,550 |
| Mo | 6 | 6 | 57 |
| Ni | 9 | 5 | 5-4 |
| Pb | 14 | 15 | 282 |
| Sn | 15 | K10 | K100 |
| Ti | 88 | 74 | 13 |
| V | 12 | 11 | 34 |
| Y | 5 | 7 | 19 |
| Żn | 26 | 20 | 2,300 |
| Total Hg | .049 mg/kg | | .8 ug/1 |
| Total CN | K0.3 mg/kg | K.03 mg/kg | 96 ug/1 |

Data obtained from U.S. EPA analytical results. Data set EEIB samples collected at American Chemical Service, Inc. and Griffith Landfill June 12, 1980.

^{1.} K indicates lower detection limit.

^{2.} Sample number correspond to those given in Table 5.

Page No: 48

TABLE 7

ECOLOGY AND ENVIRONMENT, INC. WELL SAMPLING RESULTS ECOLOGY AND ENVIRONMENT, INC. WELL SAMPLING DATA AMERICAN CHEMICAL SERVICE, INC. AND GRIFFITH LANDFILL GRIFFITH, INDIANA NOVEMBER 3, 1982

| | Monitoring Well #1 (ppm) | Monitoring Well #2 (ppm) | Monitoring Well #3 (ppm) | Monitoring Well #4 |
|----------------------|--------------------------------|--------------------------------|--------------------------|-----------------------|
| | | | | |
| 1,2-Trans- | | | | |
| dichloroethylene | - | 34 | - | - |
| Ethylbenzene | 1.6 | 10 | - | - |
| Toluene | 16 | 35 | - | - |
| Vinyl chloride | - | 680 ppb | - | - |
| 2,4-Dimethylphenol | - | | | - |
| Pentachlorophenol | - | 36 | _ | _ |
| Bis-(2-chloroethyl) | | | | |
| ether | _ | 327 | - | - |
| Benzene | 24 | 29 | | - |
| 1,1,1-Trichloroethan | e - | 1.1 | - | - |
| Chloroethane | _ | 980 | 96 | - |

Data obtained from E&E analytical results for sampling at ACS November 3, 1982.

^{1.} Well #4 was dry. A sample was not collected.




FIGURE 4 LOCATION OF WELLS SAMPLED IN LAKE COUNTY GROUNDWATER SURVEY

TABLE 8 (continued)

INDIANA STATE BOARD OF BEALTH 1981 LAKE COUNTY GROUNDWATER SURVEY RESULTS (PPM)

| Well | Location | n Turbidity | рĦ | CaCO ₂ H | Mo | Pe | Mn | Ca | Mg | Na | K | a | 80, | PO, | Da | Cđ | Cr (TOT) | Pb | TOC | NO, | 000 |
|-------------------|----------|-------------|-------|---------------------|-----|------|------|-----|-----|----|-----|-----------|-----|------|------|-------|-------------|-------|------|-----|-------------|
| | | | | | | | | | | | | | 3 | | | | | | | | |
| Jewell Rogers | | | | | | | | | | | | | | | | | | | | | |
| 712 E. Klm | 15 | 0.6 | 7.8 | 200 | 200 | .77 | .03 | 50 | 18 | 7 | .7 | <5 | 18 | <.09 | .050 | <.002 | .010 | <.010 | 2 | | S |
| Salisbury Eng | | | | | | | | | | | | | | | | | | | | | |
| 1501 E. Main | 16 | 10 | 7.6 | 322 | 344 | 1.4 | .02 | 74 | 34 | 19 | 2.3 | <5 | 34 | .15 | .260 | <.002 | <.010 | <.010 | 2.2 | | G |
| American Chemical | l 17 | .5 | 7.6 | 312 | 396 | .14 | <.02 | 59 | 40 | ឲ | 5.7 | 5 | 60 | <.09 | .080 | <.002 | <.010 | <.010 | 1.0 | | G |
| American Chemical | l 18 | 35 | 7.3 | 306 | 396 | 3.3 | .03 | 58 | 39 | 65 | 6.8 | (5 | 62 | <.09 | .110 | <.002 | .010 | <.010 | 1.0 | | G |
| Silvester Reder | 19 | 30 | 7.3 | 398 | 312 | 3.7 | .09 | 94 | 40 | 16 | 1.8 | 21 | 100 | <√09 | .150 | <.002 | .010 | .020 | 1.5 | | • |
| Kim Evans | 20 | 20 | 7.3 | 474 | 388 | 2.6 | .02 | 96 | 57 | 22 | 2.9 | <5 | 130 | <.09 | .170 | <.002 | .010 | <.010 | 1.0 | | G |
| 1902 Bilison Ave. | 21 | 25 | 7.3 | 790 | 456 | 3.3 | .05 | 146 | 104 | 45 | 3.9 | 51 | 350 | <.09 | .070 | <.002 | .030 | .010 | 1.2 | | 9999 |
| Howard Long | 22 | 25 | 7.3 | 628 | 464 | 3.2 | .03 | 122 | | 26 | 3.1 | (5 | 210 | <.09 | | <.002 | | .010 | 1.5 | | (5 |
| Glen Slaney | | | | | | | | | | | | | | | , | | | | | | |
| 553 N. Raymond | 23 | 5 | 7.6 | 224 | 252 | .92 | <.02 | 50 | 24 | 14 | 1.7 | (5 | 5 | <.09 | .200 | <.002 | <.010 | <.010 | 1.4 | | G |
| Gose Rome | | • | | | | | | | | | | - | - | | | | | | | | |
| 1106 S. Broad | 24 | 30 | 7.3 | 668 | 460 | 4.8 | .03 | 123 | 87 | 37 | 3.9 | <5 | 280 | <.09 | .050 | <.002 | .010 | <.010 | 2.2 | | G |
| Prank Rozick | 25 | 8 | 7.6 | 240 | 168 | 1.1 | .02 | 53 | 26 | 7 | 1.4 | 7 | 77 | <.09 | | <.002 | | <.010 | 1.3 | | (5 |
| John Price | 26 | 6 | 7.7 | 236 | 120 | . 84 | .08 | 54 | 24 | 12 | .9 | 17 | 120 | .15 | .090 | <.002 | .010 | <.010 | 1.9 | | 6 |
| Douglas Maldron | 27 | ě | 7.7 | 204 | 224 | 1.1 | <.02 | 51 | 18 | 12 | 1.2 | <5 | (5 | .2 | .130 | <.002 | .010 | <.010 | 2.2 | | G |
| Citizen's TV | 28 | 5 | 7.8 | 228 | 316 | 1.0 | <.02 | 49 | 26 | 37 | 2.5 | (5 | (5 | .2 | | <.002 | .010 | <.010 | 41.0 | | (5 |
| Lovin Home | 29 | 2 | 7.8 | 156 | 168 | .64 | | 38 | 15 | 6 | .9 | - | 5 | .15 | | <.002 | .010 | <.010 | <1.0 | G | |
| Ernest Van Byssum | _ | _ | . • - | | | | | | | | | | | | | | | | | | |
| 1818 E. Elm | 30 | 10 | 7.6 | 228 | 244 | 2.9 | .04 | 62 | 18 | 11 | 1.0 | G | G | .2 | .080 | <.002 | .020 | <.010 | 3.1 | | G |
| Hayworth Home | 31 | 10 | 7.4 | 300 | 328 | 2.1 | .02 | 75 | 27 | 13 | 1.4 | (5 | 12 | .05 | | <.002 | | <.010 | 4.0 | | (5 |
| Arthur Hegedus | | | | | | | | | _ | | | | | | | | | | | | |
| 1009 S. Wood | 32 | 20 | 7.4 | 500 | 392 | 3.5 | .03 | 96 | 63 | 26 | 3.5 | 4 | 200 | <.09 | .140 | <.002 | .010 | <.010 | 2.4 | | 24 |

...

TABLE 8

INDIANA SIRTE ECARD OF HEALTH 1981 LAKE COUNTY GROUNDMATER SURVEY RESULTS (FPM)

| Well | Locatio | n Turbidity | рH | CaCO ₄ H | Мо | Pe | Mn | Ca | Mg | Na | ĸ | a | 5 0, | PO ₄ | Ba | Oğ . | (101) Ct | Pb | TOC | 1102 | cop |
|------------------|---------|-------------|-----|---------------------|-----|------|-----|-----|----|-----|-----|----|-------------|-----------------|----|------|-------------|----|------|------|-----|
| | | | | | | | | _ | | | | | | | | | | | | | _ |
| Ramon Mathis Far | m 1 | 7 | 7.3 | 229 | 123 | 1.8 | .22 | 64 | 17 | 10 | .8 | 15 | 93 | .15 | - | - | - | _ | 2.6 | .2 | (5 |
| Pritchett | 2 | .1 | 7.7 | 164 | 76 | <.05 | .04 | 46 | 12 | 3 | 3.5 | 13 | 52 | . 09 | - | _ | _ | _ | 2 | 4.2 | G |
| Crago | 3 | .7 | 7.3 | | 140 | .47 | | 54 | 17 | Ă | 1.2 | -6 | 60 | <.09 | _ | - | - | _ | 6.4 | 1.2 | 18 |
| Brown | Ä | 2 | 7.5 | 126 | 72 | 1 | .06 | 38 | 8 | ž | .2 | 8 | 53 | .15 | • | - | - | _ | 1.5 | <.1 | (5 |
| Roseveer-Hove | 5 | 5 | 7.2 | 344 | 188 | ī.1 | .89 | 93 | 27 | 3 | 2.6 | 14 | 130 | .09 | - | - | _ | _ | 4.3 | 2.7 | 10 |
| Rosevear-Tennant | . 6 | ĭ | 7.1 | 400 | 276 | 2 | .29 | | 28 | ű | 30 | 28 | 77 | <.09 | - | _ | - | - | 4.7 | <19 | 10 |
| Rosevear-Barn | 7 | 5 | 7.0 | | 302 | .15 | | 166 | 39 | 7 | 20 | 32 | 180 | <.09 | _ | _ | - | _ | 7.5 | œ | 17 |
| Huber Sod Co | • | •• | | | | •== | | -00 | | • | | | | 1002 | | | | | | | |
| Milrant | 8 | 9 | 6.8 | 468 | 348 | 2.2 | .96 | 118 | 42 | 30 | 38 | 59 | 150 | <.09 | _ | - | _ | _ | 10.7 | .8 | 22 |
| Huber Sod CoHo | me 9 | 25 | 6.8 | 466 | 344 | 5. | 1.0 | 124 | 38 | 30 | 42 | 59 | 150 | <.09 | _ | _ | - | _ | 10.9 | .9 | 25 |
| Jerry Baydan | 10 | 20 | 7.1 | 516 | 376 | 2.4 | .05 | 121 | | 8 | 1.6 | - | 140 | <.09 | - | - | _ | _ | 1.2 | <.1 | હ |
| Ron Sherman | ii | 1 | 7.1 | 586 | 386 | .31 | | 128 | 65 | 26 | 2.1 | 44 | 200 | <.09 | _ | _ | - | _ | 1.2 | .5 | Ğ |
| Henson Bone | 12 | 40 | 7.1 | 510 | 378 | 5.4 | .06 | 106 | 61 | 12 | 1.9 | હ | 150 | <.09 | _ | _ | - | _ | 2.9 | <.1 | Ğ |
| Methery Home | 13 | 70 | 7.7 | 8 | 372 | .35 | | <2 | ⟨2 | 180 | .2 | હ | 75 | <.09 | _ | _ | _ | _ | 1.7 | ₹.1 | હ |
| Ray Creekmar | 14 | 30 | 7.2 | • | 352 | 3.8 | .04 | 83 | 50 | 14 | 1.7 | 7 | 86 | <.09 | - | _ | _ | _ | 2.9 | ₹.1 | 3 |

(

aquifer beneath the site separated by a clay layer. It has been suggested in the literature that the clay layer is impermeable and continuous. However this has not been confirmed. Existing information indicates that the majority of the private water wells in the vicinity of the site use the lower aquifer as their water source. If the clay layer is impervious and continuous, then any contamination would be limited of the upper aquifer in which case a smaller number of private wells would be in danger of contamination. Obviously, if the clay layer is not impervious and continuous then both the aquifer and corresponding wells are at risk. In order to investigate the contamination of these groundwater receptors, monitoring wells will be installed during the remedial investigation. In addition, a survey of residential well water quality will be conducted during the remedial investigation.

Surface water in the vicinity of the site is limited to the marsh west of ACS property and a creek that flows through the marsh. This creek flows to Turkey Creek which is approximately one mile south of the ACS property. Contamination of these bodies of surace water would be from runoff from the ACS site or surface leachate from waste disposal sites. Existing records do not indicate any leachate runoff during the past three years. At the present time there is no surface water quality data available.

2.4.3 ENVIRONMENTAL AND PUBLIC HEALTH EFFECTS

Based on the available information, there appears to be a higher potential for public health effects than for environmental effects. This is based on the fact that there have been no visible environmental effects since the clay wall was installed around the north end of the ACS Off-site Containment Area during the early 1980's. Adverse environmental effects or surface leachate were not observed during this initial site visit.

The potential for environmental and public health effects due to surface water contamination is unknown. To date there is no data concerning surface water contamination.

There appears to be a higher potential for public health effects due to the contaminant migration found in Monitoring Well \$3 located to the southeast of the Off-site Containment Area. The degree of potential is based on whether or not the upper or lower aquifers are contaminated and the relative number of wells that tap into each aquifer.

As part of the remedial investigation a risk assessment will be conducted to more accurately define the potential for environmental and public health effects.

2.5 DISCUSSION OF DATA GAPS

The review of available data has provided the following information concerning the American Chemical Services, Inc. site including the Griffith Landfill and Kapica Drum, Inc. (now Pazmey Corp.).

- General information concerning geology and hydrogeology of the area from published studies and reports. Some site specific soils information is available from on-site soil borings and off-site well logs.
- 2. Specific information as to the types and quantities of wastes disposed of by ACS.
- 3. Non-specific information as the types and quantities of waste disposed of by Kapica Drum, Inc. Basically all that is known is that Kapica Drum, Inc. reconditioned drums containing hazardous and non-hazardous residues from ACS and other clients. It has been reported the drum reside and rinse water was disposed of on Kapica Drum property and ACS property. In addition this information is second hand since it was supplied by ACS, not Kapica Drum, Inc.
- 4. Specific information as to the types of waste disposed of by ACS at the Griffith Landfill. Non-specific information concerning the types of waste disposed of by Kapica Drum, Inc. at the Griffith Landfill. Again this is second hand information supplied by ACS.
- 5. Specific information concerning the location of known waste disposal on ACS property and areas of suspected soild contamination.
- 6. Non-specific information concerning the location of waste disposal on Griffith Landfill property.
- 7. Specific but limited data concerning on-site migration of hazardous wastes on ACS property. No data is available concerning hazardous waste migration from suspected disposal locations on Kapica Drum, Inc. or Griffith Landfill property.
- 8. Very limited data concerning waste migration outside of ACS, Kapica Drum, Inc. and Griffith Landfill property. In particular there is very little data concerning groundwater contamination.
- 9. Detailed information concerning property ownership was available however there is a question as to whether or not

part of the ACS Off-site Containment Area is on Griffith Landfill property.

The information needed to fill the gaps in the available data are as follows:

- 1. Concerning the on-site geology, information needed is:
 - a. Stratigraphy at the site determined by boreholes extending to bedrock.
 - Characterization of geotechnical, hydrological, and geological parameters of the soils and sediments on-site.
 - c. Confirmation of the given geological data including well logs and hydrogeologic data such as hydraulic conductivities and transmissivities.
 - d. Better definition of the water table configuration.
 - e. Better definition of the permeability, extent and continuity of the clay layer.
- 2. Specific information concerning the types and quantities of hazardous wastes disposed of by Kapica Drum, Inc. and accepted for disposal by the Griffith Landfill. In general more information concerning the hazardous waste activities of Kapica Drum, Inc. and Griffith Landfill is needed. A request for information similar to that sent to ACS by the U.S. EPA would provide useful information.
- 3. More detailed characterization of the waste on the ACS property as it exists now. All of the waste on ACS property has been buried 8-10 years. A more detailed characterization of all waste disposal sites is need from a health and safety standpoint and with regard to future remedial action alternatives. The details of the characterization will be contained in the Site Sampling and Analyses Plan.
- 4. More detailed evaluation of the extent of migration of hazardous wastes from the site. This includes the ACS, Kapica Drum, Inc. and Griffith Landfill property.
- 5. More detailed information concerning potential receptor contamination. Specifically, a survey of public water supplies should be conducted to determine those residents that use groundwater. It should also be determined which

aquifer they use and selected wells should be sampled and analyzed for hazardous waste components.

2.6 INITIAL REMEDIAL MEASURES

Based on the review of available information and the initial site visit, initial remedial measures are not considered warranted at this time. In the early 80's a clay containment wall was built around the north end of the ACS Off-site Containment Area where leachate had been observed. There was evidence at the Off-site Containment Area of heavy ground vegetation from the previous growing season. No leachate or any other alarming conditions were observed at the Off-site Containment Area or any other of the known disposal sites during the site visit.

One item of concern is the detection of benzene and acetone in the drinking water of a homeowner near the ACS site. Samples of six other nearby wells were found to be free of contaminants. As part of the remedial investigation one of the first tasks will be to conduct a detailed drinking water contamination survey of the area around the site. However it is recommended that the water from the homeowner be sampled again to provide verification of the previous data. If the contaminants are found again, an alternate water supply should be provided and the drinking water contamination survey should be implemented immediately.

During December 1984, the Region V Technical Assistance Team (TAT) conducted a site assessment for the American Chemical Services, Inc. site. Their findings are in concurrance that initial remedial measures are not necessary at this time. In their report it was also recommended that the contaminated well water be sampled and analyzed again.

In summary the preparation of a Limited Feasibility Study Memo is not considered necessary at this time. If resampling of the O'Neil well confirms the contamination, then the Limited Feasibility Study Memo should be prepared detailing the drinking water contamination survey and the options for alternative drinking water supplies.

S 9AM

