

# JAMES S. HARRIS

Contractor



P. O. BOX 6 • OFFICE & SHOP 1831 M-40 NORTH • PHONE AREA 616 - 673-4961 • ALLEGAN, MICHIGAN 49010

## ESTIMATE FOR BUILDING BERM AT DUMP SITE

We estimate it will take between 8000 and 10000 cyds of fill to build the berm around the dump area. The berm will be 40' wide and approximately 4' high from the original ground. We feel it necessary to get a good road around the berm, so it can be raised in height as needed. The price to haul spread and compact the fill dirt will be \$1.60 per cubic yard.

At the start of the berm, there will be some crane and dozer work to get it ready for truck hauling. The estimated cost for this work is \$1,000.00. dollars.

If it is possible to cast a berm up with the dragline crane, we estimate the cost to be from \$10,000 to \$12,000 dollars, as there will be dozer work to level the dirt out.

This berm should contain the paper waste for several years, then it can be raised higher to contain more, the eventual height could go to twenty feet. That is the reason for starting it at 40' wide.

*James S. Harris*