

[11.7.86]

K7

US EPA RECORDS CENTER REGION 5



466351

PRELIMINARY REPORT

Subsurface Soil Exploration

Griffith Sanitary Landfill

Griffith, Indiana

Prepared for:

Mr. Don Torrenge

Torrenge Engineering, Inc.  
Engineers & Surveyors  
907 Ridge Road  
Munster, IN 46321

EXHIBIT

C

**K&S**

# Testing and Engineering Inc.

9715 KENNEDY AVENUE

HIGHLAND, INDIANA 46322

PHONE: (219) 924-5231

Nov. 7, 1986

File No. 220

Torrenga Engineering, Inc.  
Engineers & Surveyors  
907 Ridge Road  
Munster, IN 46321

Attn: Mr. Don Torrenga

PRELIMINARY REPORT

Subsurface Soil Exploration  
Griffith Sanitary Landfill  
Griffith, Indiana


Dear Mr. Torrenga:


We have completed a preliminary subsurface exploration for the above referenced project. This exploration was performed in accordance with your verbal authorization.

This report includes a summary of our field exploration, site characterization and engineering analysis based on the soil borings. Additional work is underway to complete our assessment of the site and will be presented in a final report. In the enclosed topographical plot plan we are identifying the proposed locations for the monitoring wells.

We appreciate the opportunity to be of service to you on this. If you have any questions, please contact us.

Very truly yours,  
K & S Testing and Engineering, Inc.

  
Dibakar Sundi, P.E.  
Project Engineer

  
Petar Kostur, P.G.  
President

DS:PK/cac

• Soil Testing and Foundation Consultants •

Subsurface Soil Exploration  
Griffith Sanitary Landfill  
Griffith, Indiana

INDEX

Page

INTRODUCTION

Purpose	1
Background	1
Work Summary	1

SITE CHARACTERIZATION

General	2
Surface Conditions	2
Subsurface Conditions	2

SITE ASSESSMENT

General	6
Soil Properties	6
Migration Potential	6
Summary	7

ADDITIONAL WORK 8

REFERENCES 9

EXHIBITS

Nos.

Regional Site & Surface Topography	1
Regional Potentiometric Surface	2
Regional Rock Surface Contours	3
Physiographic Units	4

INDEX CONT.

EXHIBITS

	<u>Nos.</u>
Major Bedrock Structural Features	5
Typical Monitoring Well Details	6
Soil Boring Logs	7-9
Soil Test Data	10-11
Grain Size Diagram	12-15
Cation Exchange Test Results	16
Generalized Subsurface Profile	17
Topographical Plot Plan	18

## 1.0 INTRODUCTION

### 1.1 Purpose

This study was undertaken to assess the subsurface soil condition, assess the suitability of using new areas for placing fill within the existing landfill site.

The body of the report contains a summary of our field and laboratory activities and engineering assessments.

The field exploration procedures, boring logs and laboratory test data are attached with this report.

### 1.2 Background

We understand the landfill was opened in the 1950's, and has been in use since then. Additionally, we understand that this landfill is primarily used for sanitary waste disposal. Portions of this landfill have been filled and these areas are marked (Phase I through Phase IV) in the topographic plot plan.

### 1.3 Work Summary

Our field work consisted of drilling three (3) exploratory soil boring. In this report these borings are identified as Soil Borings 6, 7 and 8 or for brevity SB-6, SB-7 and SB-8. The soil borings were drilled with a CME-55, rotary drill rig, using 3.25 inch I.D. hollow-stem augers. Standard split-spoon penetration testing was performed as each boring was advanced to provide blow count data and soil samples for testing. During our drilling, the sampling was done continuously, to the entire boring depths. Ground water was observed and water levels recorded while drilling. At the completion of drilling at each location, the boreholes were grouted shut.

This field and laboratory work was combined with published geologic information and our experience to form the basis of this report.

## 2.0 SITE CHARACTERIZATION

### 2.1 General

The Griffith Sanitary Landfill site is located on the west side of Colfax Avenue. To the north, the landfill site is bounded by the C & O R. R. and to the south by the C & E R. R. The regional site location and topography are shown on Exhibit 1, which is the reproduction of the local U.S.G.S. topographic map.

### 2.2 Surface Conditions

The surface topography of the unused portions of the landfill area has a gentle slope or is flat. The filled area shown (Phase I through Phase IV) in the topographical plot plan (prepared by Torrenge Engineering, Inc.) is higher than the unused portions of the landfill site. There is an existing drainage ditch along the north side of the C & E R. R. A drainage ditch also exists on the south side of the C & O R. R. These two ditches are connected by a drainage ditch existing on the western portion of the landfill site. As shown in the topographic plot plan some excavations were recently made on the western portion near the C & E R. R.

The ground surface surrounding the landfill site is relatively flat with elevations around 630.0 feet, MSL. Locally, on the eastern edge of the site the surface topography is at a higher elevation. The site and the surface topography are shown in the USGS topographic map and are attached with this report.

### 2.3 Subsurface Conditions

#### 2.3.1 Basis

The data base for the subsurface conditions presented in this report is the field work conducted during this study, published geologic information, and prior subsurface explorations. Our interpretation of the subsurface conditions is based on interpolation and inference between widely spaced borings.

### 2.3.2 Site Geology

The site is formed of sediments deposited late during the Wisconsin Age as lake-bottom and near shore deposits of Glacial Lake Chicago. These sediments consist of fine lake silt and clay, sand and fine gravel laid down as glacial outwash and as till inclusions, and clay-rich till units of varying thickness. The site is a part of the Calumet Lacustrine Plain, which is a geologically heterogeneous area that has interlayered sand, lake clay, and till, forming the bulk of the sedimentary units. These sediments are water-laid sands and clays; the wind-blown dune sands being next in abundance. The deposits in a particular locality, whether wind or water-laid, sand or clay have very similar strength properties.

### 2.3.3 Soils

In summary, the undisturbed areas of this site have about a 12.0 to 14.0 foot thick layer of brown or gray fine to medium sand. This sand has been excavated in the area of Boring 6. Underlying the sand, we typically encountered a preconsolidated silty clay. The thickness of this clay layer was noted to be about 16.0 feet (extends between elevation 619.09 feet and 603.29 feet) in Boring 7 and about 23.0 feet thick (extends between elevations of 620.31 feet and 597.31 feet) in Boring 8. In Boring 6 the clay starts at the surface and it extends to a depth of 12.0 feet (elevation 611.55 to elevation 599.55 feet). Underlying, Boring 6 and 8 found alternate layers of sand and clay to the total depth of the borings. However, Boring 7 encountered gray sand beneath the clay layer which extended to the total boring depth of 54.5 feet; elevation 578.59 feet.

The ground water was noted in the upper sand layer. During our field drilling, ground water was noted at about 3.0 feet in Boring 8 and about 6.0 feet in Boring 7. Additionally, the sand samples obtained at deeper depths below the upper clay horizon were also wet.

### 2.3.4 Bedrock

Bedrock was not found at this site to the depth of drilling at 54.5 feet. However, published geologic information accounts for the consolidated rocks of Lake County, which consists of more than 4,000 feet of limestone, dolomite, sandstone, and shale of the Cambrian through Devonian Age, which rest on a

granitic basement that is designated Precambrian. The rocks constitute a series of strata that are relatively flat lying, but that are gently flexed to form a saddle like structure. This saddle, a part of the Kankakee Arch, rises between the Michigan Basin to the northeast and the Illinois Basin to the southwest. Structural dip, or inclination of the bedrock units, is generally southeastward, although the dip is northeastward in the northeast sector of Porter County. The average dip is about 5 to 7 feet per mile.

The bedrock surface which lies beneath 15 to 270 feet of unconsolidated glacial material, is largely a preglacial erosional feature and is not reflected by the present glacially derived land surface. The highest and coincidentally the shallowest area of bedrock lies under the Kankakee Plain in Southern Lake County. This bedrock high is part of a northeast-southwest trending ridge of Devonian limestone and shale in the southern part of the two counties. The surface drainage was northward from all but the south edge of the area. This bedrock ridge was the drainage divide. Bedrock elevation ranges from a low of about 450 feet above sea level near Lake Michigan to a high of about elevation 650 feet on the ridge in the south, under the Kankakee Plain. The bedrock surface elevation of our study site is expected to be within elevation of 500 to 550 feet, or within 80 to 130 feet below the existing site surface.

## 2.4 Hydrogeology

### 2.4.1 Regional Hydrogeology

The regional hydrogeology in the Lake County area can be typified by a thin upper mantle of water-bearing soils about 20 feet or so thick. The water source is primarily direct infiltration of precipitation and these deposits generally drain to the nearest waterway leading to the Calumet River and then to Lake Michigan. The area is fairly level and the natural drainage is low. The relatively recent urbanization has extensively modified the topography by creating ditches and drains.



Clayey glacial tills underlie these water-bearing soils and form an effective aquiclude. The till is a homogeneous mixture of sand, silt and clay with silt and clay size particles being the predominant particle size. These silt and clay size particles form a relatively impermeable soil matrix. Stratified drifts of coarser materials are present below the upper clayey till.

Underlying the till is the Devonian shale and limestone and Silurian dolomite and limestone and is considered to be a source of partial potable water supply. This bedrock aquifer is most productive, and it has the greatest water supply potential. Contamination from the surface is not as great in the shallow bedrock as it is in the unconsolidated system.

#### 2.4.2 Site Hydrogeology

The site hydrogeology is similar with the regional hydrogeology. In general, it consists of a layer of water-bearing sandy soils with a low ground water flow gradient, clayey glacial till, followed by coarser grained or clayey layered soils resting on bedrock.

We believe that the site ground water originates primarily from direct infiltration of rainfall. The existing ditches on the west and north of the site serve as a drainage from the site.

We believe, we penetrated the upper clayey till in the three borings completed during our fieldwork. We did not encounter any water-bearing silty or sandy seam and it was remarkably consistent, and correlates well with the regional hydrogeology. Grain sizes performed on the site clay show higher percentages of fines consisting of silt and clay size particles. Hydraulic conductivities were measured on two relatively undisturbed Shelby tube samples. The values were determined to be  $2.1 \times 10^{-8}$  cm/sec. and  $2.4 \times 10^{-8}$  cm/sec. This clay is very stiff to hard in consistency.

## 3.0 SITE ASSESSMENT

### 3.1 General

The presentation of our site assessment is organized to first consider the soil characteristics, both physical and geochemical. We then have discussed future migration potential.

The following assessment and our summary presented are based on the information contained in the report, our experience and engineering judgement.

### 3.2 Soil Properties

#### 3.2.1 Physical

The soil type at this site is well defined starting with outwash and eolian deposits of sandy soils in the upper layer, clayey till below it and again followed by sandy soils. In general the clayey till has low plasticity index, with moisture contents of about 15.0 to 18.0 percent range, about 90.0 percent fines and has a hydraulic conductivity in the order of  $10^{-8}$  cm/sec. The granular deposits can be expected to exhibit hydraulic conductivities in  $10^{-2}$  cms/sec. to  $10^{-4}$  cm/sec. range depending primarily on the percent of silt in the deposit.

#### 3.2.2 Geochemical

The cation exchange capacity testing was performed on the clayey till by Suburban Laboratories, Inc., Hillside, Illinois. The test results are typical of glacial deposits and are attached with this report.

### 3.3 Migration Potential

The significant aquiclude at this site is the clayey till found below the near surface water-bearing sandy soils. The clayey till appears continuous at this site and has lower hydraulic conductivity on the order of  $10^{-8}$  cm/sec. Also the lower water-bearing sandy soil appeared to be under an artesian head as evidenced during the field drilling operation of Boring 6. from which assumptions may be made that the clayey till is providing a significant protection against leachate infiltration to the deeper water-bearing soils.

The potential for surface or near surface horizontal migration at this site may be likely, unless provisions are made to contain the leachate or prevent it to flow horizontally away from the site.

#### 3.4 Summary

Based on available information, test results and findings as presented in this report, we conclude the following:

1. The soil conditions at this site generally conform with the published geologic and hydrogeologic information for the region.
2. The ground water in the near surface sandy deposit occur at a shallow depth from the surface.
3. It appears that the clayey till is serving as an effective confining aquifer, protecting the deeper water-bearing soils.

#### 4.0 ADDITIONAL WORK

Our additional work is currently underway at the landfill site in order to verify our site assessment and to develop additional information which could be used to develop a safe operational procedure of the landfill.

The additional work which has been proposed to be performed at this landfill includes the following:


1. Additional deep borings to further explore the continuity of the aquiclude.
2. Ground water monitoring wells to check for ground water quality and gradient.

## REFERENCES


1. Conversations with Torrenga Engineering, Inc.
2. Soil Borings, 1974 by Salisbury Engineering, Inc.
3. USGS Topographic Map, Department of Interior Geological Survey.
4. Foundation Engineering, Ralph B. Peck, Walter E. Hanson, and Thomas H. Thornburn.
5. Environmental Geology of Lake and Porter Counties, Indiana - An Aid to Planning, Edwin J. Hartke, John R. Hill, and Mark Reshkin, State of Indiana Department of Natural Resources, Geological Survey.

# K & S Testing and Engineering Inc.

1 Kennedy Ave. Highland, Indiana Phone: (219) 924-5231



**K & S Testing and Engineering Inc.**  
 15 Kennedy Ave. Highland, Indiana Phone: (219) 924-5231



**EXPLANATION**

— 660 —  
 Approximate potentiometric surface  
 in feet above mean sea level


— — — — —  
 North-south continental  
 drainage divide

Reference:  
 Environmental Geology of  
 Lake and Porter Counties, Indiana  
 Special Report 11.

Regional Potentiometric Surface  
 Griffith Sanitary Landfill  
 Griffith, Indiana  
**FILE 220 DATE 5/3/86**

## K &amp; S Testing and Engineering Inc.

15 Kennedy Ave. Highland, Indiana Phone: (219) 924-5231




## REFERENCE:

Environmental Geology of  
Lake and Porter Counties, Indiana  
Special Report 11.

Regional Rock Surface Contours  
Griffith Sanitary Landfill  
Griffith, Indiana

FILE 220 DATE 5/3/86





REFERENCE:

Environmental Geology of  
Lake and Porter Counties, Indiana  
Special Report 11.

Physiographic Units  
Griffith Sanitary Landfill  
Griffith, Indiana

FILE


220

DATE

5/3/86

## K &amp; S Testing and Engineering Inc.

715 Kennedy Ave. Highland, Indiana Phone: (219) 924-5231



## REFERENCE:


Environmental Geology of  
Lake and Porter Counties, Indiana  
Special Report 11.

Major Bedrock Structural Features  
Griffith Sanitary Landfill  
Griffith, Indiana

FILE 220

DATE 5/3/86

TYPICAL MONITORING WELL DETAILS



- |  |                   |
|--|-------------------|
|  | CONCRETE          |
|  | BENTONITE         |
|  | GRANULAR BACKFILL |
|  | WELL SCREEN       |

ENT Torrenga Engineering		LOG OF BORING NUMBER SB-6							
LOCATION Colfax Avenue, Griffith, Indiana		PROJECT NAME Griffith Sanitary Landfill							
DATE 01-29-86	RIG CME-55	FILE NUMBER 220	⊕ CALIBRATED PENETROMETER, TONS/FT. ○ UNCONFINED COMPRESSIVE STRENGTH, TONS/FT. ● WATER CONTENT PERCENT △ STANDARD PENETRATION, BLOWS/FT.						
DATE 01-29-86	FOREMAN D. Koditek								
SURFACE ELEVATION 611.55									
(Ft.)  DESCRIPTION OF MATERIAL	DEPTH (FT)	TYPE	RECOVERY	NUMBER	1	2	3	4	5
					10	20	30	40	50
					10	20	30	40	50
Very stiff gray silty clay. 2.5 5.0 7.5 10.0 12.5 15.0 17.5 20.0 22.5 25.0 Coarse gray sand. Very stiff gray silty clay. Fine to coarse gray sand. Very stiff gray silty clay. Medium dense gray fine to coarse sand. Very stiff gray silty clay. Fine to coarse gray sand.					1	●		△	
					2	●		△	
					3	●		△	
					4	●		△	
					5	●		△	
					6	●		△	
					7	●		△	
					8	●		△	
					9	●		△	
					10	●		△	
					11	●		△	
					12	●		△	
					13	●		△	
					14	●		△	84

Water Level

WATER LEVEL WHILE DRILLING 14.0 ft.

WATER LEVEL Artesian flow was noted after last sample was pulled out.

☐ SPLIT SPOON   
 ☒ SHELBY TUBE   
 ☒ AUGER   
 ☒ ROCK CORE

-PL - PLASTIC LIMIT   
 +LL - LIQUID LIMIT   
 γ<sub>u</sub> - UNIT DRY WEIGHT

**K & S TESTING AND ENGINEERING INC.**

9715 KENNEDY AVENUE  
HIGHLAND, INDIANA 46322

TELEPHONE: (219) 924-5231

CLIENT Korpena Engineering		LOG OF BORING NUMBER SB-7 (sheet 1)			
LOCATION Wolfax Avenue, Griffith, Indiana		PROJECT NAME Griffith Sanitary Landfill			
DATE 01-30-86	RIG CME-55	FILE NUMBER 220	⊕ CALIBRATED PENETROMETER, TONS/FT. ○ UNCONFINED COMPRESSIVE STRENGTH, TONS/FT. 1 2 3 4 5 ● WATER CONTENT PERCENT 10 20 30 40 50 △ STANDARD PENETRATION, BLOWS/FT. 10 20 30 40 50		
DATE 01-31-86	FOREMAN D. Koditek				
STRATA DEPTH (FT.)	SURFACE ELEVATION 633.09	DEPTH (FT.)	SAMPLE		
	DESCRIPTION OF MATERIAL		TYPE	RECOVERY	NUMBER
3.0	Medium dense dark brown fine to medium sand.	2.5	1	1	
7.0	Medium dense brown fine to medium sand.	5.0	2	2	
		7.5	3	3	
		10.0	4	4	
		12.5	5	5	
		15.0	6	6	
		17.5	7	7	
		20.0	8	8	
		22.5	9	9	
		25.0	10	10	
		27.5	11	11	
		30.0	12	12	
		32.5	13	13	
		35.0	14	14	
		37.5	15	15	
	Medium dense gray fine to medium sand.				
	Very stiff hard gray silty clay.				
WATER LEVEL WHILE DRILLING 6.0 ft. WATER LEVEL			<div style="text-align: center;">   <b>K &amp; S TESTING AND ENGINEERING INC.</b>          9715 KENNEDY AVENUE          HIGHLAND, INDIANA 46322          TELEPHONE: (219) 924-5231       </div>		
<div style="display: flex; justify-content: space-around;"> <span>⊔ SPLIT SPOON</span> <span>■ SHELBY TUBE</span> <span>Ⓐ AUGER</span> <span>▨ ROCK CORE</span> </div>					
<div style="display: flex; justify-content: space-around;"> <span>+PL - PLASTIC LIMIT</span> <span>+LL - LIQUID LIMIT</span> <span>γ<sub>d</sub> - UNIT DRY WEIGHT</span> </div>					

CLIENT Torrenga Engineering		LOG OF BORING NUMBER SB-7 (sheet 2)	
SITE LOCATION Colfax Avenue, Griffith, Indiana		PROJECT NAME Griffith Sanitary Landfill	
BORING STARTED 01-30-86	RIG CME -55	FILE NUMBER 220	<input checked="" type="checkbox"/> CALIBRATED PENETROMETER, TONS/FT. <input type="checkbox"/> UNCONFINED COMPRESSIVE STRENGTH, TONS/FT.
BORING COMPLETED 01-31-86	FOREMAN D. Koditek		
STRATA DEPTH (FT.)	SURFACE ELEVATION 633.09	DEPTH (FT.)	1 2 3 4 5 10 20 30 40 50 10 20 30 40 50
	DESCRIPTION OF MATERIAL	TYPE RECOVERY NUMBER	
29.8	Very stiff hard gray silty clay.	15	
		16	
		17	
		18	
	Dense gray fine to medium sand.	19	
		20	
		21	
		22	
		23	
		24	
		25	
		26	
		27	
47.5	Very dense gray fine to medium sand.	28	
		29	


  

▼ WATER LEVEL WHILE DRILLING 6.0 ft.

▼ WATER LEVEL

☒ SPLIT SPOON  
 ☒ SHELBY TUBE  
 ☒ AUGER  
 ☒ ROCK CORE


+PL - PLASTIC LIMIT  
 +LL - LIQUID LIMIT  
 *fc* - UNIT DRY WEIGHT



**K & S TESTING AND  
ENGINEERING INC.**

9715 KENNEDY AVENUE  
HIGHLAND, INDIANA 46322

TELEPHONE: (219) 924-5231

CLIENT Torrenga Engineering				LOG OF BORING NUMBER SB-7 (sheet 3)			
SITE LOCATION Colfax Avenue, Griffith, Indiana				PROJECT NAME Griffith Sanitary Landfill			
BORING STARTED 01-30-86		RIG CME-55		FILE NUMBER 220		<input checked="" type="radio"/> CALIBRATED PENETROMETER TONS/FT. <sup>2</sup> <input type="radio"/> UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup>	
BORING COMPLETED 01-31-86		FOREMAN D. Koditek		SAMPLE		1      2      3      4      5 <input checked="" type="radio"/> WATER CONTENT PERCENT 10      20      30      40      50 <input type="radio"/> STANDARD PENETRATION, BLOWS/FT. 10      20      30      40      50	
STRATA DEPTH (FT.)	SURFACE ELEVATION 633.09	DESCRIPTION OF MATERIAL	DEPTH (FT.)	TYPE	RECOVERY	NUMBER	
54.5		Very dense gray fine to medium sand.	52.5	/	/	29 30 31	102 <input type="radio"/> 80 <input type="radio"/> 54 <input type="radio"/>
		END OF BORING					
WATER LEVEL WHILE DRILLING 6.0 ft. WATER LEVEL				 <b>K &amp; S TESTING AND ENGINEERING INC.</b> 9715 KENNEDY AVENUE HIGHLAND, INDIANA 46322 TELEPHONE: (219) 924-5231			
<input checked="" type="checkbox"/> SPLIT SPOON <input checked="" type="checkbox"/> SHELBY TUBE <input checked="" type="checkbox"/> AUGER <input checked="" type="checkbox"/> ROCK CORE +PL - PLASTIC LIMIT            +LL - LIQUID LIMIT <i>fu</i> - UNIT DRY WEIGHT							

CLIENT Torrenga Engineering		LOG OF BORING NUMBER SE-8 (sheet 1)			
SITE LOCATION Colfax Avenue, Griffith, Indiana		PROJECT NAME Griffi.			
BORING STARTED 01-31-86	RIG CME-55	FILE NUMBER 220		TONS/FT. <sup>2</sup>	
BORING COMPLETED 02-03-86	FOREMAN D. Koditek			LENGTH	
STRATA DEPTH (FT.)	SURFACE ELEVATION 632.61	DEPTH (FT.)	TYPE RECOVERY	SAMPLE NUMBER	WATER C STANDARD PENE
	DESCRIPTION OF MATERIAL				
1.5	Mixed black & brown sand fill.	2.5	2	1	Water Level 
12.3	Medium dense gray fine to medium sand.	5.0	3	10	
		7.5	4	20	
		10.0	5	30	
		12.5	6	40	
		15.0	7	50	
		17.5	8	60	
		20.0	9	70	
		22.5	10	80	
			11	90	
			12	100	
	13	110			
	14	120			
	15	130			
	Very stiff to hard gray silty clay.				

▼ WATER LEVEL WHILE DRILLING 3.0 ft.

▼ WATER LEVEL

☐ SPLIT SPOON   
 ☒ SHELBY TUBE   
 ☐ AUGER   
 ☒ ROCK CORE


+PL - PLASTIC LIMIT   
 +LL - LIQUID LIMIT   
 *fc* - UNIT DRY WEIGHT

**K & S TESTING AND ENGINEERING INC.**

9715 KENNEDY AVENUE  
HIGHLAND, INDIANA 46322

TELEPHONE: (219) 924-5231



CLIENT Torrenga Engineering		LOG OF BORING NUMBER SB-8 (sheet 2)	
SITE LOCATION Colfax Avenue, Griffith, Indiana		PROJECT NAME Griffith Sanitary Landfill	
BORING STARTED 01-31-86	RIG CME-55	FILE NUMBER 220	<input checked="" type="checkbox"/> CALIBRATED PENETROMETER, TONS/FT. <input type="checkbox"/> UNCONFINED COMPRESSIVE STRENGTH, TONS/FT.
BORING COMPLETED 02-03-86	FOREMAN D. Koditek		
STRATA DEPTH (FT.)	SURFACE ELEVATION 632.61	DEPTH (FT.)	SAMPLE TYPE RECOVERY NUMBER 1 2 3 4 5 ● WATER CONTENT PERCENT 10 20 30 40 50 △ STANDARD PENETRATION, BLOWS/FT. 10 20 30 40 50
	DESCRIPTION OF MATERIAL		
	Very stiff to hard gray silty clay.	15	
		27.5	
		16	
		17	
		30.0	
		18	
		32.5	
		19	
		20	
35.3		35.0	
36.0	Medium dense gray fine to coarse sand.	21	
		37.5	
	Very stiff gray silty clay.	22	
		23	
		40.0	
		24	
		42.5	
43.5		25	
44.0	Medium dense fine to medium sand, wet	26	
	Very stiff gray silty clay.	27	
47.0		47.5	
	Dense gray fine to medium sand, wet.	28	
		29	
▼ WATER LEVEL WHILE DRILLING 3.0 ft. ▼ WATER LEVEL		 <b>K &amp; S TESTING AND ENGINEERING INC.</b> 9715 KENNEDY AVENUE HIGHLAND, INDIANA 46322 TELEPHONE: (219) 924-5231	
<input checked="" type="checkbox"/> SPLIT SPOON <input checked="" type="checkbox"/> SHELBY TUBE <input checked="" type="checkbox"/> AUGER <input checked="" type="checkbox"/> ROCK CORE +PL - PLASTIC LIMIT    +LL - LIQUID LIMIT <i>fc</i> - UNIT DRY WEIGHT			

<b>CLIENT</b> Torrenga Engineering		<b>LOG OF BORING NUMBER</b> SB-8 (sheet 3)						
<b>SITE LOCATION</b> Colfax Avenue, Griffith, Indiana		<b>PROJECT NAME</b> Griffith Sanitary Landfill						
<b>BORING STARTED</b> 01-31-86	<b>RIG</b> CME-55	<b>FILE NUMBER</b> 220	<div style="display: flex; justify-content: space-between;"> <div> <input checked="" type="checkbox"/> CALIBRATED PENETROMETER TONS/FT.  <input type="checkbox"/> UNCONFINED COMPRESSIVE STRENGTH TONS/FT.           </div> <div>             1    2    3    4    5           </div> </div>					
<b>BORING COMPLETED</b> 02-03-86	<b>FOREMAN</b> D. Koditek							
<b>STRATA DEPTH (FT.)</b>	<b>SURFACE ELEVATION</b> 632.61	<b>DEPTH (FT.)</b>	<b>SAMPLE</b>	<b>WATER CONTENT PERCENT</b>				
	<b>DESCRIPTION OF MATERIAL</b>			10    20    30    40    50				
				<b>STANDARD PENETRATION, BLOWS/FT.</b>				
				10    20    30    40    50				
54.5	Dense gray fine to medium sand, wet.	29 30 52.5 31	TYPE RECOVERY NUMBER	<div style="display: flex; justify-content: space-between;"> <div> <input type="checkbox"/> 10  <input type="checkbox"/> 20  <input type="checkbox"/> 30  <input type="checkbox"/> 40  <input type="checkbox"/> 50           </div> <div style="text-align: right;">             69           </div> </div>				
	END OF BORING							

☒ **WATER LEVEL WHILE DRILLING** 3.0 ft.  
☒ **WATER LEVEL**

☒ SPLIT SPOON   
 ☒ SHELBY TUBE   
 ☒ AUGER   
 ☒ ROCK CORE

+PL - PLASTIC LIMIT   
 +LL - LIQUID LIMIT   
 *fu* - UNIT DRY WEIGHT

**K & S TESTING AND ENGINEERING INC.**  
 9715 KENNEDY AVENUE  
 HIGHLAND, INDIANA 46322  
 TELEPHONE: (219) 924-5231

## SOIL TEST DATA

PROJECT Griffith LandfillCITY OR COUNTY Griffith, IN

LAB NO.	220-1	220-2	220-3
LOCATION	3" Shelby tube 3' South of Boring 6	3" Shelby tube 5' SE of Boring 6	Boring 6
DEPTH (feet)	0.0 - 1.5	0.0 - 1.5	5.5 - 7.0
GRAIN SIZE CLASSIFICATN	Gray silty clay (CL)	Gray silty clay (CL)	Gray silty clay (CL)
PASSING 1" SIEVE %			
3/4" " %			
1/2" " %			
No 4 " %	100.0	100.0	100.0
No 10 " %	99.2	99.2	99.3
No 40 " %	95.7	95.7	96.2
No 100 " %	92.9	92.9	93.1
No 200 " %	90.8	90.8	90.2
GRAVEL %			
SAND %	9.0	9.0	10.0
FINES (silt & clay) %	91.0	91.0	90.0
LIQUID LIMIT %	32.0	32.0	31.0
PLASTIC LIMIT %	19.0	19.0	17.0
PLASTICITY INDEX %	13.0	13.0	14.0
DRY DENSITY PCF	116.2	107.1	
PROCTOR DENSITY PCF			
OPTIMUM MOISTURE %			
PERCENT DENSITY %			
COEFF. OF PERMEABL cm/sec	$2.1 \times 10^{-8}$	$2.4 \times 10^{-8}$	

REMARKS:

## SOIL TEST DATA


PROJECT Griffith LandfillCITY OR COUNTY Griffith, IN

LAB NO.	220-4	220-5	
LOCATION	Boring 7	Boring 8	
DEPTH	16.0 - 17.5	21.0 - 23.0	
GRAIN SIZE CLASSIFICATN	Gray silty clay (CL)	Gray silty clay (CL)	
PASSING 1" SIEVE %			
3/4" " %			
1/2" " %	100.0	100.0	
No 4 " %	99.2	99.5	
No 10 " %	98.6	98.3	
No 40 " %	96.2	96.3	
No 100 " %	92.8	93.5	
No 200 " %	90.7	91.5	
GRAVEL %	1.0	1.0	
SAND %	8.0	8.0	
FINES (silt & clay) %	91.0	91.0	
LIQUID LIMIT %	31.0	29.0	
PLASTIC LIMIT %	19.0	17.0	
PLASTICITY INDEX %	12.0	12.0	
DRY DENSITY PCF			
PROCTOR DENSITY PCF			
OPTIMUM MOISTURE %			
PERCENT DENSITY %			
COEFF. OF PERMEABL cm/sec			

REMARKS:


K&amp;S TESTING &amp; ENGINEERING INC.

## GRAIN SIZE DIAGRAM



K&amp;S TESTING &amp; ENGINEERING INC.


## GRAIN SIZE DIAGRAM





K&amp;S TESTING &amp; ENGINEERING INC.

## GRAIN SIZE DIAGRAM





# SUBURBAN LABORATORIES, Inc.

EXHIBIT 16

4140 LITT DRIVE

HILLSDALE, ILLINOIS 60162 - 1183

ARL I. ROSENBERG  
President

May 6, 1986

H.R. THOMAS, JR.  
Director

K & S Testing and Engineering Inc.  
9715 Kennedy Avenue  
Highland, Indiana 46322

Attention: Mr. Dibakar Sundi,  
Project Engineer

S les Received: 4/29/86

Cation Exchange  
(meq/100g)

Soil Samples / Griffith Landfill


S/L #6-4558 - Sample #1, Depth 0 - 2.0 ft.

5.64

S/L #6-4559 - Sample #2, Depth 2 - 3.5 ft.

5.55

ANALYSIS CERTIFIED BY:



, Director (HRT/ak)

BORING NO.

SB-7

SB-4

ELEV.  
(ft.)

633.09

630.5

640

630

Water  
Level

620

610

600

590

580

570

MEDIUM DENSE BROWN FINE TO COARSE SAND

MEDIUM DENSE GRAY FINE TO MEDIUM SAND

VERY STIFF TO HARD GRAY SILTY CLAY

DENSE GRAY FINE TO MEDIUM SAND

VERY DENSE GRAY FINE TO MEDIUM SAND

SCALE

HORIZONTAL: 1" = 75'



VERTICAL: 1" = 20'

SB-3

SB-8

627.5

632.61



SITE PLAN

GENERALIZED SUBSURFACE  
PROFILE THRU SECTION A-A  
GRIFFITH SANITARY LANDFILL