

Exhibit B
Scope of Work and Schedule

1) RI Work Plan

Elements of the RI Work Plan will include the following:

- Project management strategy including personnel and responsibilities;
- Review of existing and available data (site conceptual model) to support development of RI tasks which may include, as appropriate, the following:
 - Physical features, including topography and bathymetry, structure locations, and utilities
 - Hydrogeologic data
 - Soil, surface water, and groundwater data
 - Sediment chemical and biological data
 - Proposed cleanup levels for all media
 - Sediment dynamics data including current, waves, and sedimentation rates
 - Natural resource data including plant and animal species, habitat types, and sensitive ecosystems
 - Location and composition of current and historical contaminant sources including stormwater and industrial discharges
 - Current property ownership and zoning
 - List of potential permits or approvals that may be required for sampling activities or the substantive requirements of applicable permits or approvals that are procedurally exempt under RCW 70.105D.090
- Data gaps identified for completion under the RI
- Proposed approach for fate and transport analysis
- Draft outline of the final RI Report including the types of data evaluation, figures, and tables to be included
- A proposed schedule for completion of all RI subtasks not currently accounted for in the schedule

2) Other Project Plans

- A Sampling and Analysis Plan (SAP).
- A Quality Assurance Project Plan (QAPP) , which will be submitted as an appendix to the SAP
- A Health and Safety Plan (HASP), which will be submitted as an appendix to the SAP.

3) Remedial Investigation

The RI will address the following:

- Nature and extent of contamination in soil, groundwater, surface water, and sediments
- Identification of source(s) for contamination
- Contaminant fate and transport processes
- Assessment of potential human health and ecological health concerns

4) Progress Reports

Progress reports will contain the following information:

- Description of the actions taken to comply with the Order and the SOW during the reporting period
- Summaries of sampling and testing reports and other data reports received by the parties
- Summaries of deviations from approved Work Plans
- Summaries of contacts with representatives of the local community, public interest groups, press, federal, state, or tribal government
- Summaries of problems or anticipated problems in meeting the schedule or objectives set forth in the SOW and the Work Plan
- Summaries of solutions developed and implement or planned to address any actual or anticipated problems or delays
- Changes in key personnel
- Description of work planned for the next reporting period

5) Schedule

<u>RI Action</u>	<u>Completion Time (after effective date of Order)</u>
Draft RI Work Plan	90 days
Draft SAP, QAPP, HASP	90 days
Final RI Work Plan	45 days after receipt of Ecology comments on draft
Final SAP, QAPP, HASP	45 days after receipt of Ecology comments on draft
Draft RI Report	120 days after completion of RI work, including receipt of final laboratory data
Draft RI incorporating Ecology comments	60 days after receipt of Ecology comments
Final RI Report	30 days after close of public comment period