



INDUSTRIAL TESTING LABORATORIES inc.

2350 Seventh Blvd.

St. Louis, Missouri 63104

Chemists

Engineers

Metallurgists

314/771-7111

THIS IS OUR
65TH
ANNIVERSARY

Report No. 88-06-5203

June 28, 1988

P.O. #: 9596

Determination of fiber content on three (3) bulk insulation samples submitted.

Clayco Construction Company
462 Summit Avenue
St. Louis, MO 63042

Attn: Mr. Mike Pinson

Test Report

<u>Sample Identification</u>	<u>I.T.L. No.</u>	<u>Fiber Content</u>
#1	116727	1-3% asbestos, chrysotile
#2	116728	5-10% asbestos, chrysotile
#3	116729	5-10% asbestos, chrysotile

Samples with concentrations reported as 1-3% asbestos or greater have been evaluated as positive and therefore, by EPA definition, are asbestos containing materials (ACM).

Industrial Testing Laboratories is accredited by the United States Environmental Protection Agency for the analysis of asbestos in bulk samples. (No. 7355)

Tests were performed using Polarized Light Microscopy and Dispersion Staining in accordance with "Interim Method for the Determination of Asbestos in Bulk Insulation Samples", EPA-600/M4-82-020.

07KF



Superfund

4.2

0400

Lab No. 116727-116729
L.B. 27990
JK/bc

Respectfully submitted,

William J. Lowry
William J. Lowry, Manager
Environmental Lab

Inv. # 21696

INVOICE

21815

INDUSTRIAL

COMPANY NAME

CLAYCO CONSTRUCTION COMPANY
314-731-8181

No. 63988

80-459
810

DATE 7/15/88

PAY EXACTLY *****418*DOLLARS*AND*75*CENTS

AMOUNT *****418.75

INDUSTRIAL TESTING LABS

CENTRAL DEPOSITORY ACCOUNT

TO
THE
ORDER
OF2350 SEVENTH BLVD
ST LOUIS, MO

63104

FILE COPY

COMMERCE BANK OF ST. LOUIS, NA
ST. LOUIS, MISSOURI

NON-NEGOTIABLE

AUTHORIZED SIGNATURE

REMITTANCE ADVICE - PLEASE DETACH BEFORE DEPOSITING

CLAYCO CONSTRUCTION COMPANY

314-731-8181

INVOICE NUMBER	INVOICE DATE	DESCRIPTION	GROSS	DISCOUNT	NET
21815	6/29/88		262.50		262.50
21696	6/29/88		156.25		156.25

** TOTAL **

418.75

418.75


Director

Lab No. 116730
L.B. 26136
JWS/gmd

Inv. #21815

INVOICE

21815



**INDUSTRIAL
TESTING
LABORATORIES
inc.**

2350 Seventh Blvd. • St. Louis, Missouri 63104

Chemists

Engineers

Metallurgists

314/771-7111

Clayco Construction Company
462 Summit Avenue
St. Louis, MO 63042

DATE June 29, 1988

REPORT NO. 88-06-5204

Attn: Mr. Mike Pinson

15
TERMS: NET ~~30~~ DAYS

PURCHASE ORDER NO.

PROFESSIONAL SERVICES:

Examination of one (1) soil sample submitted marked, "#4". \$ 262.50
(RUSH ANALYSIS)

19/gmd

We hereby certify that these goods were produced in compliance with all applicable requirements of sections 6, 7 and 12 of the Fair Labor Standards Act, as amended, and of regulations and orders of the United States Department of Labor issued under Section 14 thereof.

KINDLY REMIT FROM THIS INVOICE. NO MONTHLY STATEMENTS ARE ISSUED.

INDUSTRIAL
TESTING
LABORATORIES
inc.

2350 Seventh Blvd.

• St. Louis, Missouri 63104

Chemists

Engineers

Metallurgists

314/771-7111

Report No. 88-06-5204

June 29, 1988

Examination of one (1) soil sample submitted marked, "#4".

Clayco Construction Company
462 Summit Avenue
St. Louis, MO 63042

Attn: Mr. Mike Pinson

TEST REPORT

PCB's, *% by weight

1.3

*
as Aroclor 1260.

Respectfully submitted,

Allan M. Siegel

Allan M. Siegel, P.E.
Director

Lab No. 116730
L.B. 26136
JWS/gmd

Inv. #21815

INVOICE

21696



INDUSTRIAL TESTING LABORATORIES inc.

2350 Seventh Blvd. • St. Louis, Missouri 63104

Chemists
Engineers
Metallurgists

314/771-7111

Clayco Construction Company
462 Summit Avenue
St. Louis, MO 63042

DATE June 29, 1988

REPORT NO. 88-06-5203

Attn: Mr. Mike Pinner
~~TERMS: NET 30 DAYS~~ NET 15 DAYS

PURCHASE ORDER NO. 9596

PROFESSIONAL SERVICES:

Determination of fiber content on three (3) bulk insulation
samples submitted.

24 hour Rush 1 @ \$68.75 \$ 68.75

24 hour Rush 2 @ \$43.75 \$ 87.50

Total Due \$ 156.25

012/bc

We hereby certify that these goods were produced in compliance with all applicable requirements of sections 6, 7 and 12 of the Fair Labor Standards Act, as amended, and of regulations and orders of the United States Department of Labor issued under Section 14 thereof.

KINDLY REMIT FROM THIS INVOICE. NO MONTHLY STATEMENTS ARE ISSUED.