



MACT Emissions Test Report

**University of Iowa
Oakdale Renewable Energy Plant
Hurst Boiler Exhaust Duct
Coralville, Iowa
November 4 and 5, 2014**


**Report Submittal Date
December 8, 2014**

© Copyright 2014
All rights reserved in
Mostardi Platt

Project No. M144705

TABLE OF CONTENTS

1.0 EXECUTIVE SUMMARY	1
2.0 TEST METHODOLOGY	2
Method 1 Traverse Point Determination.....	2
Stratification Test for Gaseous Sampling	2
Method 2 Volumetric Flow Rate Determination.....	2
Method 3A Oxygen (O ₂)/Carbon Dioxide (CO ₂) Determination.....	3
Method 4 Moisture Determination	3
Method 7E Nitrogen Oxide (NO _x) Determination	3
Method 10 Carbon Monoxide (CO) Determination	3
Method 5 Filterable Particulate Matter (FPM) Determination	4
Method 26 Hydrogen Chloride (HCl) Determination.....	4
Mercury Determination by Method 30B (Sorbent Trap Method)	4
3.0 TEST RESULT SUMMARIES	5
4.0 CERTIFICATION.....	7
APPENDIX	
Appendix A - Plant Operating Data	9
Appendix B - Test Section Diagrams.....	11
Appendix C - Sample Train Diagrams.....	16
Appendix D - Calculation Nomenclature and Formulas	24
Appendix E - Laboratory Data	41
Appendix F - Reference Method Test Data (Computerized Sheets).....	60
Appendix G - Field Data Sheets	83
Appendix H - Calibration Data	114
Appendix I - Gas Cylinder Calibration Sheets	147
Appendix J – Mercury QA/QC Data.....	157



1.0 EXECUTIVE SUMMARY

MOSTARDI PLATT conducted a MACT emissions test program for University of Iowa at the Oakdale Renewable Energy Plant in Coralville, Iowa on the Hurst Boiler Exhaust Duct on November 4 and 5, 2014. This report summarizes the results of the test program and test methods used.

The test location, test dates, and test parameters are summarized below.

TEST INFORMATION		
Test Location	Test Dates	Test Parameters
Hurst Boiler Exhaust Duct	November 4 and 5, 2014	Filterable Particulate Matter (FPM), Nitrogen Oxides (NO _x), Carbon Monoxide (CO), Mercury (Hg), and Hydrogen Chloride (HCl)

Selected results of the test program are summarized below. A complete summary of emission test results follows the narrative portion of this report.


TEST RESULTS					
Test Location	Date	Test Parameter	MACT Emission Limits	Permitted Emission Limits	Emission Rates
Hurst Boiler Exhaust Duct	11/4/14	FPM	0.03 lb/mmBtu		0.0018 lb/mmBtu
		HCl	0.022 lb/mmBtu		0.0003 lb/mmBtu
	11/5/14	Hg	0.8 lb/TBtu		0.6284 lb/TBtu
		NO _x		4.13 lb/hr	2.09 lb/hr
		CO	620 ppm @ 3% O ₂		8.1 ppm @ 3% O ₂
				4.13 lb/hr	0.13 lb/hr

A standard Fd-Factor of 9,240 dscf/mmBtu for wood was used to calculate emissions on lb/mmBtu and lb/TBtu basis. The unit tripped during the third run on November 5, 2014 and testing was not completed for NO_x, CO, and Hg. Values for the data collected are shown in the tables in Section 3.0 but were not included in the average emissions due to the lack of post-test calibrations for the gas constituents. Mostardi Platt was unable to calculate a valid Hg lb/mmBtu emissions value for Run 3. In addition, the Method 30B spiked trap concentrations were assumed from previous testing but were not within the proper range for Runs 1 and 2.

The Stationary Source Audit Sample Program audit sample was obtained and submitted for analysis to Maxxam Analytics. The results of that audit sample were compared to the assigned value by ERA and found to be acceptable. The audit sample results and evaluation are appended to this report.

Operating data as provided by the University of Iowa are included in Appendix A.

The identification of individuals associated with the test program is summarized below.



TEST PERSONNEL INFORMATION		
Location	Address	Contact
Test Coordinator	The University of Iowa Oakdale Renewable Energy Plant Oakdale Campus Coralville, Iowa 52319	Mr. Mark Maxwell Environmental Engineer (319) 335-6185 (phone) mark-maxwell@uiowa.edu
Testing Company Representative	Mostardi Platt 888 Industrial Drive Elmhurst, Illinois 60126	Mr. Daniel E. Tuider Project Manager (630) 993-2100 (phone) dtuider@mp-mail.com

The test crew consisted of Messrs. J. Keable, S. McGough, and D. Tuider of Mostardi Platt.

2.0 TEST METHODOLOGY

Emission testing was conducted following the methods specified in 40CFR60, Appendix A. Schematics of the test section diagrams and sampling trains used are included in Appendix B and C, respectively. Calculation nomenclature and example calculations are included in Appendix D. Appendix E includes laboratory sample analysis. Copies of reference method data sheets and field data sheets for each test run are included in Appendix F and G.

The following methodology was used during the test program:

Method 1 Traverse Point Determination

Test measurement points were selected in accordance with Method 1. The characteristics of measurement location are summarized below.


TEST POINT INFORMATION				
Location	Upstream Diameters	Downstream Diameters	Test Parameter	Number of Sampling Points
Hurst Boiler Exhaust Duct	>0.5	>2.0	FPM, Volumetric Flow	25
			NO _x and CO	20
			Hg	3
			HCl	1

Stratification Test for Gaseous Sampling

A 20 point gaseous stratification test was performed during Run 1 on November 5, 2014. All of the results were greater than 10 % difference and consequently 20 points were used for Runs 2 and 3 (partial run).

Method 2 Volumetric Flow Rate Determination

Gas velocity was measured following Method 2, for purposes of calculating exhaust gas volumetric flow rate and emission rates on a lb/hr basis. An S-type pitot tube, differential pressure gauge, thermocouple and temperature readout were used to determine gas velocity at each sample point. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.



Method 3A Oxygen (O_2)/Carbon Dioxide (CO_2) Determination

CO_2 and O_2 concentrations were measured to determine exhaust gas molecular weight in accordance with Method 3A. A Servomex analyzer was used to determine stack gas O_2 and CO_2 content and, by difference, nitrogen content. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H and copies of gas cylinder certifications are included in Appendix I.

Method 4 Moisture Determination

USEPA Method 4 was utilized to determine water (H_2O) content of the exhaust gas. 100 milliliters (ml) of water were added to each of the first two impingers, the third impinger was left empty, and the fourth impinger was charged with approximately 200 grams of silica gel. The impingers were placed in an ice bath to maintain the sampled gas passed through the silica gel impinger outlet below 68°F in order to increase the accuracy of the sampled dry gas volume measurement. The water volumes of the impinger train were measured and the silica gel was weighed before and after each test run to determine the mass of moisture condensed.

Each sample was extracted through a heated stainless-steel probe and filter assembly at a constant sample rate of approximately 0.75 cubic feet per minute, which was maintained throughout the course of the test run. A minimum of 21 dry standard cubic feet (dscf) are sampled for, each moisture run. After each run, a leak check of the sampling train was performed at a vacuum greater than the sampling vacuum to determine if any leakage had occurred during sampling. Following the leak check, the impingers were removed from the ice bath, water levels were measured, and the silica gel weight was recorded.

All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.

Method 7E Nitrogen Oxide (NO_x) Determination

Exhaust gas nitrogen oxide concentrations and emission rates were determined in accordance with Method 7E. A Thermo Scientific 42 Series nitrogen oxide analyzer was used to determine nitrogen oxide concentrations, in the manner specified in the Method.


Exhaust gas was delivered to the analyzer via a Teflon® sampling line, heated to a minimum temperature of 250°F. Excess moisture in the exhaust gas was removed using a refrigerated condenser. The entire system was calibrated in accordance with the Method, using certified calibration gases introduced at the probe, before and after each test run.

A list of calibration gases used and the results of all calibration and other required quality assurance checks can be found in Appendix H. Copies of gas cylinder certifications are included in Appendix I.

Method 10 Carbon Monoxide (CO) Determination

Exhaust gas carbon monoxide concentrations and emission rates were determined in accordance with Method 10. A Thermo Scientific 48 Series carbon monoxide analyzer was used to determine carbon monoxide concentrations, in the manner specified in the Method.

Exhaust gas was delivered to the analyzer via a Teflon® sampling line, heated to a minimum temperature of 250°F. Excess moisture in the exhaust gas was removed using a refrigerated condenser. The entire system was calibrated in accordance with the Method, using certified calibration gases introduced at the probe, before and after each test run.



A list of calibration gases used and the results of all calibration and other required quality assurance checks can be found in Appendix H. Copies of gas cylinder certifications are included in Appendix I.

Method 5 Filterable Particulate Matter (FPM) Determination

Exhaust gas FPM concentrations and emission rates were determined in accordance with Method 5. An Environmental Supply Company sampling train was used to sample stack gas at an isokinetic rate, as specified in the Method. Particulate matter in the sample probe was recovered using an acetone wash. The probe wash and filter catch were analyzed by Mostardi Platt in accordance with the Method. Laboratory analysis data are included in Appendix D. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.

Method 26 Hydrogen Chloride (HCl) Determination


Exhaust gas Hydrogen Chloride (HCl) concentration and emission rates were determined in accordance with Method 26. An Environmental Supply Company, Inc. sampling train was used to collect the sample. A single-point sample was extracted from the gas stream and passed through dilute (0.1 N) sulfuric acid. In the dilute acid, the HCl dissolved and formed chloride (Cl⁻) ions. The sample train consisted of a Teflon® filter placed on the outlet of a heated borosilicate glass probe liner and five impingers. The first two impingers contained the dilute sulfuric acid, the third and fourth impingers contained a 0.1 N sodium hydroxide (NaOH), and the fifth impinger contained silica gel to absorb any remaining moisture. A DI rinse was performed on each set of impingers, and samples were stored in nalgene sample containers for transport. The dilute sulfuric acid samples were then analyzed for HCl by Maxxam Analytics, Inc. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H.

Mercury Determination by Method 30B (Sorbent Trap Method)

Paired trains were utilized using three test points.

Per Method 30B sampling, each sample was collected on the paired in-situ sorbent traps. A tube of silica was used to capture remaining moisture prior to the sample reaching the gas metering system.

The sample train used for this test program was designed by APEX, Inc. and meets all requirements for Method 30B sampling. Samples were analyzed onsite utilizing an Ohio Lumex, Inc. analyzer for total gaseous mercury. All of the equipment used was calibrated in accordance with the specifications of the Method. Calibration data are presented in Appendix H. Mercury quality assurance and control data are found in Appendix J.



3.0 TEST RESULT SUMMARIES


Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Test Location: Hurst Boiler Exhaust Duct
Test Method: 5

Source Condition	Normal	Normal	Normal
Date	11/4/14	11/4/14	11/4/14
Start Time	8:35	11:30	14:15
End Time	11:05	13:47	16:32
	Run 1	Run 2	Run 3
			Average
Stack Conditions			
Average Gas Temperature, °F	358.2	364.5	373.9
Flue Gas Moisture, percent by volume	13.2%	14.9%	14.7%
Average Flue Pressure, in. Hg	29.64	29.64	29.64
Gas Sample Volume, dscf	77.462	78.437	75.223
Average Gas Velocity, ft/sec	11.274	11.466	11.107
Gas Volumetric Flow Rate, acfm	13,022	13,243	12,828
Gas Volumetric Flow Rate, dscfm	7,227	7,152	6,863
Gas Volumetric Flow Rate, scfm	8,325	8,402	8,047
Average %CO ₂ by volume, dry basis	11.6	11.4	11.8
Average %O ₂ by volume, dry basis	8.9	9.1	8.8
Isokinetic Variance	99.7	102.1	102.0
Standard Fd Factor, dscf/mmBtu	9,240.0	9,240.0	9,240.0
Filterable Particulate Matter (Method 5)			
grams collected	0.0046	0.0047	0.0023
grains/acf	0.0005	0.0005	0.0003
grains/dscf	0.0009	0.0009	0.0005
lb/hr	0.057	0.057	0.028
Ib/mmBtu (Standard Fd Factor)	0.0021	0.0022	0.0011
			0.0018

HCI Test Results Summary
 University of Iowa
 Oakdale Renewable Energy Plant
 Hurst Boiler Exhaust Duct

Run No.	Location	Date	Time	Meter Volume, dscf	O ₂ , % dry	HCI detected, mg*	HCI Concentration ppmvd	Fd Factor	HCI lbs/MMBtu
1	Stack	11/4/2014	8:55-9:55	4.17	8.90	0.053	0.30	9240.0	0.0005
2	Stack	11/4/2014	12:00-13:00	4.18	9.10	0.030	0.17	9240.0	0.0003
3	Stack	11/4/2014	14:43-15:43	4.13	8.80	0.030	0.17	9240.0	0.0003
Average							0.21	9240.0	0.0003

* Runs 2 and 3 were not detected and the detection limit used in the calculation



Method 30B (Sorbent Trap) Mercury Test Results Summary

University of Iowa

Oakdale Renewable Energy Plant

Hurst Boiler Exhaust Duct


Test No.	Date	Start Time	End Time	V _m (standard L)	ng detected	ppb	O ₂ , % dry	ug/dscm	ug/wscm	Ib/Tbtu (Fd Factor)			
1A	11/5/2014	11:35	12:45	137.576	85.60	0.07	11.20	0.62	0.56	0.7733			
1B				135.462	78.90	0.07	11.20	0.58	0.52	0.7239			
Average					82.25	0.07	11.20	0.60	0.54	0.7486			
2A	11/5/2014	13:25	14:35	136.702	59.20	0.05	11.00	0.43	0.39	0.5274			
2B				132.931	53.40	0.05	11.00	0.40	0.36	0.4892			
Average					56.30	0.05	11.00	0.42	0.37	0.5083			
3A	11/5/2014	15:13	16:05	116.988	28.90	0.03	10.40	0.25	0.22	0.2836			
3B				96.283	25.60	0.03	10.40	0.27	0.24	0.3053			
Average					27.25	0.03	10.40	0.26	0.23	0.2945			
Overall Average*					69.28	0.06	11.10	0.51	0.46	0.6284			

*Unit tripped during Run 3 and was not included in the average

University of Iowa
Oakdale Renewable Energy Plant
Hurst Boiler Exhaust Duct
Gaseous Summary

Test No.	Date	Start Time	End Time	NO _x , ppm (dry)	CO, ppm (dry)	CO ₂ , % (dry)	O ₂ , % (dry)	CO ppm (dry) @ 3% O ₂	Flowrate, dscf/MMBTu	Fd Factor, dscf/MMBTu	O ₂ based NO _x lb/MMBTu	O ₂ based CO lb/MMBTu	NO _x lb/hr	CO lb/hr	
1	11/05/14	11:35	13:01	45.8	3.0	9.3	11.2	5.5	6,514.0	9,240.0	0.109	0.004	2.14	0.09	
2	11/05/14	13:25	14:48	43.9	5.9	9.6	11.0	10.7	6,479.0	9,240.0	0.102	0.008	2.04	0.17	
3	11/05/14	15:13	16:01	44.4	9.2	10.1	10.4	15.7	6,601.0	9,240.0	0.098	0.012	2.10	0.26	
Average*					44.9	4.5	9.5	11.1	8.1	6,496.5	9,240.0	0.106	0.006	2.09	0.13

*Unit tripped during Run 3 and Run 3 is not included in the average



4.0 CERTIFICATION

MOSTARDI PLATT is pleased to have been of service to University of Iowa. If you have any questions regarding this test report, please do not hesitate to contact us at 630-993-2100.

CERTIFICATION


As project manager, I hereby certify that this test report represents a true and accurate summary of emissions test results and the methodologies employed to obtain those results, and the test program was performed in accordance with the methods specified in this test report.

MOSTARDI PLATT




Project Manager

Daniel E. Tuider




Quality Assurance

Jeffrey M. Crivlare



APPENDICES




Appendix A - Plant Operating Data

HURST 2014 Boiler MACT Testing			OAK_B#1_FT839	Hurst Design
Run #	Start Time	End Time	Hurst Steam Load (KLbs/Hr)	Steam Capacity (KLbs/Hr)
FPM Runs				
1	11/4/14 8:35	11/4/14 11:05	13.44056426	20
2	11/4/14 11:30	11/4/14 13:47	13.25513696	20
3	11/4/14 14:15	11/4/14 16:32	13.17647585	20
HCI Runs				
1	11/4/14 8:55	11/4/14 9:55	13.60085547	20
2	11/4/14 12:00	11/4/14 13:00	13.04965777	20
3	11/4/14 14:43	11/4/14 15:43	13.07267843	20
Mercury Runs				
1	11/5/14 11:35	11/5/14 12:45	11.82363673	20
2	11/5/14 13:25	11/5/14 14:35	11.76296755	20
3	11/5/14 15:13	11/5/14 16:05	11.45545742	20
CO and NOx Runs				
1	11/5/14 11:35	11/5/14 13:01	11.77905421	20
2	11/5/14 13:25	11/5/14 14:48	11.78580092	20
3	11/5/14 15:13	11/5/14 16:01	11.42337514	20

Appendix B - Test Section Diagrams

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(FPM and Volumetric Flow Testing)



Job: The University of Iowa
Oakdale Renewable Energy Plant
Coralville, Iowa

Date: November 4 and 5, 2014

Area: 19.25 Square Feet

Test Location: Hurst Boiler Exhaust Duct

No. Test Ports: 5


Length: 5.5 Feet

Tests Points per Port: 5

Width: 3.5 Feet

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(NO_x and CO Testing)



Job: The University of Iowa
Oakdale Renewable Energy Plant
Coralville, Iowa

Date: November 5, 2014

Area: 19.25 Square Feet

Test Location: Hurst Boiler Exhaust Duct

No. Test Ports: 5


Length: 5.5 Feet

Tests Points per Port: 4

Width: 3.5 Feet

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Hg Testing)



Job: The University of Iowa
Oakdale Renewable Energy Plant
Coralville, Iowa

Date: November 5, 2014

Area: 19.25 Square Feet

Test Location: Hurst Boiler Exhaust Duct

No. Test Ports: 3


Length: 5.5 Feet

Tests Points per Port: 1

Width: 3.5 Feet

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(HCl Testing)



Job: The University of Iowa
Oakdale Renewable Energy Plant
Coralville, Iowa

Date: November 4, 2014

Area: 19.25 Square Feet

Test Location: Hurst Boiler Exhaust Duct

No. Test Ports: 1


Length: 5.5 Feet

Tests Points per Port: 1


Width: 3.5 Feet

Appendix C - Sample Train Diagrams


USEPA Method 2- Type S Pitot Tube Manometer Assembly




USEPA Method 3A Extractive Gaseous Sampling Diagram




USEPA Method 5- Particulate Matter Sample Train Diagram




USEPA Methods 3A, 7E and 10 Extractive Gaseous Sampling Diagram




USEPA Method 26 – Halogen Sample Train Diagram



USEPA Method 4- Moisture Content Sample Train Diagram



USEPA Method 30B- Mercury Sorbent Trap Sampling Train



Appendix D - Calculation Nomenclature and Formulas

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Test Location: Hurst Boiler Exhaust Duct
Run: 1
Date: 11/4/2014
Method: 5
Source Condition: Normal

Dry Molecular Weight

$$Md = 0.44 \times (\%CO_2) + 0.32 \times (\%O_2) + 0.28 \times \%N_2$$

$$\%CO_2 = \underline{11.6} \quad \%O_2 = \underline{8.9} \quad \%N_2 = \underline{79.5}$$

$$Md = \underline{30.212}$$

Wet Molecular Weight

$$Ms = Md \times (1-Bws) + (18.0 \times Bws)$$

$$Md = \underline{30.212} \quad Bws = \underline{0.132}$$

$$Ms = \underline{28.601}$$

Meter Volume at Standard Conditions

$$Vm(std) = \frac{17.647 \times Y \times Vm \times (Pbar + DH/13.6)}{Tm}$$

$$Y = \underline{1.001} \quad Vm = \underline{78.991} \quad Pbar = \underline{29.65}$$
$$DH = \underline{1.09} \quad Tm = \underline{535.5}$$

$$Vm(std) = \underline{77.462}$$

Volume of Water Vapor Condensed

$$Vw(std) = 0.0471 \times (\text{net H}_2\text{O gain})$$

$$\text{Net H}_2\text{O} = \underline{249.9}$$

$$Vw(std) = \underline{11.770}$$

Moisture Content

$$Bws = \frac{Vwc(std)}{Vwc(std) + Vm(std)}$$

$$Vw(std) = \underline{11.770} \quad Vm(std) = \underline{77.462}$$

$$Bws = \underline{0.132} \quad 0.148791709$$

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Test Location: Hurst Boiler Exhaust Duct
 Run: 1
 Date: 11/4/2014
 Method: 5
 Source Condition: Normal

Average Duct Velocity

$$Vs = 85.49 \times Cp \times \text{Sqrt DP (avg)} \times (Ts (\text{avg}) / (Ps \times Ms))^{1/2}$$

$$\begin{aligned} Cp &= \underline{0.840} & Ts (\text{avg}) &= \underline{818.2} & \text{Sqrt DP (avg)} &= \underline{0.160} \\ Ps &= \underline{29.64} & Ms &= \underline{28.601} \\ Vs &= \underline{11.274} \end{aligned}$$

Volumetric Flow Rate (Actual Basis)

$$Q = Vs \times A \times 60$$

$$\begin{aligned} Vs &= \underline{11.274} & A &= \underline{19.250} \\ Q &= \underline{13,022} \end{aligned}$$

Volumetric Flow Rate (Standard Basis)

$$\begin{aligned} Q_{\text{std}} &= 17.647 \times Q \times \frac{Ps}{Ts (\text{avg})} \\ Q &= \underline{13,022} & Ps &= \underline{29.64} & Ts (\text{avg}) &= \underline{818.2} \\ Q_{\text{std}} &= \underline{8,325} \end{aligned}$$

Volumetric Flow Rate (Standard Dry Basis)

$$\begin{aligned} Q_{\text{std(dry)}} &= Q_{\text{std}} \times (1 - Bws) \\ Q_{\text{std}} &= \underline{8,325} & Bws &= \underline{0.132} \\ Q_{\text{std(dry)}} &= \underline{7,227} \end{aligned}$$

Isokinetic Variation:

$$\begin{aligned} \%ISO &= \frac{0.0945 \times Ts \times Vm(\text{std})}{Vs \times \theta \times An \times Ps \times (1 - Bws)} \\ Ts &= \underline{818.2} & Vm(\text{std}) &= \underline{77.462} & Vs &= \underline{11.274} \\ An &= \underline{0.0016558} & \theta &= \underline{125} & Ps &= \underline{29.64} \\ Bws &= \underline{0.132} \\ \%ISO &= \underline{99.7} \end{aligned}$$

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Test Location: Hurst Boiler Exhaust Duct
Run: 1
Date: 11/4/2014
Method: 5
Source Condition: Normal

PM Concentration:

This example represents the filterable fraction. For other fractions, use the obtained mn for that particulate fraction.

$$Co = \frac{m_n \times 15.43}{Vm(\text{std})}$$

$$m_n (\text{g}) = \underline{0.0046} \quad Vm(\text{std}) = \underline{77.462}$$

$$Co = \underline{0.0009} \text{ gr/dscf}$$

PM Emission Rate:

$$\text{Emission Rate lb/hr} = \frac{Co}{7,000} \times Q_{\text{std(dry)}} \times 60$$

$$Co = \underline{0.0009} \quad Q_{\text{std(dry)}} = \underline{7,227}$$

$$\text{Emission Rate lb/hr} = \underline{0.057} \text{ lb/hr}$$

$$F_d = \underline{9,240.0} \quad O_2\% = \underline{8.9}$$

$$\text{Emission Rate lb/mmBtu (F}_d\text{ Factor)} = \frac{Co}{7,000} \times F_d (\text{dscf/mmBtu}) \times \frac{20.9}{20.9 - \underline{\text{O}_2\%}}$$

$$\text{Emission Rate lb/mmBtu (F}_d\text{ Factor)} = \underline{0.0021}$$

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Test Location: Hurst Boiler Exhaust Duct
Run: 1A
Date: 11/5/2014

Mercury Meter Volume at Standard Conditions (Liters)

$$Vm(\text{std}) = \frac{17.647 \times Y \times Vm}{P_{\text{bar}}}$$
$$Y = \frac{1.012}{T_m} \quad Vm = \frac{140.532}{541.80} \quad P_{\text{bar}} = \frac{29.70}{T_m}$$
$$Vm(\text{std}) = \underline{\underline{137.576}}$$

Hg Concentration:

$$\text{ppb Hg} = \frac{\text{total ng of Hg on trap}/(1000000000 * 0.0022046226/Vm(\text{std}) * 0.035314667) * Fd Factor * (20.9/(20.9-%O2)) * 1000000}{85.6}$$
$$\text{Total ng Hg} = \underline{\underline{85.6}}$$
$$\text{ppb Hg} = \underline{\underline{0.07}}$$
$$\text{ug/dscm} = \frac{\text{total ng of Hg on trap}/1000/Vm(\text{std})/1000}{0.62}$$
$$\text{ug/dscm} = \underline{\underline{0.62}}$$
$$\text{ug/wscm} = \frac{\text{ug/dscm} * (1-Bws)}{0.56}$$
$$\text{ug/wscm} = \underline{\underline{0.56}}$$

Hg Emission Rate:

$$\text{lb/TBtu (fd factor)} = \frac{\text{total ng of Hg on trap}/1000000000 * 0.0022046226/Vm(\text{std}) * 0.035314667) * Fd Factor * (20.9/(20.9-%O2)) * 1000000}{0.773313}$$
$$\text{lb/TBtu (fd factor)} = \underline{\underline{0.773313}}$$

Volumetric Flow Rate Example Calculations

Client: University of Iowa
Plant: Oakdale Renewable Energy Center
Location: Hurst Boiler Exhaust Duct
Run: Normal Load, Run 1
Date: 11/05/14

Moisture Content

$$Bws = \frac{e' - AP(t-t')}{P}$$

where: e' = saturated vapor pressure of water, in. Hg,
at the wet bulb temperature, t'
 $A = 3.67 \times 10^{-4}(1+0.00064(t'-32))$
 P = absolute pressure, in. Hg, in the duct
 t = dry bulb temperature, °F
 t' = wet bulb temperature, °F

$$Bws = \underline{\underline{0.100}}$$

Dry Molecular Weight

$$Md = 0.44 \times (\%CO_2) + 0.32 \times (\%O_2) + 0.28 \times \%N_2$$

$$\%CO_2 = \underline{\underline{9.3}} \quad \%O_2 = \underline{\underline{11.2}} \quad \%N_2 = \underline{\underline{79.5}}$$

$$Md = \underline{\underline{29.94}}$$

Wet Molecular Weight

$$Ms = Md \times (1-Bws) + (18.0 \times Bws)$$

$$Md = \underline{\underline{29.94}} \quad Bws = \underline{\underline{0.100}}$$

$$Ms = \underline{\underline{28.74}}$$

Average Duct Velocity

$$Vs = 85.49 \times Cp \times \text{Sqrt } \Delta P \text{ (avg)} \times (Ts \text{ (avg)}) / (Ps \times Ms)^{1/2}$$

$$Cp = \frac{0.840}{29.69} \quad Ts \text{ (avg)} = \frac{827.8}{28.74} \quad \text{Sqrt } \Delta P \text{ avg: } \underline{\underline{0.140}}$$

$$Vs = \underline{\underline{9.90}}$$

Volumetric Flow Rate

$$Q \text{ (Actual Basis)} = Vs \times A \times 60$$

$$Vs = \underline{\underline{9.90}} \quad A = \underline{\underline{19.250}}$$

$$Q = \underline{\underline{11435}} \text{ acfm}$$

$$Qs \text{ (Standard Basis)} = 17.647 \times Q \times \frac{Ps}{460 + Ts \text{ (avg)}}$$

$$Q = \underline{\underline{11435}} \quad Ps = \underline{\underline{29.69}} \quad Ts \text{ (avg)} = \underline{\underline{827.8}}$$

$$Qs = \underline{\underline{7238}} \text{ scfm}$$

$$Qs \text{ (Standard Basis)} = \text{scfm} \times 60 \text{ min/hr}$$

$$Qs = \underline{\underline{434278}} \text{ scfh}$$

MOSTARDI PLATT

Volumetric Flow Nomenclature

A = Cross-sectional area of stack or duct, ft²

B_{ws} = Water vapor in gas stream, proportion by volume

C_p = Pitot tube coefficient, dimensionless

M_d = Dry molecular weight of gas, lb/lb-mole

M_s = Molecular weight of gas, wet basis, lb/lb-mole

M_w = Molecular weight of water, 18.0 lb/lb-mole

P_{bar} = Barometric pressure at testing site, in. Hg

P_g = Static pressure of gas, in. Hg (in. H₂O/13.6)

P_s = Absolute pressure of gas, in. Hg = P_{bar} + P_g

P_{std} = Standard absolute pressure, 29.92 in. Hg

Q_{acf m} = Actual volumetric gas flow rate, acfm

Q_{sd} = Dry volumetric gas flow rate corrected to standard conditions, dscf/hr

R = Ideal gas constant, 21.85 in. Hg-ft³/°R-lb-mole

T_s = Absolute gas temperature, °R

T_{std} = Standard absolute temperature, 528°R

v_s = Gas velocity, ft/sec

V_{w(std)} = Volume of water vapor in gas sample, corrected to standard conditions, scf

Y = Dry gas meter calibration factor

Δp = Velocity head of gas, in. H₂O

K₁ = 17.647 °R/in. Hg

%EA = Percent excess air

%CO₂ = Percent carbon dioxide by volume, dry basis

%O₂ = Percent oxygen by volume, dry basis

%N₂ = Percent nitrogen by volume, dry basis

0.264 = Ratio of O₂ to N₂ in air, v/v

0.28 = Molecular weight of N₂ or CO, divided by 100

0.32 = Molecular weight of O₂ divided by 100

0.44 = Molecular weight of CO₂ divided by 100

13.6 = Specific gravity of mercury (Hg)

MOSTARDI PLATT

Volumetric Air Flow Calculations

$$Vm (\text{std}) = 17.647 \times Vm \times \left[\frac{(P_{\text{bar}} + (\frac{DH}{13.6}))}{(460 + Tm)} \right] \times Y$$

$$Vw (\text{std}) = 0.0471 \times Vlc$$

$$Bws = \left[\frac{Vw (\text{std})}{Vw (\text{std}) + Vm (\text{std})} \right]$$

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + [0.28 \times (100 - \%CO_2 - \%O_2)]$$

$$Ms = Md \times (1 - Bws) + (18 \times Bws)$$

$$Vs = \sqrt{\frac{(Ts + 460)}{Ms \times Ps}} \times \sqrt{DP} \times Cp \times 85.49$$

$$Acfm = Vs \times \text{Area (of stack or duct)} \times 60$$

$$Scfm = Acfm \times 17.647 \times \left[\frac{Ps}{(460 + Ts)} \right]$$

$$Scfh = Scfm \times 60 \frac{\text{min}}{\text{hr}}$$

acfm = actual cubic feet per minute

scfm = standard cubic feet per minute

scfh = standard cubic feet per hour

Cp = pitot tube correction factor

Ps = absolute flue gas pressure

Ms = molecular weight of gas (lb/lb mole)

Md = dry molecular weight of gas (lb/lb mole)

Bws = water vapor in gas stream proportion by volume

MOSTARDI PLATT

Particulate Nomenclature

- A = Cross-sectional area of stack or duct, square feet
A_n = Cross-sectional area of nozzle, square feet
B_{ws} = Water vapor in gas stream, by volume
C_a = Acetone blank residue concentration, g/g
C_{acf} = Concentration of particulate matter in gas stream at actual conditions, gr/acf
C_p = Pitot tube coefficient
C_s = Concentration of particulate matter in gas stream, dry basis, corrected to standard conditions, gr/dscf
IKV = Isokinetic sampling variance, must be 90.0 % ≤ IKV ≤ 110.0%
M_d = Dry molecular weight of gas, lb/lb-mole
M_s = Molecular weight of gas, wet basis, lb/lb-mole
M_w = Molecular weight of water, 18.0 lb/lb-mole
m_a = Mass of residue of acetone after evaporation, grams
P_{bar} = Barometric pressure at testing site, inches mercury
P_g = Static pressure of gas, inches mercury (inches water/13.6)
P_s = Absolute pressure of gas, inches mercury = P_{bar} + P_g
P_{std} = Standard absolute pressure, 29.92 inches mercury
Q_{actfm} = Actual volumetric gas flow rate, acfm
Q_{sd} = Dry volumetric gas flow rate corrected to standard conditions, dscfh
R = Ideal gas constant, 21.85 inches mercury cubic foot/"R-lb-mole
T_m = Dry gas meter temperature, °R
T_s = Gas temperature, °R
T_{std} = Absolute temperature, 528°R
V_a = Volume of acetone blank, ml
V_{aw} = Volume of acetone used in wash, ml
W_a = Weight of residue in acetone wash, grams
m_n = Total amount of particulate matter collected, grams
V_{1c} = Total volume of liquid collected in impingers and silica gel, ml
V_m = Volume of gas sample as measured by dry gas meter, dcf
V_{m(std)} = Volume of gas sample measured by dry gas meter, corrected to standard conditions, dscf
v_s = Gas velocity, ft/sec
V_{w(std)} = Volume of water vapor in gas sample, corrected to standard conditions, scf
Y = Dry gas meter calibration factor
ΔH = Average pressure differential across the orifice meter, inches water
Δp = Velocity head of gas, inches water
ρ_a = Density of acetone, 0.7855 g/ml (average)
ρ_w = Density of water, 0.002201 lb/ml
θ = Total sampling time, minutes
K₁ = 17.647 °R/in. Hg
K₂ = 0.04707 ft³/ml
K₄ = 0.09450/100 = 0.000945
K_p = Pitot tube constant, $85.49 \frac{\text{ft}}{\text{sec}} \left[\frac{(\text{lb/lb - mole})(\text{in. Hg})}{(\text{°R})(\text{in. H}_2\text{O})} \right]^{1/2}$
%EA = Percent excess air
%CO₂ = Percent carbon dioxide by volume, dry basis
%O₂ = Percent oxygen by volume, dry basis
%CO = Percent carbon monoxide by volume, dry basis
%N₂ = Percent nitrogen by volume, dry basis
0.264 = Ratio of O₂ to N₂ in air, v/v
28 = Molecular weight of N₂ or CO
32 = Molecular weight of O₂
44 = Molecular weight of CO₂
13.6 = Specific gravity of mercury (Hg)

MOSTARDI PLATT

Particulates Calculation Formulas

$$1. \quad V_{w(\text{std})} = V_{le} \left(\frac{\rho_w}{M_w} \right) \left(\frac{RT_{\text{std}}}{P_{\text{std}}} \right) = K_2 V_{le}$$

$$2. \quad V_{m(\text{std})} = V_m Y \left(\frac{T_{\text{std}}}{T_m} \right) \left(\frac{(P_{\text{bar}} + (\frac{\Delta H}{13.6}))}{P_{\text{std}}} \right) = K_1 V_m Y \frac{(P_{\text{bar}} + (\frac{\Delta H}{13.6}))}{T_m}$$

$$3. \quad B_{ws} = \frac{V_{w(\text{std})}}{(V_{m(\text{std})} + V_{w(\text{std})})}$$

$$4. \quad M_d = 0.44(\%CO_2) + 0.32(\%O_2) + 0.28(\%N_2)$$

$$5. \quad M_s = M_d (1 - B_{ws}) + 18.0(B_{ws})$$

$$6. \quad C_n = \frac{m_a}{V_a \rho_a}$$

$$7. \quad W_a = C_a V_{aw} \rho_a$$

$$8. \quad C_{acf} = 15.43 K_i \left(\frac{m_n P_s}{V_{w(\text{std})} + V_{m(\text{std})} T_s} \right)$$

$$9. \quad C_s = (15.43 \text{ grains/gram}) (m_n / V_{m(\text{std})})$$

$$10. \quad v_s = K_p C_p \sqrt{\frac{\Delta P T_s}{P_s M_s}}$$

$$11. \quad Q_{ncfm} = v_s A (60 \text{ sec/min})$$

$$12. \quad Q_{sd} = (3600 \text{ sec/hr}) (1 - B_{ws}) v_s \left(\frac{T_{\text{std}} P_s}{T_s P_{\text{std}}} \right) A$$

$$13. \quad E \text{ (emission rate, lbs/hr)} = Q_{std} (C_s / 7000 \text{ grains/lb})$$

$$14. \quad IKV = \frac{T_s V_{m(\text{std})} P_{\text{std}}}{T_{\text{std}} v_s \theta A_n P_s 60 (1 - B_{ws})} = K_4 \frac{T_s V_{m(\text{std})}}{P_s v_s A_n \theta (1 - B_{ws})}$$

$$15. \quad \%EA = \left(\frac{\%O_2 - (0.5 \%CO)}{0.264 \%N_2 - (\%O_2 - 0.5 \%CO)} \right) \times 100$$

MOSTARDI PLATT

Method 30B Determination of Vapor Phase Mercury Nomenclature

B = Breakthrough (%).

Bws = Moisture content of sample gas as measured by Method 4, percent/100.

Ca = Concentration of Hg for the sample collection period, for sorbent trap "a" ($\mu\text{g/dscm}$).

Cb = Concentration of Hg for the sample collection period, for sorbent trap "b" ($\mu\text{g/dscm}$).

Cd = Hg concentration, dry basis ($\mu\text{g/dscm}$).

Crec = Concentration of spiked compound measured ($\mu\text{g/m}^3$).

Cw = Hg concentration, wet basis ($\mu\text{g/m}^3$).

m1 = Mass of Hg measured on sorbent trap section 1 (μg).

m2 = Mass of Hg measured on sorbent trap section 2 (μg).

mrecovered = Mass of spiked Hg recovered in Analytical Bias or Field Recovery Test (μg).

ms = Total mass of Hg measured on spiked trap in Field Recovery Test (μg).

mspiked = Mass of Hg spiked in Analytical Bias or Field Recovery Test (μg).

mu = Total mass of Hg measured on unspiked trap in Field Recovery Test (μg).

R = Percentage of spiked mass recovered (%).

RD = Relative deviation between the Hg concentrations from traps "a" and "b" (%).

vs = Volume of gas sampled, spiked trap in Field Recovery Test (dscm).

Vt = Total volume of dry gas metered during the collection period (dscm); for the purposes of this method, standard temperature and pressure are defined as 20° C and 760 mm Hg, respectively.

vu = Volume of gas sampled, unspiked trap in Field Recovery Test (dscm).

MOSTARDI PLATT

MOISTURE CALCULATIONS

$$V_{wc(std)} = \frac{(V_f - V_i) \rho_w R T_{std}}{P_{std} M_w} = 0.04707(V_f - V_i)$$

$$V_{wsg(std)} = \frac{(W_f - W_i) R T_{std}}{P_{std} M_w} = 0.04715 (W_f - W_i)$$

$$V_{m(std)} = 17.64 V_m Y \frac{P_{bar} + \frac{\Delta H}{13.6}}{T_m}$$

$$B_{ws} = \frac{V_{wc(std)} + V_{wsg(std)}}{V_{wc(std)} + V_{wsg(std)} + V_{m(std)}}$$

Where:

B_{ws} = Water vapor in gas stream, proportion by volume

M_w = Molecular weight of water, 18.015 lb/lb-mole

P_{bar} = Barometric pressure at the testing site, in. Hg

P_{std} = Standard absolute pressure, 29.92 in. Hg

R = Ideal gas constant, $0.048137 \text{ (in. Hg)(ft}^3\text{)/(g-mole)(}^{\circ}\text{R)} = [21.8348(\text{in. Hg})(\text{ft}^3)/(\text{lb-mole})(}^{\circ}\text{R}]/453.592 \text{ g-mole/lb-mole}$

T_m = Absolute average dry gas meter temperature, $^{\circ}\text{R}$

T_{std} = Standard absolute temperature, $528 \text{ }^{\circ}\text{R}$

V_f = Final volume of condenser water, ml

V_i = Initial volume of condenser water, ml

V_m = Dry gas volume measured by dry gas meter, dcf

$V_{m(std)}$ = Dry gas volume measured by dry gas meter, corrected to standard conditions, scf

$V_{wc(std)}$ = Volume of condensed water vapor, corrected to standard conditions, scf

$V_{wsg(std)}$ = Volume of water vapor collected in silica gel, corrected to standard conditions, scf

W_f = Final weight of silica gel, g

W_i = Initial weight of silica gel, g

Y = Dry gas meter calibration factor

ΔH = Average pressure exerted on dry gas meter outlet by gas sample bag, in. H_2O

ρ_w = Density of water, 0.9982 g/ml

13.6 = Specific gravity of mercury (Hg)

17.64 = T_{std}/P_{std}

0.04707 = ft^3/ml 0.04715 = ft^3/g

MOSTARDI PLATT

Coal Emission Rate Calculations

A pollutant emission rate (E), expressed as pounds of pollutant per million Btu heat input from the fuel combusted can be calculated by several methods as follows:

- A. $C = C_s/7000$ where, C = pollutant concentration, lb/dscf
 c_s = pollutant concentration, grains/dscf
- B. If fuel flow is monitored and the fuel combusted during the test is sampled and analyzed for gross calorific value, then:

$$E = \frac{Q_{sd} C}{\text{fuel flow rate (lb/hr)} \text{ GCV}} \times 10^6$$

where, E = lbs per million Btu

GCV = gross calorific value, Btu/lb

Q_{sd} = dry volumetric gas flow at standard conditions, dscf/hr

- C. If an integrated gas sample is taken during the test and analyzed for %CO₂ or %O₂, dry basis by volume, with an approved USEPA Method 3 or 3A gas analyzer, then

$$E = C F_c \frac{100}{(\%CO_2)} \text{ or, } E = C F \frac{20.9}{(20.9 - \%O_2)} \quad \text{where,}$$

%CO₂ and %O₂ are expressed as percent values:

F_c = a factor representing a ratio of the volume of carbon dioxide generated to the calorific value of the fuel combusted, 1840 scf CO₂/million Btu for sub-bituminous or 1800 scf/million Btu for bituminous.

F = a factor representing a ratio of the volume of dry flue gases generated to the calorific value of the fuel combusted, 9820 dscf/million Btu for sub-bituminous or 9780 dscf/million Btu for bituminous.

- D. If fuel sample increments are taken and composited during the test and an ultimate analysis is performed and the GCV is determined, then

$$F_c = \frac{321 \times 10^3 (\%C)}{\text{GCV}} \text{ where, \%C = carbon content by weight expressed as percent}$$
$$F = \frac{[3.64 (\%H) + 1.53 (\%C) + 0.57 (\%S) + 0.14 (\%N) - 0.46 (\%O_2)]}{\text{GCV}} \times 10^6$$

1. H = Hydrogen, percent
2. C = Carbon, percent
3. S = Sulfur, percent
4. N = Nitrogen, percent
5. O = Oxygen, percent

MOSTARDI PLATT

Pollutant Concentration Correction to 3% Percent Oxygen

$$C_{adj} = C_d \frac{20.9 - 3\%}{20.9 - \%O_2}$$

where:

- C_{adj} = Pollutant concentration corrected to percent O₂
20.9 - 3% = Percent O₂, the defined O₂ correction value, percent
20.9 = Percent O₂ in air
%O₂ = Measured O₂ concentration dry basis, percent
 C_d = Pollutant concentration measured, dry basis, ppm.

MOSTARDI PLATT

ppm Conversion Calculations and Factors

ppm to lbs/scf

(ppm X) x (conversion factor X) = X lbs/scf

lbs/scf to lbs/hr

Dry ppm's with dry flow, and wet ppm's with wet flow.

(X lbs/scf) x (airflow scf/min) x (60 min/hr) = X lbs/hr

lbs/scf to lbs/mmBtu

Dry ppm's with dry diluent, and wet ppm's with wet diluent.

$\text{CO}_2 - (X \text{ lbs/scf}) \times (F_c) \times (100/\text{CO}_2) = X \text{ lbs/mmBtu}$

$\text{O}_2 - (X \text{ lbs/scf}) \times (F_d) \times (20.9/(20.9-\text{O}_2)) = X \text{ lbs/mmBtu}$

Conversion Factors

$\text{NO}_x - 1.19396 \times 10^{-7}$

$\text{SO}_2 - 1.6625 \times 10^{-7}$

$\text{CO} - 7.2664 \times 10^{-8}$

$\text{CH}_4 - 4.1637 \times 10^{-8}$

$\text{C}_3\text{H}_8 - 1.1419 \times 10^{-7}$

MOSTARDI PLATT

ppmv to lb/hr Conversion Calculations

$$1. \quad ppm SO_2 \times 1.660 \times 10^{-7} = \frac{lbs/SO_2}{scf}$$

$$\frac{lbs SO_2}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs SO_2}{hr}$$

$$2. \quad ppm NO_x \times 1.194 \times 10^{-7} = \frac{lbs/NO_{x2}}{scf}$$

$$\frac{lbs NO_x}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs NO_x}{hr}$$

$$3. \quad ppm CO \times 7.266 \times 10^{-8} = \frac{lbs/CO}{scf}$$

$$\frac{lbs CO}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs CO}{hr}$$

$$4. \quad ppm C_3H_8 \times 1.142 \times 10^{-7} = \frac{lbsC_3H_8}{scf}$$

$$\frac{lbs C_3H_8}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs C_3H_8}{hr}$$

$$5. \quad ppm CH_4 \times 4.164 \times 10^{-8} = \frac{lbs/CH_4}{scf}$$

$$\frac{lbs CH_4}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs CH_4}{hr}$$

$$6. \quad ppm NMHC \text{ as } C_3H_8 \times 9.3427 \times 10^{-8} = \frac{lbs C}{scf}$$

$$\frac{lbs C}{scf} \times \frac{lbsscf}{min} \times \frac{60 min}{hr} = \frac{lbs C}{hr}$$

MOSTARDI PLATT

Calculations for Hydrogen Chloride by Method 26 or 26A

Concentration

$$\frac{\text{lb HCl}}{\text{dscf}} = \frac{\mu\text{g HCl in sample}}{4.536 \times 10^8 \times \text{dscf}}$$

where:

$$4.536 \times 10^8 = \mu\text{g/lb}$$

dscf = Volume of gas sampled

$$\mu\text{g/lb HCl} = \mu\text{g Cl} \times \frac{36.453}{35.453}$$

Parts Per Million

$$\text{ppm HCl} = \frac{\text{lb HCl}}{\text{dscf}} \div \frac{36.453}{385 \times 10^6}$$

where:

385 = Volume of 1 lb mole of gas at 68°F and 29.92 in. Hg

10^6 = Conversion of ppm v/v

Emission Rate

$$\text{lb HCl/dscf} \times \text{dscfm} \times 60 \text{ min/hr} = \text{lb/hr HCl}$$

Appendix E - Laboratory Data

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Project Number: M144705
 Test Location: Hurst Boiler Exhaust Duct
 Test Method: 5
 Filterable Analysis Date: 11/10/2014

Filter Drying Temp °F: Ambient-Des. 24 hrs
 Analyst: JMG

Description	Sample Date	ID#	vol. (ml)	Initial Weight (grams)	Final Weight (grams)	Net Weight Gain (grams)
Filterable Particulate						
Test No. 1	11/4/2014					
Source Condition:	Normal					
M5 Filter		7670		0.4489	0.4498	0.0009
Acetone Wash (M5 Pans)		3675	40 ml	5.2267	5.2305	0.0038
Acetone Blank						0.0001
Total Front Half Weight						0.0046
Filterable Particulate						
Test No. 2	11/4/2014					
Source Condition:	Normal					
M5 Filter		7695		0.4479	0.4491	0.0012
Acetone Wash (M5 Pans)		3676	45 ml	5.2241	5.2277	0.0036
Acetone Blank						0.0001
Total Front Half Weight						0.0047
Filterable Particulate						
Test No. 3	11/4/2014					
Source Condition:	Normal					
M5 Filter		7669		0.4520	0.4528	0.0008
Acetone Wash (M5 Pans)		3677	40 ml	5.2432	5.2448	0.0016
Acetone Blank						0.0001
Total Front Half Weight						0.0023
Reagent Blank Summary						
Acetone Wash (M5 Pans)		3678	100 ml	5.2447	5.2449	0.0002

mostardi platt

Chain-of-Custody Form

Project Number: M144705			Date Results Required:			
Client: UNIVERSITY OF IOWA			TAT Required:			
Plant/Test Location: OAKDALE /			Project Supervisor: DAN TURNER			
Sample Number	Sample Date	Sample Point/Identification	# of Conts	Sub Lab	Analysis Required	Volume, mls
001	11/4/14	HURST BOILER EXHAUST DUCT TEST 1	2		M5	
002	11/4/14	HURST BOILER EXHAUST DUCT TEST 2	2		M5	
003	11/4/14	HURST BOILER EXHAUST DUCT TEST 3	2		M5	
004	11/4/14	HURST BOILER EXHAUST DUCT TEST 1	2		M26	
005	11/4/14	HURST BOILER EXHAUST DUCT TEST 2	2		M26	
006	11/4/14	HURST BOILER EXHAUST DUCT TEST 3	2		M26	
007	11/5/14	HURST BOILER EXHAUST DUCT TEST 1	2		30B	
008	11/5/14	HURST BOILER EXHAUST DUCT TEST 2	2		30B	
009	11/5/14	HURST BOILER EXHAUST DUCT TEST 3	2		30B	
010	11/4/14	H2SO4 REAGENT BLANK	1		M56	
011	11/4/14	NaOH REAGENT BLANK	1		M56	
012	11/4/14	ACETONE REAGENT BLANK	1		M5	
013						
014						
015						
016						
017						
018						
019						
020						
Delivered to Lab by: DAN TURNER / 11/6/14 1400			Date/Time: 11/6/14		Received by: Dan Turner	
					Processed by: Dan Turner	
Date/Time: 11/10/14						

Laboratory Notes:

UNIT WENT DOWN DURING TEST 3 OF THE 30B ON
11/5/14.



Your Project #: M144705
Site#: HURST BOILER
Site Location: UNIVERISTY OF IOWA
Your C.O.C. #: 004, 005, 001, 002, 003

Attention: Data Reporting

Mostardi Platt
888 Industrial Rd
Elmhurst, IL
USA 60126-1121

Report Date: 2014/11/28
Report #: R3237848
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4L6336

Received: 2014/11/13, 15:30

Sample Matrix: Stack Sampling Train

Samples Received: 6

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Anions in Water by Ion Chromatography (1)	1	N/A	2014/11/27	BRL SOP-00105	EPA 300.0 m
Hydrogen Halides -Midget H ₂ SO ₄ Imp	5	2014/11/27	2014/11/27	8RL SOP-00108	EPA 26 m
Volume of Sulfuric Acid Impinger	5	N/A	2014/11/27		

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) SCC/CAEAL

Encryption Key

Clayton Johnson

28 Nov 2014 17:52:51 -05:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Clayton Johnson, Project Manager - Air Toxics, Source Evaluation

Email: Johnson@maxxam.ca

Phone# (905)817-5769

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Total Cover Pages : 1
Page 1 of 8

Maxxam Analytics International Corporation o/a Maxxam Analytics 6740 Campbell Road, Mississauga, Ontario, LSN 2L8 Tel: (905) 817-5700 Toll-Free: 800-563-6266 Fax: (905) 817-5777 www.maxxam.ca



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

EPA M26 HYDROGEN HALIDES AND HALOGENS(M)

Maxxam ID		YM2026	YM2027	YM2028	YM2028			
Sampling Date		2014/11/04	2014/11/04	2014/11/04	2014/11/04			
COC Number		004	005	001	001			
	Units	H ₂ SO ₄ REAGENT BLANK	DI REAGENT BLANK	TEST 1 H ₂ SO ₄ IMPS	TEST 1 H ₂ SO ₄ IMPS Lab-Dup	RDL	QC Batch	MDL
Sulfuric Acid Volume	ml	100	125	37	N/A	1	3839753	1
Hydrochloric Acid	ug	<30	<30	53	53	30	3839781	6.0

RDL = Reportable Detection Limit
QC Batch = Quality Control Batch
Lab-Dup = Laboratory Initiated Duplicate
N/A = Not Applicable

Maxxam ID		YM2029	YM2030			
Sampling Date		2014/11/04	2014/11/04			
COC Number		002	003			
	Units	TEST 2 H ₂ SO ₄ IMPS	TEST 3 H ₂ SO ₄ IMPS	RDL	QC Batch	MDL
Sulfuric Acid Volume	ml	44	49	1	3839753	1
Hydrochloric Acid	ug	<30	<30	30	3839781	6.0

RDL = Reportable Detection Limit
QC Batch = Quality Control Batch



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

RESULTS OF ANALYSES OF STACK SAMPLING TRAIN

Maxxam ID		YM2031			
Sampling Date		2014/11/04			
	Units	AUDIT-102814K-1440	RDL	QC Batch	MDL
Chloride (Cl)	mg/L	22	0.3	3839819	0.01

RDL = Reportable Detection Limit
QC Batch = Quality Control Batch



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

TEST SUMMARY

Maxxam ID: YM2026
Sample ID: H₂SO₄ REAGENT BLANK
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ Imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern
Volume of Sulfuric Acid Impinger		3839753	N/A	2014/11/27	Frank Mo

Maxxam ID: YM2027
Sample ID: DI REAGENT BLANK
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ Imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern
Volume of Sulfuric Acid Impinger		3839753	N/A	2014/11/27	Frank Mo

Maxxam ID: YM2028
Sample ID: TEST 1 H₂SO₄ IMPS
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ Imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern
Volume of Sulfuric Acid Impinger		3839753	N/A	2014/11/27	Frank Mo

Maxxam ID: YM2028 Dup
Sample ID: TEST 1 H₂SO₄ IMPS
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern

Maxxam ID: YM2029
Sample ID: TEST 2 H₂SO₄ IMPS
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ Imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern
Volume of Sulfuric Acid Impinger		3839753	N/A	2014/11/27	Frank Mo

Maxxam ID: YM2030
Sample ID: TEST 3 H₂SO₄ IMPS
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Hydrogen Halides -Midget H ₂ SO ₄ Imp	IC/SPEC	3839781	2014/11/27	2014/11/27	Ann-Marie Stern
Volume of Sulfuric Acid Impinger		3839753	N/A	2014/11/27	Frank Mo



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

TEST SUMMARY

Maxxam ID: YM2031
Sample ID: AUDIT-102814K-1440
Matrix: Stack Sampling Train

Collected: 2014/11/04
Shipped:
Received: 2014/11/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Anions in Water by Ion Chromatography	IC/EC	3839819	N/A	2014/11/27	Ann-Marie Stern



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

GENERAL COMMENTS

Results relate only to the items tested.

Page 6 of 8

Maxxam Analytics International Corporation o/a Maxxam Analytics 6740 Campobello Road, Mississauga, Ontario, LSN 2L8 Tel: (905) 817-5700 Toll-Free: 800-563-6266 Fax: (905) 817-5777 www.maxxam.ca



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

QUALITY ASSURANCE REPORT

QA/QC	Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	Units	QC Limits
3839781	A_S		Matrix Spike(YM2028)	Hydrochloric Acid	2014/11/27	96	%	80 - 120	
3839781	A_S		Spiked Blank	Hydrochloric Acid	2014/11/27	101	%	90 - 110	
3839781	A_S		Method Blank	Hydrochloric Acid	2014/11/27	<30		ug	
3839781	A_S		RPD - Sample/Sample Dup	Hydrochloric Acid	2014/11/27	NC		%	20

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).



Maxxam Job #: B4L6336
Report Date: 2014/11/28

Mostardi Platt
Client Project #: M144705
Site Location: UNIVERISTY OF IOWA

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Frank Mo, B.Sc., Inorganic Lab. Manager

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Chain-of-Custody Form						
Project Number: M144705			Date Results Received:			
Client: University of Iowa			TAT Request:			
Sampling Location: Hurst Boiler			Project Supervisor: CT			
Sample Number	Sample Desc.	Sample Description	Lab Class	Lab	Analyzer Required	Volume (mls)
001	11/4/14	Test 1-H2S/04 sample	1	MAN	M20-HCI	100
002	11/4/14	Test 2-H2S/04 sample	1	MAN	M20-HCI	100
003	11/4/14	Test 3-H2S/04 sample	1	MAN	M20-HCI	100
004	11/4/14	H2S/04 Reagent Block	1	MAN	M20-HCI	100
005	11/4/14	04 Reference Blank	1	MAN	M20-HCI	100
006		Audit Sample				
007						
008						
009						
010						
011						
012						
013						
014						
015						
016						
017						
018						
019						
020						
Submitted to lab by: C. W. Hause			Received by: C. W. Hause	Date/Time: 11/4/14 10:47 AM	Processed by: C. W. Hause	Date/Time:

Laboratory Notes



December 3, 2014

Jenna Ghanma
Mostardi Platt
888 Industrial Drive
Elmhurst, IL 60123

Enclosed is your final report for ERA's Stationary Source Audit Sample (SSAS) Program. Your final report includes an evaluation of all results submitted by your laboratory to ERA.

Data Evaluation Protocols: All analytes in ERA's SSAS Program have been evaluated comparing the reported result to the acceptance limits generated using the criteria contained in the TNI SSAS Table.

For any "Not Acceptable" results, please contact your state regulator for any corrective action requirements.

Thank you for your participation in ERA's SSAS Program. If you have any questions, please contact our Proficiency Testing Department at 1-800-372-0122.

Sincerely,

Kristina Sanchez
Quality Officer

cc: Project File Number 102814K



A Waters Company

Recipient Type	Report Recipient	Contact
Agency	IA-DNR (SSAS) 7900 Hickman Road Suite 1 Windsor Heights, IA 50324 USA	Dennis Thielen dennis.thielen@dnr.iowa.gov Phone: 515-281-4899
Facility	University of Iowa - Oakdale Campus 2320 Crosspark Rd Coralville, IA 52241 USA	Mark Maxwell mark-maxwell@uiowa.edu Phone: 319-335-6185
Lab	Maxxam Analytics Inc 6740 Campobello Rd Mississauga, ON L5N 2L8 Canada	Clayton Johnson Project Manager - Source Evaluation cjohnson@maxxam.ca Phone: (905) 817-5769
Tester	Mostardi Platt 888 Industrial Drive Elmhurst, IL 60123 USA	Jenna Ghanma jghanma@mp-mail.com Phone: 630-993-2685





102814K Laboratory Exception Report

A Waters Company

Clayton Johnson
Project Manager - Source Evaluation
Maxxam Analytics Inc
6740 Campobello Rd
Mississauga, ON L5N 2L8
(905) 817-5769

Not Reported
M748564

EPA ID:
ERA Customer Number:

Evaluation Checks

There are no values reported with < where the assigned value was greater than 0.

Not Acceptable Evaluations

There were no Not Acceptable evaluations for this study.





A Waters Company

Project No. M144705
Hurst Boiler Exhaust Duct

Final Report Results For Laboratory Maxxam Analytics Inc





ERA
A Waters Company

Project No. M144705
Hurst Boiler Exhaust Duct

SSAP Evaluation Report


Project Number: **102814K**

ERA Customer Number: **M748564**

Laboratory Name: **Maxxam Analytics Inc**

Inorganic Results





102814K Evaluation Final Complete Report

A Waters Company

Project No. M144705

Clayton Johnson
Project Manager - Source Evaluation
Maxxam Analytics Inc
6740 Campobello Rd
Mississauga, ON L5N 2L8
(905) 817-5769

Not Reported
M748564

EPA ID:
ERA Customer Number:

TN
Analyte
Code

Analyte

SSAP Hydrogen Halides in Impinger Solution (cat# 1140-1) Study Dates: 10/28/14 - 12/03/14

Units	Reported Value	Assigned Value	Acceptance Limits	Performance Evaluation	Method Description	Analysis Date	Analyst Name
mg/L	22.1	22.8	20.5 - 25.1	Acceptable	EPA 26A 2000	11/27/2014	
mg/L	33.0	33.0	29.7 - 36.3	Not Reported			

Hurst Boiler Exhaust Duct



Ohio Lumex Calibration and Results Summary
 University of Iowa
 Oakdale Renewable Energy Center
 Hurst Boiler Exhaust Duct
 November 5, 2014

No	Description	M, mg	C, ng	Area	Maximum	Time
19	University of Iowa	1				
20	Std_25 Ricca	1	25	10700	1120	12:47:02 PM
21	Std_50 Ricca	1	48	20400	2760	12:49:25 PM
22	Std_100 Ricca	1	99	42100	4470	12:53:02 PM
23	Std_10 Ricca	1	10	4390	482	12:58:23 PM
24	Std_5 Ricca	1	5.2	2210	257	1:00:56 PM
25	Std_25 HP ICV	1	24	10300	900	1:03:14 PM
26	Test 1A 210119 Section 1	1	84	35700	2590	1:07:30 PM
27	Test 1A 210119 Section 2	1	1.6	666	25	1:09:40 PM
	Test 1A Total		85.6			
28	Std_250 Ricca	1	250	106000	13600	1:11:53 PM
29	Test 1B 211390 Section 1 25ng Spike	1	102	43300	2740	1:17:45 PM
30	Test 1B 211390 Section 2 25ng Spike	1	1.9	811	24	1:20:17 PM
	Test 1B Total		78.9			
31	Test 2A 012446 Section 1	1	55	23300	2120	1:23:29 PM
32	Test 2A 012446 Section 2	1	4.2	1770	14	1:29:55 PM
	Test 2A Total		59.2			
33	Test 2B 201242 Section 1 25ng Spike	1	76	32300	2340	1:33:55 PM
34	Test 2B 201242 Section 2 25ng Spike	1	2.4	1010	10	1:38:01 PM
	Test 2B Total		53.4			
35	Test 3A 210456 Section 1	1	28	11900	1070	1:40:47 PM
36	Test 3A 210456 Section 2	1	0.9	391	14	1:45:58 PM
	Test 3A Total		28.9			
37	Std_25 Ricca	1	24	10300	890	1:47:41 PM
38	Test 3B 211459 Section 1 25ng Spike	1	49	21000	1280	1:50:06 PM
39	Test 3B 211459 Section 2 25ng Spike	1	1.6	662	20	1:53:55 PM
	Test 3B Total		25.6			
40	Void	1	15	6540	693	1:56:54 PM
41	Std_25 Ricca	1	23	9950	875	1:59:43 PM
42		1				

Appendix F - Reference Method Test Data (Computerized Sheets)

Client:	University of Iowa		
Facility:	Oakdale Renewable Energy Plant		
Test Location:	Hurst Boiler Exhaust Duct		
Project #:	M144705		
Test Method:	5		
Test Engineer:	SMcG		
Test Technician:	JHK		
Ib/mmBtu Emissions by:	Standard		
Type of Fuel Firing:	Wood		
Standard Fuel Factor Fd, dscf/mmBtu:	R1	R2	R3
Temp ID:	9240.00	9240.00	9240.00
Meter ID:	CM19	CM19	CM19
Pitot ID:	CM19	CM19	CM19
Nozzle Diameter (Inches):	170	170	170
Meter Calibration Factor (Y):	0.551	0.551	0.551
Meter Orifice Setting (Delta H):	1.001	1.001	1.001
Nozzle Kit ID Number and Material:	1.512	1.512	1.512
Pitot Tube Coefficient:	Glass Misc	Glass Misc	Glass Misc
Probe Length (Feet):	0.840	4.0	
Probe Liner Material:		Glass	
Sample Plane:		Horizontal	
Port Length (Inches):		6.00	
Port Size (Diameter, Inches):		6.00	
Port Type:		Flange	
Duct Shape:		Rectangular	
Length (Feet):		3.5	
Width (Feet):		5.5	
Duct Area (Square Feet):		19.250	
Equivalent Diameter Rectangular Duct (Feet):		4.278	
Upstream Diameters:		>.5	
Downstream Diameters:		>2	
Number of Ports Sampled:		5	
Number of Points per Port:		5	
Minutes per Point:		5.0	
Minutes per Reading:		5.0	
Total Number of Traverse Points:		25	
Test Length (Minutes):		125	
Train Type:		Hot Box	
Source Condition:		Normal	
Servomex Serial Number:			
Moisture Balance ID:			
# of Runs			3

Run 1-Method 5

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Test Location: Hurst Boiler Exhaust Duct
 Source Condition: Normal

Date: 11/4/14
 Start Time: 8:35
 End Time: 11:05

DRY GAS METER CONDITIONS			STACK CONDITIONS		
ΔH:	1.09	in. H ₂ O	Static Pressure	-0.10	in. H ₂ O
Meter Temperature, T _m :	75.5	°F	Flue Pressure (Ps):	29.64	in. Hg. abs.
Sqrt ΔP:	0.160	in. H ₂ O	Carbon Dioxide:	11.60	%
Stack Temperature, T _s :	358.2	°F	Oxygen:	8.90	%
Meter Volume, V _m :	78.991	ft ³	Nitrogen:	79.50	%
Meter Volume, V _{mstd} :	77.462	dscf	Gas Weight dry, Md:	30.212	lb/lb mole
Meter Volume, V _{wstd} :	11.770	wscf	Gas Weight wet, Ms:	28.601	lb/lb mole
Isokinetic Variance:	99.7	%l	Excess Air:	73.627	%
Standard Fuel Factor F _d :	9,240.0	dscf/mmBtu	Gas Velocity, V _s :	11.274	fps
Test Length	125.00	in mins.	Volumetric Flow:	13,022	acfpm
Nozzle Diameter	0.551	in inches	Volumetric Flow:	7,227	dscfm
Barometric Pressure	29.65	in Hg	Volumetric Flow:	8,325	scfm
Calculated F _o :	1.03		Fo Validity:	Pass	

MOISTURE DETERMINATION

Initial Impinger Content:	1973.9	ml	Silica Initial Wt.	833.7	grams
Final Impinger Content:	2194.9	ml	Silica Final Wt.	862.6	grams
Impinger Difference:	221.0	ml	Silica Difference:	28.9	grams
Total Water Gain:	249.9		Moisture, Bws:	0.132	

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp			Collected Vol. ft ³	Point Vel ft/sec
						Inlet °F	Outlet °F	Sqrt. Δp		
1-1	8:35:00	0.02	0.82	48,115	356	72	71	0.141	2.788	9.977
-2	8:40:00	0.01	0.41	50,903	359	72	71	0.100	1.964	7.055
-3	8:45:00	0.02	0.82	52,867	356	72	71	0.141	2.767	9.977
-4	8:50:00	0.02	0.82	55,634	357	74	72	0.141	2.783	9.977
-5	8:55:00	0.01	0.41	58,417	353	74	72	0.100	1.986	7.055
	9:00:00			60,403						
2-1	9:03:00	0.03	1.23	60,403	361	74	73	0.173	3,413	12.219
-2	9:08:00	0.03	1.23	63,816	362	77	74	0.173	3,409	12.219
-3	9:13:00	0.03	1.24	67,225	360	77	74	0.173	3,404	12.219
-4	9:18:00	0.03	1.24	70,629	359	78	74	0.173	3,440	12.219
-5	9:23:00	0.02	0.83	74,069	354	78	74	0.141	2,809	9.977
	9:28:00			76,878						
3-1	9:40:00	0.04	1.64	76,878	364	77	75	0.200	3,947	14.110
-2	9:45:00	0.04	1.65	80,825	363	78	75	0.200	3,926	14.110
-3	9:50:00	0.04	1.65	84,751	362	78	75	0.200	3,967	14.110
-4	9:55:00	0.03	1.24	88,718	360	78	75	0.173	3,427	12.219
-5	10:00:00	0.03	1.25	92,145	352	79	75	0.173	3,443	12.219
	10:05:00			95,588						
4-1	10:10:00	0.03	1.24	95,588	357	77	75	0.173	3,431	12.219
-2	10:15:00	0.04	1.65	99,019	360	78	75	0.200	3,962	14.110
-3	10:20:00	0.03	1.24	102,981	361	78	75	0.173	3,413	12.219
-4	10:25:00	0.03	1.24	106,394	358	79	75	0.173	3,444	12.219
-5	10:30:00	0.02	0.83	109,838	355	79	76	0.141	2,803	9.977
	10:35:00			112,641						
5-1	10:40:00	0.03	1.24	112,641	360	77	76	0.173	3,433	12.219
-2	10:45:00	0.03	1.24	116,074	360	78	76	0.173	3,433	12.219
-3	10:50:00	0.02	0.83	119,507	357	78	76	0.141	2,805	9.977
-4	10:55:00	0.02	0.83	122,312	356	79	76	0.141	2,812	9.977
-5	11:00:00	0.01	0.42	125,124	354	79	76	0.100	1,982	7.055
	11:05:00			127,106						

Total	2:05:00		78.991	76.8	74.3		78.991
Average		1.09	358.2	75.5		0.160	
Min		0.41	352.0	71.0		0.100	
Max		1.65	364.0	79.0		0.200	

Run 2-Method 5

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Test Location: Hurst Boiler Exhaust Duct
 Source Condition: Normal

Date: 11/4/14
 Start Time: 11:30
 End Time: 13:47

DRY GAS METER CONDITIONS				STACK CONDITIONS						
Meter Temperature, Tm:	74.8	*F		Static Pressure	-0.10	in. H ₂ O				
Sqrt ΔP:	0.161	in. H ₂ O		Flue Pressure (Ps):	29.64	in. Hg. abs.				
Slack Temperature, Ts:	364.5	*F		Carbon Dioxide:	11.40	%				
Meter Volume, Vm:	79.876	ft ³		Oxygen:	9.10	%				
Meter Volume, Vmstd:	78.437	dscf		Nitrogen:	79.5	%				
Meter Volume, Vwstd:	13.711	wscf		Gas Weight dry, Md:	30.188	lb/lb mole				
Isokinetic Variance:	102.1	%l		Gas Weight wet, Ms:	28.375	lb/lb mole				
Standard Fuel Factor Fd:	9,240.00	dscf/mmBtu		Excess Air:	78.548	%				
Test Length	125.00	in mins.		Gas Velocity, Vs:	11.466	fps				
Nozzle Diameter	0.551	in inches		Volumetric Flow:	13,243	acfm				
Barometric Pressure	29.65	in Hg		Volumetric Flow:	7,152	dscfm				
Calculated Fo:	1.04			Volumetric Flow:	8,402	scfm				
MOISTURE DETERMINATION				Fo Validity:	Pass					
Initial Impinger Content:	2005.3	ml		Silica Initial Wt.	848.0	grams				
Final Impinger Content:	2275.3	ml		Silica Final Wt.	869.1	grams				
Impinger Difference:	270.0	ml		Silica Difference:	21.1	grams				
Total Water Gain:	291.1			Moisture, Bws:	0.149					
Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Outlet °F	Sqrt. Δp	Collected Vol. ft ³	Point Vel ft/sec
1-1	11:30:00	0.02	0.83	27.642	364	73	73	0.141	2.804	10.055
-2	11:35:00	0.02	0.83	30.446	367	73	72	0.141	2.788	10.055
-3	11:40:00	0.02	0.82	33.234	368	73	72	0.141	2.780	10.055
-4	11:45:00	0.02	0.83	36.014	368	75	72	0.141	2.789	10.055
-5	11:50:00	0.01	0.42	38.803	359	75	73	0.100	1.976	7.110
	11:55:00			40.779						
2-1	11:58:00	0.03	1.24	40.779	367	75	73	0.173	3.431	12.315
-2	12:03:00	0.04	1.65	44.210	368	75	73	0.200	3.948	14.220
-3	12:08:00	0.03	1.24	48.158	366	77	73	0.173	3.422	12.315
-4	12:13:00	0.03	1.25	51.580	365	77	73	0.173	3.434	12.315
-5	12:18:00	0.02	0.84	55.014	361	77	73	0.141	2.807	10.055
	12:23:00			57.821						
3-1	12:26:00	0.04	1.66	57.821	366	76	73	0.200	3.971	14.220
-2	12:31:00	0.04	1.66	61.792	367	77	73	0.200	3.949	14.220
-3	12:36:00	0.04	1.66	65.741	366	77	74	0.200	3.967	14.220
-4	12:41:00	0.04	1.66	69.708	369	78	74	0.200	3.943	14.220
-5	12:46:00	0.03	1.25	73.651	364	78	74	0.173	3.447	12.315
	12:51:00			77.098						
4-1	12:54:00	0.03	1.24	77.098	368	77	74	0.173	3.420	12.315
-2	12:59:00	0.03	1.24	80.518	370	77	74	0.173	3.441	12.315
-3	13:04:00	0.03	1.24	83.959	372	77	74	0.173	3.423	12.315
-4	13:09:00	0.03	1.24	87.382	369	77	74	0.173	3.416	12.315
-5	13:14:00	0.02	0.83	90.798	363	77	74	0.141	2.813	10.055
	13:19:00			93.611						
5-1	13:22:00	0.02	0.87	93.611	330	76	74	0.141	2.873	10.055
-2	13:27:00	0.03	1.27	96.484	353	77	74	0.173	3.450	12.315
-3	13:32:00	0.02	0.83	99.934	369	77	74	0.141	2.802	10.055
-4	13:37:00	0.02	0.83	102.736	370	78	74	0.141	2.794	10.055
-5	13:42:00	0.01	0.42	105.530	364	78	74	0.100	1.988	7.110
	13:47:00			107.518						

Total	2:05.00		79.876	76.3	73.4		79.876
Average		1.11	364.5	74.8		0.161	
Min		0.42	330.0	72.0		0.100	
Max		1.66	372.0	78.0		0.200	

Run 3-Method 5

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Test Location: Hurst Boiler Exhaust Duct
 Source Condition: Normal

Date: 11/4/14
 Start Time: 14:15
 End Time: 16:32

DRY GAS METER CONDITIONS			STACK CONDITIONS		
ΔH:	1.03	In. H ₂ O	Static Pressure	-0.10	in. H ₂ O
Meter Temperature, T _m :	81.4	°F	Flue Pressure (Ps):	29.64	in. Hg. abs.
Sqrt ΔP:	0.156	In. H ₂ O	Carbon Dioxide:	11.80	%
Stack Temperature, T _s :	373.9	°F	Oxygen:	8.80	%
Meter Volume, V _m :	77.553	ft ³	Nitrogen:	79.4	%
Meter Volume, V _{mstd} :	75.223	dscf	Gas Weight dry, Md:	30.240	lb/lb mole
Meter Volume, V _{wstd} :	12.985	wsfc	Gas Weight wet, Ms:	28.438	lb/lb mole
Isokinetic Variance:	102.0	%l	Excess Air:	72.359	%
Standard Fuel Factor F _d :	9,240.00	dscf/mmbtu	Gas Velocity, Vs:	11.107	fps
Test Length	125.00	in mins.	Volumetric Flow:	12,828	acfm
Nozzle Diameter	0.551	in inches	Volumetric Flow:	6,863	dscfm
Barometric Pressure	29.65	in Hg	Volumetric Flow:	8,047	scfm
Calculated F _o :	1.03		Fo Validity:	Pass	

MOISTURE DETERMINATION

Initial Impinger Content:	1932.6	ml	Silica Initial Wt.	852.7	grams
Final Impinger Content:	2189.6	ml	Silica Final Wt.	871.4	grams
Impinger Difference:	257.0	ml	Silica Difference:	18.7	grams
Total Water Gain:	275.7		Moisture, Bws:	0.147	

Port- Point No.	Clock Time	Velocity Head Δp In. H ₂ O	Orifice ΔH In. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp		Sqr. Δp	Collected Vol. ft ³	Point Vel ft/sec
						Inlet °F	Outlet °F			
1-1	14:15:00	0.02	0.82	8.548	377	77	77	0.141	2.799	10.101
-2	14:20:00	0.02	0.82	11.347	378	80	77	0.141	2.802	10.101
-3	14:25:00	0.02	0.82	14.149	379	82	78	0.141	2.803	10.101
-4	14:30:00	0.02	0.83	16.952	379	83	78	0.141	2.804	10.101
-5	14:35:00	0.01	0.42	19.756	372	83	78	0.100	1.992	7.142
	14:40:00			21.748						
2-1	14:43:00	0.03	1.24	21.748	378	81	79	0.173	3.458	12.371
-2	14:48:00	0.03	1.25	25.206	375	84	80	0.173	3.447	12.371
-3	14:53:00	0.03	1.25	28.653	375	85	80	0.173	3.454	12.371
-4	14:58:00	0.03	1.25	32.107	373	85	80	0.173	3.464	12.371
-5	15:03:00	0.02	0.84	35.571	371	86	81	0.141	2.822	10.101
	15:08:00			38.393						
3-1	15:11:00	0.03	1.26	38.393	371	86	81	0.173	3.491	12.371
-2	15:16:00	0.04	1.67	41.884	372	85	81	0.200	3.998	14.285
-3	15:21:00	0.04	1.67	45.882	374	85	81	0.200	3.996	14.285
-4	15:26:00	0.03	1.25	49.878	375	85	81	0.173	3.460	12.371
-5	15:31:00	0.02	0.84	53.338	370	84	81	0.141	2.828	10.101
	15:36:00			56.166						
4-1	15:39:00	0.03	1.25	56.166	374	83	81	0.173	3.477	12.371
-2	15:44:00	0.03	1.25	59.643	375	83	80	0.173	3.421	12.371
-3	15:49:00	0.03	1.25	63.064	374	83	80	0.173	3.482	12.371
-4	15:54:00	0.02	0.83	66.546	374	83	80	0.141	2.811	10.101
-5	15:59:00	0.02	0.84	69.357	369	84	80	0.141	2.833	10.101
	16:04:00			72.190						
5-1	16:07:00	0.02	0.83	72.190	374	82	80	0.141	2.823	10.101
-2	16:12:00	0.03	1.25	75.013	375	82	80	0.173	3.459	12.371
-3	16:17:00	0.02	0.83	78.472	373	82	79	0.141	2.812	10.101
-4	16:22:00	0.02	0.83	81.284	372	82	79	0.141	2.819	10.101
-5	16:27:00	0.01	0.42	84.103	368	82	79	0.100	1.998	7.142
	16:32:00			86.101						

Total	2.05 00		77.553	83.1	79.6	77.553
Average		1.03	373.9	81.4		0.156
Min		0.42	368.0	77.0		0.100
Max		1.67	379.0	86.0		0.200

Client: University of Iowa
Facility: Oakdale Renewable Energy Center
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/4/14
Run 1

Time	CO2 % (dry)	O2 % (dry)
8:35	11.97	8.60
8:36	12.74	7.78
8:37	12.34	8.28
8:38	11.76	8.86
8:39	11.32	9.24
8:40	10.97	9.55
8:41	10.84	9.66
8:42	11.04	9.46
8:43	11.22	9.29
8:44	11.39	9.20
8:45	11.28	9.24
8:46	11.37	9.17
8:47	11.63	8.95
8:48	11.66	8.87
8:49	11.77	8.78
8:50	12.09	8.50
8:51	12.33	8.26
8:52	12.25	8.37
8:53	11.92	8.66
8:54	11.90	8.69
8:55	11.74	8.82
8:56	12.01	8.54
8:57	11.93	8.64
8:58	12.01	8.58
8:59	12.48	8.10
9:00	12.32	8.25
9:01	12.57	8.11
9:02	11.68	8.91
9:03	11.04	9.49
9:04	11.39	9.19
9:05	11.34	9.18
9:06	11.52	9.06
9:07	11.52	9.07
9:08	11.27	9.24
9:09	11.41	9.17
9:10	11.51	9.04
9:11	11.78	8.77
9:12	11.93	8.64
9:13	11.92	8.66
9:14	11.82	8.73
9:15	11.65	8.93
9:16	11.44	9.11
9:17	11.68	8.75
9:18	11.70	8.91
9:19	11.45	9.14
9:20	11.19	9.30
9:21	11.39	9.17
9:22	11.86	8.69
9:23	12.19	8.32
9:24	11.54	9.05
9:25	11.10	9.46
9:26	10.72	9.78
9:27	10.76	9.74
9:28	10.78	9.79
9:29	10.94	9.61
9:30	11.23	9.32
9:31	11.35	9.18
9:32	11.77	8.82
9:33	11.93	8.68
9:34	11.77	8.82
9:35	11.65	8.92
9:36	11.62	8.96
9:37	11.57	8.97
9:38	11.75	8.81
9:39	11.79	8.79
9:40	11.97	8.65
9:41	11.79	8.76
9:42	11.68	8.92
9:43	11.66	8.90
9:44	11.69	8.90
9:45	11.73	8.86

9:46	11.78	8.85
9:47	12.12	8.40
9:48	12.45	8.18
9:49	11.79	8.83
9:50	11.11	9.44
9:51	11.15	9.38
9:52	11.23	9.32
9:53	11.62	8.99
9:54	11.54	9.03
9:55	11.71	8.89
9:56	11.65	8.95
9:57	11.60	8.97
9:58	11.76	8.84
9:59	11.71	8.88
10:00	11.84	8.76
10:01	11.38	9.15
10:02	11.78	8.83
10:03	11.33	9.22
10:04	11.32	9.26
10:05	11.36	9.22
10:06	11.23	9.32
10:07	11.43	9.12
10:08	11.54	9.09
10:09	11.56	9.01
10:10	11.77	8.83
10:11	11.80	8.73
10:12	12.38	8.30
10:13	11.78	8.84
10:14	11.45	9.14
10:15	11.20	9.39
10:16	11.40	9.16
10:17	11.47	9.14
10:18	11.54	9.04
10:19	11.62	8.97
10:20	11.62	8.94
10:21	11.72	8.89
10:22	11.41	9.16
10:23	11.54	9.03
10:24	11.65	8.93
10:25	11.62	8.96
10:26	11.77	8.83
10:27	11.94	8.63
10:28	11.90	8.72
10:29	11.91	8.69
10:30	11.76	8.83
10:31	11.61	8.99
10:32	11.23	9.30
10:33	11.88	8.74
10:34	11.92	8.68
10:35	12.13	8.47
10:36	12.69	7.90
10:37	11.95	8.69
10:38	11.45	9.17
10:39	11.05	9.51
10:40	11.01	9.52
10:41	11.21	9.34
10:42	11.33	9.26
10:43	11.29	9.30
10:44	11.21	9.34
10:45	11.20	9.41
10:46	11.26	9.29
10:47	11.36	9.15
10:48	11.52	9.06
10:49	11.66	8.93
10:50	11.73	8.83
10:51	11.77	8.84
10:52	11.55	8.99
10:53	11.79	8.79
10:54	11.90	8.71
10:55	11.84	8.74
10:56	11.87	8.74
10:57	11.97	8.64
10:58	12.08	8.54
10:59	12.13	8.51
11:00	12.46	8.11
11:01	12.51	8.16
11:02	11.98	8.68
Average	11.65	8.93
Min	10.72	7.78
Max	12.74	9.79

Client: University of Iowa
 Facility: Oakdale Renewable Energy Center
 Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/4/14
Run 2

<u>Time</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>
11:30	11.24	9.31
11:31	11.44	9.18
11:32	11.24	9.33
11:33	11.13	9.37
11:34	11.59	8.99
11:35	11.67	8.90
11:36	11.66	8.95
11:37	11.62	8.92
11:38	11.73	8.84
11:39	11.70	8.85
11:40	11.63	8.94
11:41	11.77	8.80
11:42	11.91	8.65
11:43	11.92	8.64
11:44	11.60	8.96
11:45	11.29	9.22
11:46	11.44	9.11
11:47	11.66	8.87
11:48	11.89	8.67
11:49	12.34	8.25
11:50	11.79	8.80
11:51	11.33	9.24
11:52	11.25	9.32
11:53	11.33	9.22
11:54	11.37	9.20
11:55	11.41	9.17
11:56	11.43	9.13
11:57	11.45	9.12
11:58	11.59	8.97
11:59	11.54	9.01
12:00	11.78	8.77
12:01	11.68	8.88
12:02	11.34	9.19
12:03	11.40	9.14
12:04	11.50	9.04
12:05	11.40	9.16
12:06	11.60	8.95
12:07	11.61	8.95
12:08	11.71	8.88
12:09	11.52	9.03
12:10	11.56	9.00
12:11	11.53	9.01
12:12	12.11	8.42
12:13	12.46	8.10
12:14	12.40	8.25
12:15	11.50	9.13
12:16	10.74	9.78
12:17	10.95	9.57
12:18	10.97	9.56
12:19	11.12	9.42
12:20	11.33	9.25
12:21	11.50	9.09
12:22	11.39	9.19
12:23	11.52	9.05
12:24	11.62	8.94
12:25	11.44	9.10
12:26	11.39	9.19
12:27	11.46	9.08
12:28	11.39	9.14
12:29	11.55	9.02
12:30	11.54	9.01
12:31	11.41	9.16
12:32	11.47	9.08
12:33	11.47	9.08
12:34	11.72	8.86
12:35	11.71	8.90

12:36	12.05	8.52
12:37	12.47	8.11
12:38	12.71	7.90
12:39	12.03	8.62
12:40	11.49	9.08
12:41	11.19	9.37
12:42	11.29	9.27
12:43	11.30	9.27
12:44	11.45	9.11
12:45	11.67	8.92
12:46	11.67	8.93
12:47	11.84	8.74
12:48	11.80	8.78
12:49	11.68	8.89
12:50	11.84	8.93
12:51	11.49	9.07
12:52	11.62	8.95
12:53	11.67	8.89
12:54	11.79	8.79
12:55	11.95	8.65
12:56	11.81	8.80
12:57	11.71	8.88
12:58	11.80	8.80
12:59	12.16	8.40
13:00	12.17	8.45
13:01	12.59	8.07
13:02	12.21	8.43
13:03	11.62	8.95
13:04	11.38	9.20
13:05	11.38	9.18
13:06	11.38	9.18
13:07	11.42	9.14
13:08	11.67	8.90
13:09	11.70	8.87
13:10	11.74	8.79
13:11	12.01	8.59
13:12	11.81	8.80
13:13	11.46	9.06
13:14	12.03	8.53
13:15	11.73	8.86
13:16	11.74	8.83
13:17	11.73	8.78
13:18	11.71	9.10
13:19	8.48	12.07
13:20	8.30	12.17
13:21	8.82	11.66
13:22	9.02	11.27
13:23	9.33	10.91
13:24	8.55	11.88
13:25	9.10	11.32
13:26	10.74	9.69
13:27	11.08	9.42
13:28	11.07	9.45
13:29	11.27	9.27
13:30	11.35	9.20
13:31	11.66	8.90
13:32	11.54	9.07
13:33	11.69	8.83
13:34	11.84	8.74
13:35	12.01	8.56
13:36	12.07	8.49
13:37	12.04	8.55
13:38	12.05	8.54
13:39	11.88	8.67
13:40	11.84	8.75
13:41	11.69	8.83
13:42	11.99	8.58
13:43	12.39	8.20
13:44	11.98	8.56
13:45	11.69	8.91
13:46	12.29	8.29
13:47	11.84	8.78
Average	11.50	9.06
Min	8.30	7.90
Max	12.71	12.17

Client: University of Iowa
Facility: Oakdale Renewable Energy Center
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/4/14
Run 3

Time	CO2 % (dry)	O2 % (dry)
14:15	11.54	8.98
14:16	11.73	8.83
14:17	11.76	8.82
14:18	11.85	8.70
14:19	11.91	8.66
14:20	11.90	8.66
14:21	12.04	8.54
14:22	11.83	8.73
14:23	11.96	8.60
14:24	11.83	8.73
14:25	11.79	8.73
14:26	11.76	8.78
14:27	11.79	8.75
14:28	11.76	8.76
14:29	11.66	8.87
14:30	11.68	8.87
14:31	11.57	8.93
14:32	11.53	8.96
14:33	11.81	8.70
14:34	11.76	8.78
14:35	12.69	7.85
14:36	11.98	8.59
14:37	11.50	9.03
14:38	11.37	9.12
14:39	11.34	9.19
14:40	11.29	9.22
14:41	11.31	9.18
14:42	11.68	8.87
14:43	11.82	8.78
14:44	11.86	8.72
14:45	11.95	8.64
14:46	12.10	8.50
14:47	12.16	8.45
14:48	12.03	8.53
14:49	11.85	8.75
14:50	11.77	8.79
14:51	11.72	8.82
14:52	11.84	8.73
14:53	11.78	8.79
14:54	11.69	8.88
14:55	11.52	9.03
14:56	11.57	8.98
14:57	11.68	8.87
14:58	11.74	8.83
14:59	12.60	7.94
15:00	12.54	8.01
15:01	11.84	8.77
15:02	11.22	9.32
15:03	11.18	9.32
15:04	11.18	9.34
15:05	11.27	9.27
15:06	11.44	9.10
15:07	11.49	9.06
15:08	11.76	8.83
15:09	11.89	8.68
15:10	11.97	8.60
15:11	11.89	8.70
15:12	11.98	8.60
15:13	12.00	8.56
15:14	12.10	8.49
15:15	12.07	8.51
15:16	12.11	8.46
15:17	12.08	8.52
15:18	11.97	8.62
15:19	12.09	8.50
15:20	11.99	8.59

15:21	11.69	8.92
15:22	11.81	8.93
15:23	11.63	8.93
15:24	11.87	8.72
15:25	12.14	8.41
15:26	12.44	8.19
15:27	11.98	8.65
15:28	11.66	8.91
15:29	11.53	9.05
15:30	11.45	9.11
15:31	11.53	9.04
15:32	11.58	8.99
15:33	11.70	8.87
15:34	11.74	8.84
15:35	11.80	8.79
15:36	11.81	8.76
15:37	11.92	8.68
15:38	11.92	8.67
15:39	11.92	8.66
15:40	11.90	8.69
15:41	11.98	8.61
15:42	11.73	8.86
15:43	11.67	8.89
15:44	11.79	8.80
15:45	11.81	8.78
15:46	11.79	8.79
15:47	11.71	8.86
15:48	11.79	8.80
15:49	11.67	8.87
15:50	12.34	8.23
15:51	12.05	8.58
15:52	11.67	8.92
15:53	11.69	8.90
15:54	11.66	8.92
15:55	11.72	8.86
15:56	11.61	8.96
15:57	11.67	8.92
15:58	11.78	8.81
15:59	11.67	8.89
16:00	11.74	8.81
16:01	11.85	8.74
16:02	12.03	8.53
16:03	11.92	8.68
16:04	11.85	8.73
16:05	11.99	8.59
16:06	11.98	8.62
16:07	11.94	8.65
16:08	11.88	8.72
16:09	11.92	8.68
16:10	11.95	8.64
16:11	11.87	8.73
16:12	11.87	8.71
16:13	11.87	8.73
16:14	11.91	8.69
16:15	12.39	8.15
16:16	12.13	8.52
16:17	11.83	8.78
16:18	11.79	8.81
16:19	11.65	8.94
16:20	11.59	9.00
16:21	11.67	8.90
16:22	11.60	8.97
16:23	11.75	8.82
16:24	11.77	8.81
16:25	11.84	8.74
16:26	11.93	8.62
16:27	12.02	8.57
16:28	12.15	8.42
16:29	12.16	8.44
16:30	12.18	8.43
16:31	12.12	8.48
16:32	11.94	8.65
Average	11.82	8.75
Min	11.18	7.85
Max	12.69	9.34

Method 30B (Sorbent Trap) Mercury Test Results Summary

University of Iowa

Oakdale Renewable Energy Plant

Hurst Boiler Exhaust Duct

Test No.	Date	Start Time	End Time	V _m (standard L)	ng detected	ppb	O ₂ , % dry	ug/dscm	ug/wscm	Ib/Tbtu (Fd Factor)	paired trap agreement, % difference			
1A	11/5/2014	11:35	12:45	137.576	85.60	0.07	11.20	0.62	0.58	0.7733				
1B				135.462	78.90	0.07	11.20	0.58	0.52	0.7239				
Average				82.26	0.07	11.20	0.60	0.54	0.7486	3.30				
2A	11/5/2014	13:25	14:35	136.702	59.20	0.05	11.00	0.43	0.39	0.5274				
2B				132.931	53.40	0.05	11.00	0.40	0.36	0.4892				
Average				56.30	0.05	11.00	0.42	0.37	0.5083	3.75				
3A	11/5/2014	15:13	16:05	116.988	28.90	0.03	10.40	0.25	0.22	0.2836				
3B				96.283	25.60	0.03	10.40	0.27	0.24	0.3053				
Average				27.25	0.03	10.40	0.26	0.23	0.2945	-3.68				
Overall Average*				69.28	0.06	11.10	0.51	0.46	0.6284					

*Unit tripped during Run 3 and was not included in the average

METHOD 30B TEST RESULTS

Project #: M144705
 Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Fuel Type: Wood
 Hg Analyzer ID:

Location: Hurst Boiler Exhaust Duct
 Condition: Normal
 Data Taken By: JHK
 Fuel Factor: 9240
 Diluent: O2 %

Test Number:	1A	Trap Number:	OL210119
Pressure, Barometric(Hg"):	29.700		
Initial Volume (liters)	0		
Final Volume (liters)	140.532		
Meter Temperature (°F)	81.80		
Meter Calibration (Y)	1.012		
CO2 %	9.30		
O2 %	11.20		

Start Time:	11:35	End Time:	12:45	Date:	11/5/2014
Hg (ng)					85.6
Water Vapor In Flue Gas (Bws)					0.100
Meter Volume (Standard liters)					137.576
Hg (ppb)					0.07
Hg (ug/dscm)					0.62
Hg (lb/Tbtu), Fd Factor					0.773313

Test Number:	2A	Trap Number:	OLC012446
Pressure, Barometric(Hg"):	29.700		
Initial Volume (liters)	0		
Final Volume (liters)	140.464		
Meter Temperature (°F)	85.00		
Meter Calibration (Y)	1.012		
CO2 %	9.60		
O2 %	11.00		

Start Time:	13:25	End Time:	14:35	Date:	11/5/2014
Hg (ng)					59.2
Water Vapor in Flue Gas (Bws)					0.104
Meter Volume (Standard liters)					136.702
Hg (ppb)					0.05
Hg (ug/dscm)					0.43
Hg (lb/Tbtu), Fd Factor					0.527360

Test Number:	3A	Trap Number:	OL210456
Pressure, Barometric(Hg"):	29.700		
Initial Volume (liters)	0		
Final Volume (liters)	101.459		
Meter Temperature (°F)			
Meter Calibration (Y)	1.012		
CO2 %	10.10		
O2 %	10.40		

Start Time:	15:13	End Time:	16:05	Date:	11/5/2014
Hg (ng)					28.9
Water Vapor in Flue Gas (Bws)					0.100
Meter Volume (Standard liters)					118.988
Hg (ppb)					0.03
Hg (ug/dscm)					0.25
Hg (lb/Tbtu), Fd Factor					0.283639

METHOD 30B TEST RESULTS

Project #: M144705
 Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Fuel Type: Wood
 Hg Analyzer ID: 0

Location: Hurst Boiler Exhaust Duct
 Condition: Normal
 Data Taken By: JHK
 Fuel Factor: 9240
 Diluent: O2 %

Test Number: 1B Trap Number: OL211390
 Pressure, Barometric(Hg")..... 29.700
 Initial Volume (liters)..... 0
 Final Volume (liters)..... 142.173
 Meter Temperature (°F)..... 82.93
 Meter Calibration (Y)..... 0.987
 CO2 %..... 9.30
 O2 %..... 11.20

	Start Time:	11:35	End Time:	12:45	Date:	11/5/2014
Hg (mg).....						78.9
Water Vapor in Flue Gas (Bws):.....						0.100
Meter Volume (Standard liters):.....						135.462
Hg (ppb):.....						0.07
Hg (ug/dscm):.....						0.58
Hg (lb/Tbtu), Fd Factor.....						0.723911
Spiked Trap Run.....						Y
Spike Concentration.....						25

Test Number: 2B Trap Number: OL201242
 Pressure, Barometric(Hg")..... 29.700
 Initial Volume (liters)..... 0
 Final Volume (liters)..... 140.639
 Meter Temperature (°F)..... 87.30
 Meter Calibration (Y)..... 0.987
 CO2 %..... 9.60
 O2 %..... 11.00

	Start Time:	13:25	End Time:	14:35	Date:	11/5/2014
Hg (mg).....						53.4
Water Vapor in Flue Gas (Bws):.....						0.104
Meter Volume (Standard liters):.....						132.931
Hg (ppb):.....						0.05
Hg (ug/dscm):.....						0.40
Hg (lb/Tbtu), Fd Factor.....						0.489191
Spiked Trap Run.....						Y
Spike Concentration.....						25

Test Number: 3B Trap Number: OL211459
 Pressure, Barometric(Hg")..... 29.700
 Initial Volume (liters)..... 0
 Final Volume (liters)..... 101.81
 Meter Temperature (°F)..... 87.00
 Meter Calibration (Y)..... 0.987
 CO2 %..... 10.10
 O2 %..... 10.40

	Start Time:	15:13	End Time:	16:05	Date:	11/5/2014
Hg (mg).....						25.6
Water Vapor in Flue Gas (Bws):.....						0.100
Meter Volume (Standard liters):.....						96.283
Hg (ppb):.....						0.03
Hg (ug/dscm):.....						0.27
Hg (lb/Tbtu), Fd Factor.....						0.305281
Spiked Trap Run.....						Y
Spike Concentration.....						25

Compliance Stratification Test Results Summary
 University of Iowa
Oakdale Renewable Energy Plant
Hurst Boiler Exhaust Duct
November 5, 2014

Number of Ports Sampled: 5
 Number of Points per Port: 4
 Total Number of Traverse Points: 20

Port No.	Point No.	Point Marking, Inches	Time	O ₂ %	Actual % Difference O ₂ %	CO ₂ %	Actual % Difference CO ₂ %	NO _x ppm	Actual % Difference NO _x ppm	CO ppm	Actual % Difference CO ppm
1	1	11.25	11:37	9.21	19.19	11.34	23.53	64.0	42.79	0.9	64.71
	2	21.75	11:40	9.40	17.53	11.12	21.13	62.3	39.00	0.3	88.24
	3	32.25	11:43	10.06	11.74	10.40	13.29	51.3	14.46	2.1	17.65
	4	42.75	11:46	10.56	7.35	10.02	9.15	55.8	24.50	0.3	88.24
2	1	11.25	11:57	9.68	15.07	10.83	17.97	45.1	0.62	4.7	84.31
	2	21.75	12:00	11.01	3.40	9.57	4.25	46.3	3.30	5.0	96.08
	3	32.25	12:03	10.59	7.08	9.97	8.61	41.6	7.18	1.4	45.10
	4	42.75	12:06	12.70	11.43	7.85	14.49	33.5	25.26	3.5	37.25
3	1	11.25	12:15	9.69	14.98	10.79	17.54	66.0	47.26	1.1	56.86
	2	21.75	12:18	10.74	5.77	9.78	6.54	54.0	20.48	0.3	88.24
	3	32.25	12:21	13.53	18.71	7.16	22.00	33.1	26.15	1.6	37.25
	4	42.75	12:24	14.14	24.06	6.65	27.56	28.5	36.41	1.9	25.49
4	1	11.25	12:34	9.55	16.21	10.98	19.61	45.4	1.29	3.8	49.02
	2	21.75	12:37	9.95	12.70	10.63	15.80	47.1	5.09	6.1	139.22
	3	32.25	12:40	12.56	10.20	8.03	12.53	46.6	3.97	3.1	21.57
	4	42.75	12:43	13.43	17.83	7.27	20.81	40.5	9.64	0.7	72.55
5	1	11.25	12:52	13.66	19.85	7.04	23.31	31.8	29.05	3.5	37.25
	2	21.75	12:55	12.19	6.95	8.32	9.37	36.3	19.01	3.2	25.49
	3	32.25	12:58	12.55	10.11	8.03	12.53	34.5	23.03	3.9	52.94
	4	42.75	13:01	12.75	11.87	7.82	14.81	32.7	27.04	3.6	41.18
Average				11.40		9.18		44.8		2.6	

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/5/14

Run 1

<u>Time</u>	<u>NOx ppmvd</u>	<u>CO ppmvd</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>
11:35	63.80	1.50	11.55	9.05
11:36	64.40	1.00	11.37	9.19
11:37	64.00	0.90	11.34	9.21
11:38	65.40	0.90	11.37	9.20
11:39	63.90	0.50	11.19	9.37
11:40	62.30	0.30	11.12	9.40
11:41	61.20	0.50	10.81	9.80
11:42	53.70	0.70	9.91	10.72
11:43	51.30	2.10	10.40	10.06
11:44	56.70	3.70	10.51	9.99
11:45	57.50	0.80	10.36	10.20
11:46	55.80	0.30	10.02	10.56
11:55	41.50	9.10	10.68	9.86
11:56	42.70	4.60	10.77	9.75
11:57	45.10	4.70	10.83	9.68
11:58	45.90	4.90	11.00	9.50
11:59	49.20	4.90	11.05	9.57
12:00	46.30	5.00	9.57	11.01
12:01	43.80	2.10	9.31	11.26
12:02	42.20	1.90	8.58	11.98
12:03	41.60	1.40	9.97	10.59
12:04	43.20	1.60	8.35	12.41
12:05	28.50	1.60	7.83	12.76
12:06	33.50	3.50	7.85	12.70
12:13	63.60	7.70	11.15	9.40
12:14	65.60	2.40	10.98	9.56
12:15	66.00	1.10	10.79	9.69
12:16	64.20	0.70	10.74	9.78
12:17	62.20	0.60	10.39	10.21
12:18	54.10	0.30	9.78	10.74
12:19	50.20	1.10	9.25	11.49
12:20	38.00	1.00	7.18	13.60
12:21	33.10	1.60	7.16	13.53
12:22	31.60	2.50	7.38	13.31
12:23	29.20	2.70	6.50	14.35
12:24	28.50	1.90	6.65	14.14
12:32	43.40	4.20	10.73	9.80
12:33	43.90	4.10	10.65	9.86
12:34	45.40	3.80	10.98	9.55
12:35	45.70	4.10	10.88	9.63
12:36	46.40	5.00	10.91	9.59
12:37	47.10	6.10	10.63	9.95
12:38	48.50	10.50	11.09	9.55
12:39	47.80	14.70	8.56	11.98
12:40	46.60	3.10	8.03	12.56
12:41	44.60	1.30	7.74	12.83
12:42	43.80	0.80	7.65	12.95
12:43	40.50	0.70	7.27	13.43
12:50	30.10	2.90	7.03	13.68
12:51	31.20	3.80	6.99	13.77
12:52	31.80	3.50	7.04	13.66
12:53	31.20	2.80	6.88	13.84
12:54	32.60	2.30	8.00	12.45
12:55	36.30	3.20	8.32	12.19
12:56	35.50	3.00	8.25	12.22
12:57	35.80	3.20	8.51	12.02
12:58	34.50	3.90	8.03	12.55
12:59	32.20	3.00	7.84	12.63
13:00	33.30	3.10	7.83	12.76
13:01	32.70	3.60	7.82	12.75
Average	45.80	3.00	9.36	11.23
Min	28.50	0.30	6.50	9.05
Max	66.00	14.70	11.55	14.35

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/5/14

Run 2

Time	NOx ppmvd	CO ppmvd	CO2 % (dry)	O2 % (dry)
13:25	26.50	3.20	6.51	14.30
13:26	24.90	4.80	6.73	14.02
13:27	24.60	4.80	6.60	14.16
13:28	25.50	4.70	6.63	14.14
13:29	27.00	4.40	7.25	13.38
13:30	29.40	3.70	7.39	13.20
13:31	30.20	5.00	7.29	13.40
13:32	32.60	7.60	9.22	11.12
13:33	42.10	22.00	10.19	10.27
13:34	50.60	11.10	10.52	9.96
13:35	53.50	4.80	9.94	10.63
13:36	51.40	3.10	9.48	11.00
13:43	47.10	2.10	10.19	10.31
13:44	45.60	3.30	10.26	10.24
13:45	45.10	5.70	10.45	10.06
13:46	44.90	5.40	10.62	9.84
13:47	45.00	8.00	10.00	10.63
13:48	41.60	6.30	9.21	11.29
13:49	41.70	3.00	8.27	12.40
13:50	35.90	1.50	7.47	13.18
13:51	36.50	1.10	7.41	13.20
13:52	33.10	1.00	5.98	14.92
13:53	25.70	0.60	5.33	15.53
13:54	25.80	0.60	5.23	15.63
14:01	41.40	12.20	10.27	10.24
14:02	41.10	9.50	10.23	10.27
14:03	40.60	9.40	10.47	10.03
14:04	40.00	12.00	10.24	10.30
14:05	38.30	13.60	10.17	10.30
14:06	39.80	15.30	10.78	9.71
14:07	42.00	14.50	10.55	10.05
14:08	39.60	9.80	9.82	10.69
14:09	37.20	7.80	9.12	11.41
14:10	35.80	5.30	8.61	12.02
14:11	32.50	5.00	8.60	11.87
14:12	35.40	7.10	8.58	11.83
14:19	49.90	4.60	11.04	9.46
14:20	50.40	4.20	11.00	9.47
14:21	52.50	3.10	11.24	9.27
14:22	53.00	4.00	11.20	9.30
14:23	54.50	3.40	11.09	9.39
14:24	56.10	3.40	10.92	9.56
14:25	56.30	2.80	10.88	9.67
14:26	52.70	5.80	10.37	10.04
14:27	58.10	15.40	10.77	9.72
14:28	62.30	7.80	10.54	9.95
14:29	64.10	3.80	10.33	10.12
14:30	64.70	1.70	10.22	10.33
14:37	52.80	1.60	11.07	9.39
14:38	50.90	2.20	11.14	9.36
14:39	49.80	3.20	11.14	9.39
14:40	48.70	3.10	11.14	9.36
14:41	47.50	3.90	11.14	9.34
14:42	47.20	5.40	11.16	9.37
14:43	46.00	9.00	10.75	10.04
14:44	43.80	5.90	10.85	9.34
14:45	46.10	6.60	11.30	9.21
14:46	49.10	5.60	10.82	9.76
14:47	52.70	4.20	11.15	9.43
14:48	51.60	3.40	9.76	10.68
Average	43.50	5.90	9.61	10.94
Min	24.60	0.60	5.23	9.21
Max	64.70	22.00	11.30	15.63

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/5/14

Run 3

<u>Time</u>	<u>NOx ppmvd</u>	<u>CO ppmvd</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>
15:13	43.30	9.50	11.24	9.29
15:14	43.60	8.40	11.20	9.30
15:15	43.30	7.30	11.32	9.20
15:16	44.70	6.40	11.40	9.13
15:17	44.50	6.10	11.37	9.16
15:18	43.60	7.00	10.88	9.63
15:19	42.70	11.40	10.96	9.53
15:20	42.80	12.20	10.70	9.78
15:21	45.50	21.40	11.54	8.96
15:22	52.70	28.00	11.24	9.26
15:23	54.10	10.70	10.96	9.49
15:24	52.50	3.80	10.86	9.61
15:32	41.60	10.90	10.91	9.55
15:33	41.10	12.40	10.85	9.64
15:34	42.70	10.70	10.87	9.61
15:35	42.80	13.00	11.07	9.42
15:36	44.30	15.60	11.07	9.42
15:37	45.30	13.70	10.55	10.02
15:38	45.20	9.30	10.44	9.95
15:39	45.90	11.90	9.91	10.63
15:40	46.40	9.80	9.75	10.79
15:41	44.40	7.60	9.65	10.85
15:42	41.40	5.20	9.10	11.48
15:43	42.40	5.00	8.82	11.74
15:50	55.40	19.40	10.89	9.53
15:51	56.30	4.70	10.64	9.87
15:52	53.20	2.60	10.46	9.95
15:53	49.90	3.60	10.22	10.31
15:54	43.50	4.80	9.67	10.86
15:55	40.30	5.90	9.59	10.91
15:56	39.40	6.30	9.20	11.45
15:57	32.70	4.70	7.64	12.93
15:58	29.80	5.80	7.72	12.78
15:59	31.00	5.50	7.95	12.57
16:00	32.80	5.60	7.81	12.70
16:01	32.40	6.50	7.87	12.65

Average	43.70	9.20	10.18	10.33
Min	29.80	2.60	7.64	8.96
Max	56.30	28.00	11.54	12.93

Client:	University of Iowa
Facility:	Oakdale Renewable Energy Center
Test Location:	Hurst Boiler Exhaust Duct
Project #:	M144705
Test Method:	2
Test Engineer:	SMcG
Test Technician:	JHK
Type of Fuel Firing:	Wood
Temp ID:	CM19
Meter ID:	CM19
Pitot ID:	91
Pitot Type:	S-Type
Pitot Tube Coefficient:	0.840
Probe Length:	4.0
Sample Plane:	Horizontal
Port Length:	6.00
Port Size (diameter):	6.00
Port Type:	Flange
Duct Shape:	Rectangular
Length (traverse side of duct):	3.5
Width:	5.5
Location of Test Ports:	Side of duct
Duct Area:	19.25
Equivalent Diameter Rectangular Duct:	4.278
Upstream Diameters:	>0.5
Downstream Diameters:	>2.0
Number of Ports Sampled:	5
Number of Points per Port:	5
Total Number of Traverse Points:	25
Operating Level:	Normal
Normal Load:	(Normal)
Servomex Serial Number:	
Moisture Balance ID:	
Fluke ID:	
Stack Liner Material:	S
Default WAF:	0.995
Calculated WAF:	
Type of WAF Applied:	N
Actual WAF Applied to all runs:	

METHOD 2 VOLUMETRIC FLOW DATA

Project Number:	M144705	Operating Level:	Normal	(Normal)
Client:	University of Iowa	Run No.:	1	
Facility:	Oakdale Renewable Energy Center	Test Date:	11/5/2014	
Test Location:	Hurst Boiler Exhaust Duct	Start Time:	11:10	
Pitot ID:	91	End Time:	11:23	
Pitot Coefficient:	0.840	Test Engineer:	SMcG	Test Tech: JHK
Probe Length, Feet:	4	Port Length, Inches:	6	

Port	Point	DP	Sqrt.	Temp	Velocity	Port	Point	DP	Sqrt.	Temp	Velocity
		(in. H ₂ O)	DP	(°F)	(V)			(in. H ₂ O)	DP	(°F)	(V)
A	1	0.02	0.1414	370.0	10.02	D	1	0.03	0.1732	370.0	12.27
A	2	0.02	0.1414	370.0	10.02	D	2	0.03	0.1732	369.0	12.26
A	3	0.02	0.1414	369.0	10.01	D	3	0.02	0.1414	369.0	10.01
A	4	0.01	0.1000	368.0	7.07	D	4	0.02	0.1414	367.0	10.00
A	5	0.01	0.1000	361.0	7.04	D	5	0.02	0.1414	364.0	9.98
B	1	0.02	0.1414	371.0	10.02	E	1	0.02	0.1414	370.0	10.02
B	2	0.02	0.1414	370.0	10.02	E	2	0.02	0.1414	369.0	10.01
B	3	0.02	0.1414	370.0	10.02	E	3	0.01	0.1000	368.0	7.07
B	4	0.01	0.1000	367.0	7.07	E	4	0.01	0.1000	366.0	7.06
B	5	0.02	0.1414	363.0	9.97	E	5	0.01	0.1000	360.0	7.04
C	1	0.04	0.2000	371.0	14.17						
C	2	0.04	0.2000	371.0	14.17						
C	3	0.03	0.1732	370.0	12.27						
C	4	0.02	0.1414	368.0	10.00						
C	5	0.02	0.1414	364.0	9.98						

Test Parameters

P _{bar} - Barometric pressure, inches Hg	29.70	% CO ₂	9.30
P _g - Stack Pressure, inches of H ₂ O	-0.10	% O ₂	11.20
P _s - Absolute stack pressure, inches Hg	29.69	% N ₂	79.50
t _s - Average stack temperature, °F	367.8	Md - dry basis lb/lb mole	29.94
Duct Shape:	Rectangular	Ms - wet basis lb/lb mole	28.742
Length, Feet	3.5		
Width, Feet	5.5		
Cross Sectional Area of Stack, Ft ²	19.25	Bws - Moisture content fraction	0.100
		Moisture determined by wb/db?	N

Method 2 Results

Average DP	0.0204	Q - ACFM	11,435
Average Sqrt DP	0.1400	Qsd - DSCFM	6,514
Average Velocity Vs (ft/sec)	9.900	Qs - SCFM	7,238
		Qs - SCFH	434,278

METHOD 2 VOLUMETRIC FLOW DATA

Project Number:	M144705	Operating Level:	Normal	(Normal)
Client:	University of Iowa	Run No.:	2	
Facility:	Oakdale Renewable Energy Center	Test Date:	11/5/2014	
Test Location:	Hurst Boiler Exhaust Duct	Start Time:	13:06	
Pitot ID:	91	End Time:	13:17	
Pitot Coefficient:	0.840	Test Engineer:	S McG	Test Tech: JHK
Probe Length, Feet:	4	Port Length, Inches:	6	

Port	Point	DP	Sqrt.	Temp	Velocity	Port	Point	DP	Sqrt.	Temp	Velocity
		(in. H ₂ O)	DP	(°F)	(V)			(in. H ₂ O)	DP	(°F)	(V)
A	1	0.02	0.1414	368.0	10.00	D	1	0.03	0.1732	368.0	12.25
A	2	0.02	0.1414	369.0	10.01	D	2	0.03	0.1732	370.0	12.27
A	3	0.01	0.1000	367.0	7.07	D	3	0.02	0.1414	369.0	10.01
A	4	0.01	0.1000	367.0	7.07	D	4	0.02	0.1414	368.0	10.00
A	5	0.01	0.1000	363.0	7.05	D	5	0.01	0.1000	366.0	7.06
B	1	0.03	0.1732	369.0	12.26	E	1	0.02	0.1414	368.0	10.00
B	2	0.02	0.1414	369.0	10.01	E	2	0.02	0.1414	369.0	10.01
B	3	0.02	0.1414	368.0	10.00	E	3	0.02	0.1414	369.0	10.01
B	4	0.01	0.1000	366.0	7.06	E	4	0.01	0.1000	367.0	7.07
B	5	0.02	0.1414	363.0	9.97	E	5	0.01	0.1000	364.0	7.06
C	1	0.04	0.2000	370.0	14.16						
C	2	0.04	0.2000	371.0	14.17						
C	3	0.03	0.1732	369.0	12.26						
C	4	0.01	0.1000	368.0	7.07						
C	5	0.03	0.1732	365.0	12.23						

Test Parameters

P _{bar} - Barometric pressure, inches Hg	29.70	% CO ₂	9.30
P _g - Stack Pressure, inches of H ₂ O	-0.10	% O ₂	11.20
P _s - Absolute stack pressure, inches Hg	29.69	% N ₂	79.50
t _s - Average stack temperature, °F	367.6	Md - dry basis lb/lb mole	29.94
Duct Shape:	Rectangular	Ms - wet basis lb/lb mole	28.742
Length, Feet	3.5		
Width, Feet	5.5		
Cross Sectional Area of Stack, ft ²	19.25	Bws - Moisture content fraction	0.100
		Moisture determined by wb/db (Y or N)	N

Method 2 Results

Average DP	0.0204	Q - ACFM	11,370
Average Sqrt DP	0.1392	Qsd - DSCFM	6,479
Average Velocity Vs (ft/sec)	9.844	Qs - SCFM	7,199
		Qs - SCFH	431,939

METHOD 2 VOLUMETRIC FLOW DATA

Project Number:	M144705	Operating Level:	Normal	(Normal)
Client:	University of Iowa	Run No.:	3	
Facility:	Oakdale Renewable Energy Center	Test Date:	11/5/2014	
Test Location:	Hurst Boiler Exhaust Duct	Start Time:	15:01	
Pitot ID:	91	End Time:	15:13	
Pitot Coefficient:	0.840	Test Engineer:	SMcG	Test Tech: JHK
Probe Length, Feet:	4	Port Length, Inches:	6	

Port	Point	DP	Sqrt.	Temp	Velocity	Port	Point	DP	Sqrt.	Temp	Velocity
		(in. H ₂ O)	DP	(°F)	(V)			(in. H ₂ O)	DP	(°F)	(V)
A	1	0.02	0.1414	375.0	10.04	D	1	0.03	0.1732	371.0	12.27
A	2	0.02	0.1414	374.0	10.04	D	2	0.03	0.1732	371.0	12.27
A	3	0.01	0.1000	371.0	7.09	D	3	0.02	0.1414	370.0	10.01
A	4	0.01	0.1000	370.0	7.08	D	4	0.02	0.1414	368.0	10.00
A	5	0.01	0.1000	364.0	7.06	D	5	0.01	0.1000	366.0	7.06
B	1	0.03	0.1732	373.0	12.29	E	1	0.02	0.1414	371.0	10.02
B	2	0.03	0.1732	373.0	12.29	E	2	0.02	0.1414	370.0	10.01
B	3	0.02	0.1414	371.0	10.02	E	3	0.02	0.1414	369.0	10.01
B	4	0.02	0.1414	369.0	10.01	E	4	0.01	0.1000	368.0	7.07
B	5	0.02	0.1414	366.0	9.99	E	5	0.01	0.1000	365.0	7.06
C	1	0.04	0.2000	374.0	14.20						
C	2	0.04	0.2000	372.0	14.18						
C	3	0.03	0.1732	371.0	12.27						
C	4	0.02	0.1414	370.0	10.01						
C	5	0.02	0.1414	367.0	10.00						

Test Parameters

P _{bar} - Barometric pressure, inches Hg	29.70	% CO ₂	9.60
P _g - Stack Pressure, inches of H ₂ O	-0.10	% O ₂	11.20
P _s - Absolute stack pressure, inches Hg	29.69	% N ₂	79.20
t _s - Average stack temperature, °F	370.0	Md - dry basis lb/lb mole	29.98
Duct Shape:	Rectangular	Ms - wet basis lb/lb mole	28.750
Length, Feet	3.5		
Width, Feet	5.5		
Cross Sectional Area of Stack, F ²	19.25	Bws - Moisture content fraction	0.103
		Moisture determined by wb/db (Y or N)	N

Method 2 Results

Average DP	0.0212	Q - ACFM	11,656
Average Sqrt DP	0.1425	Qsd - DSCFM	6,601
Average Velocity Vs (ft/sec)	10.092	Qs - SCFM	7,359
		Qs - SCFH	441,535

METHOD 4 MOISTURE DETERMINATION

Project Number:	M144705	Run Number:	1	
Client:	University of Iowa	Operating Level:	Normal	(Normal)
Facility:	Oakdale Renewable Energy Center	Time:	Start- 11:35	End- 12:20
Test Location:	Hurst Boiler Exhaust Duct	Test Engineer:	SMcG	
Test Date:	11/5/2014	Test Tech:	JHK	
Pressure, Barometric(Hg"):	29.70	Meter Calibration (Y):	1.001	
Delta H:	1.512	Meter Delta H (dH):	1.512	
Meter Initial Volume:	89.114	Initial Wt:	837.2	
Meter Final Volume:	122.881	Final Wt:	853.1	
Meter Temperature:	76.55	Initial Volume:	1928.6	
Meter Volume dscf:	33.141	Final Volume:	1991.3	
Water Vapor in Flue Gas (Bws): 0.100				

Project Number:	M144705	Run Number:	2	
Client:	University of Iowa	Operating Level:	Normal	(Normal)
Facility:	Oakdale Renewable Energy Center	Time:	Start- 13:25	End- 14:10
Test Location:	Hurst Boiler Exhaust Duct	Test Engineer:	SMcG	
Test Date:	11/5/2014	Test Tech:	JHK	
Pressure, Barometric(Hg"):	29.70	Meter Calibration (Y):	1.001	
Delta H:	1.512	Meter Delta H (dH):	1.512	
Meter Initial Volume:	23.422	Initial Wt:	855.8	
Meter Final Volume:	57.188	Final Wt:	863.3	
Meter Temperature:	76.10	Initial Volume:	1980.0	
Meter Volume dscf:	33.168	Final Volume:	2054.4	
Water Vapor in Flue Gas (Bws): 0.104				


Project Number:	M144705	Run Number:	3	
Client:	University of Iowa	Operating Level:	Normal	(Normal)
Facility:	Oakdale Renewable Energy Center	Time:	Start- 15:13	End- 15:58
Test Location:	Hurst Boiler Exhaust Duct	Test Engineer:	SMcG	
Test Date:	11/5/2014	Test Tech:	JHK	
Pressure, Barometric(Hg"):	29.70	Meter Calibration (Y):	1.001	
Delta H:	1.512	Meter Delta H (dH):	1.512	
Meter Initial Volume:	58.037	Initial Wt:	849.2	
Meter Final Volume:	91.811	Final Wt:	856.9	
Meter Temperature:	75.90	Initial Volume:	1965.0	
Meter Volume dscf:	33.188	Final Volume:	2035.2	
Water Vapor in Flue Gas (Bws): 0.100				

Appendix G - Field Data Sheets

Isokinetic Sampling Cover Sheet
 Test Engineer: S. McC.
 Test Technician: J. HK

Plant Information		Meter and Probe Data		Traverse Data		Stack Parameters	
Run Number:	1	Date:	11/4/14	Meter Y Value:	1.001	Static Pressure:	-1
Test Location:	Hurst Boiler Exhaust Duct	Client Name:	University Iowa	Pilot Coefficient:	.840	ΔH Value:	1.512
Duct Shape:	Circular or Rectangular	Length:	3.5	Nozzle Diameter:	.55	Train Type:	Hot Box
Flue Area:	19.250	Upstream Diameters:		Probe Liner:	Glass	Filler Number/Weight:	1670 / 0.489
Port Type:	Flange	Port Length:	6"	Post-Test Nozzle Weight:	.00	Thimble Number/Weight:	
Test Method:	5/Flame	Source Condition:	Normal	Post-Test Nozzle Leak Check:	.00	@ 19 "Hg	
				Post-Test Pilot Leak Check:	✓ @ 3.8 "H ₂ O	Post-Test Pilot Leak Check:	✓ @ 3.4 "H ₂ O
Points/Port:	5	Total Test Time:	125 min.	Min/Point:	5	Sample Planes:	Horizontal or Vertical
Ports Sampled:	25	Total Points:	1				

- 1) _____ 2) _____ 3) _____ 4) _____



Comments:

Post-Test Nozzle Verification:

Isokinetic Sampling Field Data Sheet

Project Number M144705
 Client University Iowa
 Plant Oakdale

Date 11-4-14
 Test Location Hurst Boiler Exhaust Duct
 Test Method 5/14/14
 Operator Page Number

① SMCG Test Tech. JHK
 1 of 1

Port-Point #:	Time	(ΔP)	Orifice Setting (ΔH)	Meter Volume (IV,1 ft ³ , Actual)	Meter Rate, Cubic Feet Min.	Theoretical Meter Volume, (V _m) ft ³ , per point	Theoretical Meter Volume, (V _m) ft ³ , total	Stack Temp., °F	Meter Temp. Outlet, °F	Pump Vacuum, "Hg	Probe Temp., °F	Filter Well	Impinger Outlet	CPM Filter Temp, °F	Temp, °F
1-1	8:35	.02	.82	48.115				356	72	71	5.5	250	248	65	
2	8:40	.01	.41	50.903				359	72	71	4.0	252	250	62	
3	8:45	.02	.82	52.867				356	72	71	5.5	251	250	60	
4	8:50	.02	.82	55.634				357	74	72	5.5	251	250	61	
5	8:55	.01	.41	58.417				353	74	72	4.0	250	252	61	
	9:00			60.403				381							
2-1	9:03	.03	1.23	40.403				361	74	73	6.5	249	250	60	
2	9:08	.03	1.23	63.814				362	77	74	6.5	251	250	59	
3	9:13	.03	1.24	67.223				360	77	74	6.5	252	250	60	
4	9:18	.03	1.24	70.629				364	78	74	6.5	250	250	61	
5	9:23	.02	.83	74.049				359	78	74	6.5	250	250	61	
	9:28			76.878				354	78	74	6.5	250	250	62	
3-1	9:40	.04	1.64	76.878				361	77	75	7.5	252	249	60	
2	9:45	.04	1.65	80.825				363	78	75	7.5	251	250	61	
3	9:50	.04	1.65	84.781				364	78	75	7.5	250	250	61	
4	9:55	.03	1.24	88.718				360	78	75	6.5	250	250	62	
5	10:00	.03	1.25	92.145				352	79	75	6.5	251	250	62	
	10:05			95.588				379							
4-1	10:10	.03	1.24	95.588				367	77	75	6.5	250	250	60	
2	10:15	.04	1.65	99.019				360	78	75	7.5	251	249	59	
3	10:20	.03	1.24	102.981				361	78	75	7.5	250	250	60	
4	10:25	.03	1.24	106.394				368	79	75	6.5	249	250	61	
5	10:30	.02	.83	109.838				358	79	75	6.5	250	249	61	
	10:35			112.641				355	79	75	6.5	250	249	61	
5-1	10:40	.03	1.24	112.441				360	77	76	6.5	250	250	60	
2	10:45	.03	1.24	116.074				360	78	76	6.5	250	250	60	
3	10:50	.02	.83	119.507				357	78	76	6.5	249	250	62	
4	10:55	.02	.83	122.312				354	79	76	6.5	250	249	62	
5	11:00	.01	.42	125.124				357	79	76	6.5	250	249	62	
	11:05			127.106				359	79	76	6.5	250	249	62	

MOSTARDI PLATT

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 11/4/14

TEST NO: 1

METHOD: 5

WEIGHED/MEASURED BY: DT

BALANCE ID: 510-10

IMPINGER	FINAL WEIGHT MLS / GRAMS	INITIAL WEIGHT MLS / GRAMS	GAIN	IMPINGER CONTENTS
IMPINGER 1	894.9	737.4		D1 H2O
IMPINGER 2	780.5	735.3		D1 H2
IMPINGER 3	519.5	501.2		SCAN
IMPINGER 4	862.6	833.7	28.9	SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS 2194.9 FINAL TOTAL 1973.9 INITIAL TOTAL 221.0 TOTAL IMPINGER GAIN

SILICA 862.6 FINAL TOTAL 833.7 INITIAL TOTAL 28.9 TOTAL SILICA GAIN

Isokinetic Sampling Cover Sheet
 Test Engineer: S. MCG
 Test Technician: J. HK

Plant Information		Meter and Probe Data		Traverse Data		Stack Parameters	
Run Number:	(2)	Date: 11/4/14	Meter Y Value: 1.001	ΔH Value: 1.512	Point/Port: 5	Static Pressure: -1	Barometric Pressure: 29.65
Test Location:	Hurst Boiler Exhaust Duct	Client Name: University of Iowa	Pilot Coefficient: .840	Train Type: Hot Box	Total Test Time: 125 Min.	CO ₂ %: / /	CO ₂ %: / /
Duct Shape:	Circular or Rectangular	Length: 3.5	Nozzle Diameter: .55	Filter Number/Weight: 7695 / 0.9419	Min/Point: S	Imp and/or silica balance Model and S/N: 462 - 0149001	Avg. 7, / Servomex Serial #: 462 - 0149001
Flue Area:	19.250	Width: 5.5	Probe Liner: Glass	Thimble Number/Weight: .00 @ 14 "Hg	Sample Plane: Horizontal or Vertical	Initial Imp. Volume or Weight: 2005.3	Determined by: Method 3 or Method 3A
Port Type:	Flange	Upstream Diameters:	Post-Test Nozzle Leak Check: .00	Leak Check: .00 @ 14 "Hg		Final Silica Weight: 818.0	Imp. Volume or Weight Gain: 210.0
Test Method:	S/PP	Port Length: 6"	Pre-Test Pilot Leak Check: ✓ @ 3.6 "H ₂ O	Post-Test Pilot Leak Check: ✓ @ 2.4 "H ₂ O		Initial Silica Weight: 869.1	Silica Weight Gain: -210.1
		Source Condition: Normal					
						Comments:	1) _____ 2) _____ 3) _____ 4) _____

Isokinetic Sampling Field Data Sheet

Project Number M144705 Date 11/4/14 Test Number
 Client: University, Iowa Test Location: Hurst Boiler Exhaust Duct Operator:
 Plan: 5 Test Method: 5 Page Number: 1

Port- Point #:	Time	(AP)	Orifice Setting (ΔH)	Meter Volume (Vm) ft ³ , Actual	Meter Rate, Cubic Feet Min.	Theoretical Meter Volume, (Vm) ft ³ , per point	Theoretical Meter Volume, (Vm) ft ³ , per point	Stack Temp., °F	Meter Temp Outlet, °F	Pump vacuum, " Hg	Probe Temp., °F	Filter Temp., °F	Impinger Outlet Well Temp, °F	CPM Filter Temp
1-1	11:30	.02	.83	27.642										
2	11:35	.02	.83	30.446										
3	11:40	.02	.82	33.234										
4	11:45	.02	.83	36.014										
5	11:50	.01	.42	38.803										
	11:55			40.779										
2-1	11:58	.03	1.24	40.779										
2	12:03	.04	1.45	44.210										
3	12:08	.03	1.24	48.158										
4	12:13	.03	1.25	51.580										
5	12:18	.02	.84	55.014										
	12:23			57.821										
3-1	12:26	.04	1.66	57.821										
2	12:31	.04	1.66	61.792										
3	12:36	.04	1.66	65.741										
4	12:41	.04	1.66	69.708										
5	12:46	.03	1.25	73.651										
	12:51			77.098										
4-1	12:54	.03	1.24	77.098										
2	12:59	.03	1.24	80.518										
3	13:04	.03	1.24	83.959										
4	13:09	.03	1.24	87.382										
5	13:14	.02	.83	90.798										
	13:19			93.461										
5-1	13:22	.02	.87	93.611										
2	13:27	.02	1.27	96.484										
3	13:32	.02	.83	99.934										
4	13:37	.02	.83	102.736										
5	13:42	.01	.42	105.330										
	13:47			107.518										

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 11/4/14

TEST NO: 2

METHOD: 5

WEIGHED/MEASURED BY: DT

BALANCE ID: S10-CO

IMPINGER	FINAL WEIGHT MLS / GRAMS	INITIAL WEIGHT MLS / GRAMS	GAIN	IMPINGER CONTENTS
IMPINGER 1	931.2	708.5		D1 H ₂ O
IMPINGER 2	721.6	682.5		D1 H ₂ O
IMPINGER 3	622.5	614.3		BLANK
IMPINGER 4	869.1	848.0		SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS	<u>2275.3</u>	<u>2005.3</u>	<u>270</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL IMPINGER GAIN

SILICA	<u>869.1</u>	<u>848.0</u>	<u>21.1</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL SILICA GAIN

Isokinetic Sampling Cover Sheet
 Test Engineer: S. McC G.
 Test Technician: J. HK

Plant Information	
Run Number:	②
Test Location:	Hurst Boiler Exhaust Duct
Duct Shape:	Circular or Rectangular
Flue Area:	19.250
Port Type:	Flange
Test Method:	5/way
Date:	11/4/14
Client Name:	University Iowa
Length:	3.5
Upstream Diameters:	Width: 5.5
Port Length:	6"
Source Condition:	Normal
Port Diameter:	6"


Meter and Probe Data	
Meter ID:	CM19
Pilot ID:	170
Nozzle Kit ID:	Glass Miss
Probe Length:	4
Pre-Test Nozzle Leak Check:	.60
Pre-Test Pilot Leak Check:	✓ & 3.4
Meter Y Value:	1.001
Pilot Coefficient:	.840
Nozzle Diameter:	.51
Probe Liner:	Glass
Post-Test Nozzle Leak Check:	@ 15 "Hg
Post-Test Pilot Leak Check:	"H ₂ O
AH Value:	1.512
Train Type:	Hot Box
Filter Number/Weight:	7669 / 0.4520
Thimble Number/Weight:	0.00 @ 14 "Hg
Leak Check:	✓ a. 3.4

Traverse Data	
Ports Sampled:	5
Total Points:	25
Point(s)/Port:	5
Total Test Time:	125 min.
Min/Point:	5
Sample Planes:	Horizontal or Vertical

Stack Parameters	
Barometric Pressure:	29.65
CO ₂ %:	1 / Avg. 11.8
Imp and/or silica balance Model and S/N:	1 / Servomex Serial #: 4622 - 0 / 440D1
Initial Imp. Volume or Weight:	1932.4
Initial Silica Weight:	852.7
Final Imp. Volume or Weight:	2189.6
Final Silica Weight:	871.4
Static Pressure:	- .1
O ₂ %:	1 / Avg. 8.8
Determined by:	Method 3 or Method 3A
Imp. Volume or Weight Gain:	257.0
Silica Weight Gain:	18.7

Comments:

1) _____ 2) _____ 3) _____ 4) _____



Isokinetic Sampling Field Data Sheet

Project Number M144705
 Client University, Iowa
 Plant Oakdale

Date 11-4-14
 Test Location Hurst Boiler Exhaust Duct
 Test Method 5/80
 Operator: Page Number: 1 of 1

(3) SMC G Test Tech: SHK
 1 of 1

Port- Point #:	Time	(ΔP)	Orifice Setting (ΔH)	Meter Volume (Vm) ft ³ , Actual	Meter Rate, Cubic Feet/ Min.	Theoretical Meter Volume, (Vm) ft ³ , per point	Theoretical Meter Volume, (Vm) ft ³ , total	Stack Temp., °F	Meter Temp. Outlet, Inlet, °F	Pump vacuum, "Hg	Probe Temp. °F	Filter Temp. °F	Impinger Outlet Well	CPM Filter Temp °F
1-1	14:15	.02	.82	08.548										
2	14:20	.02	.82	11.347										
3	14:25	.02	.82	14.149										
4	14:30	.02	.83	16.952										
5	14:35	.01	.42	19.756										
	14:40			21.748										
2-1	14:43	.03	1.24	21.748										
2	14:48	.03	1.25	25.206										
3	14:53	.03	1.25	28.653										
4	14:58	.03	1.25	32.107										
5	15:03	.02	.84	35.571										
	15:08			38.393										
2-1	15:11	.03	1.26	38.393										
2	15:16	.04	1.67	41.854										
3	15:21	.04	1.67	45.882										
4	15:26	.03	1.25	49.878										
5	15:31	.02	.84	53.338										
	15:36			56.166										
4-1	15:39	.03	1.25	56.166										
2	15:44	.03	1.25	59.643										
3	15:49	.03	1.25	63.064										
4	15:54	.02	.83	66.546										
5	15:59	.02	.84	69.357										
	16:04			72.190										
6-1	16:07	.02	.83	72.190										
2	16:12	.03	1.25	75.013										
3	16:17	.02	.83	78.972										
4	16:22	.02	.83	81.284										
5	16:27	.01	.92	84.103										
	16:32			86.011										

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 11/4/14

TEST NO: 3

METHOD: 5

WEIGHED/MEASURED BY: DT

BALANCE ID: 510-10

	FINAL WEIGHT	INITIAL WEIGHT	IMPINGER	IMPINGER
Circle One:	MLS / GRAMS	MLS / GRAMS	GAIN	CONTENTS
IMPINGER 1	932.8	713.4		O1H2O
IMPINGER 2	748.2	717.6		O1H2O
IMPINGER 3	508.6	501.6		BLANK
IMPINGER 4	871.4	852.7		SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS 2189.6 1932.6 257
 FINAL TOTAL INITIAL TOTAL TOTAL IMPINGER GAIN

SILICA 871.4 852.7 18.7
 FINAL TOTAL INITIAL TOTAL TOTAL SILICA GAIN

M26

MULTI METHOD NON-ISOKINETIC FIELD DATA SHEET

Project Name/Number: University of Iowa Oakdale M144705 Date: 11-4-2014
 Test Location: Hurst boiler exhaust duct Source Condition:
 Test Method: 26 Meter ID: MM1 Pre-Calibration Date: 10-27-2014
 Meter ΔH: N/A Meter Y: 0.998 Test Engineer: JHK

Test (Run) No.	1	Barometric Pressure (P_{bar}) 29.65 in. Hg				Gas Sample Analysis		
Static Pressure:	- . 1	Stack Temperature: (From Method Test Data)				%CO ₂	%O ₂	
Clock Time 24 hour	Meter Volume (V _m) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (l _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg	Condensate	Silica Gel or Train
855	0.000	2.0	80		4		mls (V _f)	grams (W _f)
900	10.105		80		4		mls (V _i)	grams (W _i)
905	20.239		80		4		= mls gained	= grams gained
910	30.172		80		4			
915	40.163		80		4			
920	50.199		80		4			
925	60.076		81		3			
930	70.165		81		3			
935	80.206		81		3			
940	90.133		81		3			
945	100.153		82		3			
950	110.179		82		3			
955	122.293		82		3			
Total Vol. in ft ³ (V _m) =	4.319	Multiply total volume collected in Liters by 0.035315 to convert to ft ³						
Comments:							Pre-Test Leak Check:	Post-Test Leak Check:
Test (Run) No.	2	Barometric Pressure (P_{bar}) 29.65 in. Hg				Gas Sample Analysis		
Static Pressure:	- . 1	Stack Temperature: (From Method Test Data)				%CO ₂	%O ₂	
Clock Time 24 hour	Meter Volume (V _m) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (l _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg	Condensate	Silica Gel or Train
1200	0.001	2.0	78		2		mls (V _f)	grams (W _f)
1205	10.067		78		2		mls (V _i)	grams (W _i)
1210	20.194		78		2		= mls gained	= grams gained
1215	30.187		78		2			
1220	40.199		79		2			
1225	50.203		79		2			
1230	60.112		79		2			
1235	70.176		79		2			
1240	80.103		79		2			
1245	90.109		79		2			
1250	100.184		79		2			
1255	110.089		79		2			
1300	122.036		79		2			
Total Vol. in ft ³ (V _m) =	4.310	Multiply total volume collected in Liters by 0.035315 to convert to ft ³						
Comments:							Pre-Test Leak Check:	Post-Test Leak Check:

Mcb
MULTI METHOD NON-ISOKINETIC FIELD DATA SHEET

Project Name/Number: University of Iowa HVAC 70117703 Date: 11-7-2017
Test Location: Hurst boiler exhaust duct Source Condition:
Test Method: 26 Meter ID: MM1 Pre-Calibration Date: 10-27-2014
Meter ΔH: N/A Meter Y: 0.998 Test Engineer: JHK

Test (Run) No. <u>3</u>		Barometric Pressure (P_{bar}) <u>29.65</u> in. Hg					Gas Sample Analysis	
Static Pressure: <u>-1</u>		Stack Temperature: <u>86.23</u> (From Method			Test Data)		%CO ₂	%O ₂
Clock Time 24 hour	Meter Volume (V _m) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg		
1443	0.000	2.0	85			2		
1448	10.201		85			2		
1453	20.312		85			2		
1458	30.191		86			2		
1503	40.187		86			2		
1508	50.035		86			2		
1513	60.187		86			2		
1518	70.123		87			2		
1523	80.144		87			2		
1528	90.096		87			2		
1533	100.016		87			2		
1538	110.225	V	87			2		
1543	122.372		87			2		
Total Vol. in ft ³ (V _m) =	<u>4.321</u>	Multiply total volume collected in Liters by 0.035315 to convert to ft ³						
Comments:							Pre-Test Leak Check: <u>0</u> @ <u>10</u> "Hg	Post-Test Leak Check: <u> </u> @ <u> </u> "Hg
Test (Run) No.		Barometric Pressure (P_{bar})					in. Hg	
Static Pressure:		Stack Temperature:			(From Method		Test Data)	
Clock Time 24 hour	Meter Volume (V _m) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg		
1443	0.000	2.0	85			2		
1448	10.201		85			2		
1453	20.312		85			2		
1458	30.191		86			2		
1503	40.187		86			2		
1508	50.035		86			2		
1513	60.187		86			2		
1518	70.123		87			2		
1523	80.144		87			2		
1528	90.096		87			2		
1533	100.016		87			2		
1538	110.225	V	87			2		
1543	122.372		87			2		
Total Vol. in ft ³ (V _m) =		Multiply total volume collected in Liters by 0.035315 to convert to ft ³						
Comments:							Pre-Test Leak Check: <u> </u> @ <u> </u> "Hg	Post-Test Leak Check: <u> </u> @ <u> </u> "Hg

MERCURY SORBENT TRAP FIELD DATA SHEET

Project Name/Number: University Iowa / Oakdale / M144705
 Sampling Location: Hurst Boiler Exhaust Duct
 Date: 11-5-2014
 Source Condition: Normal
 Dry Gas Meter No. MM5
 Run Number: 1
 Barometric Pressure: 29.70
 Test Engineer: JHK
 Trap Number: OL 21019

Sample Train A					
Clock Time 24 hour	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (t _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
1135	368	360	80	0.000	12
1140	368	360	80	10.006	12
1145	368	360	80	20.145	12
1150	368	360	80	30.019	12
1155	368	362	81	40.023	12
1200	368	362	81	50.098	12
1205	369	362	81	60.064	12
1210	370	362	82	70.030	12
1215	370	364	82	80.198	13
1220	372	364	82	89.980	13
1225	374	367	83	100.012	13
1230	374	367	83	110.067	13
1235	377	370	84	120.111	14
1240	377	371	84	130.055	14
Total Volume	375	370	84	140.532	
1245	375				

Dry Gas Meter No. MM5 BY = 0.987 Trap Number OL 211390 Spike Value 25 ng

Sample Train B					
Clock Time 24 hour	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (t _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
1135	368	360	81	0.000	13
1140	368	360	81	10.681	13
1145	368	360	81	20.790	13
1150	368	360	81	30.921	13
1155	368	362	82	40.996	14
1200	368	362	82	50.877	14
1205	369	362	82	61.172	14
1210	370	362	83	71.303	14
1215	370	364	83	81.514	15
1220	372	364	84	91.496	15
1225	374	367	84	101.424	15
1230	374	367	85	111.577	15
1235	377	370	85	121.678	15
1240	377	371	85	131.545	15
Total Volume	375	370	85	142.173	
1245	375				

Train A: Pre-Test Leak Check - Pass @ 25 mHg
 Post-Test Leak Check - Pass @ 25 mHg
 Train B: Pre-Test Leak Check - Pass @ 25 mHg
 Post-Test Leak Check - Pass @ 25 mHg

Average	A	371.07	364.07	81.80
	B	371.07	364.07	82.93

MERCURY SORBENT TRAP FIELD DATA SHEET

Project Name/Number: University Iowa / Oakdale / M144705
 Sampling Location: Hurst Boiler Exhaust Duct
 Date: 11-5-2014
 Source Condition: Normal
 Dry Gas Meter No. MM5 Y = 1.012
 Run Number: 2
 Barometric Pressure: 29.7
 Test Engineer: JHK
 Trap Number: OLC012446

Sample Train A					
Clock Time	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (T _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
24 hour					
1325	384	364	85	0.000	15
1330	384	364	85	10.227	15
1335	385	365	85	20.231	15
1340	385	365	85	30.202	15
1345	384	368	85	40.179	15
1350	385	370	85	50.032	15
1355	385	373	85	60.133	15
1400	385	375	85	70.072	15
1405	385	376	85	80.071	15
1410	385	377	85	90.110	15
1415	385	377	85	100.152	15
1420	385	378	85	110.178	15
1425	386	379	85	120.211	15
1430	386	379	85	130.133	15
1435	388	379	85	140.464	

Dry Gas Meter No. MM5B Y = 0.987 Trap Number OL201242 Spike Value 25 ng

Sample Train B					
Clock Time	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (T _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
24 hour					
1325	384	364	87	0.000	13
1330	384	364	87	10.219	13
1335	385	365	87	20.163	13
1340	385	365	87	30.188	13
1345	384	368	87	40.040	13
1350	385	370	87	50.094	14
1355	385	372	87	60.063	14
1400	385	375	88	70.055	14
1405	385	376	87	80.132	14
1410	385	377	87	90.146	13
1415	385	377	87	100.158	13
1420	385	378	88	110.162	13
1425	386	379	88	120.209	13
1430	386	379	88	130.201	13
1435	388	379	88	140.639	

Train A: Pre-Test Leak Check - Pass @ 25 μHg
 Post-Test Leak Check - Pass @ 25 μHg
 Train B: Pre-Test Leak Check - Pass @ 25 μHg
 Post-Test Leak Check - Pass @ 25 μHg

Average	A	385.13	372.60	85.0
Project No. M144705	Hurst Boiler Exhaust Duct	385.13	372.60	87.33

DS-021 Method 30B Hg Sorbent Trap

Trap ID



OLC012446



Sorbent Trap Chain of Custody

Plant/Source: _____

Test Location: HURST BOILER EXHAUST DUCT

Boiler ID: _____

Trap A B (Circle One) RUN 2 Unspiked Spiked At: _____Certified Accuracy \pm 10%, Traceable to NISTQA/QC Signature (Trap Maker) Brian JohnsonLot Number: U-24C

QA/QC Signature (Spiker) _____

Spike Date: _____ Spike Time: _____

- High Flow Coil Pre-filter 240 mm
 Static Pre-filter AGS 300 mm
 Fluffy Pre-filter 185 mm 450 mm

Estimated Hg in Section 1: _____ ng

Type of Trap: 30B

Sampled By: _____

Test Start (Date/Time)		Leak Check Pass/Fail		Test End (Date/Time)		Leak Check Pass/Fail	
Date	Time	Duct Temp (°F or °C)	Sorbent Trap Temp (°F or °C)	Flow Rate (cc/min)	Dry Gas Meter Liters Initial	Dry Gas Meter Liters Final	Total Volume Pulled
Total/Average							

Chain of Custody

Relinquished by Tech.: _____

Date: _____

Received by: _____

Date: _____

Relinquished by: _____

Date: _____

Received for Laboratory by: _____

Date: _____

Make sure all of your sampling conditions prevent moisture condensation in the trap media. Moisture condensation is a major cause of breakthrough and spike loss in sorbent traps and should be prevented at all costs.

For Analysis contact us:

Ohio Lumex Co., Inc. 9263 Ravenna Road Unit A-3, Twinsburg, OH 44087 USA

Phone 330-405-0837 Fax 330-405-0847 US Toll Free: 888-876-2611

Impregnated Activated Carbon - Refer to MSDS

Deactivated glass and glass wool

Project No. M144705

Hurst Boiler Exhaust Duct

Best Before: July 2016

MERCURY SORBENT TRAP FIELD DATA SHEET

Project Name/Number: University Iowa / Oakdale / M144705
 Sampling Location: Hurst Boiler Exhaust Duct
 Date: 11-5-2014
 Source Condition: Normal
 Dry Gas Meter No. MM5 Y = -1.012

Run Number: 3 Barometric Pressure: 29.70
 Test Engineer: JHK Trap Number: OL210456

Sample Train A					
Clock Time 24 hour	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (t _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
1513	375	362	84	0,000	15
1518	375	362	84	11,551	15
1523	376	365	84	21,652	15
1528	376	365	84	31,543	15
1533	377	367	84	41,751	15
1538	379	368	84	51,715	15
1543	379	368	84	61,664	15
1548	379	369	84	71,606	15
1553	380	370	84	81,612	15
1558	380	371	84	91,619	15
1603	381	373	84	101,459	15
1608	381	373	84	..	15
1613					
1618					
Total					
1623					

Dry Gas Meter No. MM5B Y = 0.987 Trap Number OL211459 Spike Value 25 ng

Sample Train B					
Clock Time 24 hour	Stack Temp. °F	Sorbent Trap Temp. °F	Meter Temp. (t _m) °F	Meter Volume (V _m) liters	Meter Vacuum, Hg
1513	375	362	87	0,000	14
1518	375	362	87	11,714	14
1523	376	365	87	21,789	14
1528	376	365	87	31,633	14
1533	377	367	87	41,697	14
1538	379	368	87	51,687	14
1543	379	368	87	61,599	14
1548	379	369	87	71,611	14
1553	380	370	87	81,501	14
1558	380	371	87	91,766	14
1603	381	373	87	101,810	14
1608	381	373	87	..	14
1613					
1618					
Total					
1623					

Train A: Pre-Test Leak Check - Pass @ 25 □Hg
 Post-Test Leak Check - Pass @ □Hg
 Train B: Pre-Test Leak Check - Pass @ □Hg
 Post-Test Leak Check - Pass @ □Hg

GAS TRAVERSE DATA

Project: M144705 UNIVERSITY OF IOWA

Location: HURST BOILER EXHAUST DUCT

Date: 11/05/14 Test No: 115 STRATIFICATION Time: 1135-1301

Point No.	Time	NO _x	SO ₂	CO	CO ₂	O ₂
1 - 1	1135-1137	64.0		0.9	11.34	9.21
- 2	1138-1140	62.3		0.3	11.12	9.40
- 3	1141-1143	51.3		2.1	10.4	10.06
- 4	1144-1146	55.8		0.3	10.02	10.56
						1137
						1140
						1143
						1146
2 - 1	1155-1157	45.1		4.7	10.83	9.68
- 2	1158-1200	46.3		5.0	9.57	11.01
- 3	1201-1203	41.6		1.4	9.97	10.59
- 4	1204-1206	33.5		3.5	7.85	12.7
						1157
						1200
						1203
						1206
3 - 1	1213-1215	66.0		1.1	10.79	9.69
- 2	1216-1218	54.1		0.3	9.78	10.14
- 3	1219-1221	33.1		1.6	7.16	13.53
- 4	1222-1224	28.5		1.9	6.65	14.14
						1215
						1218
						1221
						1224
4 - 1	1232-1234	45.4		3.8	10.98	9.55
- 2	1235-1237	47.1		6.1	10.63	9.95
- 3	1238-1240	46.6		3.1	8.03	12.56
- 4	1241-1243	40.5		0.7	7.27	13.43
						1234
						1237
						1240
						1243
5 - 1	1250-1252	31.8		3.5	7.04	13.66
- 2	1253-1255	36.3		3.2	8.32	12.19
- 3	1256-1258	34.5		3.9	8.03	12.55
- 4	1259-1301	32.7		3.6	7.82	12.75
						1252
						1255
						1258
						1301

Data Taken By: D7/JHK

PART 60 GASEOUS FIELD DATA SHEET

Project Number:

M144705

Date:

11/5/14

Client:

UNIVERSITY OF IOWA

Operator:

DAN TUOER

Test Location:

H-1857 BOILER EXHAUST Duct

Fuel Factor:

Volumetric Flow Rate Determination Field Data Sheet

Project Number: M144705
 Client: Univ. Iowa / Oakdale
 Test Location: Hurst Boiler Exhaust Duct
 Source Condition: Normal
 Test Engineer: SMcG

Date: 11-5-14
 Test Number: ① Pre-1
 Start Time: 11:10
 End Time: 11:23
 Test Tech: JHK

Duct Diameter 4.278 ft
 Flue Area 19.250 ft²
 Port Length 6"
 P_{bar} 29.7 "Hg CO₂ % 9.3 Upstream Disturbance, Diameters _____
 Static .1 "H₂O O₂ % 11.2 Downstream Disturbance, Diameters _____
 Static " "Hg N₂ % Pitot ID 091 Pitot Coefficient (C_p) .840
 P_s " "Hg Meter No. CM19 Wet Bulb Temp Leak Checks
 _____ Dry Bulb Temp 367.8 Pre ✓ 3.5
 _____ B_{ws} .100 Post ✓ 3.7

Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees	Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees
1-1	.02	370			4-1	.03	370		
2	.02	370			2	.03	369		
3	.02	369			3	.03	369		
4	.01	368			4	.02	367		
5	.01	361			5	.02	364		
					5-1	.02	370		
					2	.02	369		
					3	.01	368		
					4	.01	366		
					5	.01	360		
Average									

$$.44 \times CO_2\% + .32 \times O_2\% + .28 \times N_2\% = \underline{\hspace{2cm}} (Md)$$

$$(\underline{\hspace{1cm}} Md \times \underline{\hspace{1cm}} 1-Bws) + (18 \times \underline{\hspace{1cm}} Bws) = \underline{\hspace{2cm}} (Ms)$$

$$85.49 \times \underline{\hspace{1cm}} Cp \times \sqrt{\frac{(\underline{\hspace{1cm}}) Ts}{Ms \times \underline{\hspace{1cm}} Ps}} \times \underline{\hspace{1cm}} \sqrt{\Delta P} = \underline{\hspace{1cm}} \text{ ft/sec (Vs)}$$

$$\underline{\hspace{1cm}} Vs \times \underline{\hspace{1cm}} \text{ Flue Area} \times 60 = \underline{\hspace{2cm}} \text{ acfm}$$

$$17.647 \times \underline{\hspace{1cm}} \text{ acfm} \times \frac{Ps}{Ts \cdot R} = \underline{\hspace{1cm}} \text{ scfm} \times 60 = \underline{\hspace{1cm}} \text{ scfh}$$

Volumetric Flow Rate Determination Field Data Sheet

Project Number:

M144705

Date:

11-5-14

Client:

Univ. Iowa / Oakdale

Test Number:

(2) Post-1 / Pre-2

Test Location:

Hurst Boiler Exhaust Duct

Start Time:

13:06

Source Condition:

Normal

End Time:

13:17

Test Engineer:

SMCG

Test Tech:

JHK

Duct Diameter 4.278 ft

Upstream Disturbance, Diameters _____

Flue Area 19.250 ft²

Downstream Disturbance, Diameters _____

Port Length 60 "

Pitot ID 091 Pitot Coefficient (C_p) .840

P_{bar} 29.7 "Hg

Wet Bulb Temp _____

Static .1 "H₂O

Dry Bulb Temp 367.6

Static "Hg

B_{ws} _____

P_s "Hg

Meter No. CM19

Leak Checks _____

Pre ✓ 03.7

Post ✓ 03.8

Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees	Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees
1-1	.02	368			4-1	.03	368		
2	.02	369			2	.03	370		
3	.01	367			3	.02	369		
4	.01	367			4	.02	368		
5	.01	363			5	.01	366		
2-1	.03	369			5-1	.02	368		
2	.02	369			2	.02	369		
3	.02	368			3	.02	369		
4	.01	366			4	.01	367		
5	.02	363			5	.01	364		
3-1	.04	370							
2	.04	371							
3	.03	369							
4	.01	368							
5	.03	365							
Average									

$$.44 \times CO_2\% + .32 \times O_2\% + .28 \times N_2\% = \text{Md} \text{ (Md)}$$

$$(\text{Md} \times 1 - B_{ws}) + (18 \times B_{ws}) = \text{Ms} \text{ (Ms)}$$

$$85.49 \times C_p \times \sqrt{\frac{Ts}{Ms} \times \frac{Ps}{Ps}} \times \sqrt{\Delta P} = \text{ft/sec (Vs)}$$

$$Vs \times \text{Flue Area} \times 60 = \text{acfpm}$$

$$17.647 \times \text{acfpm} \times \frac{Ps}{Ts} = \text{scfm} \times 60 = \text{scfh}$$

Volumetric Flow Rate Determination Field Data Sheet

Project Number: M144705 Date: 11-5-14
 Client: Univ. Iowa / Oakdale Test Number: (3) Post-2 / Pre-3
 Test Location: Hurst Boiler Exhaust Duct Start Time: 15:01
 Source Condition: Normal End Time: 15:13
 Test Engineer: SMCG Test Tech: JHK

Duct Diameter 4.278 ft Upstream Disturbance, Diameters _____
 Flue Area 19.250 ft² Downstream Disturbance, Diameters _____
 Port Length 6" Pitot ID 091 Pitot Coefficient (C_p) .840
P_{bar} 29.7 "Hg Wet Bulb Temp _____ Leak Checks _____
Static -.1 "H₂O O₂ % 9.6 Pre ✓ 0.28
Static "Hg N₂ % 11.2 Dry Bulb Temp _____ Post ✓ 0.37
P_s "Hg Meter No. CM19 B_{ws} .104

Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees	Port-Point #	ΔP	Temp. °F	$\sqrt{\Delta P}$	Null Point Angle, Degrees
1-1	.02	375			4-1	.03	371		
2	.02	374			2	.03	371		
3	.01	371			3	.02	370		
4	.01	370			4	.02	368		
5	.01	364			5	.01	366		
					5-1	.02	371		
2-1	.03	373			2	.02	370		
2	.03	373			3	.02	369		
3	.02	371			4	.01	368		
4	.02	369			5	.01	365		
5	.02	366							
3-1	.04	374							
2	.04	372							
3	.03	371							
4	.02	370							
5	.02	367							
Average									

$$.44 \times CO_2\% + .32 \times O_2\% + .28 \times N_2\% = \underline{\hspace{2cm}} (Md)$$

$$(\underline{\hspace{1cm}} Md \times \underline{\hspace{1cm}} 1-B_{ws}) + (18 \times \underline{\hspace{1cm}} B_{ws}) = \underline{\hspace{2cm}} (Ms)$$

$$85.49 \times \underline{\hspace{1cm}} C_p \times \sqrt{\frac{(\underline{\hspace{1cm}}) T_s \text{ } ^\circ R}{\underline{\hspace{1cm}} M_s \times \underline{\hspace{1cm}} P_s}} \times \underline{\hspace{1cm}} \sqrt{\Delta P} = \underline{\hspace{2cm}} \text{ ft/sec (Vs)}$$

$$\underline{\hspace{1cm}} V_s \times \underline{\hspace{1cm}} \text{ Flue Area} \times 60 = \underline{\hspace{2cm}} \text{ acfm}$$

$$17.647 \times \underline{\hspace{1cm}} \text{ acfm} \times \frac{P_s}{T_s \text{ } ^\circ R} = \underline{\hspace{2cm}} \text{ scfm} \times 60 = \underline{\hspace{2cm}} \text{ scfh}$$

MOISTURE FIELD DATA SHEET

Project Name/Number: University Iowa/Oakdale/M144705

Date: 11-5-14

Source Condition: Normal

Test Location: Hurst Boiles East Coast Duct

Meter ID: CM 19

Pre-Calibration Date:

Test Method:

Meter Y: 1.001

Test Engineer: SMCG

Test (Run) No. ①		Barometric Pressure (P_{bar}) 29.7			in. Hg		Gas Sample Analysis					
Static Pressure: -.1		Stack Temperature: 367.8 (From Method			Test Data)		9.3	%CO ₂	11.2 %O ₂			
Clock Time 24 hour	Meter Volume (ft ³ or L) (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg	<u>Condensate</u>		Silica Gel or Train			
11:35	89.114	1.5	75	74	63	7.0						
11:40	92.879		74	74	55	7.0						
11:45	96.609		75	75	59	7.0						
11:50	100.352		76	75	60	7.0						
11:55	104.106		78	75	60	7.0						
12:00	107.858		79	76	61	7.0						
12:05	111.629		80	76	62	7.0						
12:10	115.382		80	76	62	7.0						
12:15	119.130		80	76	63	7.0						
12:20	122.881		81	76	63	7.0						
Total Vol. in ft ³ (V _m) =	33.767	Multiply total volume collected in Liters by 0.035315 to convert to ft ³										
Comments:							Pre-Test Leak Check:	Post-Test Leak Check:				
							.00 @ .15 "Hg	.00 @ .15 "Hg				
Test (Run) No. ②		Barometric Pressure (P_{bar}) 29.7			in. Hg		Gas Sample Analysis					
Static Pressure: -.1		Stack Temperature: 367.6 (From Method			Test Data)		9.3	%CO ₂	11.2 %O ₂			
Clock Time 24 hour	Meter Volume (ft ³ or L) (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg	<u>Condensate</u>		Silica Gel or Train			
13:25	23.422	1.5	74	74	44	4.0						
13:30	27.183		74	75	44	4.0						
13:35	30.937		75	75	45	4.0						
13:40	34.691		76	75	45	4.0						
13:45	38.443		77	75	46	4.0						
13:50	42.190		78	75	47	4.0						
13:55	45.936		79	75	49	4.0						
14:00	49.684		80	75	49	4.0						
14:05	53.441		80	75	50	4.0						
14:10	57.188		80	75	51	4.0						
Total Vol. in ft ³ (V _m) =	33.766	Multiply total volume collected in Liters by 0.035315 to convert to ft ³										
Comments:							Pre-Test Leak Check:	Post-Test Leak Check:				
							.00 @ .14 "Hg	.00 @ .16 "Hg				

MOISTURE FIELD DATA SHEET

Project Name/Number: University Iowa / Oakdale / M144705 Date: 11-5-14
 Test Location: Hurst Boiler Exhaust Duct Source Condition: Normal
 Test Method: 4 Meter ID: CM19 Pre-Calibration Date: _____
 Meter ΔH: 1.512 Meter Y: 1.601 Test Engineer: SMCG

Test (Run) No. <u>③</u>		Barometric Pressure (P_{bar}) <u>29.7</u> in. Hg					Gas Sample Analysis		
Static Pressure: <u>- .1</u>		Stack Temperature: <u>370.0</u> (From Method _____)					<u>9.6</u>	%CO ₂ <u>11.2</u> %O ₂	
Clock Time 24 hour	Meter Volume (Vm) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg			
15:13	58.037	1.5	74	74	58	4.5	<u>Condensate</u> <u>Silica Gel or Train</u>		
15:18	61.798	1	75	74	53	4.5	2035.2 / <u> </u> / <u> </u> mls (V _i) <u>856.9</u> grams (W _i)		
15:23	65.549	1	75	74	54	4.5	-1965.0 / <u> </u> / <u> </u> mls (V _i) <u>-849.2</u> grams (W _i)		
15:28	69.303	1	76	75	54	4.5	= <u>7.7</u> mls gained = <u>7.7</u> grams gained		
15:33	73.050	1	77	75	54	4.5			
15:38	76.811	1	78	75	55	4.5			
15:43	80.547	1	79	75	55	4.5			
15:48	84.305	1	79	75	56	4.5			
15:53	88.052	1	79	75	56	4.5			
15:58	91.811	1	79	75	56	4.5			
Total Vol. in ft ³ (Vm)=	<u>33.774</u>	Multiply total volume collected in Liters by 0.035315 to convert to ft ³							
Comments:								Pre-Test Leak Check:	Post-Test Leak Check:
Test (Run) No.		Barometric Pressure (P_{bar}) _____ in. Hg					Gas Sample Analysis		
Static Pressure:		Stack Temperature: _____ (From Method _____)					Test Data) %CO ₂ _____ %O ₂		
Clock Time 24 hour	Meter Volume (Vm) ft ³ or L (Circle One)	Meter Gage Pressure (ΔH) in. H ₂ O	Meter Inlet Temp. (t _m) °F	Meter Outlet Temp. (t _m) °F	Impinger Outlet Temp °F	Meter Vacuum "Hg			
							<u>Condensate</u> <u>Silica Gel or Train</u>		
							/ <u> </u> / <u> </u> mls (V _i) <u> </u> grams (W _i)		
							/ <u> </u> / <u> </u> mls (V _i) <u> </u> grams (W _i)		
							= <u> </u> mls gained = <u> </u> grams gained		
Total Vol. in ft ³ (Vm)=		Multiply total volume collected in Liters by 0.035315 to convert to ft ³							
Comments:								Pre-Test Leak Check:	Post-Test Leak Check:

BWS .100

Average Meter Temperature: 75.9
(average of both inlet and outlet if applicable)

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 10/5/14

TEST NO: 1

METHOD: 4

WEIGHED/MEASURED BY: DT

BALANCE ID: S10-10

	FINAL WEIGHT	INITIAL WEIGHT	IMPINGER	IMPINGER
Circle One:	MLS / GRAMS	MLS / GRAMS	GAIN	CONTENTS
IMPINGER 1	754.3	710.3		01 H ₂ O
IMPINGER 2	704.3	715.7		01 H ₂ O
IMPINGER 3	532.7	502.6		BLANK
IMPINGER 4	853.1	837.2	15.9	SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS	<u>1991.3</u>	<u>1920.6</u>	<u>62.7</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL IMPINGER GAIN

SILICA	<u>853.1</u>	<u>837.2</u>	<u>15.9</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL SILICA GAIN

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 11/5/14

TEST NO: 2

METHOD: 4

WEIGHED/MEASURED BY: DT

BALANCE ID: S10-10

	FINAL WEIGHT	INITIAL WEIGHT	IMPINGER	IMPINGER
Circle One:	MLS / GRAMS	MLS / GRAMS	GAIN	CONTENTS
IMPINGER 1	759.2	699.5		DIAZO
IMPINGER 2	677.1	665.0		DIAZO
IMPINGER 3	618.1	615.5		BLANK
IMPINGER 4	863.3	855.8		SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS 2054.4 2831980.0 74.4
 FINAL TOTAL INITIAL TOTAL TOTAL IMPINGER GAIN

SILICA 863.3 855.8 7.5
 FINAL TOTAL INITIAL TOTAL TOTAL SILICA GAIN

IMPINGER WEIGHT SHEET

PLANT: UNIVERSITY OF IOWA

UNIT NO: HURST BOILER

LOCATION: EXHAUST DUCT

DATE: 11/5/14

TEST NO: 3

METHOD: 4

WEIGHED/MEASURED BY: DT

BALANCE ID: 510-10

	FINAL WEIGHT	INITIAL WEIGHT	IMPINGER	IMPINGER
Circle One:	MLS / GRAMS	MLS / GRAMS	GAIN	CONTENTS
IMPINGER 1	811.4	754.3		DI H ₂ O
IMPINGER 2	715.3	704.3		DI H ₂ O
IMPINGER 3	508.5	506.4		BLANK
IMPINGER 4	856.9	849.2		SILICA
IMPINGER 5				
IMPINGER 6				
IMPINGER 7				
IMPINGER 8				

IMPINGERS	<u>2035.2</u>	<u>1965</u>	<u>70.2</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL IMPINGER GAIN

SILICA	<u>856.9</u>	<u>849.2</u>	<u>7.7</u>
	FINAL TOTAL	INITIAL TOTAL	TOTAL SILICA GAIN

Appendix H - Calibration Data

MOSTARDI PLATT

Procedures for Calibration

Dry Gas Meters

The test meters are calibrated according to Method 5, Section 5.3 and "Procedures for Calibrating and Using Dry Gas Volume Meters as Calibration Standards" by P.R. Westlin and R.T. Shigehara, March 10, 1978.

Analytical Balance

The accuracy of the analytical balance is checked with Class S, Stainless Steel Type 303 weights manufactured by F. Hopken and Son, Jersey City, New Jersey.

Temperature Sensing Devices

The potentiometer and thermocouples are calibrated utilizing a NBS traceable millivolt source.


Nozzles

The nozzles are measured according to Method 5, Section 5.1.

Pitot Tubes

The pitot tubes used during this test program are fabricated according to the specification described and illustrated in the Code of Federal Regulations, Title 40, Part 60, Appendix A, Methods 1 through 5 as published in the Federal Register, Volume 42, No. 160; hereafter referred to by the appropriate method number. The pitot tubes comply with the alignment specifications in Method 2, Section 4; and the pitot tube assemblies are in compliance with specifications in the same section.

Dry Gas Meter/Control Module Calibration Diagram



METER CALIBRATION

Meter Information

Console Model	XC-260	Dry Gas Meter Number	M5 A	Encoder Model	HEDS-9100-F00
Gas Meter Model	SK25	Totalizer Scale Factor (Initial)	1.0000	Totalizer Model	RED LION
		Totalizer Scale Factor (Final)	1.0123	Temp Display Model	JENCO

Calibration Conditions

WTM ID	WTM ID	Calibration Technician	A/MH	Calibration Date	27-Oct-14
		Barometric Pressure	(Pb)	738.03939	mm Hg
WTM Cal Factor	1.0055				

Calibration Data										Results				
Run Time	Dry Gas Meter			Wet Test Meter			Standardized Volumes			Totalizer Gamma Initial	Totalizer Gamma Final	DGM Variation (ΔY)	Meter Gamma Variation (ΔY)	Corrected Flowrate (Q _c)
	Gas Temp	Totalizer Display	Gas Volume (V _w)	Gas Temp (T _w)	Totalizer SF (V _{m,dry})	Dry Gas Meter (V _{m,dry})	Wet Test Meter (V _{m,wet})	Wet Test Meter (V _{m,wet})	Wet Test Meter (V _{m,wet})					
Elapsed (⌚) min	°C	liters	liters	°C	std liters	std liters	std liters	std liters	std liters					
Run 1 - Initial	0.00	17.778	0	2556.98	17.778									
Final	38.51	19.444	117.016	2674.38	18.333									
Total/Avg	38.51	18.611	117.016	117.4	18.0555	114.257	115.666	115.482	1.011	-0.002				3.02
Run 2 - Initial	0.00	19.444	0	2674.38	18.333									
Final	30.00	20.556	59.176	2734.05	18.889									1.96
Total/Avg	30.00	20	59.176	59.67	18.611	57.507	58.216	58.584	1.019	0.006				
Run 3 - Initial	0.00	19.444	0	2734.05	18.889									
Final	30.00	21.111	28.397	2762.37	18.889									0.93
Total/Avg	30.00	20.278	28.397	28.32	18.889	27.570	27.910	27.778	1.008	-0.005				0.93
														1.012

Average Meter Calibration Factor Y

1.012

Note: For Calibration Factor Y, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is ±0.02

METER CALIBRATION

Meter Information			
Console Model	XC-260	Dry Gas Meter Number	M5 8
Gas Meter Model	SK25	Totalizer Scale Factor (Initial)	1.0000
		Totalizer Scale Factor (Final)	0.9870
Calibration Conditions			
WTM ID	15340981	Calibration Technician	AMH
WTM Cal Factor	1.0055	Barometric Pressure	(Pb) 738.039395 mm Hg

Calibration Data										Results		
Run Time	Dry Gas Meter			Wet Test Meter			Standardized Volumes			Totalizer Gamma	Totalizer Gamma	Corrected Flowrate
	Gas Temp	Totalizer Display	Gas Volume (V_w)	Gas Temp (t_w)	Gas Volume ($V_{w,stat}$)	Wet Test Meter ($V_{w,stat}$)	Initial SF	Final SF	Wet Test Meter ($V_{w,stat}$)			
Elapsed (min)	°C	liters	liters	°C	liters	liters	std liters	std liters	std liters	std liters	std liters	slm
Run 1 - Initial	0.00	21.111	0	27.62.37	18.889							
Final	38.00	21.111	118.781	28.80.84	19.444							
Total/Avg	38.00	21.111	118.781	118.47	19.1665	114.995	113.496		116.092	1.010	0.023	3.07
Run 2 - Initial	0.00	21.111	0	2880.84	19.444							
Final	30.22	22.778	55.886	2935.95	20							1.79
Total/Avg	30.22	21.9445	55.886	55.11	19.722	53.952	53.248		53.901	0.999	0.012	
Run 3 - Initial	0.00	22.778	0	2935.95	20							
Final	30.00	22.778	27.886	2962.137	20.556							0.86
Total/Avg	30.00	22.778	27.886	26.187	20.278	26.845	26.495		25.564	0.952	-0.035	
									0.987			

Average Meter Calibration Factor Y**0.987**

Note: For Calibration Factor Y, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is ±0.02

Stack Temperature Sensor Calibration

Meter Box # : M5

Name : AMH

Ambient Temperature : 64 °F

Date : October 27, 2014

Calibrator Model # : CL23A

Serial # : T-249465

Date Of Certification : August 7, 2012

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	1	0.2
250	251	0.1
600	600	0.0
1200	1201	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

METER CALIBRATION

Meter Information					
Console Model	XC-260	Dry Gas Meter Number	M5 A	Encoder Model	HEDS-9100-F00
Gas Meter Model	SI225	Totalizer Scale Factor (Initial)	1.0000	Totalizer Model	RED LION
		Totalizer Scale Factor (Final)	0.9951	Temp Display Model	JENCO
Calibration Conditions					Calibration Date 7-Nov-14
WTM ID	16745468	Calibration Technician	SVD	Calibration Date	7-Nov-14
WTM Cal Factor	1.0039	Barometric Pressure	(Pb)	Barometric Pressure	749.21411 mm Hg

Results

Run Time	Dry Gas Meter	Wet Test Meter			Standardized Volumes			Results		
		Gas Temp	Totalizer Display	Gas Volume	Gas Temp	Totalizer Initial SF	Totalizer Final SF	Wet Gas Meter	Totalizer Gamma	Meter Gamma
Elapsed (θ) min	(t _m)	(V _m)	(V _m)	(V _m)	(t _w)	(V _{mstd})	(V _{mstd})	(V _{wstd})	(ΔY)	(ΔY)
Run 1 - Initial	0.00	15.556	0	1539.62	15.556					
Final	38.51	18.333	123.395	1663.08	18.333					
Total/Avg	38.51	16.945	123.395	123.46	16.9445	123.013	122.414	123.558	1.004	0.009
Run 2 - Initial	0.00	18.333	0	1663.08	18.333					
Final	30.00	18.333	62.586	1724.89	18.333					
Total/Avg	30.00	18.333	62.586	61.81	18.333	62.095	61.792	61.564	0.991	-0.004
Run 3 - Initial	0.00	18.333	0	1724.89	18.333					
Final	30.00	18.333	28.732	1753.21	18.333					
Total/Avg	30.00	18.333	28.732	28.32	18.333	28.507	28.368	28.207	0.990	-0.006

0.995

Average Meter Calibration Factor Y

Note: For Calibration Factor Y, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is +0.02.

METER CALIBRATION

Meter Information					
Console Model	XC-260	Dry Gas Meter Number	M5 B	Encoder Model	HEDS-9100-F00
Gas Meter Model	SK25	Totalizer Scale Factor (Initial)	1.00000	Totalizer Model	RED LION
Totalizer Scale Factor (Final)					
			0.9941	Temp Display Model	JENCO
Calibration Conditions					
WTM ID	14159239	Calibration Technician	SVD	Calibration Date	7-Nov-14
WTM Cal Factor	1.0011	Barometric Pressure	(Pb)		
			749.214114	mm Hg	

Calibration Data										Results			
Run Time Elapsed (e) min	Dry Gas Meter			Wet Test Meter			Standardized Volumes			Totalizer Gamma Initial (Y)	Totalizer Gamma Variation (ΔY)	Meter Gamma (Y)	Corrected Flowrate (Q _m) slm
	Gas Temp (T _m) °C	Totalizer Display (V _m) liters	Gas Volume (V _w) liters	Gas Temp (t _w) °C	Totalizer Initial SF (V _{mstd}) std liters	Totalizer Final SF (V _{wstd}) std liters	DGM Dry Gas Meter (V _{mstd}) std liters	Wet Test Gas Meter (V _{wstd}) std liters	Wet Test Motor (V _{wstd}) std liters				
Run 1 - Initial	0.00	15.556	0	2561.71	15.556								
Final	38.00	18.333	124.288	2686.50	18.333								
Total/Avg	38.00	16.9445	124.288	124.79	16.9445	123.903	123.166	124.540	1.005	0.011			3.28
Run 2 - Initial	0.00	18.333	0	2666.5	18.333								
Final	30.22	18.333	57.567	2743.22	18.333								1.87
Total/Avg	30.22	18.333	57.567	56.72	18.333	57.115	56.776	56.337	0.986	-0.008			
Run 3 - Initial	0.00	18.333	0	2743.22	18.333								
Final	30.00	18.333	25.668	2768.62	18.333								0.84
Total/Avg	30.00	18.333	25.668	25.4	18.333	25.467	25.315	25.228	0.991	-0.003			
									0.994				

Average Meter Calibration Factor Y

0.994

[Note: For Calibration Factor Y, the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is +/- 0.02]

Stack Temperature Sensor Calibration

Meter Box # : M5

Name : SVD

Ambient Temperature : 61 °F

Date : November 7, 2014

Calibrator Model # : CL23A

Serial # : T-249465

Date Of Certification : August 7, 2012

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	1	0.2
250	251	0.1
600	599	0.1
1200	1201	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} \times 100 \leq 1.5\%$$

Ref. Temp., °F + 460

Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No. CM19
 Standard Meter No. 16745468
 Standard Meter (Y) 1.0039

Date: October 29, 2014
 Calibrated By: KJC
 Barometric Pressure: 29.34

Run Number	Orifice Setting in H ₂ O Chg (H)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr	Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tdo	Dry Gas Meter Avg. Temp. F° fd	Time Min	Time Sec	Y	Chg (H)
Final		103.922	22.713	60	62	61					
Initial		98.122	16.865	68	61	61					
Difference	1 0.20	5.800	5.848	64	62	61					1.428
Final		9.922	28.727	60	64	62					
Initial		4.233	23.008	59	62	61					
Difference	2 0.50	5.689	5.719	60	63	62					1.479
Final		16.925	35.741	60	65	63					
Initial		10.232	29.022	60	63	62					
Difference	3 0.70	6.693	6.719	60	64	63					1.481
Final		23.121	41.943	60	66	64					
Initial		17.214	36.028	60	65	64					
Difference	4 0.90	5.907	5.915	60	66	64					
Final		28.908	47.730	60	67	64					
Initial		23.411	42.230	60	66	64					
Difference	5 1.20	5.497	5.500	60	67	64					1.564
Final		97.963	16.726	58	61	60					
Initial		92.221	11.034	58	60	59					
Difference	6 2.00	5.742	5.692	58	61	60					1.632

Average 1.001

1.512

Stack Temperature Sensor Calibration

Meter Box # : CM19

Name : KJC

Ambient Temperature : 63 °F

Date : October 29, 2014

Calibrator Model # : CL23A

Serial # : T-249465

Date Of Certification : August 7, 2012

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	1	0.2
250	247	0.4
600	596	0.4
1200	1198	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No.	CM19
Standard Meter No.	4319699
Standard Meter (Y)	1.0053

November 5, 2014

SVD

29.50

Calibrated By:
Barometric Pressure:

Run Number	Orifice Setting in H ₂ O Chg (ft)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr		Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tao	Dry Gas Meter Avg. Temp. F° td		Time Min	Time Sec	Y	Chg (H)
				tr	tdi			td	td				
Final		37.288	18.858	60	63	62							
Initial		26.306	7.743	58	61	60							
Difference	1	0.20	10.982	11.115	59	62							
Final		42.529	24.144	60	65	62							
Initial		37.288	18.858	60	63	62							
Difference	2	0.50	5.241	5.286	60	64							
Final		48.811	30.495	61	67	63							
Initial		42.529	24.144	60	65	62							
Difference	3	0.70	6.282	6.351	61	66							
Final		53.974	35.728	60	68	64							
Initial		48.811	30.495	61	67	63							
Difference	4	0.90	5.163	5.233	61	66							
Final		59.389	41.198	61	68	64							
Initial		53.974	35.728	60	68	64							
Difference	5	1.20	5.415	5.470	61	68							
Final		26.306	7.743	58	61	60							
Initial		20.974	2.431	58	59	63							
Difference	6	2.00	5.332	5.312	58	60							

Average _____

0.996

1.555

Stack Temperature Sensor Calibration

Meter Box # : CM19

Name : SVD

Ambient Temperature : 60 °F

Date : November 5, 2014

Calibrator Model # : CL23A

Serial # : T-249465

Date Of Certification : August 7, 2012

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (° F)	Test Thermometer Temperature (° F)	Temperature Difference %
0	-2	0.4
250	247	0.4
600	596	0.4
1200	1198	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Ref. Temp., °F + 460



S TYPE PITOT TUBE INSPECTION WORKSHEET

Pitot Tube No: 91

Date: 10/13/2014

Inspectors Name: TFN

Type of Probe: (circle one) M2 MS M17 Probe Length: 4 ft.



Pitot tube assembly level? yes no

Pitot tube openings damaged? yes (explain below) no

$$a_1 = \underline{1.5}^\circ (< 10^\circ), \quad a_2 = \underline{3.5}^\circ (< 10^\circ) \quad z = A \sin g = \underline{0.034} \text{ (in.)}; (< 0.125 \text{ in.})$$

$$b_1 = \underline{1}^\circ (< 5^\circ), \quad b_2 = \underline{4}^\circ (< 5^\circ) \quad w = A \sin q = \underline{0.025} \text{ (in.)}; (< 0.03125 \text{ in.})$$

$$\gamma = \underline{2}^\circ, \theta = \underline{1.5}^\circ, A = \underline{0.973} \text{ (in.)} \quad P_A = \underline{0.487} \text{ (in.)}, P_B = \underline{0.487} \text{ (in.)}, D_t = \underline{0.375} \text{ (in.)}$$

Calibration required? yes no


S TYPE PITOT TUBE INSPECTION WORKSHEET

Pitot Tube No: 170

Date: 10/13/2014

Inspector's Name: TFN

Type of Probe: (circle one) M2 M5 M17 Probe Length: 4 ft.



Pitot tube assembly level? yes no

Pitot tube openings damaged? yes (explain below) no

$$a_1 = \underline{2}^\circ (<10^\circ), \quad a_2 = \underline{1.5}^\circ (<10^\circ) \quad z = A \sin g = \underline{0.020} \text{ (in.)}; (<0.125 \text{ in.})$$

$$b_1 = \underline{2}^\circ (<5^\circ), \quad b_2 = \underline{1.5}^\circ (<5^\circ) \quad w = A \sin q = \underline{0.020} \text{ (in.)}; (<0.03125 \text{ in.})$$

$$\gamma = \underline{1}^\circ, \theta = \underline{1}^\circ, A = \underline{1.144} \text{ (in.)} \quad P_A = \underline{0.572} \text{ (in.)}, P_B = \underline{0.572} \text{ (in.)}, D_1 = \underline{0.375} \text{ (in.)}$$


Calibration required? yes no

Nozzle Calibration

Date: 5/30/2012

Nozzle ID No.: SG2

Analyst: RICHES



<u>0.551</u>	1
<u>0.551</u>	2
<u>0.552</u>	3
<u>0.550</u>	4

Average
<u>0.551</u>

WEIGHING
SOLUTIONS
INC.

SALES-SERVICE-RENTALS
3310-14 N. HARLEM AVENUE
CHICAGO, IL 60634

PHONE
773-836-2800
FAX
773-836-2891

CALIBRATION REPORT

Company Name Mostardi Platt
Date SEPTEMBER 4, 2013
Location LAB
Weight Set # E 559

Model # E 0640
Serial/ID # 60451121051238
Manufacturer OHAUS
Tolerance $\pm 0.05\%$

Capacity	Before Cal.:	After Cal.:
62g		
0.1mg	0.0001g	0.0001g
0.1mg	1.0000g	1.0000g
1g		
10g	10.0001g	10.0000g
20g	20.0002g	20.0000g
50g	50.0004g	50.0000g

	Accept	Reject
Linearity	✓	
Cornerload	✓	
Repeatability	✓	
Hysteresis	✓	

Comments Cleaned and adjusted calibration to N.I.S.T. specifications.

Jerry M. Platt
Technician
678
State of IL Registration



RLWS Mass Value CERTIFICATE

Contractor:

Weighing Solutions Inc
PO Box 95
River Grove, IL 60171-0095



Purchase Order #:

1268
Weighing Solutions Inc
3310 N Harlem Ave

Address:

Chicago, IL 60634

City & State:

19 OCT 2012

Date Received:

24 OCT 2012

Date Calibrated:

21.41 to 21.72 °C

Temperature Range:

727.3 to 727.6 mmHg

Pressure Range:

44 to 46 %

Relative Humidity Range:

1.1406 to 1.1419 mg/cm³

Air Density:

1927133

Traceable Report #:

681/280058-10, 822/278785-10

NIST Certificate #:

12

Tested By:

Modified Substitution (W105-0023)

Procedure:

2 Years

Contractor Req Recall Date:

02/11/11, 10/21/09 Due: 02/11/15, 10/21/13

Primary Standard Calibration Date:

02/11/11, 10/21/09 Due: 02/11/15, 10/21/13

Description of Weights:

100 g. Polished Weight, 50 g to 5 kg Satin Finish Weights & 5-10 kg Satin Finish Grip Handle

Weights, ASTM Class "2", Set S/N 5661

Although there are two NIST numbers,

one or both may apply.

Nominal Value	Id.	Conventional Mass Corr.		Unc. K=2 (mg)	Tol. (mg)	Balance Used	Standard Set Used		Assumed Density (g/cm³)
		As Found (mg)	As Left (mg)				Calibrated/due MM-DD-YY/MM-DD-YY		
50 g		-0.118	-0.118	0.026	0.25	1183Q	K594Q	08-10-12/11-09-12	7.85
100 g		-0.143	-0.143	0.049	0.50	1183Q	K594Q	08-10-12/11-09-12	7.84
100 g	.	-0.221	-0.221	0.049	0.50	1183Q	K594Q	08-10-12/11-09-12	8.00
200 g		-0.020	-0.020	0.059	1.0	619Q	K594Q	08-10-12/11-09-12	7.84
300 g		-1.257	-1.257	0.086	1.5	619Q	K594Q	08-10-12/11-09-12	7.84
400 g		-1.326	-1.326	0.098	1.5	619Q	K594Q	08-10-12/11-09-12	7.84
1 kg		-0.57	-0.57	0.14	5.0	619Q	K594Q	08-10-12/11-09-12	7.85
1 kg	..	0.90	0.90	0.14	5.0	619Q	K594Q	08-10-12/11-09-12	7.84
3 kg		-5.83	-5.83	0.81	15	975Q	K594Q	08-10-12/11-09-12	7.84
5000 g		-0.8	-0.8	1.1	25	975Q	K594Q	08-10-12/11-09-12	7.84
10 kg	...	12.1	12.1	1.8	50	975Q	K594Q	08-10-12/11-09-12	7.84
10 kg	16.1	16.1	1.8	50	975Q	K594Q	08-10-12/11-09-12	7.84

Check with your local state agency for certification of compliance on legal-for-trade items.

Prepared By:



230 West Coleman Street • Rice Lake, WI 54868 • USA
TEL: 715-234-9171 • FAX: 715-234-6967

Page 1 of 1 Page

Dated 24 OCT 2012

Dan Demers Metrologist

This report is not to be used to claim product endorsement by Rice Lake Weighing Systems or any agency of the U.S. Government.
This document shall not be reproduced, except in full, without the written approval of Rice Lake Weighing Systems' Metrology Laboratory.

Project No. M144705

Hurst Boiler Exhaust Duct

RLWS Mass Value CERTIFICATE

Contractor:

Weighing Solutions Inc
PO Box 95
River Grove, IL 60171-0095



Purchase Order #:

1268
Weighing Solutions Inc
3310 N Harlem Ave

Client:

Address:

City & State:

Chicago, IL 60634

Date Received:

19 OCT 2012

Date Calibrated:

23 OCT 2012 to 24 OCT 2012

Temperature Range:

21.00 to 21.79 °C

Pressure Range:

725.6 to 727.5 mmHg

Relative Humidity Range:

43 to 49 %

Indicates As Found >= Tol

Air Density:

1.1381 to 1.1436 mg/cm³

Traceable Report #:

1927133A

NIST Certificate #:

681/280058-10, 822/278785-10

Tested By:

12

Procedure:

Modified Substitution (W105-0023)

Contractor Req Recall Date:

2 Years

Primary Standard Calibration Date:

02/11/11, 10/21/09 Due: 02/11/15, 10/21/13

Description of Weights:

1 mg to 100 g Polished Kit, ASTM Class "1", S/N E559

Although there are two NIST numbers,
one or both may apply.

Nominal Value	Id.	Conventional Mass Corr.		Unc. K=2 (mg)	Tol. (mg)	Balance Used	Standard Set Used		Assumed Density (g/cm³)	
		As Found (mg)	As Left (mg)				Calibrated/due	MM-DD-YY/MM-DD-YY		
1 mg		0.0057	0.0057	0.0012	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
2 mg		0.0027	0.0027	0.0013	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
2 mg		0.0048	0.0048	0.0013	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
5 mg		0.0041	0.0041	0.0013	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
10 mg		-0.0017	-0.0017	0.0018	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
20 mg		-0.0018	-0.0018	0.0016	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
20 mg		-0.0022	-0.0022	0.0016	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
50 mg		0.0068	0.0068	0.0019	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
100 mg		-0.0056	-0.0056	0.0015	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
200 mg		-0.0029	-0.0029	0.0015	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
200 mg		-0.0022	-0.0022	0.0015	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
500 mg		-0.0072	-0.0072	0.0018	0.010	327Q	K594Q	08-10-12/11-09-12	7.95	
1 g		-0.0225	-0.0225	0.0026	0.034	327Q	K594Q	08-10-12/11-09-12	7.95	
2 g		0.0134	0.0134	0.0026	0.034	327Q	K594Q	08-10-12/11-09-12	7.95	
2 g		0.0179	0.0179	0.0026	0.034	327Q	K594Q	08-10-12/11-09-12	7.95	
5 g		0.0052	0.0052	0.0052	0.034	327Q	K594Q	08-10-12/11-09-12	7.95	
10 g		-0.038	0.000	<input checked="" type="checkbox"/>	0.012	0.050	676Q	K594Q	08-10-12/11-09-12	7.95
20 g		0.053	0.053	0.012	0.074	676Q	K594Q	08-10-12/11-09-12	7.95	
20 g		-0.046	-0.046	0.012	0.074	676Q	K594Q	08-10-12/11-09-12	7.95	
50 g		0.034	0.034	0.026	0.12	1183Q	K594Q	08-10-12/11-09-12	7.95	
100 g		-0.289	0.142	<input checked="" type="checkbox"/>	0.049	0.25	1183Q	K594Q	08-10-12/11-09-12	7.95

Check with your local state agency for certification of compliance on legal-for-trade items.

Prepared By:

RICE LAKE
WEIGHING SYSTEMS



230 West Coleman Street • Rice Lake, WI 54868 • USA
TEL: 715-234-9171 • FAX: 715-234-6967

Page 1 of 1 Page

Dated 24 OCT 2012

Dan Demers Metrologist

Project No. M144705

Hurst Boiler Exhaust Duct

This report is not to be used to claim product endorsement by Rice Lake Weighing Systems or any agency of the U.S. Government.
This document shall not be reproduced, except in full, without the written approval of Rice Lake Weighing Systems' Metrology Laboratory.

State of Illinois



Department of Agriculture

Registration Number: 1604

Expires: 02/28/2014

Bureau of Weights and Measures

Registered Service Company Certificate of Registration

This is to certify that the named company has met all requirements
for registration with this office for weighing devices.

A handwritten signature in black ink, appearing to read "Dennis R. Baier".

Issued To:

WEIGHING SOLUTIONS, INC.
3310-14 N HARLEM AVE
CHICAGO, IL 60634

Bureau Chief
Bureau of Weights & Measures

Registered Technician - Registration Cards

STATE OF ILLINOIS
DEPARTMENT OF AGRICULTURE
Registered Technician:
0678 LITTLE, JAMES M.
Registered Service Company:
1604 WEIGHING SOLUTIONS, INC.
Registered For:
Scale
Expires February 28, 2014

Registered Technician's Signature

The Department of Agriculture requires that all persons selling, installing, servicing, repairing, or reconditioning weighing or measuring devices used in trade or commerce be registered.

This Technician has met all of the qualifications of the State of Illinois and is currently registered with the Illinois Department of Agriculture in good standing.

Bureau of Weights & Measures
Telephone (217) 785-8301

IT.406-1122 X021-406-B030

Pre/Post	Date	Time	Analyst	Ambient Temperature degrees F	Relative Humidity %	Barometric Pressure inches Hg	Calibration Standard 50.0000g	% Error	Calibration Standard 5.0000g	% Error	Calibration Standard 0.5000g	% Error
Pre	11/10/2014	8:00 AM	JMG	70	23.0	29.18	49.9997 g	0.00	4.9999 g	0.00	0.5001 g	-0.02
Post	11/10/2014	3:00 PM	JMG	70	23.0	29.08	49.9998 g	0.00	4.9999 g	0.00	0.5001 g	-0.02
Pre	11/11/2014	8:00 AM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Post	11/11/2014	3:00 PM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Pre	11/12/2014	8:00 AM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Post	11/12/2014	3:00 PM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Pre	11/13/2014	8:00 AM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Post	11/13/2014	3:00 PM	JMG	71	23.0	29.00	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Pre	11/14/2014											
Post	11/14/2014											
Pre	11/17/2014											
Post	11/17/2014											
Pre	11/18/2014	8:00 AM	JMG	72	22.0	29.41	49.9998 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Post	11/18/2014	3:00 PM	JMG	72	22.0	29.41	49.9999 g	0.00	5.0001 g	0.00	0.5000 g	0.00
Pre	11/19/2014											
Post	11/19/2014											
Pre	11/20/2014	10:00 AM	JMG	74	22.0	29.44	50.0000 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Post	11/20/2014	3:15 PM	JMG	74	22.0	29.44	50.0000 g	0.00	5.0000 g	0.00	0.5000 g	0.00
Pre	11/21/2014											
Post	11/21/2014											
Pre	11/24/2014	7:30 AM	JMG	73	23.0	28.50	50.0002 g	0.00	5.0001 g	0.00	0.5000 g	0.00
Post	11/24/2014	3:15 PM	JMG	73	23.0	28.44	50.0002 g	0.00	5.0001 g	0.00	0.5000 g	0.00
Pre	11/25/2014	8:00 AM	JMG	73	22.0	29.38	50.0002 g	0.00	5.0002 g	0.00	0.5001 g	-0.02
Post	11/25/2014											
Pre	11/26/2014											
Post	11/27/2014											
Pre	11/28/2014											
Post	11/28/2014											

CALIBRATION SUMMARY

Project Number: M144705 Date: 11/4/14
 Client: UNIVERSITY OF IOWA Operator: DAN TUOER
 Test Location: HURST BOILER EXHAUST DUCT
 Make & Model: SERVOMEX SERVOPRO 1440 Box Truck: 5
 S/N: 0144001/4662

Type	Cal Level	Cylinder ID	Cylinder Value	Analyzer Response	Difference, % of Span	Cylinder Pressure (psi)	Cylinder Expiration Date
CO ₂ %	Zero	—	0.0	0.01	-0.05	—	—
	Mid	CC183734	9.968	9.98	-0.06	1050	5/23/22
	High	CC415912	19.47	19.47	0.0	900	10/14/21
O ₂ %	Zero	—	0.0	0.06	-0.27	—	—
	Mid	CC455275	11.99	12.03	-0.18	1950	9/22/12
	High	CC94285	22.25	22.2	0.22	800	10/15/21

CO₂%

Run #	C _{ma}	Pre Cal	Post Cal	Pre Zero	Post Zero	C _o	C _m	C	C _{gas}
1	9.968	10.03	10.01	0.01	0.02			11.65	11.6
2	9.968	10.01	10.03	0.02	0.01			11.50	11.4
3	9.968	10.03	10.00	0.01	0.01			11.82	11.8
4									
5									
6									

O₂%

Run #	C _{ma}	Pre Cal	Post Cal	Pre Zero	Post Zero	C _o	C _m	C	C _{gas}
1	11.99	12.00	11.99	0.0	0.0			8.93	8.9
2	11.99	11.99	11.95	0.0	-0.02			9.06	9.1
3	11.99	11.95	11.95	-0.02	-0.01			8.75	8.8
4									
5									
6									

$$C_{\text{gas}} = \frac{(C - C_o) \times C_{\text{ma}}}{(C_m - C_o)}$$

where:

C_{gas} = Effluent gas concentration, dry basis, %

C = Average gas concentration indicated by gas analyzer, dry basis, %

C_o = Average of initial and final system calibration bias check responses for the zero gas, %

C_m = Average of initial and final system calibration bias check responses for the upscale calibration gas, %

C_{ma} = Actual concentration of the upscale calibration gas, %

Client: University of Iowa
 Facility: Oakdale Renewable Energy Center
 Project #: M144705

Test Location: Hurst Boiler Exhaust Duct
 Date: 11/4/14
 Operator: DET

Operating Condition:	Normal				Point Markings (including port length):
Probe Length:	4.0	ft		Point #	Inches
Probe Type:	Extractive			1	13.01
Sample Plane:	Horizontal			2	27.00
Port Length:	6.00	in.		3	40.99
Port Size (diameter):	6	in.			
Port Type:	Flange				
Duct Shape:	Rectangular				
Length (traverse side of duct):	3.5	ft			
Width:	5.5	ft			
Location of Test Ports:					
Duct Area:	19.25	Sq. Ft.			
Equivalent Diameter Rectangular Duct:	4.278				
Upstream Diameters:	>.5				
Downstream Diameters:	>2				
Number of Ports Sampled:	5				
Number of Points per Port:	4				
Total Number of Traverse Points:	20				

Type	Setting	Cylinder ID	Cylinder Value	Analyzer Response	Difference, % of Span	Expiration Date	Final Bottle Pressure, PSI
CO2 % (dry)	Zero		0	0.01	-0.05%		
	Mid	CC183734	9.968	9.98	-0.06%	5/23/2022	1050
	High	CC415912	19.47	19.47	0.00%	10/14/2021	900
O2 % (dry)	Zero		0	0.06	-0.27%		
	Mid	CC455275	11.99	12.03	-0.18%	9/22/2022	1950
	High	CC94285	22.25	22.20	0.22%	10/15/2021	800

Response Time Data

Type	RM Analyzer Make/Model	RM Analyzer s/n	Analyzer Span	RM Gas Span
CO2 % (dry)	Servomex ServoPro 1440	4662-01440D1	20	19.47
O2 % (dry)	Servomex ServoPro 1440	4662-01440D1	25	22
		Start	95% Response	Time (min)
Upscale		8:01:00	8:03:00	2
Downscale		8:04:00	8:06:00	2

Client: University of Iowa
Facility: Oakdale Renewable Energy Center
Fuel Type: Wood
Fuel Factor: 9240
Diluent: O2 %

Location: Hurst Boiler Exhaust Duct
Date: 11/4/14
Operator: DET
Project #: M144705
Fuel Factor: by Standard

CO2 % (dry) Correction Data													
Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	9.97	10.03	10.01	0.01	0.02	0.02	10.02	11.65	11.6	-0.15	-0.10	-0.05	0.05
2	9.97	10.01	10.03	0.02	0.01	0.02	10.02	11.50	11.4	-0.26	0.10	0.00	-0.05
3	9.97	10.03	10.00	0.01	0.01	0.01	10.02	11.82	11.8	-0.10	-0.15	0.00	0.00

CO2 % (dry) Correction Data

Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	11.99	12.00	11.99	0.00	0.00	0.00	12.00	8.93	8.9	0.18	-0.04	0.27	0.00
2	11.99	11.99	11.95	0.00	-0.02	-0.01	11.97	9.06	9.1	0.36	-0.18	0.36	-0.09
3	11.99	11.95	11.95	-0.02	-0.01	-0.02	11.95	8.75	8.8	0.36	0.00	0.31	0.04

Calibration Corrected Data

Run #	Run Date	Start Time	End Time	CO2 % (dry)	O2 % (dry)
1	11/4/14	8:35	11:02	11.6	8.9
2	11/4/14	11:30	13:47	11.4	9.1
3	11/4/14	14:15	16:32	11.8	8.8

Client: University of Iowa
Facility: Oakdale Renewable Energy Center
Project #: M144705
Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/4/14

Linearity Cal/Pre 1 Cal

<u>Time</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>	
7:36	0.01	22.20	ih
7:37	5.44	14.16	
7:38	19.15	-0.41	
7:39	19.36	-0.16	
7:40	19.47	ih	-0.05
7:41	14.32	3.94	
7:42	0.03	12.25	
7:43	0.01	12.03	
7:44	0.01	iz	12.03 im
7:45	7.99	2.20	
7:46	9.98	im	0.06 iz
7:47	9.75	1.45	
7:48	0.15	20.61	
7:49	0.06	20.65	
7:50	0.04	11.18	
7:51	0.01	0.02	
7:52	0.01	-0.02	
7:53	0.01	-0.02	
7:54	0.01	0.09	
7:55	0.01	0.03	
7:56	0.01	-0.04	
7:57	0.00	-0.04	
7:58	0.00	-0.04	
7:59	0.33	-0.06	
8:00	9.72	-0.14	
8:01	10.03	m	0.00 z
8:02	8.20	2.90	
8:03	0.13	11.80	
8:04	0.01	z	12.00 m

Client: University of Iowa
Facility: Oakdale Renewable Energy Center
Project #: M144705

Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/4/14

Post 1/Pre 2

<u>Time</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>
11:04	2.28	11.42
11:05	0.04	11.98
11:06	0.02	z
11:07	4.35	5.81
11:08	9.96	0.04
11:09	10.01	m
		0.00
		z

Post 2/Pre 3

<u>Time</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>		
13:59	0.01	11.94		
14:00	0.01	z	11.95	m
14:01	7.15		2.40	
14:02	10.00		0.00	
14:03	10.03	m	-0.02	z

Post 3

<u>Time</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>	
16:42	0.01	11.93	
16:43	0.01	z	11.95
16:44	6.43		m
16:45	10.00	m	-0.01
16:46	10.04		-0.03

CALIBRATION SUMMARY

Project Number:

M144705

Date:

11/5/14

Client:

UNIVERSITY OF IOWA

Operator:

DAN TUIDER

Test Location:

HURST BOILER

EXHAUST DUCT

Box Truck:

5

Analyzer Type, S/N, and Span	Cal Level	Cylinder ID Serial Number	Expected Cal Value	Actual Response	Difference As % of Span	Cylinder Pressure (psi)	Cylinder Expiration Date
NO _x	Zero	—	0.0	0.2	-0.22	—	—
	Mid	CC422360	46.68	47.3	-0.68	950	2/17/17
	High	CC310556	90.78	91.2	-0.46	700	6/12/22
SO ₂	Zero	—	—	—	—	—	—
	Mid	—	—	—	—	—	—
	High	—	—	—	—	—	—
CO ₂	Zero	—	0.0	0.0	0.0	—	—
	Mid	CC183739	9.968	9.97	-0.01	1000	5/23/22
	High	CC415912	19.47	19.50	-0.15	850	10/14/21
O ₂	Zero	—	0.0	-0.01	0.04	—	—
	Mid	CC455275	11.99	11.96	0.13	1900	9/22/22
	High	CC94285	22.25	22.30	-0.22	750	10/15/21
CO	Zero	—	0.0	0.0	0.0	—	—
	Mid	XCO132998	14.89	14.9	-0.03	1400	12/3/20
	High	SG91464793AK	30.63	30.5	0.42	1900	7/16/21

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Project #: M144705

Test Location: Hurst Boiler Exhaust Duct
 Date: 11/5/14
 Operator: Dan Tulder

Operating Condition:	Normal					
Probe Length:	4.0	ft				
Probe Type:	Extractive					
Sample Plane:	Horizontal					
Port Length:	6.00	in.				
Port Size (diameter):	6	in.				
Port Type:	Flange					
Duct Shape:	Rectangular					
Length (traverse side of duct):	3.5	ft				
Width:	5.5	ft				
Location of Test Ports:	Side of duct					
Duct Area:	19.25	Sq. Ft.				
Equivalent Diameter Rectangular Duct:	4.278					
Upstream Diameters:	>.5					
Downstream Diameters:	>2					
Number of Ports Sampled:	5					
Number of Points per Port:	4					
Total Number of Traverse Points:	20					

Type	Setting	Cylinder ID	Cylinder Value	Analyzer Response	Difference, % of Span	Expiration Date	Final Bottle Pressure, PSI
NOx ppmvd	Zero		0	0.20	-0.22%		
	Mld	CC422360	46.68	47.30	-0.68%	2/17/2017	
	High	CC310556	90.78	91.20	-0.46%	6/12/2022	
CO ppmvd	Zero		0	0.00	0.00%		
	Mid	XC013299B	14.89	14.90	-0.03%	12/3/2020	
	High	SG9146479BAL	30.63	30.50	0.42%	7/16/2021	
CO2 % (dry)	Zero		0	0.00	0.00%		
	Mid	CC183734	9.968	9.97	-0.01%	5/23/2022	
	High	CC415912	19.47	19.50	-0.15%	10/14/2021	
O2 % (dry)	Zero		0	-0.01	0.04%		
	Mld	CC455275	11.99	11.96	0.13%	9/22/2022	
	Hlgh	CC94285	22.25	22.30	-0.22%	10/15/2021	

Response Time Data

Type	RM Analyzer Make/Model	RM Analyzer s/n	Analyzer Span	RM Gas Span
NOx ppmvd	TECO 42i-HL	1023743809	500	90.78
CO ppmvd	TECO 48i	0603715217	1000	30.63
CO2 % (dry)	Servomex ServoPro 1440	4662-01440D1	20	19.47
O2 % (dry)	Servomex ServoPro 1440	4662-01440D1	25	22
	Start		95% Response	Time (min)
Upscale	11:15:00		11:17:00	2
Downscale	11:21:00		11:23:00	2

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Fuel Type: Wood
 Fuel Factor: 9240
 Diluent: O2 %

Location: Hurst Boiler Exhaust Duct
 Date: 11/5/14
 Operator: Dan Tuider
 Project #: M144705
 Fuel Factor: by Standard

NOx ppmvd Correction Data													
Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	46.68	46.70	46.60	0.40	0.30	0.35	46.65	45.80	45.8	0.77	-0.11	-0.11	-0.11
2	46.68	46.60	45.90	0.30	0.20	0.25	46.25	43.50	43.9	1.54	-0.77	0.00	-0.11
3	46.68	45.90		0.20		0.20	45.90	43.70	44.4				

CO ppmvd Correction Data													
Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	14.89	14.90	14.90	0.00	0.00	0.00	14.90	3.00	3.0	0.00	0.00	0.00	0.00
2	14.89	14.90	14.90	0.00	0.00	0.00	14.90	5.90	5.9	0.00	0.00	0.00	0.00
3	14.89	14.90		0.00		0.00	14.90	9.20	9.2				

CO2 % (dry) Correction Data													
Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	9.97	10.00	10.00	0.01	0.05	0.03	10.00	9.36	9.3	-0.15	0.00	-0.26	0.21
2	9.97	10.00	10.01	0.05	0.03	0.04	10.01	9.61	9.6	-0.21	0.05	-0.15	-0.10
3	9.97	10.01		0.03		0.03	10.01	10.18	10.1				

O2 % (dry) Correction Data													
Run #	Cma	Precal	Postcal	Pre zero	Post zero	Co	Cm	C	Cgas	Span Bias	Span Drift	Zero Bias	Zero Drift
1	11.99	11.99	11.95	0.05	0.06	0.06	11.97	11.23	11.2	0.04	-0.18	-0.31	0.04
2	11.99	11.95	11.93	0.06	0.06	0.06	11.94	10.94	11.0	0.13	-0.09	-0.31	0.00
3	11.99	11.93		0.06		0.06	11.93	10.33	10.4				

Calibration Corrected Data

Run #	Run Date	Start Time	End Time	NOx ppmvd	CO2 % (dry)	O2 % (dry)	CO ppmvd
1	11/5/14	11:35	13:01	45.8	9.3	11.2	3.0
2	11/5/14	13:25	14:48	43.9	9.6	11.0	5.9
3	11/5/14	15:13	16:01	44.4	10.1	10.4	9.2

Client: University of Iowa
 Facility: Oakdale Renewable Energy Plant
 Project #: M144705
 Test Location: Hurst Boiler Exhaust Duct
 Operating Condition: Normal
 Date: 11/5/14

Linearity Cal/Pre 1 Cal

<u>Time</u>	<u>NOx ppmvd</u>	<u>CO ppmvd</u>	<u>CO2 % (dry)</u>	<u>O2 % (dry)</u>	
8:10	0.00	-0.10	0.00	22.30	in
8:11	0.10	-0.10	10.51	9.02	
8:12	0.00	-0.10	20.20	0.00	
8:13	0.00	-0.10	19.56	0.00	
8:14	0.00	-0.20	19.50	0.00	
8:15	0.00	-0.10	19.50	0.00	ih
8:16	0.00	0.70	14.37	0.09	
8:17	0.00	394.80	0.02	0.14	
8:18	0.00	827.00	0.01	0.14	
8:19	0.00	836.10	0.01	0.15	
8:20	0.00	896.70	0.00	0.15	
8:21	0.00	967.90	0.00	0.14	
8:22	0.80	938.90	0.01	0.13	
8:23	85.50	211.60	0.00	0.01	
8:24	155.10	1.50	0.00	0.01	
8:25	153.00	1.40	0.00	0.00	
8:26	151.60	1.40	0.00	0.00	
8:27	143.20	8.70	0.00	0.09	
8:28	6.10	353.40	0.00	0.11	
8:29	0.20	473.80	0.00	0.05	
8:30	0.20	484.80	0.00	0.03	
8:31	2.00	478.00	0.01	0.19	
8:32	72.70	141.10	0.00	-0.04	
8:33	91.40	1.50	0.00	-0.04	
8:34	91.20	lh	0.00	-0.04	
8:35	91.00	1.00	0.00	0.50	
8:36	29.80	1.40	0.00	11.91	
8:37	0.20	0.20	0.00	11.95	
8:38	0.20	iz	-0.10	11.96	im
8:39	0.10	-0.10	4.75	6.09	
8:40	0.00	-0.10	9.66	0.74	
8:41	0.10	-0.10	9.97	0.00	im
8:42	0.00	2.30	6.31	0.05	
8:43	0.00	41.00	0.01	0.00	
8:44	0.00	37.50	0.00	-0.01	
8:45	0.00	30.50	0.00	-0.01	ih
8:46	0.00	29.70	0.00	-0.01	
8:47	0.00	29.70	0.00	-0.01	
8:48	0.00	29.60	0.00	-0.01	
8:49	18.30	24.50	0.01	0.07	
8:50	49.90	1.80	0.00	-0.02	
8:51	48.10	0.00	0.00	-0.02	
8:52	47.70	-0.10	0.00	-0.02	
8:53	47.50	0.00	0.00	-0.01	
8:54	47.30	im	0.00	iz	iz
8:55	31.20	2.00	0.00	0.04	
8:56	0.20	13.70	0.00	0.04	
8:57	0.10	14.90	0.00	0.04	
8:58	0.00	14.90	im	0.00	0.04
11:10	0.50	0.30	9.99	0.00	
11:11	0.40	0.30	10.00	m	-0.01
11:12	0.40	0.30	5.50		6.05
11:13	0.40	0.40	0.10		11.88
11:14	0.40	z	0.60	0.04	11.99
11:15	0.40	0.60	0.03		10.75
11:16	23.50	0.60	0.02		0.20
11:17	45.60	0.50	0.02		0.06
11:18	46.50	0.60	0.02		0.05
11:19	46.70	0.40	0.02		0.05
11:20	46.70	0.00	0.02		0.05
11:21	46.70	m	0.00	z	0.05
11:22	15.60	7.40	0.01		0.04
11:23	0.50	14.70	0.01		0.04
11:24	0.40	14.90	m	0.01	0.04

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Project #: M144705

Test Location: Hurst Boiler Exhaust Duct
Operating Condition: Normal
Date: 11/5/14

Post 1/Pre 2

Time	NOx ppmvd	CO ppmvd	CO2 % (dry)	O2 % (dry)
13:06	2.60	1.90	0.08	11.91
13:07	0.30	z	0.04	11.95
13:08	0.30	0.00	1.50	9.34
13:09	0.20	0.00	9.86	0.09
13:10	0.20	0.00	10.00	m
13:11	0.20	0.00	8.63	0.01
13:12	30.40	0.00	0.18	0.06
13:13	46.60	m	0.05	z
13:14	46.40	0.00	0.03	0.06
13:15	43.60	0.70	0.03	0.06
13:16	2.50	11.90	0.02	0.05
13:17	0.30	14.90	0.02	0.05
13:18	0.20	14.90	m	0.02

Post 2/Pre 3

Time	NOx ppmvd	CO ppmvd	CO2 % (dry)	O2 % (dry)
14:54	0.30	0.00	0.03	11.92
14:55	0.20	0.00	0.03	11.93
14:56	0.20	z	0.02	11.93
14:57	0.20	0.00	2.99	7.48
14:58	0.20	0.00	9.93	0.06
14:59	0.20	0.00	10.01	m
15:00	1.10	0.00	7.78	0.01
15:01	36.70	0.00	0.14	0.06
15:02	46.20	0.00	0.04	0.06
15:03	45.90	m	0.03	z
15:04	39.50	0.90	0.02	0.06
15:05	1.90	12.20	0.02	0.06
15:06	0.20	14.90	0.02	0.06
15:07	0.20	14.90	m	0.02

NO₂ to NO Converter Test

Client: University of Iowa
Facility: Oakdale Renewable Energy Plant
Location: Hurst Boiler Exhaust Duct
Date: 11/4/14
Project #: M144705

	Conv. Temp:	632.4 °C
	Max:	84.3 ppm
	Min:	83.2 ppm
	% of Max:	1.30 %

Pre-Calibration			Test			Post-Calibration		
<u>T</u> ime	<u>NO</u> _x	Cal Flag	<u>T</u> ime	<u>NO</u> _x		<u>T</u> ime	<u>NO</u> _x	Cal Flag
16:51	0.3	z	17:09	84.3	Max	17:45:00	0.2	z
16:52	4.8		17:10	84.2		17:46:00	5.1	
16:53	121.0		17:11	84.2		17:47:00	122.2	
16:54	154.1		17:12	84.1		17:48:00	108.2	
16:55	153.5		17:13	84.1		17:49:00	93.5	
16:56	153.4	h	17:14	83.9		17:50:00	92.7	m
16:57	150.7		17:15	84.0				
16:58	96.8		17:16	83.7				
16:59	94.0		17:17	83.9				
17:00	93.5		17:18	83.7				
17:01	92.4		17:19	83.6				
17:02	91.8	m	17:20	83.6				
			17:21	83.7				
			17:22	84.1				
			17:23	83.8				
			17:24	84.0				
			17:25	83.7				
			17:26	83.9				
			17:27	83.7				
			17:28	83.8				
			17:29	83.7				
			17:30	83.6				
			17:31	83.5				
			17:32	83.3				
			17:33	83.5				
			17:34	83.2	Min			
			17:35	83.4				
			17:36	83.3				
			17:37	83.7				
			17:38	83.4				
			17:39	83.6				

PRE-CAL RESULT

zero	0.3
mid	0.67%
high	1.25%

POST-CAL RESULT

zero	0.2
mid	1.27%

Type	RM Analyzer Make/Model	RM Analyzer s/n	Analyzer Span	RM Gas Span			
NO _x ppmvd	TECO 42i-HL	1023743809	90.78	151.5			
Type	Setting	Cylinder ID	Cylinder Value	Analyzer Response	Difference, % of Span	Expiration Date	Final Bottle Pressure, PSI
NO _x ppmvd	Zero	0	0	0.30	-0.20%		0
	Mid	CC310556	90.78	91.80	-0.67%	6/12/2022	750
	High	CC360686	151.5	153.40	-1.25%	5/16/2021	1350

Appendix I - Gas Cylinder Calibration Sheets

CERTIFICATE OF ANALYSIS Grade of Product: EPA Protocol

Airgas Specialty Gases

12722 South Wentworth Avenue
Chicago, IL 60628
(773) 785-3000 Fax: (773) 785-1528
www.airgas.com

Part Number: E02NI99E15A0163
Cylinder Number: CC422360
Laboratory: ASG - Chicago - IL
PGVP Number: B12014
Gas Code: NO,BALN

Reference Number: 54-124418926-2
Cylinder Volume: 144.3 Cubic Feet
Cylinder Pressure: 2015 PSIG
Valve Outlet: 660
Certification Date: Feb 17, 2014

Expiration Date: Feb 17, 2017

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
NOX	45.00 PPM	46.68 PPM	G1	+/- 1.0% NIST Traceable	02/08/2014, 02/17/2014
NITRIC OXIDE	45.00 PPM	46.63 PPM	G1	+/- 1.0% NIST Traceable	02/08/2014, 02/17/2014
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	13061056	CC423751	99.86 PPM NITRIC OXIDE/NITROGEN	+/- 0.8%	Nov 19, 2019
PRM	12312	680179	10.01 PPM NITROGEN DIOXIDE/NITROGEN	+/- 2.0%	Oct 15, 2014
GMIS	124206889130	CC323209	4.824 PPM NITROGEN DIOXIDE/NITROGEN	+/- 2.0%	Oct 25, 2015

The SRM, PRM or RGM noted above is only in reference to the GMIS used in the assay and not part of the analysis.

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nexus 470 AEP0000428	FTIR	Jan 21, 2014
Nexus 470 AEP0000428	FTIR	Jan 21, 2014

Triad Data Available Upon

Request

Notes:

Approved for Release

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E02NI99E15A3576
Cylinder Number: CC310556
Laboratory: ASG - Chicago - IL
PGPV Number: B12014
Gas Code: NO,BALN

Reference Number: 54-124439571-2
Cylinder Volume: 144.3 Cubic Feet
Cylinder Pressure: 2015 PSIG
Valve Outlet: 660
Certification Date: Jun 12, 2014

Expiration Date: Jun 12, 2022

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
NOX	90.00 PPM	90.78 PPM	G1	+/- 0.9% NIST Traceable	06/05/2014, 06/12/2014
NITRIC OXIDE	90.00 PPM	90.47 PPM	G1	+/- 0.9% NIST Traceable	06/05/2014, 06/12/2014
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	13061056	CC423751	99.86 PPM NITRIC OXIDE/NITROGEN	+/- 0.8%	Nov 19, 2019
PRM	12312	680179	10.01 PPM NITROGEN DIOXIDE/NITROGEN	+/- 2.0%	Feb 14, 2012
GMIS	124206889102	CC320508	4.979 PPM NITROGEN DIOXIDE/NITROGEN	+/- 2.0%	May 04, 2015


The SRM, PRM or RGM noted above is only in reference to the GMIS used in the assay and not part of the analysis.

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nexus 470 AEP0000428	FTIR	May 28, 2014
Nexus 470 AEP0000428	FTIR	May 28, 2014

Triad Data Available Upon Request

Notes:



Approved for Release

Airgas Specialty Gases

12722 South Wentworth Avenue

Chicago, IL 60628

(773)785-3000 Fax: (773) 785-1928

www.airgas.com

CERTIFICATE OF ANALYSIS Grade of Product: EPA Protocol

Part Number: E02NI99E15A0283
Cylinder Number: CC360686
Laboratory: ASG - Chicago - IL
PGVP Number: B12013
Gas Code: NO,BALN

Reference Number: 54-124373811-3
Cylinder Volume: 144.4 CF
Cylinder Pressure: 2015 PSIG
Valve Outlet: 660
Certification Date: May 16, 2013

Expiration Date: May 16, 2021

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
NOX	150.0 PPM	151.5 PPM	G1	+/- 0.6% NIST Traceable	05/09/2013, 05/16/2013
NITRIC OXIDE	150.0 PPM	151.5 PPM	G1	+/- 0.6% NIST Traceable	05/09/2013, 05/16/2013
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NO	12061954	CC367722	250.8 PPM NITRIC OXIDE/NITROGEN	+/- 0.5%	May 04, 2018
NO2	124206889130	CC323209	4.824 PPM NITROGEN DIOXIDE/NITROGEN	+/- 2.0%	Oct 25, 2015

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nexus 470 AEP0000428	FTIR	May 01, 2013
Nexus 470 AEP0000426	FTIR	May 01, 2013

Triad Data Available Upon

Request

Notes:

Approved for Release

Airgas.

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E02NI99E15A1129 Reference Number: 54-124348254-5
Cylinder Number: XC013299B Cylinder Volume: 144.3 CF
Laboratory: ASG - Chicago - IL Cylinder Pressure: 2015 PSIG
PGVP Number: B12012 Valve Outlet: 350
Gas Code: APPVD Analysis Date: Dec 03, 2012

Expiration Date: Dec 03, 2020

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis, unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty
CARBON MONOXIDE	15.00 PPM	14.59 PPM	G1	+/- 1% NIST Traceable
NITROGEN	Balance			

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Expiration Date
NTRM/CO	08060201	CC255804	51.26 PPM CARBON MONOXIDE/NITROGEN	Jan 17, 2018

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
Nexus 470 AEP0000426	FTIR	Nov 05, 2012

Triad Data Available Upon Request

Notes:

Approved for Release

CERTIFICATE OF ANALYSIS Grade of Product: EPA Protocol

Part Number: E02NI99E15A0497 Reference Number: 54-124384692-1
Cylinder Number: SG9146479BAL Cylinder Volume: 144.3 CF
Laboratory: ASG - Chicago - IL Cylinder Pressure: 2015 PSIG
PGVP Number: B12013 Valve Outlet: 350
Gas Code: CO,BALN Certification Date: Jul 16, 2013

Expiration Date: Jul 16, 2021

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
CARBON MONOXIDE	30.00 PPM	30.63 PPM	G1	+/- 1.0% NIST Traceable	07/16/2013
NITROGEN	Balance				
CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
CO	12060505	CC353897	49.53 PPM CARBON MONOXIDE/NITROGEN	+/- 0.6%	Dec 20, 2017
ANALYTICAL EQUIPMENT					
Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration			
Nexus 470 AEP0000428	FTIR	Jun 21, 2013			

Triad Data Available Upon Request

Notes:

Approved for Release

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E02NI90E15A0123 Reference Number: 54-124435717-5
Cylinder Number: CC183734 Cylinder Volume: 149.8 CF
Laboratory: ASG - Chicago - IL Cylinder Pressure: 2015 PSIG
PGVP Number: B12014 Valve Outlet: 580
Gas Code: CO2,BALN Certification Date: May 23, 2014

Expiration Date: May 23, 2022

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
CARBON DIOXIDE	10.00 %	9.968 %	G1	+/- 0.7% NIST Traceable	05/23/2014
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	97050816	SG9167530BAL	7.029 % CARBON DIOXIDE/NITROGEN	+/- 0.5%	May 01, 2016

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
CO2-1 HORIBA VIA-510 V1E3H7P5	NDIR	May 23, 2014

Triad Data Available Upon

Request

Notes:



Approved for Release

**Airgas Specialty Gases**

12722 South Wentworth Avenue
Chicago, IL 60628
(773) 785-3000 Fax: (773) 785-1928
www.airgas.com

**CERTIFICATE OF ANALYSIS
Grade of Product: EPA Protocol**

Part Number: E02NI80E15ACMD7 Reference Number: 54-124399697-2
Cylinder Number: CC415912 Cylinder Volume: 156.5 CF
Laboratory: ASG - Chicago - IL Cylinder Pressure: 2015 PSIG
PGPV Number: B12013 Valve Outlet: 580
Gas Code: CO2,BALN Certification Date: Oct 14, 2013

Expiration Date: Oct 14, 2021

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
CARBON DIOXIDE	19.50 %	19.47 %	G1	+/- 0.8% NIST Traceable	10/14/2013
NITROGEN	Balance				
CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
CO2	06120405	CC184974	19.66 % CARBON DIOXIDE/NITROGEN	+/- 0.5%	May 01, 2016
ANALYTICAL EQUIPMENT					
Instrument/Make/Model	Analytical Principle		Last Multipoint Calibration		
CO2-1 HORIBA VIA-510 V1E3H7P5	NDIR		Oct 11, 2013		

Triad Data Available Upon Request

Notes:

Approved for Release

CERTIFICATE OF ANALYSIS**Grade of Product: EPA Protocol**

Part Number: E02NI88E15A3424
Cylinder Number: CC455275
Laboratory: ASG - Chicago - IL
PGVP Number: B12014
Gas Code: O2,BALN

Reference Number: 54-124455443-1
Cylinder Volume: 145.4 Cubic Feet
Cylinder Pressure: 2015 PSIG
Valve Outlet: 590
Certification Date: Sep 22, 2014

Expiration Date: Sep 22, 2022

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
OXYGEN	12.00 %	11.99 %	G1	+/- 1% NIST Traceable	09/22/2014
NITROGEN	Balance				
CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	06120208	CC195923	20.9 % OXYGEN/NITROGEN	+/- 0.4%	Dec 01, 2015
ANALYTICAL EQUIPMENT					
Instrument/Make/Model		Analytical Principle		Last Multipoint Calibration	
O2-1 HORIBA MPA-510 3VUYL9NR		Paramagnetic		Sep 17, 2014	

Triad Data Available Upon Request



Signature on file

Approved for Release

Page 1 of 54-124455443-1

CERTIFICATE OF ANALYSIS

Grade of Product: EPA Protocol

Part Number: E02NI78E15A0124
Cylinder Number: CC94285
Laboratory: ASG - Chicago - IL
PGVP Number: B12013
Gas Code: O2,BALN

Reference Number: 54-124399697-1
Cylinder Volume: 146.3 CF
Cylinder Pressure: 2015 PSIG
Valve Outlet: 590
Certification Date: Oct 15, 2013

Expiration Date: Oct 15, 2021

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a volume/volume basis unless otherwise noted.

Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS					
Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
OXYGEN	22.00 %	22.25 %	G1	+/- 1.0% NIST Traceable	10/15/2013
NITROGEN	Balance				
CALIBRATION STANDARDS					
Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM/O2	06120211	CC195925	20.90 % OXYGEN/NITROGEN	+/- 0.4%	Dec 01, 2015
ANALYTICAL EQUIPMENT					
Instrument/Make/Model	Analytical Principle		Last Multipoint Calibration		
O2-1 HORIBA MPA-510 3VUYL9NR	Paramagnetic		Sep 23, 2013		

Triad Data Available Upon Request

Notes:

Approved for Release

Appendix J - Mercury QA/QC Data

Spike Recovery Summary
Oakdale Renewable Energy Plant
Hurst Boiler Exhaust Duct
11/5/2014

Test Run	Start Time	End Time	Actual Concentration, ng	Expected Spike Concentration, ng	Sample Volume, standard liters	Recovery %
1A	11:35	12:45	85.6	N/A	137.576	78.46
1B			103.9	25	135.462	
2A	13:25	14:35	59.2	N/A	136.702	83.33
2B			78.4	25	132.931	
3A	15:13	16:05	28.9	N/A	116.988	107.26
3B			50.6	25	96.283	
Average Recovery %						89.69

Certificate of Analysis

Product Description:

Name:	Mercury	Source Material:	Mercury Metal
Part Number:	100033-1	Material Purity:	99.9998%
Lot Number:	1309308	Matrix:	2% (v/v) HNO ₃

Certified Value: 1000 µg/mL ± 6 µg/mL

The Certified value is based on gravimetric and volumetric preparation, and confirmed against SRM 3133 (lot number 061204) by inductively coupled plasma optical emission spectrometry (ICP-OES) using an internal laboratory-developed method. The uncertainty in the certified value is calculated for a 95% confidence interval and coverage factor *k* is about 2.

Density: 1.009 g/mL ± 0.002 g/mL @ 22.4°C

Uncertified Values:

Trace Metal Impurity Scan: The data reported are based upon a scan of this specific lot at 1000 µg/mL via ICP analysis. The values are reported in µg/L.

Ag	<	10	Cu	<	0.1	Li	<	0.02	Rb	<	0.02	Th	<	0.02
Al	<	0.1	Dy	<	0.02	Lu	<	0.02	Re	<	0.02	Tl	<	0.02
As	<	0.05	Er	<	0.02	Mg	<	0.5	Rh	<	0.02	Tl	<	0.02
Au	<	0.02	Eu	<	0.02	Mn	<	0.1	Ru	<	0.02	Tm	<	0.02
B	<	1	Fe	<	1	Mo	<	0.1	Sb	<	0.02	U	<	0.1
Ba	<	0.02	Ga	<	0.02	Na	<	3	Sc	<	0.02	V	<	0.05
Be	<	0.02	Gd	<	0.02	Nb	<	0.02	Se	<	0.1	W	<	0.02
Bi	<	0.02	Ge	<	0.02	Nd	<	0.02	Si	<	10	Y	<	0.02
Ca	<	1	Hf	<	0.02	Ni	<	0.02	Sm	<	0.02	Yb	<	0.02
Cd	<	0.02	Ho	<	0.02	Os	na		Sn	<	1	Zn	<	2
Ce	<	0.02	In	<	0.02	Pb	<	0.05	Sr	<	0.02	Zr	<	0.02
Co	<	0.05	Ir	<	0.02	Pd	<	0.02	Ta	<	0.02	Hg	M	
Cr	<	0.1	K	<	1	Pr	<	0.02	Tb	<	0.02			
Cs	na		La	<	0.02	Pt	<	0.02	Te	<	0.02			

Preparation Information:

The standard solution is prepared using high purity materials and assayed by analytical methods for conformity prior to use. This standard was prepared using the methods developed at NIST for SRM Spectrometric Standard Solutions under appropriate laboratory conditions.

Sub-boiling distilled high-purity acid has been used to place the materials in solution and to stabilize the standard. The matrix is as noted above in 18 megaohm deionized water.

Stability of this product is based upon rigorous short term and long term testing of the solution for the certified value. This testing includes, but is not limited to, the effect of temperature and packaging on the product.

Lot No.: 1309308
 Rev. No.: 5.1.0
 Page 1 of 2

High-Purity Standards is certified to ISO 9001:2008 and accredited to ISO/IEC 17025:2005 and ISO Guide 34:2009.

Intended Use:

This Certified Reference Material (CRM) is intended for use as a calibration standard for the quantitative determination of mercury, calibration of instruments such as ICPOES, ICPMS, AAS and XRF, and validation of analytical methods. It also can be used in EPA, ASTM and other methods.

Traceability Information:

The traceability of this standard is maintained through an unbroken chain of comparisons to appropriate standards with suitable procedure and measurement uncertainties. The maintenance of the base and derived units of International System of Units (SI) with traceability of measurement results (contemporary metrology) to SI ensures their comparability over time as follows.

a. Standard Weight and Analytical Balance

The standard weights (NBS weights Inventory No 20231A) are calibrated every two years by South Carolina Metrology Laboratory that is a participant in "NIST Weights and Measures Measurement Assurance Program" with a certificate of measurement traceability to NIST primary standards.

The balances are calibrated yearly by the ISO 17025 accredited metrology service, and are verified weekly by an in-house method using standard weights.

b. Volumetric Device

The calibration of volumetric vessels is checked annually using the NBS 602 method.

c. Thermometer

The standard thermometers are calibrated every year by the ISO 17025 accredited metrology service. The thermometers used in-house are verified against the standard thermometers yearly.

d. Calibration Standards:

The Calibration Standard is directly traceable to SRM 3100 Series Spectrometric Standard Solutions.

Packaging and Storage Conditions:

The standard is packaged in a pre-cleaned polyethylene bottle. To maintain the integrity of this product, the solution should be kept tightly capped and stored under normal laboratory conditions.

Refer to Material Safety Datasheet (MSDS) for hazardous information.**Expiration Information:**

The expiry date is guaranteed to be valid for eighteen months from the shipping date provided. For this reason, standards from the same lot may have different expiration dates.

Preparation Date: April 3, 2013

Shipped Date: November 21, 2013

Expiration Date: May 21, 2015

Certificate Issue Date: April 29, 2013

Quality Information:

ISO/IEC 17025:2005 Accreditation
Certificate Number AT-1529



Vanny T. Yib,
Inorganic Laboratory Manager



ISO Guide 34:2009 (RMP) Accreditation
Certificate Number AR-1436



Angel Sellers'
Quality Manager

NOTICE: HPS products are intended for laboratory use only. All products should be handled and used by trained professional personnel. The responsibility for the safe handling and use of these products rests solely with the buyer and/or user. The data and information as stated was furnished by the manufacturer of the product. The information provided in this certificate pertains only to the lot number specified. None of the information provided in this certificate may be used, reproduced or transmitted in any form or by any means without written approval from High Purity Standards.

Lot No.: 1309308
Rev. No.: 5.1.0
Page 2 of 2

High-Purity Standards is certified to ISO 9001:2008 and accredited to ISO/IEC 17025:2005 and ISO Guide 34:2009.



RICCA CHEMICAL COMPANY

Arlington, TX 76012

Pocomoke City, MD 21851

Batesville, IN 47006

<http://www.riccacalchemical.com>

1-888-GO-RICCA

customerservice@riccacalchemical.com

Certificate of Analysis

Mercury ICP Standard, 1 mL = 1 mg Hg (1,000 ppm Hg)

Hg in 3% HNO₃

Lot Number: 4310B59

Product Number: PHG1KN

Expiration Date: APR 2015

Manufacture Date: 10/25/2013

The certified value for this product is confirmed in independent testing by a second qualified chemist. The uncertainty associated with the certified value is $\pm 0.5\%$ relative, which is the sum of the estimated errors due to the purity of the raw material, the volumetric preparation of the solution, and transpiration of the solution through the container wall.

The final solution concentration is confirmed by AA, ICP, or ICP-MS, and is traceable to NIST Standard Reference Material 3133. All trace level elements were determined by ICP or ICP-MS.

This product number replaces 4801 as of 2007.

Contains:

Name	CAS#	Grade
Mercury, Hg	7439-97-6	High Purity
Nitric Acid, HNO ₃	7697-37-2	Trace Metals
Water, Deionized, H ₂ O	7732-18-5	ACS; ASTM D 1193 (Type I), EP, USP

Test Name	Assay Method	Specification	Result
Appearance	Clarity, Color, Odor	Clear, colorless, odorless	Passed Test
Assay at 20 °C (traceable to NIST SRM 999)	Titrimetric vs. Potassium Thiocyanate (Volhard's Indicator)	1000 \pm 5 ppm Hg	1001 ppm Hg

I=Spectral Interference N=Not Tested

Trace Elements by ICP or ICP - MS

All values reported in mg/l (ppm)

Aluminum (Al)	0.02003	Gallium (Ga)	< 0.0006	Osmium (Os)	< 0.003	Tantalum (Ta)	0.00152
Antimony (Sb)	< 0.0001	Germanium (Ge)	< 0.0003	Palladium (Pd)	0.09381	Tellurium (Te)	0.02324
Arsenic (As)	< 0.0007	Gold (Au)	N	Phosphorus (P)	< 0.02	Terbium (Tb)	< 0.00003
Barium (Ba)	0.0021	Hafnium (Hf)	< 0.001	Platinum (Pt)	0.00058	Thallium (Tl)	0.00512
Beryllium (Be)	< 0.0001	Holmium (Ho)	< 0.0001	Potassium (K)	< 0.00002	Thorium (Th)	< 0.0002
Bismuth (Bi)	0.00043	Indium (In)	< 0.00003	Praseodymium (Pr)	< 0.00003	Thulium (Tm)	< 0.00002
Boron (B)	< 0.00005	Iridium (Ir)	< 0.00007	Rhenium (Re)	< 0.00003	Tin (Sn)	< 0.0002
Cadmium (Cd)	< 0.00007	Iron (Fe)	< 0.001	Rhodium (Rh)	< 0.00003	Titanium (Ti)	< 0.001
Calcium (Ca)	1	Lanthanum (La)	< 0.00004	Rubidium (Rb)	< 0.00004	Tungsten (W)	0.02310
Cerium (Ce)	< 0.00003	Lithium (Li)	< 0.02936065	Ruthenium (Ru)	< 0.00007	Uranium (U)	0.00009
Cesium (Cs)	< 0.00005	Lutetium (Lu)	< 0.0003	Samarium (Sm)	< 0.002	Vanadium (V)	0.00007
Chromium (Cr)	< 0.00006	Magnesium (Mg)	0.0032	Scandium (Sc)	< 0.00008	Ytterbium (Yb)	< 0.001
Cobalt (Co)	< 0.00002	Manganese (Mn)	< 0.00002	Selenium (Se)	< 0.004	Yttrium (Y)	< 0.00009
Copper (Cu)	< 0.00005	Molybdenum (Mo)	0.0076	Silicon (Si)	< 0.007	Zinc (Zn)	< 0.0003
Dysprosium (Dy)	< 0.0001	Neodymium (Nd)	< 0.0002	Silver (Ag)	0.0029	Zirconium (Zr)	< 0.002
Erbium (Er)	< 0.00007	Nickel (Ni)	< 0.0001	Sodium (Na)	< 0.02		
Europium (Eu)	< 0.00008	Niobium (Nb)	0.00125	Strontrium (Sr)	< 0.00006		
Gadolinium (Gd)	< 0.0002			Sulfur (S)	N		

Specification	Reference	Method Number
Mercury ICP Standard, 1 mL = 1 mg Hg (1,000 ppm Hg) Hg in 3% HNO ₃	EPA	200.7

Volumetric glassware complies with Class A tolerance requirements of ASTM E 288 and NIST Circular 434; it is calibrated before first use and recalibrated regularly in accordance with ASTM E 542 and NIST Procedure NBSIR 74-461. Balances are calibrated regularly with weights certified traceable to the NIST national mass standard. Thermometers and temperature probes are calibrated before first use and recalibrated regularly with a thermometer traceable to NIST standards. All products are prepared according to master documents that ensure manufacture according to validated methods. Batch records document raw material traceability and production and testing history for each lot manufactured.

(e (unopened container):

Part Number	Shelf Life
PHG1KN-100	18 months
PHG1KN-500	18 months

Recommended Storage: 15°C - 30°C (59°F - 86°F)



LaNelle Ohlhausen
Quality Assurance

This Certificate of Analysis is designed to comply with ISO Guide 31 "Reference Materials – Contents of Certificates and Labels."

To determine manufacture site using lot number, visit <http://www.riccachemical.com/Documents/lot.pdf>.

Ohio Lumex - Analytical Bias Test
14-Feb-08

Minimum Mass Sample Determination					
Test Run	Test Time	Fraction	Actual Concentration, ng	Expected Spike Concentration, ng	Recovery %
1	15:31	Hg ⁰	28	30	93.33
2	16:03	Hg ⁰	28	30	93.33
3	16:46	Hg ⁰	27	30	90.00
1	15:54	HgCl ₂	31	30	103.33
2	16:13	HgCl ₂	29	30	96.67
3	16:38	HgCl ₂	28	30	93.33

Maximum Mass Sample Determination					
Test Run	Test Time	Fraction	Actual Concentration, ng	Expected Spike Concentration, ng	Recovery %
1	18:49	Hg ⁰	1950	1900	102.63
2	18:57	Hg ⁰	1890	1900	99.47
3	19:11	Hg ⁰	1780	1900	93.68
1	18:41	HgCl ₂	1910	1900	100.53
2	18:51	HgCl ₂	1810	1900	95.26
3	19:00	HgCl ₂	1860	1900	97.89

END OF THE REPORT