
EQM CONTACT
Environmental Quality Management
18000 Carillon Boulevard
Cincinnati, OH 45240
(513)-265-8875

Mr. Eric Bowman

CONSULTANT CONTACT
KIESER & ASSOCIATES, LLC
536 E. Mich. Ave, Ste 300
Kalamazoo, MI 49007
(269) 344-7117
Mr. Brian Boyer, P.E.



KALAMAZOO COUNTY, MICHIGAN





ESER ASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA-IB

INDEX OF DRAWING SHEETS

- 1 Cover Sheet
- 2 Site SA-1B Vegetation Plan
- 3 Detail Drawings
- 4-6 Specifications



SITE LOCATION MAP

CITY OF KALAMAZOO
http://www.kalamazoocity.org/onlinegis/CXviewer.htm
T2s R11w, SE 1/4 of Section 22
in Kalamazoo County, Michigan.



Know what's below. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT

<u>NOTE TO CONTRACTOR:</u> 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".


EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- 2. ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- 7. SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. With EPA oversight, Contractor is not required to obtain permits for re-vegetation work.
- The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.









ER









PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF SEED.

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER PINNING.

THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.

WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 5" OVERLAP, STAPLE THROUGH OVERLAPPED AREA APPROXIMATELY 12" APART.

BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.

. LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.

NOTES:

1. ON-CENTER PLANT SPACING INDICATED ON PLANTING PLAN.

2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

- EROSION BLANKET INSTALLED BEFORE PLANTING

PROFILE

PLANTING

GROUNDOOMER - NO SCALE

SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE

EROSION CONTROL BLANKET DETAIL NO SCALE

SOIL EROSION CONTROL **GEOTEXTILE SILT FENCE**

STAKING AND PLANTING TREE DETAIL

BACK FILL 1 PART COMPOST WITH 5 PARTS EXISTING SOIL

- COMPACT BACK FILL IN BOTTOM OF HOLE

ROOT BALL TO BE 1/3 - 1/2 ABOVE EXISTING GRADE BASED ON SOIL DRAINAGE TWICE RADIUS IMPORTED TOP SOIL PEEL BACK BURLAP ON BAB SHRUBS

SHRUB DETAIL CONTAINER AND B&B

NO SCALE

SER

SA-1B VEGETATION

GENERAL PART 1.

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding.
- C. Seed protection on slopes.
- Planting special seed mixes.
 - 1. DP-3 (Short Stature Prairie Seed Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - 1. Submit seed tags to Engineer prior to seeding.
 - 2. Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Topsoil
 - 1. Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed to minimize weed seed viability.
- - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

SEED MIXTURE

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Chad Hughson

Contact: Cheryl Tolley

Contact: Randy Counterman

Contact: Trish Hacker-Henning

14921 Hand Road

Fort Wayne, Indiana 46818

Ph; (260) 489-8511

Fx: (260) 489-8607

Email: mail@carthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140

Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214

Fax: (616) 691-7872 Email: cherylt@iserv.net

6) Native Landscapes

28092 M-40 Hwy. Paw Paw, MI 49079 Phone: 269-929-3455

Email: randy.counterman@gmail.com

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

Page 2

Page I

SER

B. Special Native Seed Mixes

1) Midwestern Short Stature Prairie Seed Mix (DP-3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientific Name	Common Name
Grasses, Sedges, and	Rushes
Bouteloua curtipendula	Side Oats Grama
Carex bicknellii	Bicknell's Sedge
Elymus virginicus	Virginia Wild Rye
Schizachyrium scoparium	Little Bluestem
Sporobolus heterolepis	Prairie Dropseed

Forbs

Forbs	
Asclepias syriaca	Common Milkweed
Asclepias tuberosa	Butterfly Milkweed
Aster ericoides	White Heath Aster
Coreopsis lanceolata	Sand Coreopsis
Corcopsis palmata	Prairie Coreopsis
Echinacea purpurea	Purple Coneflower
Gentiana andrewsii	Fringe-top Bottle Gentian
Helianthus occidentalis	Few-leaf Sunflower
Lespedeza capitata	Round-headed Bushclover
Liatris aspera	Rough Blazingstar
Liatris scariosa nieuwlandii	Savanna Blazingstar
Lupinus perennis	Wild Blue Lupine
Parthenium integrifolium	Wild Quinine
Penstemon digitalis	Foxglove Beard Tongue
Petalostemum purpureum	Purple Prairie Clover
Potentilla arguta	Tall Cinquefoil
Pycnanthemum virginianum	Mountain Mint
Rudbuckia fulgida	Showy Black-eyed Susan
Rudbeckia hirta	Black-eyed Susan
Solidago nemoralis	Gray Goldenrod
Tradescantia ohiensis	Ohio Spiderwort
Verbena stricta	Hoary Vervain
Zizia aurea	Golden Alexanders

Temporary Cover Grasses

Avena sativa Seed Oats

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

- C. Weed seed content shall not exceed 0.25 percent for any variety of seed mixture.
- D. Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

A. Within all disturbed Project Areas, the surface of the topsoil shall be rough graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions.

3.02 SEEDING & FERTILIZING

- A. Contractor shall broadcast seed all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- B. Seed shall be applied to all Repair Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the Repair Areas.

3.03 MULCHING & EROSION CONTROLS

- A. On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- B. Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- C. All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Hanes Geo Components 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

Portage Creek Area Time Critical Removal Action

Specifications 02920

FQM Project Number: 030281.0087

KIESER & ASSOCIATES, LLC

Contact: Mark Cavanaugh

Page 4

Page 3

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. Straw Single Net Erosion Blankets (100% biodegradable).
 - 2. TerraTex HPG-44 Geotextile Fabric
 - 3. Ecolofence 24" Silt Fence
- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all crosion control devices throughout the duration of the construction period.
- All temporary crosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of A. vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC