

POOR LEGIBILITY

ONE OR MORE PAGES IN THIS DOCUMENT ARE DIFFICULT TO READ
DUE TO THE QUALITY OF THE ORIGINAL

CITY OF MOUNTAIN VIEW

July 18, 1969

Capital Improvement Review Committee
c/o Al St. Cyr, Asst. City Manager
A. H. McKinnon, Director of Public Works

MOFFETT BOULEVARD SANITARY SEWER RELOCATION, PROJECT 69-4

Enclosed in triplicate is a Capital Improvement Project request for the subject sewer main improvements. This project is being initiated to eliminate a serious maintenance problem by replacing a 1,000 foot section of shallow 6" VCP sanitary sewer main located 2.5 feet from the curb and 18 sewer laterals from Walker Drive to 300 feet northward of Winston Place along (Old) Moffett Boulevard. It is to be noted that the crews responded to 48 lateral stoppages last year. A breakdown of current maintenance costs and anticipated maintenance costs upon replacement of the sewer main is attached.

The maintenance problem is caused by the intrusion of roots from pine trees located in a planter behind the curb. The sewer main is to be replaced at a new location 21 feet from the face of curb and at a greater depth than the existing facility.

The estimated cost of \$22,000 is to be encumbered from the 1966 Sewer Bond Fund.

A. H. MCKINNON

gb

City Manager w/o
Director of Public Works w/c
Director of Planning w/c
Asst. Dir. of Public Works w/c
Senior Engineer w/c
Public Works Supt. w/c
Design Engineer w/c
P/y w/c