



U.S. DEPARTMENT OF TRANSPORTATION
RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION
JOHN A. VOLPE NATIONAL TRANSPORTATION SYSTEMS CENTER
ENVIRONMENTAL ENGINEERING DIVISION, DTS-33
55 BROADWAY, KENDALL SQUARE
CAMBRIDGE, MASSACHUSETTS 02142

MILLWORK WEST SITE IMPROVEMENTS

ASBESTOS REMOVAL PROJECT

LIBBY, MONTANA

MAY 2002

LIST OF DRAWINGS	
<u>SHEET NO.</u>	<u>TITLE</u>
C-1	<u>SITE PLAN</u>
A-1	FLOOR PLANS
A/P-1	TOILET ROOM PLAN, ARCHITECTURAL & PLUMBING DETAILS
S-1	STRUCTURAL – BUILDING #2 – NEW SLAB PLAN, SECTIONS, DETAILS & NOTES
E-1	ELECTRICAL PLAN

CONTRACTOR SUPPORT PROVIDED BY:

CDM Federal Programs Corporation
a Subsidiary of Camp Dresser & McKee Inc.

*consulting
engineering
construction
operations*
ONE CAMBRIDGE PLACE
50 HAMPSHIRE STREET
CAMBRIDGE, MASSACHUSETTS 02139

- NOTES
1. THESE DRAWINGS AND ACCOMPANYING SPECIFICATIONS HAVE BEEN PREPARED FOR THE GOVERNMENT'S USE IN PROVIDING A GENERAL DESCRIPTION OF THE WORK TO BE DONE FOR THE GOVERNMENT'S REMOVAL CONTRACTOR AT BUILDING NO. 1 AND BUILDING NO. 2 ON HIGHWAY 2 IN LIBBY, MONTANA.
 2. THE WORK DESCRIBED IN THE DRAWINGS AND SPECIFICATIONS WILL BE CONSTRUCTED IN TWO WOOD FRAME METAL CLAD BUILDINGS ORIGINALLY INTENDED TO SERVE AS A TEMPORARY LOCATION FOR THE MILLWORK WEST LUMBER AND BUILDING MATERIALS BUSINESS.
 3. THE WORK DESCRIBED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS NOT INTENDED TO BE PUBLICLY BID.
 4. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE PROVIDED TO THE GOVERNMENT'S REMOVAL CONTRACTOR FOR ESTIMATES, CONSTRUCTION SCHEDULING, OBTAINING LOCAL SUBCONTRACTORS APPROPRIATELY LICENSED TO PERFORM SPECIALTY CONSTRUCTION (PLUMBER, ELECTRICIAN, ETC.), OBTAINING NECESSARY LOCAL PERMITS (REST ROOM PERMIT) AND COMPLETING THE WORK.
 5. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO PROVIDE A GENERAL DESCRIPTION OF THE WORK TO BE PERFORMED. THE GOVERNMENT'S REMOVAL CONTRACTOR IS REQUIRED TO VERIFY ALL DIMENSIONS PRIOR TO STARTING THE WORK.
 6. NO PROPERTY LINE OR TOPOGRAPHICAL SURVEYS WERE AVAILABLE TO REFERENCE FOR PREPARATION OF THE DRAWINGS.
 7. NO INVESTIGATIONS HAVE BEEN MADE WITH RESPECT TO THE CURRENT USE OR POTENTIAL USE OF THE EXISTING BUILDINGS.
 8. EVALUATION OF THE EXISTING BUILDINGS WITH RESPECT TO STRUCTURAL INTEGRITY, BUILDING CODE COMPLIANCE, EXISTING CONDITION WERE NOT INCLUDED IN THE DESIGN SCOPE OF WORK.
 9. CDM'S SCOPE OF WORK FOR EXISTING BUILDING NO. 2 WAS LIMITED TO DESIGN OF A REINFORCED CONCRETE SLAB TO BE INSTALLED BY THE GOVERNMENT'S REMOVAL CONTRACTOR, DESIGN OF A SINGLE UNISEX, HANDICAPPED ACCESSIBLE REST ROOM MEETING THE REQUIREMENTS OF THE ANSI ACCESSIBILITY CODE, 1998 EDITION, REST ROOM WATER SERVICE, REST ROOM VENTILATION, DESIGN OF A SEPTIC TANK LOCATED OFF OF THE PROPERTY, REST ROOM WATER SERVICE, REST ROOM VENTILATION, DESIGN OF A SEPTIC TANK LOCATED ON THE PROPERTY FROM THE PROPERTY LINE, AND DESIGN OF A REST ROOM PERMITTED SEPTIC TANK LOCATED ON THE PROPERTY APPROXIMATELY 300 FT. FROM BUILDING NO. 2.
 10. CDM'S SCOPE OF WORK FOR EXISTING BUILDING NO. 1 WAS LIMITED TO DESIGN OF ASPHALT PAVEMENT TO BE INSTALLED BY THE GOVERNMENT'S REMOVAL CONTRACTOR OVER APPROXIMATELY 60% OF THE INTERIOR FLOOR AREAS.

PRELIMINARY - FOR REVIEW ONLY