

ASBESTOS ASSESSMENT SURVEY

H-K Building 13
 Project Number: 0980193E
 Project: G. HEILEMAN BREWERY "E"
 Date Inspected: 03/21/89
 Inspector: MARK VOTH

Building Number: 13
 Building Name: BOILER HOUSE
 SEATTLE, WASHINGTON
 Building Type: POWER HSE
 Year Constructed: 1933

*****	AREA NUMBER: 01	AREA DESCRIPTION: 1st Floor	AREA AVERAGE % ASBESTOS: %	*****
-------	-----------------	-----------------------------	----------------------------	-------

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
boiler #1-encased in steel	00-999999	%	boiler/tank insulation	OMB	937	sq.ft.				\$26,470	\$21,204	\$47,674
boiler #2-encased in steel	00-999999	%	boiler/tank insulation	OMB	937	sq.ft.				\$26,470	\$21,204	\$47,674
boiler #3-encased in steel	00-999999	%	boiler/tank insulation	OMB	1300	sq.ft.				\$36,725	\$29,419	\$66,144

AREA COMMENTS

The boiler insulation is encased in a metal jacket and could not be accessed for sampling. The material is in good condition with no visible contact or water damage. The material is up to 12' from the floor. At a minimum, it is recommended that the material be maintained and monitored. If removal is planned, gross removal procedures are recommended. This appears to be a high traffic area.

AREA # 01 TOTAL \$89,665 \$71,827 \$161,492

*****	AREA NUMBER: 02	AREA DESCRIPTION: 1st Floor-Catwalk Level	AREA AVERAGE % ASBESTOS: %	*****
-------	-----------------	---	----------------------------	-------

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
above boiler #1-fire box-at west wall	00-999999	%	boiler/tank insulation	OMB	739	sq.ft.				\$20,877	\$16,724	\$37,601

AREA COMMENTS

The deaeration tank insulation is encased in a metal jacket and can not be accessed for sampling. The material is in good condition with no visible contact or water damage. The material is approximately 20' to 30' from the floor. At a minimum, it is recommended that the materials be maintained and monitored. If removal is planned, gross removal procedures are recommended. This appears to be a high traffic area.

AREA # 02 TOTAL \$20,877 \$16,724 \$37,601

*****	AREA NUMBER: 03	AREA DESCRIPTION: 1st Floor	AREA AVERAGE % ASBESTOS: 46%	*****
-------	-----------------	-----------------------------	------------------------------	-------

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
NW corner-above boiler feed water pumps	00-356083	30%	pipe covering	OMA	7 ft. 4 in.	O.D. BFW	41	II		\$62	\$39	\$101
NW corner-above boiler feed water pumps	00-356083	30%	pipe covering	OMA	130 ft. 6 in.	O.D. BFW	41	II		\$1,687	\$1,054	\$2,741
NW corner-above boiler feed water pumps	00-356083	30%	pipe covering	OMA	10 ft. 10 in.	O.D. BFW	41	II		\$189	\$140	\$329
along west wall-near catwalk	00-356083	30%	pipe covering	OMA	100 ft. 8 in.	O.D. BFW	41	II		\$1,415	\$1,011	\$2,426
along west wall-near catwalk	00-356083	30%	pipe covering	OMA	20 ft. 10 in.	O.D. BFW	41	II		\$377	\$279	\$656
between boilers #1 & 2-near floor	00-356083	30%	pipe covering	OMA	40 ft. 4 in.	O.D. BFW	41	II		\$357	\$223	\$580
boilers #2 & 3-front-near catwalk	00-356083	30%	pipe covering	OMA	34 ft. 6 in.	O.D. BFW	41	II		\$441	\$276	\$717

H-K Building 3
 Project Number: 0980193E
 Project: G. HEILEMAN BREWERY "E"
 Date Inspected: 03/21/89
 Inspector: MARK VOTH

ASBESTOS ASSESSMENT SURVEY

Building Number: 13
 Building Name: BOILER HOUSE
 SEATTLE, WASHINGTON
 Building Type: POWER HSE
 Year Constructed: 1933

boiler #1-near economizer	00-356083	30%	pipe covering	OMA	15 ft. 4 in. O.D. BFW	41 II	\$134	\$84	\$218
boiler #1-near economizer	00-356083	30%	pipe covering	OMA	45 ft. 6 in. O.D. BFW	41 II	\$584	\$365	\$949
boilers #2 & 3-front-near catwalk	00-356083	30%	pipe covering	OMA	17 ft. 4 in. O.D. BFW	41 II	\$152	\$95	\$247
near NW corner-deaerator-above pumps	00-356087	30%	pipe covering	OMA	5 ft. 10 in. O.D. TV	41 II	\$94	\$70	\$164
NW corner-above boiler feed water pumps	00-356087	30%	pipe covering	OMA	20 ft. 8 in. O.D. TV	41 II	\$283	\$202	\$485
NW corner-above boiler feed water pumps	00-356087	30%	pipe covering	OMA	20 ft. 10 in. O.D. TV	41 II	\$377	\$279	\$656
near NW corner-deaerator-above pumps	00-356087	30%	pipe covering	OMA	105 ft. 8 in. O.D. TV	41 II	\$1,486	\$1,062	\$2,548
NW corner-above boiler feed water pumps	00-356091	70%	pipe covering	OMA	20 ft. 6 in. O.D. HPS/R	41 II	\$260	\$162	\$422
NW corner-above boiler feed water pumps	00-356091	70%	pipe covering	OMA	15 ft. 4 in. O.D. HPS/R	41 II	\$134	\$84	\$218
along west wall-near catwalk	00-356091	70%	pipe covering	OMA	138 ft. 4 in. O.D. HPS/R	41 II	\$1,231	\$770	\$2,001
along west wall-near catwalk	00-356091	70%	pipe covering	OMA	35 ft. 6 in. O.D. HPS/R	41 II	\$454	\$284	\$738
east wall-near sink	00-356091	70%	pipe covering	OMA	30 ft. 6 in. O.D. HPS/R	41 II	\$389	\$243	\$632
between boilers #1 & 2-near floor	00-356091	70%	pipe covering	OMA	36 ft. 4 in. O.D. HPS/R	41 II	\$321	\$201	\$522
SW corner-at fuel oil heat exchanger	00-356091	70%	pipe covering	OMA	55 ft. 4 in. O.D. HPS/R	41 II	\$491	\$307	\$798
along south wall-near catwalk	00-356091	70%	pipe covering	OMA	35 ft. 4 in. O.D. HPS/R	41 II	\$312	\$195	\$507
boilers #2 & 3-front-near catwalk	00-356091	70%	pipe covering	OMA	25 ft. 4 in. O.D. HPS/R	41 II	\$223	\$139	\$362
along north wall-at ceiling	00-356095	20%	wrapped cardboard/paper pipe	OMA	60 ft. 4 in. O.D. DW	41 II	\$535	\$335	\$870
near northwest corner-at ceiling	00-356095	20%	wrapped cardboard/paper pipe	OMA	25 ft. 4 in. O.D. DW	41 II	\$223	\$139	\$362
east wall-near sink	00-356095	20%	wrapped cardboard/paper pipe	OMA	20 ft. 4 in. O.D. DW	41 II	\$178	\$112	\$290
along north wall-at ceiling	00-356099	40%	corrugated pipe covering	OMA	30 ft. 4 in. O.D. LPS/R	41 II	\$268	\$167	\$435
lunch room stairwell-along ceiling	00-356099	40%	corrugated pipe covering	OMA	35 ft. 4 in. O.D. LPS/R	41 II	\$312	\$195	\$507
east wall-near sink	00-356206	70%	pipe covering	OMA	12 ft. 4 in. O.D. CON	41 II	\$107	\$67	\$174
along west wall-near catwalk	01-356084	70%	mjp on pipe covering	OMA	3 10 in. O.D. BFW	41 II	\$188	\$117	\$305
NW corner-above boiler feed water pumps	01-356084	70%	mjp on pipe covering	OMA	2 10 in. O.D. BFW	41 II	\$125	\$78	\$203
NW corner-above boiler feed water pumps	01-356084	70%	mjp on pipe covering	OMA	15 6 in. O.D. BFW	41 II	\$580	\$341	\$921
along west wall-near catwalk	01-356084	70%	mjp on pipe covering	OMA	5 8 in. O.D. BFW	41 II	\$241	\$141	\$382
NW corner-above boiler feed water pumps	01-356084	70%	mjp on pipe covering	OMA	2 4 in. O.D. BFW	41 II	\$56	\$31	\$87
boiler #1-near economizer	01-356084	70%	mjp on pipe covering	OMA	8 6 in. O.D. BFW	41 II	\$309	\$182	\$491
boilers #2 & 3-front-near catwalk	01-356084	70%	mjp on pipe covering	OMA	4 6 in. O.D. BFW	41 II	\$155	\$91	\$246
between boilers #1 & 2-near floor	01-356084	70%	mjp on pipe covering	OMA	8 4 in. O.D. BFW	41 II	\$225	\$125	\$350
boilers #2 & 3-front-near catwalk	01-356084	70%	mjp on pipe covering	OMA	9 4 in. O.D. BFW	41 II	\$253	\$140	\$393
boiler #1-near economizer	01-356084	70%	mjp on pipe covering	OMA	3 4 in. O.D. BFW	41 II	\$84	\$47	\$131
	01-356085	45%				41 II			
	01-356086	45%				41 II			
near NW corner-deaerator-above pumps	02-356088	70%	mjp on pipe covering	OMA	14 8 in. O.D. TW	41 II	\$674	\$396	\$1,070
NW corner-above boiler feed water pumps	02-356088	70%	mjp on pipe covering	OMA	1 8 in. O.D. TW	41 II	\$48	\$28	\$76
NW corner-above boiler feed water pumps	02-356088	70%	mjp on pipe covering	OMA	1 10 in. O.D. TW	41 II	\$63	\$39	\$102
near NW corner-deaerator-above pumps	02-356088	70%	mjp on pipe covering	OMA	2 10 in. O.D. TW	41 II	\$125	\$78	\$203
	02-356089	60%				41 II			
	02-356090	70%				41 II			
along west wall-near catwalk	03-356092	0%	mjp on pipe covering	OMA	1 6 in. O.D. HPS/R	41 II	\$39	\$23	\$62
NW corner-above boiler feed water pumps	03-356092	0%	mjp on pipe covering	OMA	2 4 in. O.D. HPS/R	41 II	\$56	\$31	\$87
along west wall-near catwalk	03-356092	0%	mjp on pipe covering	OMA	45 4 in. O.D. HPS/R	41 II	\$1,264	\$702	\$1,966
between boilers #1 & 2-near floor	03-356092	0%	mjp on pipe covering	OMA	6 4 in. O.D. HPS/R	41 II	\$169	\$94	\$263
SW corner-at fuel oil heat exchanger	03-356092	0%	mjp on pipe covering	OMA	25 4 in. O.D. HPS/R	41 II	\$702	\$390	\$1,092
along south wall-near catwalk	03-356092	0%	mjp on pipe covering	OMA	5 4 in. O.D. HPS/R	41 II	\$140	\$78	\$218
boilers #2 & 3-front-near catwalk	03-356092	0%	mjp on pipe covering	OMA	8 4 in. O.D. HPS/R	41 II	\$225	\$125	\$350
	03-356093	70%				41 II			

H-K Building 3
 Project Number: 0980193E
 Project: G. HEILEMAN BREWERY "E"
 Date Inspected: 03/21/89
 Inspector: MARK VOTH

ASBESTOS ASSESSMENT SURVEY

Building Number: 13
 Building Name: BOILER HOUSE
 SEATTLE, WASHINGTON
 Building Type: POWER HSE
 Year Constructed: 1933

near northwest corner-at ceiling east wall-near sink	03-356094	70%	mjp on wrapped cardboard/paper	OMA	1 4 in. O.D.	DW	41 11	\$28	\$16	\$44
	04-356096	50%					41 11			
	04-356096	50%	mjp on wrapped cardboard/paper	OMA	4 4 in. O.D.	DW	41 11	\$112	\$62	\$174
	04-356097	50%					41 11			
	04-356098	50%	mjp on corrugated pipe cover	OMA	2 4 in. O.D.	LPS/R	41 11	\$56	\$31	\$87
	05-356200	80%					41 11			
lunch room stairwell-along ceiling	05-356200	80%	mjp on corrugated pipe cover	OMA	5 4 in. O.D.	LPS/R	41 11	\$140	\$78	\$218
	05-356201	70%					41 11			
	05-356202	70%	mjp on non-suspect pipe cover	OMA	9 6 in. O.D.	DW	41 11	\$348	\$204	\$552
	06-356203	10%					41 11			
near north side-boiler #1-at ceiling along west wall-near catwalk	06-356203	10%	mjp on non-suspect pipe cover	OMA	2 6 in. O.D.	DW	41 11	\$77	\$45	\$122
	06-356204	10%					41 11			
	06-356205	10%	mjp on pipe covering	OMA	7 4 in. O.D.	CON	41 11	\$197	\$109	\$306
	07-356207	70%					41 11			
	07-356208	80%	boiler/tank insulation	OMB	92 sq.ft.		41 11	\$2,599	\$2,082	\$4,681
	07-356209	80%					41 11			
along west wall-old hot water tank	08-356213	30%	boiler/tank insulation	OMB	30 sq.ft.		41 11	\$848	\$679	\$1,527
	08-356214	30%					41 11			
west wall-upper fuel oil heat exchanger	08-356215	30%	boiler/tank insulation	OMB	30 sq.ft.		41 11	\$848	\$679	\$1,527
	09-356216	60%					41 11			
	09-356217	60%	boiler/tank insulation	OMB	25 sq.ft.		41 11	\$706	\$566	\$1,272
	09-356218	60%					41 11			
west wall-lower fuel oil heat exchanger	10-356219	60%	boiler/tank insulation	OMB	100 sq.ft.		41 11	\$2,825	\$2,263	\$5,088
	10-356220	60%					41 11			
	10-356221	60%	boiler/tank insulation	OMB	25 sq.ft.		41 11	\$706	\$566	\$1,272
	12-356225	60%					41 11			
boiler #2-lower drum ends	12-356226	40%	boiler/tank insulation	OMB	100 sq.ft.		41 11	\$2,825	\$2,263	\$5,088
	12-356227	40%					41 11			
boiler #2-upper drum	13-356228	70%	boiler/tank insulation	OMB	25 sq.ft.		41 11	\$706	\$566	\$1,272
	13-356229	60%					41 11			
	13-356230	50%	boiler/tank insulation	OMB	100 sq.ft.		41 11	\$2,825	\$2,263	\$5,088
	14-356231	50%					41 11			
boiler #3-lower drum ends	14-356232	40%	boiler/tank insulation	OMB	100 sq.ft.		41 11	\$2,825	\$2,263	\$5,088
	14-356233	40%					41 11			
boiler #3-upper drum	15-356234	40%	boiler/tank insulation	OMB	100 sq.ft.		41 11	\$2,825	\$2,263	\$5,088
	15-356235	40%					41 11			
	15-356236	40%					41 11			

AREA COMMENTS

The materials are in good condition with minor contact and water damage. The materials are approximately 2' to 20' from the floor. At a minimum, it is recommended that the materials be repaired and monitored. If removal is planned, gross removal procedures are recommended. This appears to be a high traffic area.

AREA # 03 TOTAL \$31,112 \$21,499 \$52,611

ASBESTOS ASSESSMENT SURVEY

H-K Building 13
Project Number: 0980193E
Project: G. HEILEMAN BREWERY "E"
Date Inspected: 03/21/89
Inspector: MARK VOTH

Building Number: 13
Building Name: BOILER HOUSE
SEATTLE, WASHINGTON
Building Type: POWER HSE
Year Constructed: 1933

***** AREA NUMBER: 04			AREA DESCRIPTION: 1st Floor-Catwalk Level			AREA AVERAGE % ASBESTOS: 55X			*****		
LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
above boiler #2 & 3-near catwalk	00-356083	30X	pipe covering	OMA	34 ft.	4 in. O.D. BFW	42	II	\$303	\$190	\$493
northwest corner-near deaerator tank	00-356087	30X	pipe covering	OMA	24 ft.	6 in. O.D. TW	42	II	\$312	\$195	\$507
above boilers-along ceiling	00-356091	70X	pipe covering	OMA	120 ft.	4 in. O.D. HPS/R	42	II	\$1,070	\$670	\$1,740
above boilers-along ceiling	00-356091	70X	pipe covering	OMA	40 ft.	10 in. O.D. HPS/R	42	II	\$755	\$559	\$1,314
above boilers-along ceiling	00-356091	70X	pipe covering	OMA	60 ft.	14 in. O.D. HPS/R	42	II	\$1,510	\$1,194	\$2,704
above boilers-along ceiling	00-356091	70X	pipe covering	OMA	70 ft.	6 in. O.D. HPS/R	42	II	\$909	\$568	\$1,477
northwest corner-near deaerator tank	00-356091	70X	pipe covering	OMA	47 ft.	6 in. O.D. HPS/R	42	II	\$610	\$381	\$991
above boiler #2-near ceiling	00-356091	70X	pipe covering	OMA	65 ft.	6 in. O.D. HPS/R	42	II	\$844	\$527	\$1,371
along east wall-near ceiling	00-356091	70X	pipe covering	OMA	25 ft.	6 in. O.D. HPS/R	42	II	\$324	\$203	\$527
northwest corner-near deaerator tank	00-356091	70X	pipe covering	OMA	19 ft.	4 in. O.D. HPS/R	42	II	\$169	\$106	\$275
above boilers-along ceiling	00-356091	70X	pipe covering	OMA	95 ft.	12 in. O.D. HPS/R	42	II	\$2,092	\$1,608	\$3,700
along east wall-near ceiling	00-356091	70X	pipe covering	OMA	12 ft.	4 in. O.D. HPS/R	42	II	\$107	\$67	\$174
above boiler #2-near ceiling	00-356095	20X	wrapped cardboard/paper pipe	OMA	45 ft.	4 in. O.D. DW	42	II	\$401	\$251	\$652
above boilers #2 & 3-near catwalk	01-356084	70X	mjp on pipe covering	OMA	4	4 in. O.D. BFW	42	II	\$112	\$62	\$174
	01-356085	45X					42	II			
	01-356086	45X					42	II			
northwest corner-near deaerator tank	02-356088	70X	mjp on pipe covering	OMA	5	6 in. O.D. TW	42	II	\$193	\$114	\$307
	02-356089	60X					42	II			
	02-356090	70X					42	II			
above boilers-along ceiling	03-356092	0X	mjp on pipe covering	OMA	13	12 in. O.D. HPS/R	42	II	\$986	\$616	\$1,602
northwest corner-near deaerator tank	03-356092	0X	mjp on pipe covering	OMA	6	6 in. O.D. HPS/R	42	II	\$232	\$136	\$368
above boilers-along ceiling	03-356092	0X	mjp on pipe covering	OMA	30	4 in. O.D. HPS/R	42	II	\$843	\$468	\$1,311
above boilers-along ceiling	03-356092	0X	mjp on pipe covering	OMA	6	6 in. O.D. HPS/R	42	II	\$232	\$136	\$368
northwest corner-near deaerator tank	03-356092	0X	mjp on pipe covering	OMA	3	4 in. O.D. HPS/R	42	II	\$84	\$47	\$131
above boiler #2-near ceiling	03-356092	0X	mjp on pipe covering	OMA	7	6 in. O.D. HPS/R	42	II	\$271	\$159	\$430
above boilers-along ceiling	03-356092	0X	mjp on pipe covering	OMA	3	14 in. O.D. HPS/R	42	II	\$260	\$167	\$427
along east wall-near ceiling	03-356092	0X	mjp on pipe covering	OMA	4	6 in. O.D. HPS/R	42	II	\$155	\$91	\$246
along east wall-near ceiling	03-356092	0X	mjp on pipe covering	OMA	6	4 in. O.D. HPS/R	42	II	\$169	\$94	\$263
above boilers-along ceiling	03-356092	0X	mjp on pipe covering	OMA	2	10 in. O.D. HPS/R	42	II	\$125	\$78	\$203
	03-356093	70X					42	II			
	03-356094	70X					42	II			
above boiler #2-near ceiling	04-356096	50X	mjp on wrapped cardboard/paper	OMA	5	4 in. O.D. DW	42	II	\$140	\$78	\$218
	04-356097	50X					42	II			
	04-356098	50X					42	II			
above boiler #1-near deaerator tank	11-356222	0X	boiler/tank insulation	ONB	45	sq.ft.					
	11-356223	0X									
	11-356224	0X									

ASBESTOS ASSESSMENT SURVEY

H-K Building 13
 Project Number: 0980193E
 Project: G. HEILEMAN BREWERY "E"
 Date Inspected: 03/21/89
 Inspector: MARK VOTH

Building Number: 13
 Building Name: BOTTLER HOUSE
 SEATTLE, WASHINGTON
 Building Type: POWER HSE
 Year Constructed: 1933

AREA COMMENTS

The materials are in good to fair condition with minor contact and water damage. The materials are approximately 20' to 30' from the floor. At a minimum, it is recommended that the materials be repaired and monitored. If removal is planned, gross removal procedures are recommended. This appears to be a high traffic area.

AREA # 04 TOTAL \$13,208 \$8,765 \$21,973

***** AREA NUMBER: 05 AREA DESCRIPTION: 2nd Floor AREA AVERAGE % ASBESTOS: 67% *****

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
lunch room-northwest corner-along floor	00-356237	60%	pipe covering	OMA	10 ft. 4 in.	O.D.	LPS/R	59	II	\$89	\$56	\$145
lunch room-northwest corner-along floor	16-356238	70%	mjp on pipe covering	OMA	4 4 in.	O.D.	LPS/R	59	II	\$112	\$62	\$174
	16-356239	70%						59	II			
	16-356240	80%						59	II			

AREA COMMENTS

The materials are in fair condition with contact and water damage. The materials are up to 3' from the floor. At a minimum, it is recommended that the materials be repaired and monitored. If removal is planned, glove bag removal procedures are recommended. This appears to be a moderate traffic area.

AREA # 05 TOTAL \$201 \$118 \$319

***** AREA NUMBER: 06 AREA DESCRIPTION: 2nd Floor AREA AVERAGE % ASBESTOS: 0% *****

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	QUANTITY	UNITS OF MEASURE	PIPE ID	EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
lunch room-ceiling	17-356241	0%	acoustical tile	OMG	750 sq.ft.							
	17-356242	0%										
	17-356243	0%										

AREA COMMENTS:

AREA # 06 TOTAL \$0 \$0 \$0

BUILDING # 13 TOTAL \$155,063 \$118,933 \$273,996