ASBESTOS ASSE

H-K Building ... 15 Project Number: 0980193E

Project: G. HEILEMAN BREWERY "E"

Date Inspected: 03/28/89 Inspector: MARK VOTH Building Number: 15

Building Hame: OLD KEG WASHING

SEATTLE, WASHINGTON 98134

Building Type: KEGGING Year Constructed: 1940

***** ******** AREA NUMBER: 01 AREA DESCRIPTION: 1st Floor AREA AVERAGE % ASBESTOS: 27%

LOCATION OF THE MATERIAL	SAMPLE NUMBER	ASB	MATERIAL DESCRIPTION	O&M CODE	UNITS OF QUANTITY MEASURE		EXP POT	PL	REMOVAL COSTS	REPLACEMENT COSTS	TOTAL COSTS
along north wall-at ceiling	00-356344	30%	wrapped cardboard/paper pipe	OHA	64 ft. 4 in. O.D.	DW		111	\$571		\$928
along south wall-at ceiling	00-356344	30%	wrapped cardboard/paper pipe	OHA	80 ft. 4 in. 0.D.	DW	23	111	\$714	\$446	\$1,160
above keg line-along ceiling	00-356351	30%	pipe covering	DHA	143 ft. 4 in. 0.D.	HPS/R	23	111	\$1,276		\$2,074
northwest stairwell-along ceiling	00-356351	30%	pipe covering	OHA	17 ft. 6 in. 0.0.	HPS/R	23	111	\$221	\$138	\$359
near southeast corner-at keg line	00-356351	30%	pipe covering	AHO	44 ft. 4 in. O.D.	HPS/R	23	111	\$392		\$638
along north row of columns-at ceiling	00-356351	30%	pipe covering	OHA	63 ft. 4 in. O.D.	HPS/R	23	111	\$562		\$914
northwest corner-at ceiling	00-356351	30%	pipe covering	OHA	8 ft. 6 in. 0.D.	HPS/R	23	111	\$104		\$169
near west wall-along celling	00-356351	30%	pipe covering	OMA	70 ft. 6 in. 0.D.	HPS/R	23	111	\$909		\$1,477
along south wall-at ceiling	04-356345	40%	imjp on wrapped cardboard/paper	OHA	5 4 in. O.D.	DW	23	111	\$140	\$78	\$218
along north wall-at ceiling	04-356345	40%	mjp on wrapped cardboard/paper	AMO	7 4 in. O.D.	DW	23	111	\$197	\$109	. \$306
	04-356346	40%					23	111			
	04-356347	40%	ſ				23	111			
northwest corner-at ceiling	05-356348	7%	mjp on non-suspect pipe cover	OMA	2 4 in. O.D.	DW	23	111	\$56	\$31	\$87
near west wall-along ceiling	05-356348		mjp on non-suspect pipe cover	OHA	3 4 in. O.D.	DW	23	111	\$84	\$47	. \$131
	05-356349	10%	1				23	111			
	05-356350	10%	Į.				23	111			
near southeast corner-at keg line	06-356352		mjp on pipe covering	OHA	4 4 in. O.D.	HPS/R	23	111	\$112	\$62	\$174
northwest corner-at ceiling	06-356352	3%	mjp on pipe covering	DHA	2 6 in. 0.D.	HPS/R	23	111	\$77	\$45	\$122
above keg line-along ceiling	06-356352	3%	mjp on pipe covering	AHO	14 4 in. 0.0.	HPS/R	23	111	\$393	\$219	\$612
above keg line-along ceiling	06-356352	3%	mjp on pipe covering	OHA	2 6 in. 0.D.	HPS/R	23	111	\$77	\$45	\$122
along north row of columns-at ceiling	06-356352		mjp on pipe covering	AMO	2 4 in. O.D.	HPS/R	23	111	\$56	\$31	\$87
near west wall-along ceiling	06-356352	3%	mjp on pipe covering	OHA	1 6 in. O.D.	HPS/R	23	111	\$39	\$23	\$62
	06-356353	10%	1.0			-	23	111	i		
	06-356354	10%	1		•		23	111			

AREA COMMENTS,

AREA # 01 TOTAL \$5,980 \$3,660 \$9,640

The materials are in good condition with minor contact and water damage. The materials are approximately 30 to 12' from the floor. At a minimum, it is recommended that the materials be repaired and monitored. If removal is planned, glove bag removal procedures are recommended. This appears to be a low traffic area.

L	********** AREA NUMBER: 02	AREA DESCRIPTION: 2nd F	Floor	AREA AVERAGE % ASBE	ESTOS: 25%	***
	LOCATION OF THE MATERIAL	SAMPLE NUMBER ASB MATE	O&M CODE CODE		EXP REMOVAL POT PL COSTS	REPLACEMENT TOTAL COSTS COSTS
	near S electrical panel-at heat exchange north wall-near stairs near S electrical panel-heat exchanger		covering OHA ed cardboard/paper pipe OHA /tank insulation OHB	17 ft. 4 in. O.D. HPS/F 12 ft. 4 in. O.D. DW 193 sq.ft.	R 38 111 \$152 38 111 \$107 38 111 \$5,452	\$67 \$174

HALL-KIMBRELL ENVIRONMENTAL INC.

06/09/89

ASBESTOS ASSE

H-K Building #: 15

Project Number: 0980193E

Project: G. HEILEMAN BREWERY "E"

Date Inspected: 03/28/89

Inspector: MARK VOTH

Building Number: 15

Building Name: OLD KEG WASHING

SEATTLE, WASHINGTON 98134

Building Type: KEGGING

Year Constructed: 1940

near S electrical panel-at heat exchange	01-356334 01-356335 02-356337 02-356338 02-356339	20% 20% 10% 10% 10%	mjp on pipe covering	ОНА	2 4 in. 0.D.	HPS/R	38 111 38 111 38 111 38 111 38 111	\$56	\$31	\$87
north wall-near stairs	03-356341 03-356342 03-356343	30% 40% 40%	mjp on wrapped cardboard/paper	OHA	3 4 in. 0.D.	DW	38 111 38 111 38 111	\$84	\$47	\$131

AREA COMMENTS

AREA # 02 TOTAL \$5,851 \$4,608 \$10,459

The materials are in fair condition with minor contact and water damage. The materials are approximately 1' to 10' from the floor. At a minimum, it is recommended that the materials be repaired and monitored. If removal is planned, gross removal procedures are recommended. This appears to be a low traffic area.

BUILDING # 15	TOTAL	\$11,831	\$8,268	\$20,099