

June 16, 2004

Ethan Construction LLC  
3100 Airport Way South  
Seattle, WA 98134

Office: 447-0263

Request For Asbestos Abatement Quotation No. 61604

Where: Rainier Brewery 3100 Airport Way South, Seattle, WA

Description: Remove ACM pipe insulation on vertical and horizontal piping. All piping is accessible without the use of scaffolding. A ladder will be required for the vertical piping.

Location 1: Remove 12' - 3" OD pipe insulation (1 Vertical run)

(21-4) 3 - 3" 90° ells  
1 - 3" 45° ell

Remove 15' - 4" OD pipe insulation (1 Vertical run)

1 - 4" 90° ell

Remove 15' - 8" OD pipe insulation (1 Vertical run)

1 - 8" 90° ell

1 - 8" 45° ell

The above 3 systems are adjacent to each other and accessible from the same workstation.

Location 2: Remove 21' ACM exterior wrap from 12" OD foamglass insulated vertical piping (9)

Remove 1 - 12" 90° ell skin and insulation

Remove 3' ACM exterior wrap from 8" OD foamglass insulated horizontal piping

Remove 1 - 8" 90° ell skin and insulation

Remove ACM exterior wrap/skin from all 6 sides of a 12" x 20" valve box insulated with foamglass

Remove outer cover from 18' - 4" OD foam insulated piping

The above 2 systems are readily accessible from the floor; no ladders will be required.

Dispose of 2 bags of ACM pipe insulation and 3 bags of ACM rope packing.

Bid to include PSCAA permit fee, disposal cost, supplies and personal air monitoring.

RCLLC 0004357

Clearance air monitoring will be provided by an independent third party.

Glove bags or a mini-containment will be required.

The removal can start at 8AM Monday through Saturday and is to be completed on, or before July 23, 2004.

Direct questions to Paul Jackson @ 714-7446

Fax bid to: Elan Hazan @ Ethan Construction LLC, @ 447-0299.