AMRO Environmental Laboratories Corporation

111 Herrick Street, Merrimack, NH 03054
TEL: (603) 424-2022 • FAX: (603) 429-8496
www.amrolabs.com

July 14, 2010

ANALYTICAL TEST RESULTS

Raymond Siegener
GEI Consultants, Inc.
400 Unicorn Park Drive
Woburn, MA 01801
TEL: (781) 721-4098
FAX: (781) 721-4073

Subject: 09382-2 Canton Airport

Workorder No.: 1007027

Dear Raymond Siegener:

AMRO Environmental Laboratories Corp. received 15 samples on 7/8/2010 for the analyses presented in the following report.

AMRO is accredited in accordance with NELAC and certifies that these test results meet all the requirements of NELAC, where applicable, unless otherwise noted in the case narrative.

The enclosed Sample Receipt Checklist details the condition of your sample(s) upon receipt. Please be advised that any unused sample volume and sample extracts will be stored for a period of 60 days from sample receipt date (90 days for samples from New York). After this time, AMRO will properly dispose of the remaining sample(s). If you require further analysis, or need the samples held for a longer period, please contact us immediately.

This report consists of a total of 26 pages. This letter is an integral part of your data report. All results in this project relate only to the sample(s) as received by the laboratory and documented in the Chain-of-Custody. This report shall not be reproduced except in full, without the written approval of the laboratory. If you have any questions regarding this project in the future, please refer to the Workorder Number above.

Sincerely,

Suzanne Karan
for Nancy Stewart

Nancy Stewart
Vice President

State Certifications: NH (NELAC): 1001, MA: M-NH012, CT: PH-0758, NY: 11278 (NELAC), ME: NH012 and 1001.

Hard copy of the State Certification is available upon request.

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027
Date Received: 7/8/2010

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Collection Date	Collection Time
1007027-01A	093822-AT100(0-12)	7/7/2010	8:00 AM
1007027-02A	093822-AT100-DUP1	7/7/2010	7:00 AM
1007027-03A	093822-BY120(0-12)	7/7/2010	12:20 PM
1007027-04A	093822-AT100(9-12)	7/7/2010	8:02 AM
1007027-05A	093822-PR12(0-6)	7/7/2010	8:45 AM
1007027-06A	093822-BE110(9-12)	7/7/2010	9:10 AM
1007027-07A	093822-PR13(0-6)	7/7/2010	9:50 AM
1007027-08A	093822-PR14(0-6)	7/7/2010	10:15 AM
1007027-09A	093822-BO120(0-6)	7/7/2010	10:40 AM
1007027-10A	093822-BY120(9-12)	7/7/2010	12:22 PM
1007027-11A	093822-PR15(0-6)	7/7/2010	12:35 PM
1007027-12A	093822-PR16 (0-6)	7/7/2010	1:10 PM
1007027-13A	093822-PR17(0-6)	7/7/2010	1:30 PM
1007027-14A	093822-BY130(0-6)	7/7/2010	12:54 PM
1007027-15A	093822-CJ130(0-6)	7/7/2010	1:50 PM

AMRO Environmental Laboratories Corp.

14-Jul-10

Lab Order: 1007027
Client: GEI Consultants, Inc.
Project: 09382-2 Canton Airport

DATES REPORT

Sample ID	Client Sample ID	Collection Date	Matrix	Analytical Test Name / Preparatory Test Name	Prep Date	Analysis Date / Batch ID	TCLP Date
1007027-01A	093822-AT100(0-12)	7/7/2010 8:00:00 AM	Soil	EPA 9045C pH/Corrosivity in Soil		7/8/2010 R44979	
				Percent Moisture		7/8/2010 R44980	
1007027-02A	093822-AT100-DUP1	7/7/2010 7:00:00 AM		EPA 9045C pH/Corrosivity in Soil		7/8/2010 R44979	
				Percent Moisture		7/8/2010 R44980	
1007027-03A	093822-BY120(0-12)	7/7/2010 12:20:00 PM		EPA 9045C pH/Corrosivity in Soil		7/8/2010 R44979	
				Percent Moisture		7/8/2010 R44980	
1007027-04A	093822-AT100(9-12)	7/7/2010 8:02:00 AM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010 R44980	
1007027-05A	093822-PR12(0-6)	7/7/2010 8:45:00 AM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010 R44980	
1007027-06A	093822-BE110(9-12)	7/7/2010 9:10:00 AM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010 R44980	

AMRO Environmental Laboratories Corp.

14-Jul-10

Lab Order: 1007027
Client: GEI Consultants, Inc.
Project: 09382-2 Canton Airport

DATES REPORT

Sample ID	Client Sample ID	Collection Date	Matrix	Analytical Test Name / Preparatory Test Name	Prep Date	Analysis Date / Batch ID	TCLP Date
1007027-07A	093822-PR13(0-6)	7/7/2010 9:50:00 AM	Soil	EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-08A	093822-PR14(0-6)	7/7/2010 10:15:00 AM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-09A	093822-BO120(0-6)	7/7/2010 10:40:00 AM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-10A	093822-BY120(9-12)	7/7/2010 12:22:00 PM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-11A	093822-PR15(0-6)	7/7/2010 12:35:00 PM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-12A	093822-PR16 (0-6)	7/7/2010 1:10:00 PM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	

AMRO Environmental Laboratories Corp.

14-Jul-10

Lab Order: 1007027
Client: GEI Consultants, Inc.
Project: 09382-2 Canton Airport

DATES REPORT

Sample ID	Client Sample ID	Collection Date	Matrix	Analytical Test Name / Preparatory Test Name	Prep Date	Analysis Date / Batch ID	TCLP Date
1007027-13A	093822-PR17(0-6)	7/7/2010 1:30:00 PM	Soil	EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-14A	093822-BY130(0-6)	7/7/2010 12:54:00 PM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	
1007027-15A	093822-CJ130(0-6)	7/7/2010 1:50:00 PM		EPA 8082 PCBS IN SOIL/SOLIDS		7/9/2010	
				EPA 3540C SOPREP SOXHLET: PCBS	7/8/2010	20418	
				Percent Moisture		7/8/2010	
						R44980	

Chain-of-Custody Record

Laboratory: AMRO

Laboratory Job # (Lab use only) 1007027

GEI Consultants
400 Unicorn Park Drive
Woburn, MA 01801
PH: 781.721.4000
FX: 781.721.4073

Project Information

Project Name: Canton Airport

Project Location: Canton, MA

Project Number: 09382-2

Project Manager: Anne Leifer

Send Report to: Ray Siegener

Send EDD to: labdata@geiconsultants.com

Preservative

None	None							

Sample Handling

Samples Field Filtered: YES (NO) NA

Sampled Shipped With Ice: (YES) NO

MCP PRESUMPTIVE CERTAINTY REQUIRED -- (YES) NO

If Yes, Are MCP Analytical Methods Required? (YES) NO NA

If Yes, Are Drinking Water Samples Submitted? YES (NO) NA

If Yes, Have You Met Minimum Field QC Requirements? (YES) NO NA

Lab Sample Number	GEI Sample ID	Collection Date	Collection Time	Matrix	No. of Bottles	Sampler(s) Initials	PCBs by manual soxlet extraction	pH								Sample Specific Remarks
	093822-AT100(0-12)	7/7/10	0800	SO	1	TC	x	X								
	093822-AT100(9-12)		0802	SO	1		x									
	093822-AT100(12-18)		0804	SO	1		x									HOLD
	093822-AT100(18-24)		0806	SO	1		x									HOLD
	093822-AT100-DUP1		0700	SO	1		x	X								~~HOLD~~ SST
	093822-AT100-DUP2		0701	SO	1		x									HOLD
	093822-PR12(0-6)		0845	SO	1		x									
	093822-PR12(9-12)		0847	SO	1		x									HOLD
	093822-PR12(12-18)		0849	SO	1		x									HOLD
	093822-~~PR12~~ BE110(9-12)		0910	SO	1		x									
	093822-BE110(12-18)		0912	SO	1		x									HOLD
	093822-BE110(18-24)		0914	SO	1		x									HOLD

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. [signature]	7/7/10	1530	1. GEI Sample fridge
2. GEI Sample fridge	7/8/10	1045	2. Naomi Slayani
3. Naomi Slayani	7/8/10	1045	3. W. N. Lawson
4. W. N. Lawson	7/8/10	1155	4. Kaleigh Wallace

Turnaround Time (Business days):

Normal __X__ Other ____

10-Day ____ 7-Day ____

5-Day ____ 3-Day ____

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Additional Requirements/Comments/Remarks:

MANUAL SOXLET EXTRACTION REQUIRED.

DCR RATES APPLY.

Chain-of-Custody Record

Laboratory: AMRO

Laboratory Job # (Lab use only) 1007027

GEI Consultants
400 Unicorn Park Drive
Woburn, MA 01801
PH: 781.721.4000
FX: 781.721.4073

Project Information

Project Name: Canton Airport

Project Location: Canton, MA

Project Number: 09382-2

Project Manager: Anne Leifer

Send Report to: Ray Siegener

Send EDD to: labdata@geiconsultants.com

MCP PRESUMPTIVE CERTAINTY REQUIRED -- (YES) NO

If Yes, Are MCP Analytical Methods Required? (YES) NO NA

If Yes, Are Drinking Water Samples Submitted? YES (NO) NA

If Yes, Have You Met Minimum Field QC Requirements? (YES) NO NA

Sample Handling: Samples Field Filtered: YES (NO) NA

Sampled Shipped With Ice: (YES) NO

Lab Sample Number	GEI Sample ID	Collection Date	Collection Time	Matrix	No. of Bottles	Sampler(s) Initials	Preservative: None	Preservative: None	Analysis: PCBs by manual soxlet extraction	Analysis: pH	Sample Specific Remarks
	093822-PR13(0-6)	7/7/10	0950	SO	1	TC			x		
	093822-PR13(9-12)		0952	SO	1				x		HOLD
	093822-PR13(12-18)		0954	SO	1				x		HOLD
	093822-PR14(0-6)		1015	SO	1				x		
	093822-PR14(9-12)		1017	SO	1				x		HOLD
	093822-PR14(12-16)		1019	SO	1				x		HOLD
	093822-BO12Ø(0-6)		1040	SO	1				x		
	093822-BO12Ø(9-12)		1042	SO	1				x		HOLD
	093822-BO12Ø(12-18)		1044	SO	1				x		HOLD
	093822-BO12Ø(18-24)		1046	SO	1				x		HOLD
	093822-BY12Ø(0-12)		1220	SO	1				x	X	
	093822-BY12Ø(9-12)		1222	SO	1				x		

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. [signature]	7/7/10	1530	1. GEI Sample Fridge
2. GEI Sample Fridge	7/8/10	1045	2. [signature]
3. [signature]	7/8/10	1045	3. [signature]
[signature]	7/8/10	1155	4. Kaleigh Wallace

Turnaround Time (Business days):

Normal __X__ Other ____

10-Day ____ 7-Day ____

5-Day ____ 3-Day ____

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Additional Requirements/Comments/Remarks:

MANUAL SOXLET EXTRACTION REQUIRED.

DCR RATES APPLY.

Chain-of-Custody Record

Laboratory: AMRO

Laboratory Job # (Lab use only) 1007027

GEI Consultants
400 Unicorn Park Drive
Woburn, MA 01801
PH: 781.721.4000
FX: 781.721.4073

Project Information

Project Name: Canton Airport

Project Location: Canton, MA

Project Number: 09382-2

Project Manager: Anne Leifer

Send Report to: Ray Siegener

Send EDD to: labdata@geiconsultants.com

MCP PRESUMPTIVE CERTAINTY REQUIRED -- (YES) NO

If Yes, Are MCP Analytical Methods Required? (YES) NO NA

If Yes, Are Drinking Water Samples Submitted? YES (NO) NA

If Yes, Have You Met Minimum Field QC Requirements? (YES) NO NA

Sample Handling: Samples Field Filtered: YES (NO) NA

Sampled Shipped With Ice: (YES) NO

Lab Sample Number	GEI Sample ID	Collection Date	Collection Time	Matrix	No. of Bottles	Sampler(s) Initials	Preservative: None	Preservative: None	Analysis: PCBs by manual soxlet extraction	Sample Specific Remarks
	093822-BY120(12-18)	7/7/10	1224	SO	1	TC			x	HOLD
	093822-BY120(18-24)	↓	1226	SO	1	↓			x	HOLD
	093822-BY120-DUP1		0703	SO	1				x	HOLD
	093822-PR15(0-6)		1235	SO	1				x	
	093822-PR15(9-12)		1237	SO	1				x	HOLD
	093822-PR15(12-18)		1239	SO	1				x	HOLD
	093822-PR16(0-6)		1310	SO	1				x	
	093822-PR16(9-12)		1312	SO	1				x	HOLD
	093822-PR16(12-18)		1314	SO	1				x	HOLD
	093822-PR16-DUP1		0705	SO	1				x	HOLD
	093822-PR17(0-6)		1330	SO	1				x	
	093822-PR17(9-12)	↓	1332	SO	1	↓			x	HOLD

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Relinquished by sampler (signature)	Date	Time	Received by: (signature)
1. [signature]	7/7/10	1530	1. GEI Sample Fridge
2. GEI Sample Fridge	7/8/10	1045	2. [signature]
3. [signature]	7/8/10	1045	3. [signature]
4. [signature]	7/8/10	1155	4. Raleigh Wallace

Turnaround Time (Business days): Normal ___X___ Other _____ 10-Day _____ 7-Day _____ 5-Day _____ 3-Day _____

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Additional Requirements/Comments/Remarks:

MANUAL SOXLET EXTRACTION REQUIRED.

DCR RATES APPLY.

Chain-of-Custody Record

Laboratory: AMRO

Laboratory Job # (Lab use only) 1007027

GEI Consultants
400 Unicorn Park Drive
Woburn, MA 01801
PH: 781.721.4000
FX: 781.721.4073

Project Information

Project Name: Canton Airport

Project Location: Canton, MA

Project Number: 09382-2

Project Manager: Anne Leifer

Send Report to: Ray Siegener

Send EDD to: labdata@geiconsultants.com

MCP PRESUMPTIVE CERTAINTY REQUIRED -- (YES) NO

If Yes, Are MCP Analytical Methods Required? (YES) NO NA

If Yes, Are Drinking Water Samples Submitted? YES (NO) NA

If Yes, Have You Met Minimum Field QC Requirements? (YES) NO NA

Sample Handling: Samples Field Filtered — YES (NO) NA

Sampled Shipped With Ice — (YES) NO

Lab Sample Number	GEI Sample ID	Collection Date	Collection Time	Matrix	No. of Bottles	Sampler(s) Initials	Preservative: None	Preservative: None	Analysis: PCBs by manual soxlet extraction	Sample Specific Remarks
	093822-PR17(12-18)	7/7/10	1334	SO	1	TC			x	HOLD
	093822-BY130(0-6)		1254	SO	1				x	
	093822-BY130 (9-12)		1256	SO	1				x	HOLD
	093822-BY130 (12-18)		1258	SO	1				x	HOLD
	093822-BY130(18-24)		1300	SO	1				x	HOLD
	093822-CJ130(0-6)		1350	SO	1				x	
	093822-CJ130(9-12)		1352	SO	1				x	HOLD
	093822-CJ130 (12-18)		1354	SO	1				x	HOLD
	093822-CJ130 (18-24)		1356	SO	1				x	HOLD.
	~~093822-~~			SO	1				x	NOTUSED
	093822-			SO	1				x	
	093822-			SO	1				x	

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Relinquished by: (signature)	Date	Time	Received by: (signature)
1. [signature]	7/7/10	1530	1. GEI Sample Fridge
2. GEI Sample Fridge	7/8/10	1045	2. [signature]
3. [signature]	7/8/10	1045	3. W H Lawson
4. W H Lawson	7/8/10	1156	4. Kalleigh Wallace

Turnaround Time (Business days):

Normal __X__ Other _____

10-Day _____ 7-Day _____

5-Day _____ 3-Day _____

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Additional Requirements/Comments/Remarks:

MANUAL SOXLET EXTRACTION REQUIRED.

DCR RATES APPLY.

AMRO Environmental Laboratories Corporation

SAMPLE RECEIPT CHECKLIST

111 Herrick Street
Merrimack, NH 03054
(603) 424-2022

Client:	GEI	AMRO ID:	1007027
Project Name:	Canton Airport	Date Rec.:	7/8/10
Ship via: (circle one) Fed Ex., UPS, AMRO Courier, Hand Del., Other Courier, Other:		Date Due:	7/15/10

Items to be Checked Upon Receipt	Yes	No	NA	Comments
1. Army Samples received in individual plastic bags?			✓	
2. Custody Seals present?			✓	
3. Custody Seals Intact?			✓	
4. Air Bill included in folder if received?			✓	
5. Is COC included with samples?	✓			
6. Is COC signed and dated by client?	✓			
7. Laboratory receipt temperature. TEMP = 6°				
Samples rec. with ice ✓ ice packs___ neither___				
8. Were samples received the same day they were sampled?		✓		
Is client temperature = or <6°C ?	✓			
If no obtain authorization from the client for the analyses.				
Client authorization from: Date: Obtained by:				
9. Is the COC filled out correctly and completely?	✓			
10. Does the info on the COC match the samples?	✓			
11. Were samples rec. within holding time?	✓			
12. Were all samples properly labeled?	✓			
13. Were all samples properly preserved?			✓	
14. Were proper sample containers used?	✓			
15. Were all samples received intact? (none broken or leaking)	✓			
16. Were VOA vials rec. with no air bubbles?			✓	
17. Were the sample volumes sufficient for requested analysis?	✓			
18. Were all samples received?	✓			
19. VPH and VOA Soils only:			✓	
Sampling Method VPH (circle one): M=Methanol, E=EnCore (air-tight container)				
Sampling Method VOA (circle one): M=Methanol, SB=Sodium Bisulfate, E=EnCore, B=Bulk				
If M or SB:				
Does preservative cover the soil?				
If NO then client must be faxed.				
Does preservation level come close to the fill line on the vial?				
If NO then client must be faxed.				
Were vials provided by AMRO?				
If NO then weights MUST be obtained from client				
Was dry weight aliquot provided?				
If NO then fax client and inform the VOA lab ASAP.				
20. Subcontracted Samples:			✓	
What samples sent:				
Where sent:				
Date:				
Analysis:				
TAT:				
21. Information entered into:				
Internal Tracking Log?	✓			
Dry Weight Log?	✓			
Client Log?			✓	
Composite Log?			✓	
Filtration Log?			✓	

Received By: KW	Date: 7/8/10	Logged in By: KW	Date: 7/8/10
Labeled By: KW	Date: 7/8/10	Checked By: MG	Date: 7-8-10

NA= Not Applicable

qc/qcmemos/forms/samplerec Rev.19 04/20/09

CASE NARRATIVE

PCBs:

1. No QC deviations were observed.

WET CHEMISTRY:

1. No QC deviations were observed.

MADEP MCP Analytical Method Report Certification Form

Laboratory Name: AMRO Environmental Laboratories, Inc. Project Number: 1007027

Project Location: 09382-2 Canton Airport MADEP RTN [1]

1007027-01 1007027-08 1007027-15	1007027-02 1007027-09	1007027-03 1007027-10	1007027-04 1007027-11	1007027-05 1007027-12	1007027-06 1007027-13	1007027-07 1007027-14

Sample Matrices: Ground Water ☐ Soil / Sediment ☑ Drinking Water ☐ OtherMatrix ☐

MCP SW-846 Methods Used					
	8260B ☐	8151A ☐	8330 ☐	6010B ☐	7470A/1A ☐
	8270C ☐	8081A ☐	VPH ☐	6020 ☐	9014M [2] ☐
As specified in MADEP Compendium of Analytical Methods (check all that apply)	8082 ☑	8021B ☐	EPH ☐	7000S [3] ☐	Other ☐

1 List Release Tracking Number (RTN) if known
2 M - SW-846 Method 9014 or MADEP Physiologically Available Cyanide (PAC) Method
3 S SW-846 Methods 7000 Series List individual method analyte

An affirmative response to questions A, B, C and D is required for "Presumptive Certainty" status

A	Were all samples received by the laboratory in a condition consistent with that described on the Chain of Custody documentation for the data set?	◉ Yes ○ No [1]
B	Were all QA/QC procedures required for the specified analytical method(s)included in this report followed, including the requirement to note and discuss in a narrative QC data that did not meet appropriate performance standards or guide lines?	◉ Yes ○ No [1]
C	Does the analytical data included in this report meet all the requirements for Presumptive Certainty, as described in Section 2.0 of the MADEP document CAM VII A, Quality Assurance and Quality Control Guidelines for the Acquisition and Reporting of Analytical Data?	◉ Yes ○ No [1]
D	**VPH and EPH methods only:** Was the VPH or EPH method run without significant modifications, as specified in Section 11.3?	○ ~~Yes~~ ◉ No [1] N/A

A response to questions E and F below is required for "Presumptive Certainty" status

E	Were all QC performance standards and recommendations for the specified methods achieved?	◉ Yes ○ No [1]
F	Were results for all analyte-list compounds / elements for the specified method(s) reported?	◉ Yes ○ No [1]

[1] All NO answers must be addressed in an attached Environmental Laboratory case narrative.

I, the undersigned, attest under the pains and penalties of perjury that, based upon my personal inqury of those responsible for obtaining the information, the material contained in this analytical report is, to the best of my knowledge and belief, accurate and complete.

Signature: Suzanne Karam for Nancy Stewart Position: VOA Supervisor

Printed Name: Suzanne Karam Date: 7/14/10

DATA COMMENT PAGE

Organic Data Qualifiers

ND	Indicates compound was analyzed for, but not detected at or above the reporting limit.
J	Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed, or when the data indicates the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit but greater than the method detection limit.
H	Method prescribed holding time exceeded.
E	This flag identifies compounds whose concentrations exceed the calibration range of the instrument for that specific analysis.
B	This flag is used when the analyte is found in the associated blank as well as in the sample.
R	RPD outside accepted recovery limits
RL	Reporting limit; defined as the lowest concentration the laboratory can accurately quantitate.
S	Spike Recovery outside accepted recovery limits.
#	See Case Narrative

Micro Data Qualifiers

TNTC	Too numerous to count

Inorganic Data Qualifiers

ND or U	Indicates element was analyzed for, but not detected at or above the reporting limit.
J	Indicates a value greater than or equal to the method detection limit, but less than the quantitation limit.
H	Indicates analytical holding time exceedance.
B	Indicates that the analyte is found in the associated blank, as well as in the sample.
MSA	Indicates value determined by the Method of Standard Addition
E	This flag identifies compounds whose concentrations exceed the calibration range of the instrument for that specific analysis.
R	RPD outside accepted recovery limits
RL	Reporting limit; defined as the lowest concentration the laboratory can accurately quantitate.
S	Spike Recovery outside accepted recovery limits.
W	Post-digestion spike for Furnace AA analysis is out of control limits (85-115), while sample absorbance is less than 50% of spike absorbance.
*	Duplicate analysis not within control limits.
+	Indicates the correlation coefficient for the Method of Standard Addition is less than 0.995
#	See Case Narrative

Report Comments:

1. Soil, sediment and sludge sample results are reported on a "dry weight" basis.
2. Reporting limits are adjusted for sample size used, dilutions and moisture content, if applicable.

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-04
Collection Date: 7/7/2010 8:02:00 AM
Collection Time:
Client Sample ID: 093822-AT100(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: KA
Aroclor 1016	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1221	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1232	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1242	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1248	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1254	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1260	550	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1262	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Aroclor 1268	ND	62		µg/Kg-dry	1	7/9/2010 2:08:00 PM
Surr: Tetrachloro-m-xylene	80.3	30-150		%REC	1	7/9/2010 2:08:00 PM
Surr: Decachlorobiphenyl	69.7	30-150		%REC	1	7/9/2010 2:08:00 PM

Lab ID: 1007027-05
Collection Date: 7/7/2010 8:45:00 AM
Collection Time:
Client Sample ID: 093822-PR12(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: KA
Aroclor 1016	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1221	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1232	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1242	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1248	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1254	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1260	640	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1262	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Aroclor 1268	ND	52		µg/Kg-dry	1	7/9/2010 2:36:00 PM
Surr: Tetrachloro-m-xylene	78.2	30-150		%REC	1	7/9/2010 2:36:00 PM
Surr: Decachlorobiphenyl	66.1	30-150		%REC	1	7/9/2010 2:36:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-06
Collection Date: 7/7/2010 9:10:00 AM
Collection Time:
Client Sample ID: 093822-BE110(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1221	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1232	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1242	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1248	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1254	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1260	230	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1262	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Aroclor 1268	ND	48		µg/Kg-dry	1	7/9/2010 3:03:00 PM
Surr: Tetrachloro-m-xylene	90.9	30-150		%REC	1	7/9/2010 3:03:00 PM
Surr: Decachlorobiphenyl	78.9	30-150		%REC	1	7/9/2010 3:03:00 PM

Lab ID: 1007027-07
Collection Date: 7/7/2010 9:50:00 AM
Collection Time:
Client Sample ID: 093822-PR13(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1221	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1232	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1242	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1248	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1254	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1260	860	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1262	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Aroclor 1268	ND	52		µg/Kg-dry	1	7/9/2010 3:30:00 PM
Surr: Tetrachloro-m-xylene	77.6	30-150		%REC	1	7/9/2010 3:30:00 PM
Surr: Decachlorobiphenyl	69.3	30-150		%REC	1	7/9/2010 3:30:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-08
Collection Date: 7/7/2010 10:15:00 AM
Collection Time:
Client Sample ID: 093822-PR14(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1221	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1232	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1242	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1248	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1254	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1260	310	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1262	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Aroclor 1268	ND	90		µg/Kg-dry	1	7/9/2010 3:57:00 PM
Surr: Tetrachloro-m-xylene	102	30-150		%REC	1	7/9/2010 3:57:00 PM
Surr: Decachlorobiphenyl	63.6	30-150		%REC	1	7/9/2010 3:57:00 PM

Lab ID: 1007027-09
Collection Date: 7/7/2010 10:40:00 AM
Collection Time:
Client Sample ID: 093822-BO120(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1221	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1232	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1242	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1248	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1254	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1260	280	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1262	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Aroclor 1268	ND	50		µg/Kg-dry	1	7/9/2010 4:25:00 PM
Surr: Tetrachloro-m-xylene	79.0	30-150		%REC	1	7/9/2010 4:25:00 PM
Surr: Decachlorobiphenyl	69.6	30-150		%REC	1	7/9/2010 4:25:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-10
Collection Date: 7/7/2010 12:22:00 PM
Collection Time:
Client Sample ID: 093822-BY120(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: KA
Aroclor 1016	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1221	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1232	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1242	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1248	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1254	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1260	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1262	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Aroclor 1268	ND	140		µg/Kg-dry	1	7/9/2010 4:52:00 PM
Surr: Tetrachloro-m-xylene	79.0	30-150		%REC	1	7/9/2010 4:52:00 PM
Surr: Decachlorobiphenyl	71.8	30-150		%REC	1	7/9/2010 4:52:00 PM

Lab ID: 1007027-11
Collection Date: 7/7/2010 12:35:00 PM
Collection Time:
Client Sample ID: 093822-PR15(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: KA
Aroclor 1016	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1221	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1232	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1242	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1248	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1254	350	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1260	330	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1262	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Aroclor 1268	ND	110		µg/Kg-dry	1	7/9/2010 5:20:00 PM
Surr: Tetrachloro-m-xylene	81.7	30-150		%REC	1	7/9/2010 5:20:00 PM
Surr: Decachlorobiphenyl	75.1	30-150		%REC	1	7/9/2010 5:20:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport

Lab Order: 1007027

Lab ID: 1007027-12
Collection Date: 7/7/2010 1:10:00 PM
Collection Time:
Client Sample ID: 093822-PR16 (0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1221	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1232	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1242	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1248	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1254	620	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1260	420	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1262	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Aroclor 1268	ND	96		µg/Kg-dry	1	7/9/2010 5:47:00 PM
Surr: Tetrachloro-m-xylene	78.0	30-150		%REC	1	7/9/2010 5:47:00 PM
Surr: Decachlorobiphenyl	70.3	30-150		%REC	1	7/9/2010 5:47:00 PM

Lab ID: 1007027-13
Collection Date: 7/7/2010 1:30:00 PM
Collection Time:
Client Sample ID: 093822-PR17(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1221	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1232	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1242	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1248	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1254	300	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1260	220	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1262	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Aroclor 1268	ND	120		µg/Kg-dry	1	7/9/2010 6:14:00 PM
Surr: Tetrachloro-m-xylene	86.8	30-150		%REC	1	7/9/2010 6:14:00 PM
Surr: Decachlorobiphenyl	80.5	30-150		%REC	1	7/9/2010 6:14:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-14
Collection Date: 7/7/2010 12:54:00 PM
Collection Time:
Client Sample ID: 093822-BY130(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1221	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1232	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1242	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1248	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1254	960	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1260	550	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1262	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Aroclor 1268	ND	97		µg/Kg-dry	1	7/9/2010 6:42:00 PM
Surr: Tetrachloro-m-xylene	81.7	30-150		%REC	1	7/9/2010 6:42:00 PM
Surr: Decachlorobiphenyl	73.2	30-150		%REC	1	7/9/2010 6:42:00 PM

Lab ID: 1007027-15
Collection Date: 7/7/2010 1:50:00 PM
Collection Time:
Client Sample ID: 093822-CJ130(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PCBS BY EPA8082		**SW8082**				Analyst: **KA**
Aroclor 1016	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1221	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1232	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1242	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1248	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1254	730	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1260	310	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1262	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Aroclor 1268	ND	110		µg/Kg-dry	1	7/9/2010 7:09:00 PM
Surr: Tetrachloro-m-xylene	70.5	30-150		%REC	1	7/9/2010 7:09:00 PM
Surr: Decachlorobiphenyl	64.9	30-150		%REC	1	7/9/2010 7:09:00 PM

AMRO Environmental Laboratories Corp.

Date: *13-Jul-10*

CLIENT: GEI Consultants, Inc.
Work Order: 1007027
Project: 09382-2 Canton Airport

QC SUMMARY REPORT

Method Blank

Sample ID: **MB-20418** Batch ID: **20418** Test Code: **SW8082** Units: **µg/Kg** Analysis Date **7/9/2010 12:46:00 PM** Prep Date: **7/8/2010**

Client ID: Run ID: **GC-TRENT_100709A** SeqNo: **747409**

Analyte	QC Sample Result	RL	Units	QC Spike Amount	Original Sample Result	%REC	LowLimit	HighLimit	Original Sample or MS Result	%RPD	RPDLimit	Qua
Aroclor 1016	ND	50	µg/Kg									
Aroclor 1221	ND	50	µg/Kg									
Aroclor 1232	ND	50	µg/Kg									
Aroclor 1242	ND	50	µg/Kg									
Aroclor 1248	ND	50	µg/Kg									
Aroclor 1254	ND	50	µg/Kg									
Aroclor 1260	ND	50	µg/Kg									
Aroclor 1262	ND	50	µg/Kg									
Aroclor 1268	ND	50	µg/Kg									
Surr: Tetrachloro-m-xylene	13.19	0	µg/Kg	16	0	82.5	30	150	0			
Surr: Decachlorobiphenyl	11.74	0	µg/Kg	16	0	73.4	30	150	0			

Qualifiers: ND - Not Detected at the Reporting Limit
J - Analyte detected below quantitation limits
RL - Reporting Limit; defined as the lowest concentration the laboratory can accurately quantitate.
S - Spike Recovery outside accepted recovery limits
R - RPD outside accepted recovery limits
B - Analyte detected in the associated Method Blank
NA - Not applicable where J values or ND results occur

AMRO Environmental Laboratories Corp.

Date: *13-Jul-10*

CLIENT: GEI Consultants, Inc.
Work Order: 1007027
Project: 09382-2 Canton Airport

QC SUMMARY REPORT

Laboratory Control Spike

Sample ID: **LCS-20418** Batch ID: **20418** Test Code: **SW8082** Units: **µg/Kg** Analysis Date **7/9/2010 1:14:00 PM** Prep Date: **7/8/2010**
Client ID: Run ID: **GC-TRENT_100709A** SeqNo: **747410**

Analyte	QC Sample Result	RL	Units	QC Spike Amount	Original Sample Result	%REC	LowLimit	HighLimit	Original Sample or MS Result	%RPD	RPDLimit	Qua
Aroclor 1016	821.1	50	µg/Kg	1000	0	82.1	70.9	125	0			
Aroclor 1260	832.4	50	µg/Kg	1000	0	83.2	60.1	126	0			
Surr: Tetrachloro-m-xylene	16.02	0	µg/Kg	16	0	100	30	150	0			
Surr: Decachlorobiphenyl	12.68	0	µg/Kg	16	0	79.2	30	150	0			

Sample ID: **LCSD-20418** Batch ID: **20418** Test Code: **SW8082** Units: **µg/Kg** Analysis Date **7/9/2010 1:41:00 PM** Prep Date: **7/8/2010**
Client ID: Run ID: **GC-TRENT_100709A** SeqNo: **747411**

Analyte	QC Sample Result	RL	Units	QC Spike Amount	Original Sample Result	%REC	LowLimit	HighLimit	Original Sample or MS Result	%RPD	RPDLimit	Qua
Aroclor 1016	811.2	50	µg/Kg	1000	0	81.1	70.9	125	0			
Aroclor 1260	832.3	50	µg/Kg	1000	0	83.2	60.1	126	0			
Surr: Tetrachloro-m-xylene	13.75	0	µg/Kg	16	0	85.9	30	150	0			
Surr: Decachlorobiphenyl	12.25	0	µg/Kg	16	0	76.5	30	150	0			

Qualifiers: ND - Not Detected at the Reporting Limit; S - Spike Recovery outside accepted recovery limits; B - Analyte detected in the associated Method Blank; J - Analyte detected below quantitation limits; R - RPD outside accepted recovery limits; NA - Not applicable where J values or ND results occur; RL - Reporting Limit; defined as the lowest concentration the laboratory can accurately quantitate.

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-01
Collection Date: 7/7/2010 8:00:00 AM
Collection Time:
Client Sample ID: 093822-AT100(0-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PH/CORROSIVITY		**SW9045C**				Analyst: **KA**
pH	4.1	0		pH Units	1	7/8/2010 2:45:00 PM

Lab ID: 1007027-02
Collection Date: 7/7/2010 7:00:00 AM
Collection Time:
Client Sample ID: 093822-AT100-DUP1
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PH/CORROSIVITY		**SW9045C**				Analyst: **KA**
pH	4.1	0		pH Units	1	7/8/2010 2:45:00 PM

Lab ID: 1007027-03
Collection Date: 7/7/2010 12:20:00 PM
Collection Time:
Client Sample ID: 093822-BY120(0-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PH/CORROSIVITY		**SW9045C**				Analyst: **KA**
pH	4.2	0		pH Units	1	7/8/2010 2:45:00 PM

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-01
Collection Date: 7/7/2010 8:00:00 AM
Collection Time:
Client Sample ID: 093822-AT100(0-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	25.5	0		wt%	1	7/8/2010

Lab ID: 1007027-02
Collection Date: 7/7/2010 7:00:00 AM
Collection Time:
Client Sample ID: 093822-AT100-DUP1
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	23.8	0		wt%	1	7/8/2010

Lab ID: 1007027-03
Collection Date: 7/7/2010 12:20:00 PM
Collection Time:
Client Sample ID: 093822-BY120(0-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	60.2	0		wt%	1	7/8/2010

Lab ID: 1007027-04
Collection Date: 7/7/2010 8:02:00 AM
Collection Time:
Client Sample ID: 093822-AT100(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	21.8	0		wt%	1	7/8/2010

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-05
Collection Date: 7/7/2010 8:45:00 AM
Collection Time:
Client Sample ID: 093822-PR12(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	3.9	0		wt%	1	7/8/2010

Lab ID: 1007027-06
Collection Date: 7/7/2010 9:10:00 AM
Collection Time:
Client Sample ID: 093822-BE110(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	2.9	0		wt%	1	7/8/2010

Lab ID: 1007027-07
Collection Date: 7/7/2010 9:50:00 AM
Collection Time:
Client Sample ID: 093822-PR13(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	8.9	0		wt%	1	7/8/2010

Lab ID: 1007027-08
Collection Date: 7/7/2010 10:15:00 AM
Collection Time:
Client Sample ID: 093822-PR14(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	45.1	0		wt%	1	7/8/2010

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-09
Collection Date: 7/7/2010 10:40:00 AM
Collection Time:
Client Sample ID: 093822-BO120(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	5.6	0		wt%	1	7/8/2010

Lab ID: 1007027-10
Collection Date: 7/7/2010 12:22:00 PM
Collection Time:
Client Sample ID: 093822-BY120(9-12)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	64.7	0		wt%	1	7/8/2010

Lab ID: 1007027-11
Collection Date: 7/7/2010 12:35:00 PM
Collection Time:
Client Sample ID: 093822-PR15(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	55.8	0		wt%	1	7/8/2010

Lab ID: 1007027-12
Collection Date: 7/7/2010 1:10:00 PM
Collection Time:
Client Sample ID: 093822-PR16 (0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	50.2	0		wt%	1	7/8/2010

AMRO Environmental Laboratories Corp.

Date: *14-Jul-10*

CLIENT: GEI Consultants, Inc.
Project: 09382-2 Canton Airport
Lab Order: 1007027

Lab ID: 1007027-13
Collection Date: 7/7/2010 1:30:00 PM
Collection Time:
Client Sample ID: 093822-PR17(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	60.6	0		wt%	1	7/8/2010

Lab ID: 1007027-14
Collection Date: 7/7/2010 12:54:00 PM
Collection Time:
Client Sample ID: 093822-BY130(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	50.2	0		wt%	1	7/8/2010

Lab ID: 1007027-15
Collection Date: 7/7/2010 1:50:00 PM
Collection Time:
Client Sample ID: 093822-CJ130(0-6)
Matrix: SOIL

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE		**D2216**				Analyst: **MG**
Percent Moisture	56.7	0		wt%	1	7/8/2010