

**SCHEDULE OF PRICES**  
**Highland Park Model-T Plant ACM, LBP, and Universal Waste Removal or Abatement**

Task	Description	Estimated Quantity	Unit of Measure	Price/Unit	Total Cost
<b>1.0 ASBESTOS-CONTAINING MATERIALS</b>					
1.1	Pipe Insulation Removal and Disposal (0-2-inch lines)	3,600	Linear Feet		
1.2	Pipe Insulation Removal and Disposal (2-4-inch lines)	125	Linear Feet		
1.3	Mudded Pipe Fittings Removal and Disposal (0-2-inch lines)	250	Linear Feet		
1.4	Mudded Pipe Fittings Removal and Disposal (2-4-inch lines)	10	Fitting		
1.5	Black 9"x9" Floor Tile Removal and Disposal	21,500	Square Feet		
1.6	Tan 6"x6" Floor Tile Removal and Disposal	9,600	Square Feet		
1.7	Cloth Duct Isolation Joint Removal and Disposal	9	Joint		
1.8	Exterior Window Frame Caulk Removal and Disposal (275 Window Units)	25	Square Feet		
1.9	Door Frame Caulk Removal and Disposal (6 Doors)	5	Square Feet		
1.10	Fire Door Removal and Disposal	8	Doors and Frames		
1.11	Electrical Panel Removal and Disposal	8	Panels		
1.12	Miscellaneous Pipe Insulation Debris Removal and Disposal	3	Cubic Yards		
<b>2.0 LEAD-BASED PAINT MATERIALS</b>					
2.1	Abatement/Removal of Painted Surfaces	200,000	Square Feet		
2.2	Abatement/Removal of Floors/Debris (non-ACM)	26,500	Square Feet		
<b>3.0 UNIVERSAL WASTE (PCB, MERCURY, REFRIGERANTS, AND WASTE OILS)</b>					
3.1	Fluorescent Light Tube Removal and Disposal	1,012	Light Tube		
3.2	Light Ballast Removal and Disposal	510	Ballast		
3.3	Thermostat Removal and Disposal	3	Thermostat		
3.4	Elevator Control Equipment Removal and Disposal	2	Panel		
3.5	Air Conditioning Unit Removal and Disposal	13	AC Unit		
3.6	Drinking Fountain Removal and Disposal	1	Fountain		
3.7	Waste Lubrication Oils	10	Gallons		
<b>TOTAL COST</b>					