

## **RU-C2 Remedial Action**



# Groundwater, Soil and Soil Vapor Characterization In Support of Remedial Action at RU-C2

Hunters Point Shipyard March 2011






# **RU-C2 Overview**



- RU-C2: Located west of RU-C1 and north of RU-C4
- Key Features- Buildings 258 and 251
- Two VOC plumes in groundwater
- Primary Groundwater COCs-TCE, PCE, chlorobenzene
- Primary soil COCs- arsenic, lead, zinc, PAHs




RU-C2 Location Map



# **ROD Summary- Groundwater**



- Remedial Action Per Final ROD
- In-situ remediation of VOCs in groundwater
  - ZVI Remediation Area
    - PCE > 15 ug/L
    - TCE > 110 ug/L
  - Bioremediation Area
    - VOCs exceed respective RGs by 10-50 times after ZVI injections
  - MNA Area





# **ROD Summary**



#### Soil Excavation

- As, Pb, CVOCs, PAHs, and ZN exceed RG's
- 20A-1 Building 258 (metals, VOCs, PCBs, PAHs)
- 20B-1 Building 251 (VOCs, PCBs)
- 20B-2 and 13-1 "Hot Spot" Areas (metals, PAHs)

# 13-1 0 8 VE Area 2 20B-2 208-1 258 20A-1

#### Soil Vapor Extraction

- Source reduction measure for VOC contaminated soil
- Coincidental with locations of VOC-impacted groundwater
- Definition of SVE Limits
  - Previous soil detections
  - Future Soil Vapor Sampling







# **Pre-Design Investigation**



- Pre-design investigation work plan
  - Purpose: VOC plume characterization in support of in-situ remediation
    - Soil and grab groundwater investigation
  - Purpose: Define area warranting soil vapor extraction (SVE)
    - Collocated soil and soil vapor investigation
    - Supporting data from ongoing base-wide soil vapor survey








# **Pre-Design Investigation Activities**




- Pre-Design soil and grab groundwater investigation
  - 15 Hydropunch locations
  - Building 258 VOC Plume
    - 6 Hydropunches targeting Building 258 plume
  - Building 251 VOC Plume
    - 9 Hydropunches targeting Building 251 plume
  - Soil and grab groundwater sampling
    - VOCs, SVOCs, PAHs, Metals, bioindicator parameters

#### **Building 258 VOC Plume**



Building 251 VOC Plume






# **Soil and Soil Vapor Characterization**



- Soil and soil vapor characterization
  - 15 locations, collocated soil and soil gas
  - VOC and TO-15 analyses of samples
- Additional data from basewide soil vapor survey and groundwater monitoring program





## **Future Activities**




- Future Investigation and Remediation Activities
  - Remedial Action Workplan
  - Groundwater monitoring well decommissioning and installation
  - In-situ remediation of groundwater
    - ZVI Injections
    - Anaerobic bio-substrate injections
    - Aerobic bio-substrate injections (Optional)
    - Baseline and post-injection monitoring
  - Soil remediation
    - Soil excavation
    - SVE operations
  - Parcel-wide soil vapor sampling
  - Removal of SD/SS and clearance of RAD impacted buildings
  - Excavations as part of the TPH program



SVE Area

Excavation Area







# **Estimated Schedule**



•	Draft Pre-Design	Work Plan	Submittal
---	------------------	-----------	-----------

May 2011

Regulatory review

May - June 2011

• Working meeting with BCT

Mid June 2011

Respond to comments, submit Final Work Plan

July 2011

Mobilization/preparatory activities

Late July 2011

• Perform Pre-Design Investigation

July-August 2011

• Working meeting with BCT – mid field work


August 2011

Demobilization

Late August 2011

Summarize/present results

September 2011



Distribution of Field Activities-RU-C2