CONVERSE CONSULTANTS
ORANGE COUNTY

Consulting Engineering
and Applied Sciences

15245 Alton Parkway, Suite 100
Irvine, CA 92718-2307

Telephone (714) 453-2880
Facsimile (714) 453-2888

January 26, 1995

Mr. Louis Lodrigueza
Orange County Health Care Agency
2009 East Edinger Avenue
Santa Ana, California 92705

Subject: **SUMMARY REPORT OF ADDITIONAL SITE CHARACTERIZATION**
Fullerton Business Park North
1551 East Orangethorpe Avenue
Fullerton, California
OCHCA Case No. 94IC29
(Converse Project No. 94-42871-03)

Dear Mr. Lodrigueza:

Converse Consultants Orange County (Converse), on behalf of Red Eagle Properties, is pleased to present this Summary Report of the Additional Site Characterization activities at the referenced property. This report documents the general activities at the referenced property associated with tetrachloroethene (PCE) contamination, discovered during the removal of the southern clarifier. For site vicinity, see Figure 1.

Background

During removal of two clarifiers from the property in September 1994, soil contamination from tetrachloroethene (PCE) and total recoverable petroleum hydrocarbons (TRPH) was discovered beneath the southern clarifier. For site layout, see Figure 2.

Initial site characterization indicated that significant contamination was not present at 15 feet beneath the former clarifier. Additional investigation was requested by the California Regional Water Quality Control Board, Santa Ana Region.

On December 2, 1994, Converse advanced six (6) soil borings using a Geoprobe Systems sampling technique. Initial depths of 15 feet bgs were targeted for investigation. Soil samples were obtained from 15 feet bgs, and were field screened using an organic vapor analyzer (OVA). Soil samples were then submitted to an on-site mobil laboratory for analysis. Borings from which the soil sample exhibited elevated levels of PCE were advanced further, and samples were obtained at five-foot intervals. Additional borings were located based on soil analytical results from previous borings.

Analytical results from the soil samples obtained indicated that further study was needed to define the vertical and lateral extent of PCE contamination.

Field Activities

On January 9 through 11, 1995, Converse advanced (9) additional soil borings on the property in an attempt to vertically and laterally characterize the extent of contamination (BH-4A through BH-6A and BH-8 through BH-13) using a Geoprobe Systems sampling technique. All borings were located based on previous soil analytical data. See Figure 3 for boring locations.

Borings BH-4A, BH-5A, and BH-6A were adjacent to BH-4, BH-5, and BH-6, respectively. Soil samples were obtained from borings BH-4A and BH-6A at 5-foot intervals, beginning at 20 feet. Boring BH-5A was a continuously cored boring to 40 feet, with soil samples obtained at 5-foot intervals, beginning at 25 feet.

Borings BH-8 through BH-13 were advanced to 40 feet, with soil samples obtained at 5-foot intervals beginning at 15 feet. Boring BH-11 was a continuously cored boring.

Soil samples from each boring were submitted to an on-site mobil laboratory for analysis. Additional borings were then located based upon the mobil laboratories analytical results. At the completion of the boring activities, the boreholes were backfilled with bentonite chips and hydrated with purified water. See Appendix A for field methodologies.

Soil Analytical Results

A total of 51 soil samples were submitted to the mobil laboratory for analysis. The samples were analyzed in accordance with EPA methods 8010 (PCE). The analytical results, including the results from borings from the previous investigations are presented in Table I.

The highest concentrations of PCE contamination occurred consistently between 20 and 25 feet bgs. PCE (less than 60 ppb) was detected in some samples obtained from 40 feet bgs at three of the nine new boring locations (BH-10, BH-11, and BH-12). Samples obtained from shallower depths in these three locations did not reveal PCE soil contamination.

For a complete copy of the analytical results, see Appendix B.

Soil Conditions and Other Observations

Generally, the subsurface soil conditions consist primarily of clayey silts and silty clays encountered at approximately 15 feet bgs and extending to approximately 35 feet bgs. Some fine grained sand with silt was encountered at 20 feet bgs and 37 feet bgs in BH-11 and BH-5A, extending to approximately 40 feet bgs, where more clayey silt was encountered. See Appendix C for the boring logs.

Ground water was not encountered in any borings, and is estimated at a depth of approximately 60 feet bgs in the area, based on information obtained from nearby monitoring wells. The gradient is believed to be towards the southwest.

Conclusions and Recommendations

Based on the findings from the additional characterization activities, it appears that contamination of the soil from PCE has essentially been defined laterally to the west and northwest of the former clarifier. The vertical extent has not been completely defined, although the highest concentrations found occur above 30 feet bgs.

The highest concentrations of PCE found in the soil occur to the west and northwest of the former clarifier at depths of 20 to 25 feet bgs. It is possible that contamination could have occurred from a source between the existing building and the former clarifier (possibly a former fill pipe). The contamination detected at 40 feet could be from migration of the suspected source (fill pipe), or from a different (possibly off-site) source.

Due to the elevated concentration of PCE contamination at depths of 20 to 25 feet, the presence of PCE at 40 feet, and your verbal suggestions, Converse recommends the installation of three (3) ground water monitoring wells on the property. This will determine if ground water has been impacted by the suspected on-site source or an off-site source.

Limitations

The findings presented herein are based on our evaluation of currently available data and were prepared in accordance with generally accepted environmental principles common to the local area in which we practice. We make no other warranty, either expressed or implied.

Converse is not responsible for the accuracy of information provided by others. This report should not be regarded as a guarantee that no subsurface contamination is present at the property beyond what has been disclosed. There may be subsurface conditions that cannot be reasonably predicted with the services performed to-date.

If you have any questions, please contact us at (714) 453-2880.

Sincerely,

CONVERSE CONSULTANTS ORANGE COUNTY

J. Michael Batten
Project Geologist

Thomas J. Scheil, RGE 753
Vice President and
Principal Engineer

REGISTERED PROFESSIONAL ENGINEER
THOMAS J. SCHEIL
No. GE753
Exp. 6-30-96
GEOTECHNICAL
STATE OF CALIFORNIA

JMB/GSS/TJS

References: Converse Consultants Orange County, "Clarifier Removal and Soil Analysis, Fullerton Business Park North," October 18, 1994.

Converse Consultants Orange County, "Site Characterization Summary Report, Fullerton Business Park North," November 11, 1994.

Converse Consultants Orange County, "Summary Report, Additional Site Characterizaton, Fullerton Business Park North," December 13, 1994.

Attachments:

Figure 1 - Vicinity Map
Figure 2 - Site Layout Map
Figure 3 - Detail Map
Table I - PCE Concentrations in Soil Samples
Appendix A - Field Methodologies
Appendix B - Analytical Report
Appendix C - Boring Logs

Distribution:

1 Addressee
1 Mr. Robert Holub, Santa Ana Regional Water Quality Control Board
2 Mr. Carl Ross, Red Eagle Properties
1 Mr. Mark Boen, Red Eagle Properties

FIGURES



Reference: U.S.G.S Topographic Map, 7.5 Minute Series, Anaheim, California Quadrangle, Dated 1965, (Photorevised 1981).

0 2000 4000

SCALE IN FEET

VICINITY MAP

SITE CHARACTERIZATION
1551 East Orangethorpe Avenue
Fullerton, California

Project No.
94-42871-03

Converse Consultants
Orange County
Geotechnical Engineering
and Applied Sciences

Figure No.
1



0 60 120

SCALE IN FEET

N

Converse Consultants
Orange County
Consulting Engineering and Applied Sciences

SITE LAYOUT MAP

Fullerton Business Park North
1551 East Orangethorpe Avenue
Fullerton, California

DATE: 11/14/94	PROJECT NO: 94-42871-03	FIGURE NO: 2
SCALE: 1" = 60'	CHECKED BY:	

NOTE:
This figure is part of Converse Consultants Orange County report dated 12/6/94.



Converse Consultants
Orange County
Consulting Engineering and Applied Sciences

SITE LAYOUT MAP

Fullerton Business Park North
1551 East Orangethorpe Avenue
Fullerton, California

DATE: 12/12/94	PROJECT NO: 9442871-03	FIGURE NO: 3
SCALE: 1" = 4'	CHECKED BY:	

NOTE:
This figure is part of Converse Consultants Orange County report dated 12/15/94.

TABLES

871tbl_1.wq1
Revised: 25-JAN-95
PM: JMB

TABLE I
PCE CONCENTRATIONS IN SOIL SAMPLES
FULLERTON BUSINESS PARK NORTH
(Converse Project No. 94-42871-03)

DEPTH OF SAMPLE (FT)	BORING LOCATION NO.															
	BH-1	BH-2	BH-3	BH-4	BH-4A	BH-5	BH-5A	BH-6	BH-6A	BH-7	BH-8	BH-9	BH-10	BH-11	BH-12	BH-13
15	ND	3,500	270	ND	--	84,500	--	ND	--	130	32,000	ND	570	31	190	140
20	17	320	ND	--	ND	96,000	--	--	ND	330	26,000	ND	ND	19	ND	16
25	ND	1,950	8,900	--	12	88,000	--	--	20	ND	92,000	18,000	ND	100	41	13
30	38	ND	--	--	23	--	17,500	--	56	--	15,000	ND	ND	29	11	ND
35	ND	ND	--	--	39	--	1,070	--	ND	--	ND	ND	ND	ND	ND	ND
40	ND	ND	--	--	52	--	28	--	ND	--	ND	ND	45	16	50	ND

Reported in parts per billion (ug/kg, ppb)
ND = Not Detected
-- = Sample not obtained

APPENDIX A

FIELD METHODOLOGIES

Geoprobe Advancement

The exploration program for this study consisted of Geoprobe probe advancement and drive sampling for the collection of soil samples. The probe was advanced on January 9 - 11, 1995 by On-Site Services using a Geoprobe Systems probing machine.

Probe advancement was conducted such that the locations were open to the atmosphere (air-filled) during advancement. No fluids, including clean water, or additives were used during probe advancement.

Drive Sampling

Drive soil samples were collected from the probe locations at specified depth intervals (typically 5-foot). Soil samples were obtained by driving a 1-inch diameter steel driving tube at the end of a percussion drill steel. The sampling tube was equipped with a steel drive head which was withdrawn, via the extending rod, at the upper limit of the desired sample interval. The tube was then driven into the undisturbed soil and an approximately 100 gram sample was collected over a 1-foot vertical interval. The sample was then brought to the ground surface by withdrawing the sections of drill steel.

After the sampler was removed from the probe location, the soil sample for chemical analyses was inspected to verify that there was no head space in the sample. If gravel extended from the sample, or head space was observed in the soil sample, the sample was considered invalid and an additional attempt was made to collect a valid sample. If the retrieved sample was considered valid, the brass sleeve was covered with teflon sheeting and tightly capped.

Once at the ground surface, the soil sampling tube was capped, placed into a polyethylene bag, labeled, and immediately submitted to an on-site mobil laboratory for analysis. Soil samples were collected, stored, transported and analyzed in accordance with EPA Sample Collection Codes. A Chain-of-Custody record was maintained throughout the operation. Analytical Laboratories of Orange, California (State certified laboratory) chemically analyzed selected samples in accordance with EPA Method 8010.

After a soil sample was collected, the sampling equipment was washed with alcanox and rinsed.

Chain-of-Custody Procedures

Chain-of-Custody procedures were maintained for all soil samples collected. This form was completed by the sample collector before releasing the samples to the laboratory. The chain-of-custody form was routed with the samples through transportation and analyses. Completed chain-of-custody forms were returned to Converse along with the results from the analytical laboratory. These forms are retained by Converse in the central project files, and are included in Appendix B.

APPENDIX B

ASSOCIATED LABORATORIES
806 North Batavia - Orange, California 92668 - 714/771-6900 FAX 714/538-1209

CLIENT

Converse Environmental West (4708)
Attn: Mike Batton
15245 Alton Parkway
Suite 100
Irvine, CA 92718

LAB NO G83413
REPORTED 01/10/95

SAMPLE Soil
RECEIVED 01/09/95

IDENTIFICATION As Below
Date Collected 01/09/95

BASED ON SAMPLE As Submitted

Tetrachloroethene EPA 8010

BH-5A/1	17,500 mg/kg
BH-5A/2	1,070 mg/kg
BH-5A/3	28 mg/kg
BH-6A/1	ND<10 mg/kg
BH-6A/2	20 mg/kg
BH-6A/3	56 mg/kg
BH-6A/4	ND<10 mg/kg
BH-6A/5	ND<10 mg/kg
BH-4A/1	ND<10 mg/kg
BH-4A/2	12 mg/kg
BH-4A/3	23 mg/kg
BH-4A/4	39 mg/kg
BH-4A/5	52 mg/kg

ASSOCIATED LABORATORIES, by:

Edward S. Behare, Ph.D.
Vice President

ESB/ql

NOTE: Unless notified in writing, all samples will be discarded by appropriate disposal protocol 30 days from date reported.

ASSOCIATED LABORATORIES
806 North Batavia · Orange, California 92668 · 714/771-6900 FAX 714/538-1209

CLIENT

Converse Environmental West
Attn: Mike Batten
15245 Alton Pkwy., #100
Irvine, CA 92718-2307

LAB NO ML00791
REPORTED 01/16/95

SAMPLE Soil
IDENTIFICATION Red Eagle
Project #9442871-03
1551 Orangethorpe, Fullerton
BASED ON SAMPLE As Submitted to Our Mobile Laboratory

RECEIVED 01/10/95

	Tetrachloroethene
BH-8 @ 15-15.5'	32,000 ppb
BH-8 @ 20-20.5'	26,000 ppb
BH-8 @ 25-25.5'	92,000 ppb
BH-8 @ 30-30.5'	15,000 ppb
BH-8 @ 35-35.5'	ND<10 ppb
BH-8 @ 40-40.5'	ND<10 ppb
BH-9 @ 15-15.5'	ND<10 ppb
BH-9 @ 20-20.5'	ND<10 ppb
BH-9 @ 25-25.5'	18,000 ppb
BH-9 @ 30-30.5'	ND<10 ppb
BH-9 @ 35-35.5'	ND<10 ppb
BH-9 @ 40-40.5'	ND<10 ppb
BH-10 @ 15-15.5'	570 ppb
BH-10 @ 20-20.5'	ND<10 ppb
BH-10 @ 25-25.5'	ND<10 ppb
BH-10 @ 30-30.5'	ND<10 ppb
BH-10 @ 35-35.5'	ND<10 ppb
BH-10 @ 40-40.5'	45 ppb

ASSOCIATED LABORATORIES, by:

Edward S. Behare, Ph.D.
Vice President

ESB/ql

NOTE: Unless notified in writing, all samples will be discarded by appropriate disposal protocol 30 days from date reported.

ASSOCIATED LABORATORIES
806 N. Batavia • Orange, CA 92668
(714) 771-6900 • FAX: (714) 538-1209

CHAIN OF CUSTODY RECORD

Date 1/10/95 Page 1 of 2

CLIENT Converse Consultants
ADDRESS 15245 Alton Pkwy. Hill
IRVINE, CA. 92718-2307
PROJECT NAME RED EAGLE
PROJECT MANAGER Mike Bolton
PHONE NUMBER (714) 453-2880
SAMPLERS: (Signature)

Samples Intact Yes ✓ No ____
County Seals Intact Yes ____ No N/A
Sample Ambient ✓ Cooled ____ Frozen ____
Same Day ____ 24 Hr. ____
Regular ____ 48 Hr. ____

SAMPLE NUMBER	LOCATION DESCRIPTION	DATE	TIME	SAMPLE TYPE WATER	SAMPLE TYPE AIR	SAMPLE TYPE SOLID	NO OF CNTNRS	SUSP CONTAM	TESTS REQUIRED
1-	BH-8 15-15.5'	1/10/95	8:20			✓	1	RE	(5010) RE only
2-	BH-8 20-20.5'		8:25			✓	1		
3-	BH-8 25-25.5'		8:30			✓	1		
4-	BH-8 30-30.5'		9:15			✓	1		
5-	BH-8 35-35.5'		9:30			✓	1		
6-	BH-8 40-40.5'		9:55			✓	1		
7-	BH-9 15-15.5'		10:30			✓	1		
8-	BH-9 20-20.5'		10:45			✓	1		
9-	BH-9 25-25.5'		11:05			✓	1		
10-	BH-9 30-30.5'		11:15			✓	1		
11-	BH-9 35-35.5'		11:40			✓	1		
12-	BH-9 40-40.5'		11:55			✓	1		

Relinquished by: (Signature) [signature] 1/10/95
Received by: (Signature) [signature]
Date/Time 1/10/95

Relinquished by: (Signature)
Received by Laboratory for analysis: (Signature)
Date/Time

Special Instructions:

I hereby authorize the performance of the above indicated work.

DISTRIBUTION: White with report. Yellow to AL, Pink to Courier

ASSOCIATED LABORATORIES
806 N. Batavia • Orange, CA 92668
(714) 771-6900 • FAX: (714) 538-1209

CHAIN OF CUSTODY RECORD

Date 1/10/95 Page 2 of 2

CLIENT Converse Consultants
ADDRESS 15245 Alton Pkwy. #100
Irvine, CA. 92718-2307
PROJECT NAME RED EAGLE
PROJECT MANAGER Mike Batten
PHONE NUMBER (714) 453-2860
SAMPLERS: (Signature)

Samples Intact Yes ✓ No ____
County Seals Intact Yes ____ No N/A
Sample Ambient ____ Cooled ____ Frozen ____
Same Day ✓ 24 Hr. ____
Regular ____ 48 Hr. ____

SAMPLE NUMBER	LOCATION DESCRIPTION	DATE	TIME	SAMPLE TYPE: WATER	SAMPLE TYPE: AIR	SAMPLE TYPE: SOLID	NO OF CNTNRS	SUSP. CONTAM	TESTS REQUIRED
13-	BH-10 15-15.5'	1/10/95	2:00			✓	1	PCE	SOIL PCE only!)
14-	BH-10 20-20.5'		2:30			✓	1		
15-	BH-10 25-25.5'		3:15			✓	1		
16-	BH-10 30-30.5'		3:30			✓	1		
17-	BH-10 35-35.5'		4:10			✓	1		
18	BH-10 40-40.5'		4:55			✓	1		

Relinquished by: (Signature) [signature]
Received by: (Signature) [signature]
Date/Time 1/10/95
I hereby authorize the performance of the above indicated work.

Relinquished by: (Signature)
Received by Laboratory for analysis: (Signature)
Date/Time

Special Instructions:

DISTRIBUTION: White with report. Yellow to AL, Pink to Courier

ASSOCIATED LABORATORIES
806 North Batavia - Orange, California 92868 - 714/771-6900 FAX 714/538-1209

CLIENT

Converse Environmental West
Attn: Mike Batten
15245 Alton Pkwy., #100
Irvine, CA 92718-2307

LAB NO. ML00794
REPORTED 01/16/95

SAMPLE Soil
IDENTIFICATION Red Eagle
Project #942871-03
1551 Orangethorpe, Fullerton
BASED ON SAMPLE As Submitted to Our Mobile Laboratory

RECEIVED 01/11/95

	Tetrachloroethene
BH-11 @ 15-15.5'	31 ppb
BH-11 @ 20-20.5'	19 ppb
BH-11 @ 25-25.5'	100 ppb
BH-11 @ 30-30.5'	29 ppb
BH-11 @ 40-40.5'	16 ppb
BH-11 @ 35-35.5'	ND<10 ppb
BH-12 @ 15-15.5'	190 ppb
BH-12 @ 20-20.5'	ND<10 ppb
BH-12 @ 25-25.5'	41 ppb
BH-12 @ 30-30.5'	11 ppb
BH-12 @ 35-35.5'	ND<10 ppb
BH-12 @ 40-40.5'	50 ppb
BH-13 @ 15-15.5'	140 ppb
BH-13 @ 20-20.5'	16 ppb
BH-13 @ 25-25.5'	13 ppb
BH-13 @ 30-30.5'	ND<10 ppb
BH-13 @ 35-35.5'	ND<10 ppb
BH-13 @ 40-40.5'	ND<10 ppb

ASSOCIATED LABORATORIES, by:

Edward S. Behare, Ph.D.
Vice President

ESB/ql

NOTE: Unless notified in writing, all samples will be discarded by appropriate disposal protocol 30 days from date reported.

ASSOCIATED LABORATORIES
806 N. Batavia • Orange, CA 92668
(714) 771-6900 • FAX: (714) 538-1209

CHAIN OF CUSTODY RECORD

Date 1/11/95 Page 1 of 2

CLIENT [illegible]
ADDRESS [illegible]
[illegible]

PROJECT NAME RED EAGLE

PROJECT MANAGER [illegible]
PHONE NUMBER (714) [illegible]-2580
SAMPLERS: (Signature) [illegible]

Samples Intact Yes ✓ No ___
County Seals Intact Yes ___ No N/A
Sample Ambient ✓ Cooled ___ Frozen ___
Same Day ✓ 24 Hr. ___
Regular ___ 48 Hr. ___

SAMPLE NUMBER	LOCATION DESCRIPTION	DATE	TIME	SAMPLE TYPE: WATER	SAMPLE TYPE: AIR	SAMPLE TYPE: SOLID	NO OF CNTNRS	SUSP CONTAM	TESTS REQUIRED
1-	BH-11 - 15-15.5'	1/11/95	8:[illegible]			✓	1	PCE	
2-	BH-11 20-20.5'		8:50			✓	1	↓	(8010) PCE only
3-	BH-11 25-25.5'		9:10			✓	1	↓	↓
4-	BH-11 30-30.5'		9:30			✓	1	↓	↓
5-	BH-11 40-40.5'		9:50			✓	1	↓	↓
6-	BH-11 35-35.5'		10:10			✓	1	↓	↓
7-	BH-12 15-15.5'		10:20			✓	1	↓	↓
8-	BH-12 20-20.5'		12:00			✓	1	↓	↓
9-	BH-12 25-25.5'		12:00			✓	1	↓	↓
10-	BH-12 30-30.5		12:30			✓	1	↓	↓
11-	BH-12 35-35.5		12:45			✓	1	↓	↓
12-	BH-12 40-40.5		1:10			✓	1	↓	↓

Relinquished by: (Signature)	Received by: (Signature)	Date/Time
[illegible]	[illegible]	1/11/95
Relinquished by: (Signature)	Received by Laboratory for analysis: (Signature)	Date/Time

I hereby authorize the performance of the above indicated work.

Special Instructions:

DISTRIBUTION: White with report. Yellow to AL, Pink to Courier

ASSOCIATED LABORATORIES
806 N. Batavia • Orange, CA 92668
(714) 771-6900 • FAX: (714) 538-1209

CHAIN OF CUSTODY RECORD

Date 1/11/95 Page 2 of 2

CLIENT Converse Consultants
ADDRESS 15245 Alton Pkwy #100
Irvine, CA. 92718-2303
PROJECT NAME RED EAGLE

PROJECT MANAGER Mike Batton
PHONE NUMBER (714) 453-2880
SAMPLERS: (Signature)

Samples Intact Yes ✓ No ____
County Seals Intact Yes ____ No N/A
Sample Ambient ____ Cooled ____ Frozen ____
Same Day ✓ 24 Hr. ____
Regular ____ 48 Hr. ____

SAMPLE NUMBER	LOCATION DESCRIPTION	DATE	TIME	SAMPLE TYPE WATER	SAMPLE TYPE AIR	SAMPLE TYPE SOLID	NO OF CNTNRS	SUSP. CONTAM	TESTS REQUIRED
13-	BH-13 15-15.5'	1/11/95	2:10			✓	1	RE	8010 PCE only
14-	BH-13 20-20.5'		2:25			✓	1		
15-	BH-13 25-25.5'		2:35			✓	1		
16-	BH-13 30-30.5'		2:55			✓	1		
17-	BH-13 35-35.5'		3:10			✓	1		
18	BH 13 40-40.5'		3:30			✓	1		

Relinquished by: (Signature)
Received by: (Signature)
Date/Time 1/11/95

Relinquished by: (Signature)
Received by Laboratory for analysis: (Signature)
Date/Time

Special Instructions:

I hereby authorize the performance of the above indicated work.

DISTRIBUTION: White with report. Yellow to AL, Pink to Courier

APPENDIX C

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-4A

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/9/95	ATD		N/A
WELL CONST	1/9/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/9/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
		10											
		15											
1		20									sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, BROWN.
2		25									sm	SM	SANDY SILT: INCREASING SAND, FINE TO MEDIUM GRAIN.

DESCRIPTION: OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-4A

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
3		30			sm	ML	CLAYEY SILT: SOME SAND,DRK. BROWN.
					sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
4		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
5					sm	ML	SANDY SILT: TRACE CLAY, BROWN, FINE TO MEDIUM GRAIN SAND.
		40					PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		45					
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-11

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/11/95	ATD		N/A
WELL CONST	1/11/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/11/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0									sm	SP	ASPHALT SAND: FINE TO MEDIUM GRAIN, LT.BROWN
		5											
		10									sm	ML	CLAYEY SILT: DRK. BROWN, INCREASING FINES. INCREASING CLAY.
1		15									sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
											sm	SM	SANDY SILT: FINE GRAIN SAND, BROWN.
											sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
2		20									sm	ML	CLAYEY SILT: DRK BROWN.
											sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN, BROWN.
		25									sm	ML	CLAYEY SILT: DRK. BROWN.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03
LOG OF: BH-11

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
							OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
3		25			sm	SM	SILTY SAND/SANDY SILT: INCREASING SAND, BROWN.
					sm	ML	CLAYEY SILT: DRK. BROWN.
4		30			sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, DRK. BROWN.
					sm	ML	CLAYEY SILT: DRK. BROWN, INCREASING CLAY.
					sm	CL	SILTY CLAY: DRK. BROWN.
					sm	SM	SANDY SILT/SILTY SAND: BROWN, FINE TO MEDIUM GRAIN SAND.
5		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
					sm	ML	CLAYEY SILT: DRK. BROWN.
6		40					PROBER'S TOTAL DEPTH = 40.5 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		45					
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-6A

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/9/95	ATD		N/A
WELL CONST	1/9/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/9/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
		10											
1		15									sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, BROWN, CHLORINATED ODOR.
2		20									sm	SM	SILTY SAND: INCREASING SAND, FINE TO MEDIUM GRAIN, SLIGHT ODOR.
		25											

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-6A

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
3		30			sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN,DRK. BROWN.
4		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
					sm	SP	SAND: FINE TO MEDIUM GRAIN.
5		40			sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN. PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		45					
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-8

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/10/95	ATD		N/A
WELL CONST	1/10/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/10/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
		10											
1		15									sm	ML	SANDY SILT: FINE GRAIN SAND, BROWN, CHLORINATED ODOR.
2		20									sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, BROWN, CHLORINATED ODOR.
3		25									sm	SM	SILTY SAND: INCREASING SAND, FINE TO MEDIUM GRAIN, SLIGHT ODOR.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-8

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
4		30			sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN, DRK. BROWN, SLIGHT ODOR.
5		35			sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN, BROWN, SLIGHT ODOR.
6		40			sm	ML	CLAYEY SILT: TRACE SAND, SLIGHT ODOR.
		45					PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-9

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A

ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/10/95	ATD		N/A
WELL CONST	1/10/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/10/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
1		10									sm	SM	SANDY SILT: FINE GRAIN SAND, BROWN, CHLORINATED ODOR.
2		15									sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND,BROWN, SOME CLAY.
3		20									sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN, SLIGHT ODOR.
		25											

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-9

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
4		30			sm	ML	CLAYEY SILT: SOME FINE GRAIN SAND, DRK. BROWN, SLIGHT ODOR.
5		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, BROWN, SLIGHT ODOR.
6		40			sm	ML	SANDY SILT: FINE TO MEDIUM GRAIN SAND, SOME CLAY, SLIGHT ODOR.
		45					PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-10

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/10/95	ATD		N/A
WELL CONST	1/10/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/10/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0					ASPHALT
		5					
		10					
1					sm	ML	SANDY SILT: FINE GRAIN SAND, BROWN.
		15					
2					sm	SM	SANDY SILT/SILTY SAND: INCREASING SAND-FINE TO MEDIUM GRAIN BROWN,
		20					
3					sm	ML	SANDY SILT: FINE GRAINSAND.
		25					

DESCRIPTION

OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03
LOG OF: BH-10

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
4		30			sm	ML	SANDY SILT: SOME FINE GRAIN SAND AND CLAY, BROWN, SLIGHT ODOR.
5		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
6		40			sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, SOME CLAY.
		45					PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-5A

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25			sm	ML	CLAYEY SILT: DRK. BROWN, CHLORINATED ODOR.
					sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN SAND, BROWN, CHLORINATED ODOR.
					sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, CHLORINATED ODOR.
1		30			sm	ML	CLAYEY SILT: SOME SAND, INCREASING CLAY, DRK. BROWN.
					sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, BROWN.
2		35			sm	ML	CLAYEY SILT: BROWN, CHLORINATED ODOR.
					sm	SP	SAND: FINE TO MEDIUM GRAIN, CHLORINATED ODOR.
3		40			sm	SM	SANDY SILT: TRACE CLAY, FINE TO MEDIUM GRAIN SAND.
					sm	SM	SILTY SAND
							PROBER'S TOTAL DEPTH = 41.5 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		45					
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-5A

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.50	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/9/95	ATD		N/A
WELL CONST	1/9/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/9/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
		10											
		15											
		20											
		25											

DESCRIPTION
OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-12

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A

ELEVATIONS(REL. MSL)
GRADE LEVEL(ft)
TOP OF CASING(ft) N/A

LOCATION T R SEC. 1/4
CITY FULLERTON CO OR
COORDINATES(ft)

RECORD:	DATE/TIME
DRLG/CORING	1/11/95
WELL CONST	1/11/95
WELL DEVELOP	N/A
BACKFILL	1/11/95

GROUNDWATER:	DEPTH(ft)	DATE/TIME
ATD		N/A
SWL*		N/A
SPL*	N/A	N/A

(* PRIOR TO INITIAL DEVELOPMENT)

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0					ASPHALT
		5					
1		10			sm	ML	CLAYEY SILT: BROWN.
2		15			sm	SM	SILTY SAND: INCREASING SAND-FINE TO MEDIUM GRAIN, BROWN,
3		20			sm	SM	SILTY SAND: FINE TO MEDIUM GRAIN.
		25					

DESCRIPTION

OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03
LOG OF: BH-12

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
4		30			sm	ML	CLAYEY SILT: INCREASING CLAY, BROWN.
5		35			sm	SP	SAND: FINE TO MEDIUM GRAIN, LT. BROWN.
6		40			sm	ML	CLAYEY SILT: SOME FINE GRAIN SAND, DRK. BROWN.
		45					PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		50					
		55					
		60					
		65					

CONVERSE ENVIRONMENTAL WEST - O.C.

LOG OF: BH-13

PROJECT NAME	RED EAGLE/FULLERTON	CONTRACTOR	ON-SITE SERVICES
PROJECT NO.	94-42871-03	DRILLER(S)	ON-SITE SERVICES
SITE GEOLOGIST(S)	SSM	RIG/METHOD	GEOPROBE
LOGGED BY	SSM	SCREEN INTERVAL	N/A
		DRLR TD(ft) 41.00	WELL CONST TD(ft) N/A
ELEVATIONS(REL. MSL)		LOCATION T R SEC. 1/4	
GRADE LEVEL(ft)		CITY FULLERTON	CO OR
TOP OF CASING(ft)	N/A	COORDINATES(ft)	

RECORD:	DATE/TIME	GROUNDWATER:	DEPTH(ft)	DATE/TIME
DRLG/CORING	1/11/95	ATD		N/A
WELL CONST	1/11/95	SWL*		N/A
WELL DEVELOP	N/A	SPL*	N/A	N/A
BACKFILL	1/11/95	(* PRIOR TO INITIAL DEVELOPMENT)		

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud

PID/OVA CALIBRATION DATE: 1/6/95 CALIBRATION UNITS: 95 ppm
THE PID/OVA SIGNAL (READING) PRODUCED REPRESENTS A QUALITATIVE MEASURE OF IONIZABLE ORGANIC POLLUTANTS.
THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF ACTUAL CONDITIONS ENCOUNTERED.

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	Gvl	Scr	Smd	Sfn	Slt	Cl	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		0											ASPHALT
		5											
1		10									sm	ML	CLAYEY SILT: BROWN.
2		15									sm	SM	SANDY SILT: INCREASING SAND-FINE TO MEDIUM GRAIN, BROWN,
3		20									sm	SM	SANDY SILT: FINE TO MEDIUM GRAIN SAND, MICACEOUS.
		25											

DESCRIPTION
OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.

CONVERSE ENVIRONMENTAL WEST - O.C.
PROJECT NAME RED EAGLE/FULLERTON
PROJECT NO 94-42871-03

LOG OF: BH-13

LITHOLOGICAL PROFILE
Gvl -Gravel > 2.0 mm
Scr -Coarse Sand 2.00-0.50 mm
Smd -Medium Sand 0.50-0.25 mm
Sfn -Fine Sand 0.25-0.062 mm
Slt -Silt <0.062 mm
Cl -Clay/Mud
Gvl | Scr | Smd | Sfn | Slt | Cl

ENV SAMPLE	PID/OVA READING	DEPTH (ft)	GRAPHICS	WELL CONSTRUCTION	MOISTURE	SOIL CLASSIFICATION	DESCRIPTION
		25					OVERALL LITHOLOGY, TEXTURE, COLOR AND, FOR SAND AND GRAVEL SIZE RANGE AND MEDIAN, ANGULARITY/ROUNDNESS, SORTING, ACCESSORY MINERALS AND FOSSILS, % QUARTZ, % FELDSPAR, % LITHIC FRAGMENTS BEDFORMS AND OTHER SEDIMENTARY STRUCTURES.
4		30			sm	ML	CLAYEY SILT: INCREASING CLAY, BROWN.
5		35			sm	ML	SANDY SILT: FINE TO MEDIUM GRAIN SAND, SOME CLAY, LT. BROWN.
		40			sm	SP	SAND: FINE TO MEDIUM GRAIN SAND, LT. BROWN.
		45			sm	ML	CLAYEY SILT: DRK BROWN. PROBER'S TOTAL DEPTH = 41 FEET BELOW GROUND SURFACE. NO FREE GROUND WATER ENCOUNTERED BELOW GROUND SURFACE.
		50					
		55					
		60					
		65					