Attachment 12501.2-SPD - Instructions for Completing Mitigation Ratio-Setting Checklist.

These instructions contain specific numeric adjustments (discrete, e.g., +1.0, or ranges, e.g., +0.25 to +4.0) that were determined by the PDT after assessing a variety of impact-mitigation scenarios and determining adjustments for each step that, in combination with other step adjustments, produce a reasonable range of final mitigation ratios. For steps where a range of adjustments is provided, PMs are directed to the attached examples for additional guidance. PMs **must** enter a separate justification for each adjustment within the checklist. PMs may deviate from the guidance provided herein if such deviations can be documented in the checklist with sufficient justification.

1	Date: Corps file no.:	Project Manager: _		
	Impact site name: ORI Cowardin or HGM type:			
	For impact site name, multiple discrete (as entered or HGM) could be lumped together to determine consider each factor and, if applicable, document mitigation sites and/or types, see QMS procedure.	a mitigation ratio using one checklist. For t consideration in response column(s) using	r each proposed impact to waters of the U	S., the project manager (PM) should
		Column A: Mitigation site name: Mitigation type: Resource type: Cowardin/HGM type: Hydrology:	Column B (optional): Mitigation site name: Mitigation type: Resource type: Cowardin/HGM type: Hydrology:	Column C (optional): Mitigation site name: Mitigation type: Resource type: Cowardin/HGM type: Hydrology:

2	QUALITATIVE impact-mitigation	Note: steps 2 and 3 are mutually		
	comparison:	exclusive. If step 2 is used, then	Starting ratio: 1:1	Starting ratio: 1:1
		complete the rest of the checklist	Ratio adjustment:	Ratio adjustment:
	Has a Corps-approved functional/condition	(steps 4-10).	Baseline ratio::_	Baseline ratio::_
	assessment been obtained? If not, complete		PM justification:	PM justification:
	step 2; otherwise, complete step 3.	Starting ratio: 1:1	3	
	Yes No	Ratio adjustment:		
		Baseline ratio::_		
	0 4 1 7 711 1 (1 1)	PM justification:		
	Optional: use Table 1 (below).	1 1/1 Justilia unioni		
	Qualitative assessment of functional loss at the			
	impact site versus expected functional gain at			
	the mitigation site may warrant a lower or			
	higher mitigation ratio. Adjustments for			
	preservation-only mitigation, which provides			
	no functional gain, should generally fall			
	towards the high end of the range (towards 3-			
	4). Preservation-only of non-aquatic habitats			
	(upland buffer) may warrant adjustments higher			
	than 4.			
	Using the list of functions below, compare			
	impact (functional loss) and proposed			
	mitigation (functional gain) at impact (I) and			
	mitigation (M) sites. If, for most functions, I <			
	M, then use a single adjustment less than 0 and			
	equal or greater than -2.0 ; if $I = M$, then use			
	adjustment of 0; or if $I > M$, then use			
	adjustment greater than 0 and less than or equal			
	to 4. Add adjustment to starting ratio of 1:1 to			
	obtain baseline ratio. If adjustment is less than			
	0 (negative), add absolute value of adjustment			
	to right (impact) side of starting ratio;			
	otherwise, add to left (mitigation) side. See			
	examples in attachment 12501.3. For a suite of			
	potential functions from HGM (alternate lists of			
	functions may be used), see Table 1 (below).			
	runctions may be used), see Table 1 (below).			

2	OTTA NUMBER A UNIVERSITY OF THE STATE OF THE	N-4	Develor and Common DAMI and	Davilar and Comp DAMI and 1
3	QUANTITATIVE impact-mitigation	Note: steps 2 and 3 are mutually	Baseline ratio from BAMI procedure	Baseline ratio from BAMI procedure
	comparison:	exclusive. If step 3 is used, steps 3 and 5 may also be mutually exclusive.	(attached)::	(attached)::_
	Han atom 2 if a Commo ammound	If a functional/condition assessment		
	Use step 3 if a Corps-approved functional/condition assessment been obtained.			
	Tunctional/condition assessment been obtained.	method is used that explicitly accounts		
	T	for area (such as HGM), steps 3 and 5		
	In general, project managers should consider	are mutually exclusive; however, if a method is used that does *not*		
	requiring a functional/condition assessment and			
	using step 3 for projects where total permanent	explicitly account for area (such as		
	impacts exceed 0.5 acre or 300 linear feet.	CRAM), then both steps should be		
	A	used. Complete the rest of the		
	Acceptable functional/condition assessment	checklist (steps 4-10 or steps 4 and 6-		
	methods must be aquatic resource-based,	10, as appropriate).		
	standardized, comparable from site to site,	Develor and Company DAMI and a lateral		
	peer-reviewed, unmodified, and approved by	Baseline ratio from BAMI spreadsheet		
	the applicable Corps District. If a district-	(attached)::		
	approved method is not available, use step 2.			
	Use Before-After-Mitigation-Impact (BAMI)			
	spreadsheet (attachment 12501.4) (if a district-			
	approved functional/condition method is not			
	available, use step 2 instead). See example			
	below.			
	below.			
	Note: In an extreme case, the BAMI procedure			
	could result in a ratio (and overall mitigation			
	proposal) unacceptable to the Corps. For			
	example, providing a very large but low quality			
	mitigation site (low functional gain resulting a			
	in a very high ratio) may result in functional			
	gain equaling loss numerically, but this may not			
	be acceptable because the required			
	compensatory mitigation must be appropriate to			
	the scope and degree of the impacts (see 33			
	CFR 320.4(r)(2)).			
4	Mitigation site location: Mitigation located	Ratio adjustment:	Ratio adjustment:	Ratio adjustment:
	outside impacted watershed generally warrants		······································	
	a higher mitigation ratio. The project manager	PM justification:	PM justification:	PM justification:
	will determine the appropriate Hydrologic Unit	J	J	J
	Code (HUC) to define the term "watershed" in			
	this context. Is mitigation located outside of			
	the impacted watershed? If yes, +1.0, if no, +0.			
	11 11 11 pacted waterbried. 11 jeb, 11.0, 11 110, 10.	<u>l</u>		I

7	Risk and uncertainty: Mitigation ratios should	Ratio adjustment:	Ratio adjustment:	Ratio adjustment:
	reflect the inherent uncertainty of mitigation.	-	-	-
	Factors to consider include: 1) permittee-	PM justification:	PM justification:	PM justification:
	responsible mitigation; 2) mitigation site did			
	not formerly support targeted aquatic resources;			
	3) difficult-to-replace resources (see 33 CFR			
	332.3(e)(3) and (f)(2)); 4) modified hydrology			
	(e.g., high-flow bypass); 5) artificial hydrology			
	(e.g., pumped water source); 6) structures			
	requiring long-term maintenance (e.g., outfalls,			
	drop structures, weirs, bank stabilization			
	structures); 7) planned vegetation maintenance			
	(e.g., mowing, landclearing, fuel modification			
	activities); 8) e.g., shallow, buried structures			
	(riprap, clay liners), and 9) absence of long-			
	term preservation mechanism. Note: this list is			
	not all-inclusive.			
	F-1 (-4			
	Each factor can range from +0.1 to +0.3 depending on the level of anticipated risk and			
	the amount of maintenance or management			
	required to sustain the compensatory mitigation			
	project. Sum factor adjustments (+0 if no			
	factors). Generally, uncertainty in banks and in			
	lieu fee programs is accounted for in the credit			
	release process.			

8	Temporal loss: Constructed habitats take time	Ratio adjustment:	Ratio adjustment:	Ratio adjustment:
	to mature and replace aquatic functions; this	J.		
	typically warrants a higher mitigation ratio in	PM justification:	PM justification:	PM justification:
	cases where a delay is planned between impacts			
	and full replacement of functions. Project			
	manager should estimate the time between			
	when the authorized impacts occur and			
	constructed mitigation is expected to replace			
	lost functions, including the monitoring period.			
	In cases where all performance standards are			
	expected to be achieved prior to impacts, no			
	temporal loss should be assessed (for permittee-			
	responsible only). Similarly, in cases where			
	interim performance standards are expected to			
	be achieved, a lower ratio adjustment may be			
	appropriate. Unexpected delays in			
	compensatory mitigation project			
	implementation should be handled as			
	compliance actions.			
	a. For scheduled, known delays between			
	impacts and construction of			
	mitigation: multiply delay (in months)			
	by 0.05;			
	b. To account for time required for full			
	replacement of functions during			
	monitoring period: generally, if			
	mitigation is comprised of			
	trees/woodlands or saltmarsh, +3; if shrubs, +2; if herbaceous, +1;			
	c. Add adjustments from steps (a) and			
	(b).			

				,
9	Final mitigation ratio(s): Project manager	Column A:	Column B:	Column C:
	should enter the final mitigation ratio(s) arrived	1. Baseline ratio from step 2 or 3 =	1. Baseline ratio from step 2 or 3 =	1. Baseline ratio from step 2 or 3 =
	at after consideration of the above factors	_:_	:	_:_
	(either qualitative OR quantitative). Project	2. Total adjustments =	2. Total adjustments =	2. Total adjustments =
	manager should enter the extent of authorized	3. Final ratio::	3. Final ratio::	3. Final ratio: :
	impacts and required mitigation by area			
	(acreage) and/or distance (linear feet), as well	Proposed impact (total):	Remaining impact:	Remaining impact:
	as the corresponding resource type (lake, non-	acre		
	tidal wetland, other, pond, stream/river/ocean,	linear feet	Required mitigation:	Required mitigation:
	tidal wetland) and Cowardin or	to	acre	acre
	Hydrogeomorphic Method (HGM)	Resource type:	linear feet	linear feet
	classification type.	Cowardin or HGM:	of	of
	31	Hydrology:	Mitigation type:	Mitigation type:
	To obtain the final mitigation ratio*:	,	Resource type:	Resource type:
	a. Take baseline ratio from step 2 or 3;	Required mitigation:	Cowardin or HGM:	Cowardin or HGM:
	b. Add ratio adjustments from steps 4-8;	acre	Hydrology:	Hydrology:
	c. If total of adjustments is greater than 0	linear feet	11) d1010gj.	Trydrology.
	(positive), add total to left (mitigation) side	of	Additional PM comments:	Additional PM comments:
	of baseline ratio;	Mitigation type:	ridditional I 111 comments.	raditional Five comments.
	d. If total of adjustments is less than 0	Resource type:		
	(negative), add ABS of total to right	Cowardin or HGM:		
	(impact) side of baseline ratio;	Hydrology:		
	Note 1: minimum ratio = 1:1 if step 2 used. If step 3	Trydrology.		
	used, final ratio can be less than 1:1 assuming	Additional PM comments:		
	completed functional/condition assessment, in	Additional FIVI comments.		
	combination with other steps, justifies a ratio less			
	than 1:1 (i.e., total of adjustments is negative).			
	Note 2: Final ratio in each column should be as			
	calculated. If desired, express ratio equal to X:1			
	(traditional format: for example, $1:4 = 0.25:1$), but			
	ONLY in step 9's PM comments and in step 10.			
10	Final compensatory mitigation	PM summary:		
	requirements:			
	Summarize the checklist results, combining all			
	required mitigation for this impact site.			
*In 4	ha final datamaination of magnined mitigation dimag	t and indinations at about the consider	.d.	

- a. Indirect impacts: Compensatory mitigation may be required to offset predictable indirect impacts. The PM should document any indirect impacts caused by the proposed/authorized activity.
- b. Cumulative impacts: In some cases, cumulative impacts should be considered when determining if compensatory mitigation should be required. The extent of cumulative impacts should be documented using available information, such as analyses or data associated with a Special Area Management Plan (SAMP), Watershed Management Plan, land use/land cover scenario assessment, hydrologic modeling, etc. The information used should be fully cited herein and in the decision document. The assessment must focus on the proposed action's direct and indirect impacts (i.e., incremental impact of the proposed activity) in the context of the cumulative effects caused by past, present, and reasonably foreseeable actions, to reduce the proposed activity's contribution to cumulative effects in the region.

^{*}In the final determination of required mitigation, direct and indirect impacts should be considered:

Step 2

Table 1 for step 2. Qualitative comparison of functions (functional loss vs. gain):

Function	Impact site	Mitigation site
Short- or long-term surface water storage		
Subsurface water storage		
Moderation of groundwater flow or discharge		
Dissipation of energy		
Cycling of nutrients		
Removal of elements and compounds		
Retention of particulates		
Export of organic carbon		
Maintenance of plant and animal communities		
	Step 2 adjustment:	

Step 2 Table 1 instructions:

- **1.** Describe amount of functional loss (impact) and gain (mitigation) in each respective column. Gain and loss can be described in text (for example, small loss, moderate loss, large loss, no loss, etc.) or symbolically (for example, +, ++, +++, 0, ---, --).
- 2. Note: alternate lists of functions may be used.
- 3. Note: a single adjustment should be used to account for all functions combined (see example 7 in attachment 12501.3)

Step 3

Before-After-Mitigation-Impact (BAMI) procedure	(CRAM exam	ple)				
Functions/conditions	Impact _{Before}	Impact _{After}	Impact _{delta}	Mitigation _{Before}	Mitigation _{After}	Mitigation _{delta}
4.1 Buffer and Landscape Context						
1.1.1 Landscape Connectivity	9	3	-6	6	6	0
1.1.2 Percent of AA with Buffer	12	6	-6	3	9	6
4.1.3 Average Buffer Width	3	3	0	3	12	9
1.1.4 Buffer Condition	6	6	0	3	9	6
RAW SCORE	15.0	8.0	-7	9.0	15.7	7
FINAL SCORE	62.5	33.6	-29	37.5	65.3	28
.2 Attribute 2: Hydrology						
.2.1 Water Source	6	6	0	6	6	0
I.2.2 Hydroperiod or Channel Stability	9	12	3	3	9	6
.2.3 Hydrologic Connectivity	12	9	-3	3	12	9
RAW SCORE	27.0	27.0	0	12.0	27.0	15
INAL SCORE	75.0	75.0	0	33.4	75.0	42
3 Attribute 3: Physical Structure						
.3.1 Structural Patch Richness	6	3	-3	3	9	6
.3.2 Topographic Complexity	6	3	-3	3	6	3
RAW SCORE	12.0	6.0	-6	6.0	15.0	9
INAL SCORE	50.0	25.0	-25	25.0	62.5	38
4 Attribute 4: Biotic Structure						
.4.1 Number of Plant Layers	12	9	-3	6	9	3
.4.2 Co-Dominant Species	6	6	0	6	12	6
.4.3 Percent Invasion	6	9	3	3	12	9
.4.4 Interspersion/Zonation	9	3	-6	3	9	6
.4.5 Vertical Structure	6	3	-3	3	6	3
AW SCORE	23	14	-9	11	26	4 5
INAL SCORE	63.9	38.9	25	30.6	72.3	42
OVERALL SCORE	65.0	46.0	-19	32.0	70.0	38

Step 3 BAMI procedure instructions:

- **1.** Choose functional method. Acceptable functional assessment methods must be aquatic resource-based, standardized, comparable from site to site, peer-reviewed, and must be approved by the applicable Corps District.
- 2. List functions/condition categories in leftmost column.
- 3. Utilize Before-After-Mitigation-Impact (BAMI) procedure above to calculate function deltas.
- **4.** Obtain absolute value (ABS*) of quotient of mitigation-delta over impact-delta for overall score (if method has no overall score, use median of quotients for function categories or individual functions. *Absolute value is the nonnegative number for any real number, so if your quotient is negative, simply drop the negative sign to get the ABS. For example: the ABS of -9/3 = 3.
- 5. To get baseline ratio: If quotient (Q) is less than 1, baseline ratio = 1/Q: 1; if quotient is greater than 1, baseline ratio = 1: Q.
- **6.** Input Step 3 baseline ratio into the checklist document.