

TABLE I-1

CLOSURE COST ESTIMATES

A. DRUM STORAGE FACILITY WEST OF BLDG. 39 (2 SHELTERS)

1. Dispose of all containers of hazardous waste at an EPA-approved disposal facility.
2. Remove any corrosion from metal shelter surfaces, deposit in drums, dispose of at an EPA-approved disposal facility.
3. Remove asphalt floor overlay and curb. Deposit in drums and dispose of at an EPA-approved disposal facility.
4. Fill sumps with sand, seal with concrete.
5. Dismantle shelters.

Total Estimated Cost: \$62,300.00 R

B. SPENT CAUSTIC STORAGE TANKS EAST OF BLDG. 52 (2 TANKS)

1. Remove all liquid and sludge from tanks, dispose of at an EPA-approved disposal facility.
2. Decontaminate inside and outside of tanks.
3. Disconnect pumps, piping, valves, and fittings - decontaminate.
4. Dispose of decontamination fluids and equipment at EPA-approved disposal facility.
5. Remove tanks.
6. Analyze asphalt and soil for contamination.
7. Remove contaminated asphalt and soil. Dispose of at EPA-approved disposal facility.

Total Estimated Cost: \$28,500.00 R



TABLE I-1 (Continued)

C. WASTE ACID STORAGE TANKS, BLDG. 52 (11 TANKS)

1. Remove all liquid and sludge from tanks. Dispose of at EPA-approved disposal facility.
2. Decontaminate tanks and piping. Dispose of decontamination fluids at an EPA-approved disposal facility.
3. Remove tanks, piping, and platforms.
4. Analyze limestone and soil surrounding and under tanks; if contaminated, remove and dispose of at EPA-approved hazardous waste landfill.

Total Estimated Cost: \$24,300.00 R

D. UNDERGROUND WASTE OIL AND JET FUEL STORAGE TANKS (5 TANKS)

1. Remove all waste oil or jet fuel.
2. Remove all sludge and residue from tanks.
3. Dispose of waste oil, jet fuel, sludge, and residue at an EPA-approved disposal facility.
4. Evacuate and remove tanks.
5. Analyze surrounding soil; if contaminated, remove and dispose of at EPA-approved hazardous waste landfill.
6. Fill in holes with fresh soil or limestone screenings.

Total Estimated Cost: \$71,800.00 R

E. SLUDGE HOLDING TANK, BLDG. 14

1. Remove all sludge; dispose of at an EPA-approved facility.
2. Wash down walls and floor of concrete tank.
3. Flush all piping, pumps, and centrifuges.

Total Estimated Cost: \$29,600.00 R

TABLE I-1 (Continued)

F. EXPLOSIVES WASTE STORAGE FACILITY, BLDG. 10

1. Remove all explosive devices and material.
2. Sweep down walls, shelves, ledges, floors, etc. Remove hazardous residue.
3. Dispose of explosive devices, material, and residue at EPA-approved TSD facility.
4. Demolish building and dispose of rubble at local landfill.

Total Estimated Cost: \$31,700.00 R

NOTE: All cost estimates assume the use of outside contract services and include 10% contingencies.