

Mike Schmoller
Project Manager
Wisconsin Department of Natural Resources
South Central Region
3911 Fish Hatchery Rd
Fitchburg WI 53711

ARCADIS U.S., Inc.
126 North Jefferson Street
Suite 400
Milwaukee
Wisconsin 53202
Tel 414 276 7742
Fax 414 276 7603
www.arcadis-us.com

ENVIRONMENT

Subject:

Building Interior Polychlorinated Biphenyl Investigation Summary, Madison-Kipp Corporation, 201 Waubesa Street, Madison, Wisconsin. Facility ID No. 113125320, BRRTS No. 02-13-001569

Date:
April 21, 2015

Dear Mr. Schmoller:

On behalf of Madison-Kipp Corporation (MKC), this letter provides a summary of the supplemental subsurface investigation, wipe sampling, and indoor air sampling activities for polychlorinated biphenyls (PCBs) conducted within the manufacturing portion of the MKC facility located at 201 Waubesa Street, Madison, Wisconsin (Site).

Contact:
Jennine Trask

This letter provides a summary of the investigation activities completed, analytical results, and recommendations. A Natural Resources 712.09 submittal certification is included in Attachment A.

Phone:
414.276.7742

Background

Email:
jennine.trask@arcadis-us.com

A *Supplemental Building Interior Polychlorinated Biphenyl Work Plan Subsurface Investigation Summary* (SI Report) was submitted to the Wisconsin Department of Natural Resources (WDNR) and United States Environmental Protection Agency (U.S. EPA) on April 22, 2014, to provide details of the investigation completed from December 2013 through February 2014. On August 27, 2014, ARCADIS met with the WDNR and U.S. EPA to discuss the next steps for addressing the soils containing PCBs beneath the building. At this meeting, U.S. EPA requested the completion of indoor air and surface wipe sampling activities, a technical justification submittal for management of PCB contaminated soils beneath the building, and additional soil investigation activities for beneath the building.

Our ref:
WI001368.0024

On October 22, 2014, a *Technical Justification – Polychlorinated Biphenyl (PCB)-Impacted Soils Beneath the Main Manufacturing Building* (Technical Justification) was submitted to the WDNR. The Technical Justification included the *Supplemental Work Plan for Polychlorinated Biphenyl Building Subsurface Investigation* (Subsurface Work Plan) as an attachment. On November 4, 2014, a *Work Plan for Polychlorinated Biphenyl Building Wipe Sampling* (Wipe Sampling Work Plan) was submitted to the WDNR and U.S. EPA for approval. The WDNR approved the Wipe Sampling Work Plan in electronic correspondence dated December 8, 2014.

On December 17, 2014, MKC met with the WDNR and U.S. EPA (via telephone) to discuss the Technical Justification (Subsurface Work Plan) and Wipe Sampling Work Plan submittals. During this meeting, U.S. EPA requested continuous soil sampling during the additional soil investigation, PCB homolog analysis for select soil sample locations, and installation and sampling of one monitoring well within the building as part of the Subsurface Work Plan. In addition, U.S. EPA requested preparation and submittal of a Quality Assurance Project Plan (QAPP) for the Wipe Sampling Work Plan. On December 18, 2014, ARCADIS, WDNR, and U.S. EPA participated in a conference call to discuss the proposed QAPP requirements.

Based on the December 17 and 18, 2014, communications, the Subsurface Work Plan was revised and submitted to the WDNR and U.S. EPA on January 22, 2015, and the *Quality Assurance Project Plan Building Interior Polychlorinated Biphenyl Wipe Sampling* (Wipe Sampling QAPP) was submitted to the WDNR and U.S. EPA on February 19, 2015. The Subsurface Work Plan was approved by WDNR in electronic correspondence dated January 23, 2015. The Wipe Sampling QAPP was approved by U.S. EPA in electronic correspondence dated February 25, 2015.

Investigation Activities

The following investigation activities were completed in accordance with the approved Subsurface Work Plan and Wipe Sampling QAPP. Details of these activities are presented below.

- March 2 through 5, 2015: Advanced six soil borings using a hand cart direct push rig, collected soil samples for laboratory analysis, and installed one monitoring well using a hollow-stem auger rig.
- March 4, 2015: Conducted wipe sampling activities.

- March 13, 2015: Collected a groundwater sample from the newly installed monitoring well for laboratory analysis.
- April 1, 2015: Conducted indoor air sampling activities.
- April 2, 2015: Conducted additional wipe sampling activities.

Health and Safety

Prior to beginning the investigations, the Site health and safety plan was updated to address the planned field activities. Utility marking arrangements were made through Digger's Hotline (the State of Wisconsin Public Utility clearance service), a private utility locator, and discussions with MKC.

Soil Boring Advancement

Advancement and sampling of the soil borings was initiated on March 2, 2015. The boring locations were selected based on historical analytical results and subsequent discussions with WDNR and U.S. EPA. The soil boring locations are presented on Figure 1.

From March 2 through 5, 2015, a total of six soil borings (B-196 through B-201) were completed adjacent to previous soil boring locations B-158, B-179, B-180, B-181, and north and south of B-182 in accordance with the approved Subsurface Work Plan. The soil borings were advanced using a direct-push hand-cart Geoprobe unit. Soil samples were collected by driving a steel sampling rod (sampler) with acetate liners to the desired sampling depth using the hydraulic ram and hammer on the Geoprobe rig. Once the sampler reached the desired depth, the sampler was opened by removing a stop pin in the sampler. The sampler was driven an additional 4 feet to push a soil sample into the sampler, preserving the sample in a 1.5-inch by 4-foot acetate liner inside the sampler. The acetate sleeves allowed for continuous collection of soil samples from each boring.

Companion sampling was completed at the soil boring locations by collecting two aliquots of soil from each sampling interval and placing each aliquot into a separate resealable plastic bag. One of the companion samples from each interval was used for field screening for the presence of total ionizable volatile organic compound vapors with a calibrated photoionization detector (PID). The screening samples were warmed and the headspace PID reading of the soil was taken by inserting the probe end of the PID into the plastic bag. Following field screening activities, the screened samples were

appropriately discarded; the unscreened companion samples were used for preparing samples for analytical testing.

An ARCADIS scientist was on Site to oversee the drilling activities and visually screen and describe the condition and properties of the soil. Soil descriptions and field screening PID results were recorded on Soil Boring Logs (WDNR Form 4400-122) in Attachment B. Borehole Abandonment Forms (WDNR Form 3300-005) are also included in Attachment B.

A total of six soil borings were advanced to depths ranging from 17.5 to 23.5 feet below ground surface (ft bgs). Below is a summary of the sampling plan.

- Soil borings were advanced to the water table or where refusal was encountered. Depths of refusal from subsurface obstructions and/or limitations of equipment were as follows: B-196 (18.5 ft bgs), B-197 (17.5 ft bgs), B-198 (23 ft bgs), B-199 (19 ft bgs), B-200 (23.5 ft bgs), B-201 (19 ft bgs). It is important to note that multiple attempts were made to advance the soil borings to the water table in each soil boring location. However, subsurface obstructions and/or limitations of equipment did not allow all borings to be advanced to the water table.
- Continuous soil sampling (one soil sample from each 3-foot interval) was conducted, per boring, from the ground surface to above the water table or where refusal was encountered.
- Soil samples were submitted for analysis based on PID screening and/or visual inspection.
- A total of two duplicate and two matrix spike/matrix spike duplicate samples were collected and analyzed in accordance with the Subsurface Work Plan.
- One soil sample from Soil Borings B-197 and B-199 was submitted for laboratory analysis of PCB homolog by U.S. EPA Method 680 in accordance with the Subsurface Work Plan. These samples were selected based on the highest detected PCB aroclor results.
- A total of 54 soil samples were collected and submitted to Environmental Chemistry Consulting Services, Inc. in Madison, Wisconsin, for analysis of PCB Aroclors by U.S. EPA Method 8082. A total of two soil samples were collected and submitted to Environmental Chemistry Consulting Services in Madison, Wisconsin, for analysis of PCB homolog by U.S. EPA Method 680.

Monitoring Well Installation and Sampling

The monitoring well location, adjacent to previous soil boring location B-152, was selected based on the December 17, 2014 meeting. The monitoring well location is presented on Figure 1.

A mini-hollow stem auger rig was used to advance the soil boring for collecting soil samples. Soil samples were collected using split-spoons from ground surface to the top of the water table. Companion sampling was completed by collecting two aliquots of soil from each sampling interval and placing each aliquot into a separate re-sealable plastic bag. One of the companion samples from each interval was used for field screening for the presence of total ionizable volatile organic compound vapors with a calibrated PID. The screening samples were warmed and the headspace PID reading of the soil was taken by inserting the probe end of the PID into the plastic bag. Following field screening activities, the screened samples were appropriately discarded; the unscreened companion samples were used for preparing samples for analytical testing.

An ARCADIS scientist was on Site to oversee the drilling activities and visually screen and describe the condition and properties of the soil. Soil descriptions and field screening PID results were recorded on Soil Boring Logs (WDNR Form 4400-122) and are included in Attachment B.

The soil boring was converted into a water table monitoring well. The monitoring well screen was installed at a depth of 27.7 to 37.7 ft bgs. The monitoring well consists of a single screen and was constructed and developed in accordance with NR 141 Wis. Adm. Code. A 10-foot, 0.010-inch, polyvinyl chloride screen and Schedule 40 polyvinyl chloride riser was used. The monitoring well was completed at the surface with a flush-mount well compartment set in concrete. The well construction form (WDNR Form 4400-113A) was completed and is included in Attachment C.

The goal of well development is to produce groundwater samples that are representative of the water quality in the target interval, and to minimize sediment, drill cuttings and drilling fluids in the samples. The monitoring well was developed by surging and pumping with a surge block. The well development form (WDNR Form 4400-113B) was completed and is included in Attachment C.

On March 13, 2015, one groundwater sample was collected and submitted to Environmental Chemistry Consulting Services in Madison, Wisconsin, for analysis of dissolved PCBs by U.S. EPA Method 8082 using low-flow sampling techniques. Field

parameters were recorded using a multi-parameter meter for pH, conductivity, dissolved oxygen, redox potential, and temperature.

Wipe Sampling

A 100- by 100-foot grid pattern was used for the manufacturing footprint of the MKC facility to facilitate wipe sampling activities. The wipe sample locations are presented on Figure 2.

On March 4, 2015, wipe samples were collected from various surfaces (wall, column, floor, machine-horizontal, and machine-vertical) throughout the manufacturing portion of the MKC facility. Sample locations within each pre-approved grid were determined in the field based on visual observations and accessibility.

Wall, column, and vertical machine wipe samples were collected from the approximate breathing/working-zone height of a worker. Samples were collected by taking an individual cotton gauze pad, placing it $\frac{3}{4}$ of the way into the 80/20 iso-octane/acetone solution, squeezing the excess solution off the gauze pad, placing the 10- by 10-centimeter template over the determined sample area, and wiping the sample area in a serpentine pattern both horizontally and vertically. The gauze pad was then folded and placed in a clean laboratory-supplied vial in accordance with the QAPP. A total of two duplicate samples were collected and analyzed in accordance with the Wipe Sampling QAPP. The wipe sampling log is provided in Attachment D. A total of 40 soil samples were collected and submitted to Environmental Chemistry Consulting Services, Inc. in Madison, Wisconsin, for analysis of PCB Aroclors by U.S. EPA Method 8082.

On April 2, 2015, wipe samples were collected from floor surfaces based on the March analytical results. Samples were collected using the methods described above. The wipe sampling log is provided in Attachment D. A total of six soil samples were collected and submitted to Environmental Chemistry Consulting Services, Inc. in Madison, Wisconsin, for analysis of PCB Aroclors by U.S. EPA Method 8082.

Indoor Air Sampling

Based on the results of the wipe sampling (presented below), indoor air sampling within the manufacturing building was initiated. A total of three indoor air locations were identified in the manufacturing building for sampling. The sample locations were collected within close proximity to the two wipe sample results above criteria

from March 4, 2015, and within the middle of the manufacturing building along the center aisle. The indoor air sample locations are presented on Figure 2.

On April 1, 2015, three indoor air samples were collected for analysis of PCB Aroclors by EPA Method TO-10A. The indoor air samples were collected over an eight hour timeframe with low-volume air samplers and polyurethane foam sorbent cartridges.

After collection, the indoor air samples were packaged, placed in a cooler with ice, and submitted to Pace Analytical Services, Inc. in Schenectady, New York for PCB Aroclor analysis by Method TO-10A.

Surveying

A Wisconsin-licensed surveyor located the horizontal location of each boring to Wisconsin state plane coordinates and vertical elevation. Ground elevations were surveyed to an accuracy of +/-1 foot.

Investigative-Derived Waste

Soil cuttings generated during the investigation were containerized in appropriate steel 55-gallon drums for waste profiling and disposal off Site. Non-hazardous development, purge, and decontamination water was collected and disposed with MKC facility wastewater.

Evaluation of Results and Recommendations

The following sections present a summary of the regulatory criteria, analytical results, and recommendations.

Regulatory Criteria

The WDNR Remediation and Redevelopment Program has prepared a spreadsheet with industrial direct contact residual contaminant levels (RCLs) for chemicals, calculated using the U.S. EPA Regional Screening Table web calculator. The industrial RCLs for PCBs are summarized in Table 1.

Title 40 Code of Federal Regulations §761.61 provides cleanup and disposal options for PCB remediation waste. Soil PCB analytical results were compared to the bulk remediation waste cleanup level for high occupancy cleanup level of less than or equal

to 1 milligram per kilogram (mg/kg) and a Toxic Substance Control Act (TSCA) total PCB concentration of greater than or equal to 50 mg/kg to determine soil disposal options. These criteria are summarized in Table 1.

The analytical results of the groundwater sample were compared to the Natural Resources 140.10 Wis. Adm. Code Preventative Action Limits and Enforcement Standards. These criteria are summarized in Table 2.

The analytical results of the wipe samples were compared to the U.S. EPA *Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy* dated June 23, 1987, revised and clarified April 18, 1991. This criteria is summarized in Table 3.

The analytical results of the indoor air samples were compared to the National Institute of Occupational Safety and Health Recommended Exposure Limit for PCBs. This criteria is summarized in Table 4.

Soil Analytical Results

A total of six soil borings were advanced and sampled beneath the building floor with 54 soil samples collected and submitted for laboratory analysis of PCB Aroclors by Method 8082 and two soil samples collected and submitted for laboratory analysis of PCB homolog by Method 680. A summary of the soil analytical results is presented in Table 1 and copies of the laboratory analytical reports are provided in Attachment E. The soil boring locations are presented on Figure 1.

Based on the analytical results, 43 of the 54 samples contained PCBs above the industrial direct contact RCLs for Arcolor 1242 or Aroclor 1248 of 0.744 mg/kg, 42 of the 54 samples contained PCBs above the U.S. EPA high occupancy cleanup level of 1 mg/kg, and 36 of the 54 samples contained PCBs above the TSCA disposal limit of 50 mg/kg. These locations are presented on Figure 3.

The objective of the supplemental activities was to document the concentrations of PCBs beneath the main Site building as requested by the U.S. EPA. The highest PCB concentrations are located adjacent to the historical concrete trench located in the middle of the facility, running north to south. Figure 4 shows a cross-section with total detected PCBs in soil beneath the building along the historical trench location from north to south.

Additionally, the Subsurface Work Plan contained a provision for additional PCB laboratory analysis of select soil samples by PCB homolog Method 680. The results of the homolog analysis were compared to the PCB laboratory analytical results obtained with Method 8082 for the same soil samples. In each case, the PCB homolog analytical results were lower than the PCB Aroclor results reported by Method 8082. Thus, utilizing the PCB results by Method 8082 provides a conservative approach to the recommendations provided below. A summary of the PCB homolog analytical data for the two soil samples is presented in Table 1.

Groundwater Analytical Results

One groundwater sample was collected and submitted for analysis of dissolved PCBs by U.S. EPA Method 8082 on March 13, 2015. The groundwater results were not detected above the laboratory detection limits. A summary of the groundwater analytical results is presented in Table 2 and the laboratory report is provided in Attachment E.

Wipe Analytical Results

Results of the March 4, 2015, wipe samples were below the cleanup level in all 40 samples, with the exception of floor sample MKC-WIPE01-FLOOR and floor sample MKC-WIPE03-FLOOR. A summary of the wipe analytical results is presented in Table 3 and the laboratory report is provided in Attachment E. Floor sample MKC-WIPE01-FLOOR is located in the die Storage #2 area (Grid 1) and floor sample MKC-WIPE03-FLOOR is located along the base of the secondary containment structure for the 55-gallon steel drums (Grid 3) as shown on Figure 5.

Results of the April 2, 2015, wipe samples were below the cleanup level in all six samples, with the exception of floor sample MKC-WIPE03-FLOOR2 and floor sample MKC-WIPE05-FLOOR2. A summary of the wipe analytical results is presented in Table 3 and the laboratory report is provided in Attachment E. Floor sample MKC-WIPE03-FLOOR2 is located in the cardboard storage area (Grid 3) and floor sample MKC-WIPE05-FLOOR2 is located in the aisle way near the electrical panel (Grid 5) as shown on Figure 5.

Indoor Air Analytical Results

Results of the April 1, 2015, indoor air samples were below the criteria in all three samples. A summary of the indoor air analytical results is presented in Table 4 and the laboratory report is provided in Attachment E.

Recommendations

As shown on Figures 3 and 4, soil and groundwater PCBs have been delineated beneath the building. In general, the highest concentrations of total PCBs in soil are present along the historical trench at varying depths from 0 to 2 ft bgs up to approximately 23.5 ft bgs. This soil is present beneath 6 to 12 inches of concrete so there is no complete exposure pathway for direct contact. Therefore, no further soil activities will be completed.

In accordance with the Site groundwater monitoring program, Monitoring Well MW-28 will be sampled for dissolved PCBs on a semi-annual basis.

Based on the analytical results of the indoor air sampling activities, no additional indoor air sampling is warranted.

As shown on Figure 5, PCBs have been delineated along the floor of the manufacturing building based on the wipe sample results. There were no exceedances on the columns, walls, or equipment that were sampled. The following actions are recommended for the floor exceedances within the MKC manufacturing building:

- Installation of PCB markers to inform personnel that there are PCBs present that require special handling and disposal in accordance with 40 CFR 761. Inspection of PCB markers on a monthly basis to verify markers are intact, in good condition, and that information is visible.
- Implementation of PCB awareness program for MKC employees and contractors. The training session includes an overview of PCBs, the regulatory considerations surrounding their use, and the nature and extent of PCB concentrations detected at the Site. The training session will also cover the personal protective equipment and waste management standard operating procedures for MKC. Training sessions will be held for new employees and annual refresher training will be provided.

In cooperation with the WDNR and U.S. EPA, MKC will also evaluate the potential implementation of the following:

- Double wash/double rinse/double paint of select floor areas as shown on Figure 5 and in accordance with 40 CFR 761.30(p) for continued use of the area.

Closing

If you have any questions regarding this letter, please contact us at (414) 276-7742.

Sincerely,

ARCADIS U.S., Inc.



Trenna Seilheimer
Project Scientist



Christopher D. Kubacki, PE
Senior Engineer



Jennine L. Trask, PE
Project Manager

Attachments:

- Table 1 – Summary of Interior Building Soil Analytical Results
- Table 2 – Summary of Interior Building Groundwater Analytical Results
- Table 3 – Summary of Interior Building Wipe Analytical Results
- Table 4 – Summary of Interior Building Indoor Air Analytical Results

- Figure 1 – Interior Soil Boring and Monitoring Well Locations
- Figure 2 – Interior Building Wipe and Indoor Air Sampling Locations
- Figure 3 – Soil Locations Above TSCA Disposal Limit
- Figure 4 – Interior Building Trench Cross Section with Soil Boring and Monitoring well Locations
- Figure 5 – Wipe Locations Above U.S. EPA Spill Cleanup Policy and Floor Remediation Layout

- Attachment A Submittal Certification
- Attachment B Soil Boring Logs and Abandonment Forms

Michael Schmoller

April 21, 2015



Attachment C Well Construction and Well Development Form

Attachment D Wipe Sampling Log

Attachment E Laboratory Reports

Electronic Copies:

David Crass – Michael Best

Tony Koblinski – Madison Kipp

Alina Satkoski – Madison Kipp

Kenneth Zolnierczyk – U.S. EPA

Page:

12/12

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring Number	Industrial	EPA High	TSCA	SB-196								
				Sample I.D.	Direct	Occupancy	Disposal	SB-196 (1-2)	SB-196 (5-6)	SB-196 (8-9)	SB-196 (9-10)	SB-196 (12-13)
Sample Date	Contact	Cleanup	Limits	3/3/2015	3/3/2015	3/3/2015	3/3/2015	3/3/2015	3/3/2015	3/3/2015	3/3/2015	3/3/2015
Sample Depth (ft bgs)	RCL	Level	(Solids)	1-2	5-6	8-9	9-10	12-13	16.3-17.3			
PCBs												
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Heptachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA			
Aroclor 1016	21.2	--	--	<0.79 D	<18 D	<39 D	<7.7 D	<7.9 D	<16 D			
Aroclor 1221	0.589	--	--	<0.44 D	<9.8 D	<22 D	<4.3 D	<4.4 D	<8.7 D			
Aroclor 1232	0.589	--	--	<0.30 D	<6.7 D	<15 D	<2.9 D	<3.0 D	<5.9 D			
Aroclor 1242	0.744	--	--	86 D	2,500 D	4,800 D	2,300 D	2,200 D	3,200 D			
Aroclor 1248	0.744	--	--	<0.56 D	<13 D	<28 D	<5.5 D	<5.7 D	<11 D			
Aroclor 1254	0.744	--	--	<0.47 D	<10 D	<23 D	<4.6 D	<4.7 D	<9.3 D			
Aroclor 1260	0.744	--	--	<0.26 D	<5.7 D	<13 D	<2.5 D	<2.6 D	<5.1 D			
Total Aroclor PCBs	--	1	50	86 D	2,500 D	4,800 D	2,300 D	2,200 D	3,200 D			

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL
100 = Result exceeds EPA High Occupancy Cleanup Level
100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

G:\Project\MadisonKipp\WI001368\2015\Tables\
Table 1_Summary Soil Analytical Results.xlsx

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-197					
				Direct	Occupancy	Disposal	SB-197 (2-3)	SB-197 (5-6)	SB-197 (6-7)
Sample ID	Contact	Cleanup	Limits	3/2/2015	3/2/2015	3/2/2015	3/2/2015	3/2/2015	3/4/2015
Sample Date			(Solids)						
Sample Depth (ft bgs)	RCL	Level		2-3	5-6	6-7	9-10	14-15	16.5-17.5
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<21	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	360	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	920	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	1100	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	190	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<43	NA
Heptachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<64	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<64	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<85	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	<110	NA
Aroclor 1016	21.2	--	--	<0.090 D	<4.2 D	<3.8 D	<3.8 D	<16 D	<3.1 D
Aroclor 1221	0.589	--	--	<0.050 D	<2.4 D	<2.1 D	<2.1 D	<8.6 D	<1.7 D
Aroclor 1232	0.589	--	--	<0.034 D	<1.6 D	<1.4 D	<1.4 D	<5.9 D	<1.2 D
Aroclor 1242	0.744	--	--	21 D	1,600 D	1,200 D	1,200 D	4,000 D	890 D
Aroclor 1248	0.744	--	--	<0.064 D	<3.0 D	<2.7 D	<2.7 D	<11 D	<2.2 D
Aroclor 1254	0.744	--	--	<0.053 D	<2.5 D	<2.3 D	<2.3 D	<9.3 D	<1.8 D
Aroclor 1260	0.744	--	--	<0.029 D	<1.4 D	<1.2 D	<1.2 D	<5.1 D	<1.0 D
Total Aroclor PCBs	--	1	50	21 D	1,600 D	1,200 D	1,200 D	4,000 D	890 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

- 100 = Result exceeds Industrial Direct Contact RCL
- 100 = Result exceeds EPA High Occupancy Cleanup Level
- 100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-198					
				SB-198 (1-2) 3/2/2015	DUP-1 3/2/2015	SB-198 (4-5) 3/2/2015	SB-198 (7-8) 3/2/2015	SB-198 (9-10) 3/2/2015	SB-198 (12-13) 3/3/2015
Sample ID	Direct Contact	Occupancy Cleanup	Disposal Limits (Solids)	1-2	1-2	4-5	7-8	9-10	12-13
Sample Date	Contact	Cleanup Level	(Solids)						
Sample Depth (ft bgs)	RCL								
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<8.8 D	<8.9 D	<4.5 D	<0.031 D	<0.077 D	<0.31 D
Aroclor 1221	0.589	--	--	<4.9 D	<4.9 D	<2.5 D	<0.017 D	<0.043 D	<0.17 D
Aroclor 1232	0.589	--	--	<3.3 D	<3.4 D	<1.7 D	<0.012 D	<0.029 D	<0.12 D
Aroclor 1242	0.744	--	--	1,900 D	2,300 D	910 D	3.6 D	13 D	63 D
Aroclor 1248	0.744	--	--	<6.3 D	<6.4 D	<3.2 D	<0.022 D	<0.055 D	<0.22 D
Aroclor 1254	0.744	--	--	<5.2 D	<5.3 D	<2.7 D	<0.018 D	<0.046 D	<0.18 D
Aroclor 1260	0.744	--	--	<2.9 D	<2.9 D	<1.5 D	<0.0099 D	<0.025 D	<0.10 D
Total Aroclor PCBs	--	1	50	1,900 D	2,300 D	910 D	3.6 D	13 D	63 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL

NA = Not analyzed

100 = Result exceeds EPA High Occupancy Cleanup Level

PCBs = Polychlorinated Biphenyls

100 = Result exceeds TSCA Disposal Limits (Solids)

RCL = Residual Contaminant Level

< = Constituent not detected above noted laboratory detection limit

TSCA = Toxic Substances Control Act

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-198 (continued)				SB-199
				Direct	Occupancy	Disposal	DUP-2 3/3/2015	SB-198 (16-17) 3/3/2015
Sample ID	Contact	Cleanup	Limits (Solids)	12-13	16-17	20.4-21.4	22-23	1.2-2.2
Sample Date	RCL	Level	(Solids)					
Sample Depth (ft bgs)								
PCBs								
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<0.78 D	<0.81 D	<0.80 D	<0.0084	<18 D
Aroclor 1221	0.589	--	--	<0.43 D	<0.45 D	<0.44 D	<0.0047	<10 D
Aroclor 1232	0.589	--	--	<0.30 D	<0.31 D	<0.30 D	<0.0032	<6.8 D
Aroclor 1242	0.744	--	--	150 D	220 D	220 D	0.052 J	4,500 D
Aroclor 1248	0.744	--	--	<0.56 D	<0.58 D	<0.57 D	<0.0060	<13 D
Aroclor 1254	0.744	--	--	<0.46 D	<0.48 D	<0.47 D	<0.0050	<11 D
Aroclor 1260	0.744	--	--	<0.25 D	<0.26 D	<0.26 D	<0.0027	<5.8 D
Total Aroclor PCBs	--	1	50	150 D	220 D	220 D	0.052 J	4,500 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL
100 = Result exceeds EPA High Occupancy Cleanup Level
100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-199 (continued)					
				Direct	Occupancy	Disposal	SB-199 (5-6)	SB-199 (6.3-7.3)	SB-199 (9.9-10.9)
Sample ID	Contact	Cleanup	Limits	3/5/2015	3/5/2015	3/5/2015	3/5/2015	3/5/2015	3/5/2015
Sample Date			(Solids)	5-6	6.3-7.3	9.9-10.9	12-13	16-17	17.7-18.7
Sample Depth (ft bgs)	RCL	Level							
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	<20	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	350	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	880	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	1200	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	210	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	<42	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	<62	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	<62	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	<83	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	<100	NA	NA	NA
Aroclor 1016	21.2	--	--	<8.9 D	<8.0 D	<16 D	<0.66 D	<1.6 D	<0.016 D
Aroclor 1221	0.589	--	--	<4.9 D	<4.4 D	<8.7 D	<0.36 D	<0.88 D	<0.0086 D
Aroclor 1232	0.589	--	--	<3.4 D	<3.0 D	<5.9 D	<0.25 D	<0.60 D	<0.0059 D
Aroclor 1242	0.744	--	--	1,500 D	1,500 D	4,600 D	120 D	410 D	3.5 D
Aroclor 1248	0.744	--	--	<6.4 D	<5.8 D	<11 D	<0.47 D	<1.1 D	<0.011 D
Aroclor 1254	0.744	--	--	<5.3 D	<4.8 D	<9.3 D	<0.39 D	<0.95 D	<0.0092 D
Aroclor 1260	0.744	--	--	<2.9 D	<2.6 D	<5.1 D	<0.21 D	<0.52 D	<0.0050 D
Total Aroclor PCBs	--	1	50	1,500 D	1,500 D	4,600 D	120 D	410 D	3.5 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL

NA = Not analyzed

100 = Result exceeds EPA High Occupancy Cleanup Level

PCBs = Polychlorinated Biphenyls

100 = Result exceeds TSCA Disposal Limits (Solids)

RCL = Residual Contaminant Level

< = Constituent not detected above noted laboratory detection limit

TSCA = Toxic Substances Control Act

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-200					
				Direct	Occupancy	Disposal	SB-200 (1-2)	SB-200 (5.2-6.2)	SB-200 (6.9-7.9)
Sample ID	Contact	Cleanup	Limits	3/5/2015	3/5/2015	3/5/2015	3/5/2015	3/5/2015	3/5/2015
Sample Date			(Solids)				1-2	5.2-6.2	6.9-7.9
Sample Depth (ft bgs)	RCL	Level							
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<1.8 D	<1.7 D	<3.1 D	<0.30 D	<7.7 D	<8.3 D
Aroclor 1221	0.589	--	--	<0.99 D	<0.93 D	<1.7 D	<0.17 D	<4.3 D	<4.6 D
Aroclor 1232	0.589	--	--	<0.67 D	<0.64 D	<1.2 D	<0.11 D	<2.9 D	<3.1 D
Aroclor 1242	0.744	--	--	<1.1 D	<1.0 D	910 D	97 D	1,500 D	1,700 D
Aroclor 1248	0.744	--	--	210 D	200 D	<2.2 D	<0.22 D	<5.5 D	<5.9 D
Aroclor 1254	0.744	--	--	<1.1 D	<1.0 D	<1.8 D	<0.18 D	<4.6 D	<4.9 D
Aroclor 1260	0.744	--	--	<0.58 D	<0.55 D	<1.0 D	<0.098 D	<2.5 D	<2.7 D
Total Aroclor PCBs	--	1	50	210 D	200 D	910 D	97 D	1,500 D	1,700 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL

NA = Not analyzed

100 = Result exceeds EPA High Occupancy Cleanup Level

PCBs = Polychlorinated Biphenyls

100 = Result exceeds TSCA Disposal Limits (Solids)

RCL = Residual Contaminant Level

< = Constituent not detected above noted laboratory detection limit

TSCA = Toxic Substances Control Act

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-200 (continued)			SB-201	
				Direct	Occupancy	Disposal	SB-201 (0.6-1.6)	SB-201 (5-6)
Sample ID	Contact	Cleanup	Limits	3/5/2015	3/5/2015	3/5/2015	3/3/2015	3/3/2015
Sample Date			(Solids)					
Sample Depth (ft bgs)	RCL	Level		18-19	18-19	22.5-23.5	0.6-1.6	5-6
PCBs								
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<0.0078	<0.0078	<1.6 D	<0.0091	<0.35 D
Aroclor 1221	0.589	--	--	<0.0043	<0.0043	<0.87 D	<0.0051	<0.19 D
Aroclor 1232	0.589	--	--	<0.0029	<0.0030	<0.59 D	<0.0035	<0.13 D
Aroclor 1242	0.744	--	--	1	1.7	360 D	1.2	68 D
Aroclor 1248	0.744	--	--	<0.0056	<0.0056	<1.1 D	<0.0065	<0.25 D
Aroclor 1254	0.744	--	--	<0.0046	<0.0047	<0.93 D	<0.0054	<0.21 D
Aroclor 1260	0.744	--	--	<0.0025	<0.0025	<0.51 D	<0.0030	<0.11 D
Total Aroclor PCBs	--	1	50	1	1.7	360 D	1.2	68 D

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

- 100** = Result exceeds Industrial Direct Contact RCL
- 100** = Result exceeds EPA High Occupancy Cleanup Level
- 100** = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

G:\Aproject\MadisonKipp\WI001368\2015\tables\
Table 1_Summary Soil Analytical Results.xlsx

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-201 (continued)				SB-202	
				Direct	Occupancy	Disposal	SB-201 (6.8-7.8) 3/3/2015	SB-201 (9-10) 3/3/2015	SB-201 (12-13) 3/4/2015
Sample ID	Contact	Cleanup	Limits (Solids)	6.8-7.8	9-10	12-13	16-17	1-2	4-5
Sample Date	RCL	Level							
Sample Depth (ft bgs)									
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Heptachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<3.2 D	<3.0 D	<7.7 D	<8.3 D	<0.0088	<0.0093
Aroclor 1221	0.589	--	--	<1.8 D	<1.7 D	<4.3 D	<4.6 D	<0.0049	<0.0052
Aroclor 1232	0.589	--	--	<1.2 D	<1.1 D	<2.9 D	<3.1 D	<0.0033	<0.0035
Aroclor 1242	0.744	--	--	720 D	890 D	1,300 D	2,900 D	0.052 J	0.68
Aroclor 1248	0.744	--	--	<2.3 D	<2.2 D	<5.5 D	<5.9 D	<0.0063	<0.0067
Aroclor 1254	0.744	--	--	<1.9 D	<1.8 D	<4.6 D	<4.9 D	<0.0052	<0.0055
Aroclor 1260	0.744	--	--	<1.0 D	<0.98 D	<2.5 D	<2.7 D	<0.0029	<0.0030
Total Aroclor PCBs	--	1	50	720 D	890 D	1,300 D	2,900 D	0.052 J	0.68

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL
100 = Result exceeds EPA High Occupancy Cleanup Level
100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

G:\Aproject\MadisonKipp\WI001368\2015\tables\
Table 1_Summary Soil Analytical Results.xlsx

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-202 (continued)					
				Direct	Occupancy	Disposal	SB-202 (8-9)	SB-202 (10-10.6)	SB-202 (12-12.9)
Sample ID	Contact	Cleanup	Limits	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015
Sample Date			(Solids)	8-9	10-10.6	12-12.9	16-17	20-21	22-23
Sample Depth (ft bgs)	RCL	Level							
PCBs									
Monochlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA	NA	NA	NA	NA
Aroclor 1016	21.2	--	--	<0.0082	<0.0079	<0.0078	<0.0078	<0.0079	<0.0082
Aroclor 1221	0.589	--	--	<0.0045	<0.0044	<0.0043	<0.0043	<0.0044	<0.0045
Aroclor 1232	0.589	--	--	<0.0031	<0.0030	<0.0030	<0.0030	<0.0030	<0.0031
Aroclor 1242	0.744	--	--	0.011 J	0.025 J	<0.0046	<0.0047	<0.0047	<0.0049
Aroclor 1248	0.744	--	--	<0.0059	<0.0056	<0.0056	<0.0056	<0.0057	<0.0058
Aroclor 1254	0.744	--	--	<0.0049	<0.0047	<0.0046	<0.0047	<0.0047	<0.0049
Aroclor 1260	0.744	--	--	<0.0027	<0.0026	<0.0025	<0.0025	<0.0026	<0.0026
Total Aroclor PCBs	--	1	50	0.011 J	0.025 J	<0.0078	<0.0078	<0.0079	<0.0082

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL
100 = Result exceeds EPA High Occupancy Cleanup Level
100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

G:\Project\MadisonKipp\WI001368\2015\tables\
Table 1_Summary Soil Analytical Results.xlsx

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 1
Summary of Interior Building Soil Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring #	Industrial	EPA High	TSCA	SB-202 (continued)	
				SB-202 (24.4-25.4)	SB-202 (28-28.7)
Sample ID	Direct	Occupancy	Disposal	3/4/2015	3/4/2015
Sample Date	Contact	Cleanup	Limits		
Sample Depth (ft bgs)	RCL	Level	(Solids)	24.4-25.4	28-28.7
PCBs					
Monochlorobiphenyls, total	--	--	--	NA	NA
Dichlorobiphenyls, total	--	--	--	NA	NA
Trichlorobiphenyls, total	--	--	--	NA	NA
Tetrachlorobiphenyls, total	--	--	--	NA	NA
Pentachlorobiphenyls, total	--	--	--	NA	NA
Hexachlorobiphenyls, total	--	--	--	NA	NA
Heptahlorobiphenyls, total	--	--	--	NA	NA
Octachlorobiphenyls, total	--	--	--	NA	NA
Nonachlorobiphenyls, total	--	--	--	NA	NA
Decachlorobiphenyls, total	--	--	--	NA	NA
Aroclor 1016	21.2	--	--	<0.0080	<0.0080
Aroclor 1221	0.589	--	--	<0.0044	<0.0044
Aroclor 1232	0.589	--	--	<0.0030	<0.0030
Aroclor 1242	0.744	--	--	<0.0047	<0.0047
Aroclor 1248	0.744	--	--	<0.0057	<0.0057
Aroclor 1254	0.744	--	--	<0.0047	<0.0047
Aroclor 1260	0.744	--	--	<0.0026	<0.0026
Total Aroclor PCBs	--	1	50	<0.0080	<0.0080

General Note:

Constituent concentrations are reported as milligram per kilogram (mg/kg).

Acronyms and Abbreviations:

100 = Result exceeds Industrial Direct Contact RCL
100 = Result exceeds EPA High Occupancy Cleanup Level
100 = Result exceeds TSCA Disposal Limits (Solids)

< = Constituent not detected above noted laboratory detection limit
-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

J = Estimated result

4/16/2015

G:\Aproject\MadisonKipp\WI001368\2015\tables\
Table 1_Summary Soil Analytical Results.xlsx

NA = Not analyzed

PCBs = Polychlorinated Biphenyls

RCL = Residual Contaminant Level

TSCA = Toxic Substances Control Act

Table 2
Summary of Interior Building Groundwater Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Boring Number	NR 140 Preventive	NR 140 Enforcement	SB-202/MW-28
Sample I.D.	Action Limit	Standard	MW-28
Sample Date			3/13/2015
Sample Depth (ft bls)			27.7-37.7
Dissolved PCBs			
Aroclor 1016	0.003	0.03	<0.068
Aroclor 1221	0.003	0.03	<0.2
Aroclor 1232	0.003	0.03	<0.2
Aroclor 1242	0.003	0.03	<0.2
Aroclor 1248	0.003	0.03	<0.2
Aroclor 1254	0.003	0.03	<0.2
Aroclor 1260	0.003	0.03	<0.071

General Note:

Constituent concentrations are reported as milligram per liter (ug/L).

Acronyms and Abbreviations:

100 = Concentration exceeds the NR 140 Wis. adm. code Preventive Action Limit

100 = Concentration exceeds the NR 140 Wis. adm. code Enforcement Standard

< = Constituent not detected above noted laboratory detection limit

bls = below land surface

ft = feet

PCBs = Polychlorinated Biphenyls

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid I.D. Sample I.D.	EPA PCB Spill	Grid 1						Grid 2	
		MKC-WIPE01-COLUMN	MKC-WIPE01-FLOOR	MKC-WIPE01-FLOOR2	MKC-WIPE01-WALL	MKC-WIPE01-M1HORZ	MKC-WIPE01-M1VERT	MKC-WIPE02-COLUMN	MKC-WIPE02-FLOOR
Sample Date	Cleanup Policy	3/4/2015	3/4/2015	4/2/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015
PCBs									
Aroclor 1016	--	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1221	--	<0.3	<0.3	<1	<0.3	<0.3	<0.3	<0.3	<0.3
Aroclor 1232	--	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1242	--	0.81	<0.15	<0.5	<0.15	<0.15	<0.15	0.65	<0.15
Aroclor 1248	--	<0.15	11	1.2	<0.15	1.3	<0.15	<0.15	6.3
Aroclor 1254	--	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1260	--	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15	<0.15	<0.15
Total Aroclor PCBs	10	0.81	11	1.2	ND	1.3	ND	0.65	6.3

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID Sample Date	EPA PCB Spill Cleanup Policy	Grid 2 (continued)			Grid 3			
		MKC-WIPE02-FLOOR2	MKC-WIPE02-WALL	MKC-WIPE03-COLUMN	MKC-WIPE03-FLOOR	MKC-WIPE03-FLOOR2	MKC-WIPE03-FLOOR3	MKC-WIPE03-FLOOR4
		4/2/2015	3/4/2015	3/4/2015	3/4/2015	4/2/2015	4/2/2015	4/2/2015
PCBs								
Aroclor 1016	--	<0.5	<0.15	<0.15	<1.5	<0.5	<0.5	<0.5
Aroclor 1221	--	<1	<0.3	<0.3	<3	<1	<1	<1
Aroclor 1232	--	<0.5	<0.15	<0.15	<1.5	<0.5	<0.5	<0.5
Aroclor 1242	--	<0.5	0.76	0.35	<1.5	<0.5	<0.5	<0.5
Aroclor 1248	--	3	<0.15	<0.15	120 D	13	6.9	6
Aroclor 1254	--	<0.5	<0.15	<0.15	<1.5	<0.5	<0.5	<0.5
Aroclor 1260	--	<0.5	<0.15	<0.15	<1.5	<0.5	<0.5	<0.5
Total Aroclor PCBs	10	3	0.76	0.35	120 D	13	6.9	6

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID	EPA PCB Spill Cleanup Policy	Grid 3 (continued)						Grid 4	
		MKC-WIPE03- WALL	MKC-WIPE03- M2HORZ	MKC-WIPE03- M2VERT	MKC-WIPE03- DUP	MKC-WIPE03- M3HORZ	MKC-WIPE03- M3VERT	MKC-WIPE04- COLUMN	MKC-WIPE04- FLOOR
Sample Date		3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015
PCBs									
Aroclor 1016	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1221	--	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3
Aroclor 1232	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1242	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1248	--	<0.15	<0.15	<0.15	<0.15	3.9	<0.15	<0.15	7.8
Aroclor 1254	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1260	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Total Aroclor PCBs	10	ND	ND	ND	ND	3.9	ND	ND	7.8

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID	EPA PCB Spill	Grid 4 (continued)		Grid 5				Grid 6	
		MKC-WIPE04- DUP	MKC-WIPE04- WALL	MKC-WIPE05- COLUMN	MKC-WIPE05- FLOOR	MKC-WIPE05- FLOOR2	MKC-WIPE05- WALL	MKC-WIPE06- COLUMN	MKC-WIPE06- FLOOR
Sample Date	Cleanup Policy	3/4/2015	3/4/2015	3/4/2015	3/4/2015	4/2/2015	3/4/2015	3/4/2015	3/4/2015
PCBs									
Aroclor 1016	--	<0.15	<0.15	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15
Aroclor 1221	--	<0.3	<0.3	<0.3	<0.3	<1	<0.3	<0.3	<0.3
Aroclor 1232	--	<0.15	<0.15	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15
Aroclor 1242	--	<0.15	<0.15	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15
Aroclor 1248	--	4.4	<0.15	<0.15	3.7 HC	14	<0.15	<0.15	3.7 HC
Aroclor 1254	--	<0.15	<0.15	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15
Aroclor 1260	--	<0.15	<0.15	<0.15	<0.15	<0.5	<0.15	<0.15	<0.15
Total Aroclor PCBs	10	4.4	ND	ND	3.7	14	ND	ND	3.7

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID	EPA PCB Spill Cleanup Policy	Grid 6 (continued)			Grid 7			Grid 8	
		MKC-WIPE06- WALL	MKC-WIPE06- M21HORZ	MKC-WIPE06- M21VERT	MKC-WIPE07- COLUMN	MKC-WIPE07- FLOOR	MKC-WIPE07- WALL	MKC-WIPE08- COLUMN	MKC-WIPE08- FLOOR
Sample Date		3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015
PCBs									
Aroclor 1016	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1221	--	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3
Aroclor 1232	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1242	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1248	--	<0.15	1.5 HC	<0.15	0.96	4.2 HC	<0.15	<0.15	4.8
Aroclor 1254	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1260	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Total Aroclor PCBs	10	ND	1.5	ND	0.96	4.2	ND	ND	4.8

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 3
Summary of Interior Building Wipe Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID	EPA PCB Spill	Grid 8 (continued)		Grid 9			Grid 10		
		MKC-WIPE08- WALL	MKC-WIPE09- COLUMN	MKC-WIPE09- FLOOR	MKC-WIPE09- WALL	MKC-WIPE10- COLUMN	MKC-WIPE10- FLOOR	MKC-WIPE10- WALL	
Sample Date	Cleanup Policy	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	3/4/2015	
PCBs									
Aroclor 1016	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1221	--	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3
Aroclor 1232	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1242	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1248	--	<0.15	<0.15	3.9 HC	0.33	<0.15	2.4	<0.15	
Aroclor 1254	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Aroclor 1260	--	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15	<0.15
Total Aroclor PCBs	10	ND	ND	3.9	0.33	ND	2.4	ND	

General Note:

Only detected constituents are noted. Constituent concentrations are reported as microgram per wipe ($\mu\text{g}/\text{wipe}$).

Acronyms and Abbreviations:

100 = Result exceeds U.S. EPA's Wipe Sampling and Double Wash/Rinse Cleanup as recommended by the U.S. EPA PCB Spill Cleanup Policy dated June 23, 1987, revised and clarified April 18, 1991.

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

D = Data reported from a dilution

EPA = United States Environmental Protection Agency

HC = Result may be biased high due to high calibration verification

ND = Detected total PCBs were reported less than the laboratory detection limit

Table 4
Summary of Interior Building Indoor Air Analytical Results

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation
Madison, Wisconsin

Grid ID Sample ID Sample Date	NIOSH REL TWA	Grid 3	Grid 1	Grid 7
		MKC-AIR01	MKC-AIR02	MKC-AIR03
		4/1/2015	4/1/2015	4/1/2015
PCBs				
Aroclor 1016	--	<0.0417	<0.0417	<0.0417
Aroclor 1221	--	<0.0417	<0.0417	<0.0417
Aroclor 1232	--	<0.0417	<0.0417	<0.0417
Aroclor 1242	--	0.0553	0.0525	0.0841
Aroclor 1248	--	<0.0417	<0.0417	<0.0417
Aroclor 1254	--	<0.0417	<0.0417	<0.0417
Aroclor 1260	--	<0.0417	<0.0417	<0.0417
Total Aroclor PCBs	1	0.0553	0.0525	0.0841

General Note:

Constituent concentrations are reported as microgram per cubic meter ($\mu\text{g}/\text{m}^3$).

Acronyms and Abbreviations:

< = Constituent not detected above noted laboratory detection limit

-- = Criteria not established

NIOSH = National Institute for Occupational Safety and Health

REL = Recommended Exposure Limit

TWA = Time Weighted Average



CITY: MIKE DIV/GROUP: IM DB: GM LD: CK MADISON-KIPP
Z:\GIS\PROJECTS\ENV\MadisonKipp\ArcMap\2015-03\Interior_MW\Soils_Borings_20150311.mxd

LEGEND

- EXISTING SOIL BORING
- PLANT LAYOUT
- MONITORING WELL
- PARCELS
- BUILDING FOOTPRINTS

0 80 160
Feet


MADISON-KIPP CORPORATION
201 WAUBESA STREET
MADISON, WISCONSIN

SUPPLEMENTAL INTERIOR BUILDING SUMMARY

INTERIOR SOIL BORING AND MONITORING WELL LOCATIONS

ARCADIS

FIGURE
1





CITY: MKE DIV/GROUP: IM DB: GM LD: CK MADISON-KIPP

LEGEND

- TOTAL DETECTED PCB CONCENTRATION REPORTED ABOVE TSCA DISPOSAL LIMIT OF 50 PPM
 - TOTAL DETECTED PCB CONCENTRATION REPORTED BELOW TSCA DISPOSAL LIMIT OF 50 PPM
 - MONITORING WELL

A — A' CROSS SECTION

A horizontal number line representing distance in feet. The line starts at 0 and ends at 160, with a tick mark at 80. Below the line, the word "Feet" is written.

— PLANT LAYO

PARCELS

BUILDING FOOTPRINTS

PCB - POLYCHLORINATED BIPHENYL

PPM - PARTS PER MILLION


TSCA - TOXIC SUBSTANCE CONTROL ACT

MADISON-KIPP CORPORATION
201 WAUBESA STREET
MADISON, WISCONSIN

SOIL LOCATIONS ABOVE TSCA DISPOSAL LIMIT



FIGURE 3



Total Polychlorinated Biphenyl Isoconcentration Contour (mg/kg)


>0.744 to 1
1 to 49
50 to 499
500 to 4,999
5,000 to 9,999
10,000 to 20,000

LEGEND

- Well Screen
- Water Table Elevation for MW-22S in October 2014
- (27) Total Polychlorinated Biphenyl Concentration in mg/kg
- Geologic Contact

Concrete and soil removal along the center aisle within the building (June/July 2014). Area replaced with clean, imported backfill and finished with new concrete.

mg/kg milligram per kilogram




MADISON-KIPP CORPORATION
201 WAUBESA STREET
MADISON, WISCONSIN

**INTERIOR BUILDING TRENCH
CROSS SECTION WITH SOIL BORING AND
MONITORING WELL LOCATIONS**

 ARCADIS

FIGURE
4



CITY: MIKE DIV/GROUP: IM DB: GM LD: CK MADISON-KIPP Z:\GIS\PROJECTS_ENV\MadisonKipp\ArcMap\2015-04\Interior_Wipe_Locs_Above_20150416.mxd

Atwood Ave

Elmside Blvd

0 35 70
Feet

LEGEND

- TOTAL DETECTED PCB CONCENTRATION REPORTED ABOVE US EPA PCB SPILL CLEANUP POLICY OF 10 µg/WIPE
 - TOTAL DETECTED PCB CONCENTRATION REPORTED BELOW US EPA PCB SPILL CLEANUP POLICY OF 10 µg/WIPE
 - APPROXIMATE LOCATION OF FLOOR CONCENTRATIONS ABOVE CRITERIA
 - APPROXIMATE LOCATION OF FLOOR CONCENTRATIONS ABOVE CRITERIA
- µg/WIPE - MICROGRAM PER WIPE
[120] CONCENTRATION IN µg/WIPE

- PLANT LAYOUT
BUILDING FOOTPRINTS
PARCELS
100' GRID
1 GRID SQUARE ID

MADISON-KIPP CORPORATION
201 WAUBESA STREET
MADISON, WISCONSIN

APPROXIMATE LOCATION OF FLOOR CONCENTRATIONS ABOVE CRITERIA



FIGURE
5

ARCADIS

Attachment A

Submittal Certification

Submittal Certification

This attachment was prepared to satisfy the requirements of Wisconsin Administrative Code Chapter NR 712.09 and is applicable to the following document.

Building Interior Polychlorinated Biphenyl Investigation Summary
Madison-Kipp Corporation
201 Waubesa Street
Madison, Wisconsin

I, Jennine L. Trask, hereby certify that I am a registered professional engineer in the State of Wisconsin, registered in accordance with the requirements of ch. A-E 4, Wis. Adm. Code; that this document has been prepared in accordance with the Rules of Professional Conduct in ch. A-E 8, Wis. Adm. Code; and that, to the best of my knowledge, all information contained in this document is correct and the document was prepared in compliance with all applicable requirements in chs. NR 700 to 726, Wis. Adm. Code.

J. Nash CPM #34959
Signature, title and P.E. number



I, Trenna Seilheimer, hereby certify that I am a scientist as that term is defined in s. NR 712.03 (3), Wis. Adm. Code, and that, to the best of my knowledge, all of the information contained in this document is correct and the document was prepared in compliance with all applicable requirements in chs. NR 700 to 726, Wis. Adm. Code.

T.S. project scientist
Signature and title

4/21/15
Date

ARCADIS

Attachment B

**Soil Boring Logs and
Abandonment Forms**

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp				License/Permit/Monitoring Number				Boring Number B-196						
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Jim/Keith Last Name Firm Giles Engineering				Date Drilling Started 03/03/15		Date Drilling Completed 03/03/15		Drilling Method Direct Push						
WI Unique Well No.		DNR Well ID No.	Well Name	Final Static Water Level Feet		Surface Elevation Feet MSL		Borehole Diameter 3 inches						
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399898.08 N, 2144105.77 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat _____				Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W										
SW 1/4 of _____ 1/4 of Section 5 , T 7 NR 10 E <input checked="" type="checkbox"/> W <input type="checkbox"/> Long _____														
Facility ID 113125320		County Dane	County Code 13	Civil Town/City or Village Madison										
Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit		USCS	Graphic Log	Well Diagram	Soil Properties					ROD/ Comments
Number and type	Length All. & Recovered (in)								PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
1	27.6	0-4' 0.0-0.8' Concrete. 0.8-2.1' Fill: Sand and gravel, little clay, dark yellowish brown, loose, slightly moist. 2.1-2.2': Fill: Sand and gravel, little clay, dark brownish gray, loose, slightly moist.	1-2 1.6											
2	31.2	4-8' 4.0-6.3' Clay: Trace to some silt, increasing with depth, becomes silty at 6.0', medium stiff to soft, moderate to low plasticity, dark gray, slightly moist. 6.3-6.6' Sand: Trace clay, very fine to fine, poorly sorted, loose, dark yellowish brown, slightly moist.	4-6 6.9											
3	26.4	8-12'/ Sand: Trace to little rock fragments, trace gravel, loose to medium dense, poorly sorted, dark yellowish brown slightly moist, odor.	8-9 23.8											
			9-10 33.8											

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)							Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	22.8		12	12-16'/ 12.0-13.9' Sand: Trace to little rock fragments, little gravel, loose to medium dense, poorly sorted, dark yellowish brown slightly moist, odor.				12-14 14.6				
5	18		16	16-18.6'/ 16.0-17.3' Silty Sand: Medium dense, very fine, poorly sorted, trace to little rock fragments, dark brownish gray, slightly moist. 17.3-17.5' Large rock fragments. 18.5' Refusal.				16-17.5 18.7				
			18									
			20									
			22									
			24									
			26									
			28									

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp			License/Permit/Monitoring Number		Boring Number B-197
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Jim/Keith Last Name Firm Giles Engineering			Date Drilling Started 03/02/15	Date Drilling Completed 03/04/15	Drilling Method Direct Push
WI Unique Well No.	DNR Well ID No.	Well Name	Final Static Water Level Feet	Surface Elevation Feet MSL	Borehole Diameter 3 inches
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399837.08 N, 2144104.50 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat <input type="checkbox"/> N <input type="checkbox"/> E			Local Grid Location Long <input type="checkbox"/> S <input type="checkbox"/> W <input type="checkbox"/> Feet <input type="checkbox"/> S <input type="checkbox"/> W <input type="checkbox"/> Feet <input type="checkbox"/> W		
SW 1/4 of _____	1/4 of Section 5 , T 7 , R 10	County Code 13	Civil Town/City or Village Madison		
Facility ID 113125320	County Dane	County Code 13			

Number and Type	Length All. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	P/D/FID	Soil Properties					P 200	ROD/Comments
									Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit			
1	34.8		0	0-4'/ 0.0-0.8' Concrete. 0.8-1.5' Fill: Gravel: Little clay, trace sand, loose, poorly sorted, coarse, light yellowish brown, slightly moist. 1.5-2.9' Clay: Trace to little silt, low plasticity, medium stiff to stiff, dark gray, slightly moist.				0.8-1.5 0.6							
2	40.8		4	4-8'/ 4.0-6.0' Clay: Trace to little silt, low plasticity, medium stiff to stiff, dark gray, slightly moist. 6.0-7.4' Sand: Trace gravel, very fine to fine, moderately sorted, loose, yellowish brown, dry.				4-6 5.5							
3	34.8		8	8-12'/ 8.0-10.9' Sand: Trace gravel, very fine to fine, moderately sorted, loose, yellowish brown, dry.				6-7.4 45.6							
			10					8-10 45.5							
								0-10.9 40.5							

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	P/D/FD	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	40.8		12	12-16' / 12.0-14.0' Sand: Little gravel, trace rock fragments, very fine to fine, moderately sorted, loose, yellowish brown, dry. 14.0-15.4' Sand: Little gravel, trace rock fragments, little to some clay, slightly moist, very fine to fine, moderately sorted, loose, yellowish brown, dry. Refusal at 16.5'; offset approximately 1" north drilling resumes at 14:50 3/3/15 Refusal at 15.5'; 3rd attempt refusal at 8' 3/4/15 Able to extend the first offset to 17.5 before refusal 3/4/15				12-14 40.4					
5	18		16	16-17.5' / 16.0-17.5' Sand: Little gravel, trace rock fragments, trace silt, very fine to fine, poorly sorted, loose, light reddish brown, dry. Refusal at 17.5'				14-15.4 44.3					
			18						16-17.5 58.6				
			20										
			22										
			24										
			26										
			28										

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp	License/Permit/Monitoring Number	Boring Number B-198
----------------------------------------------	----------------------------------	-------------------------------

Boring Drilled By: Name of crew chief (first, last) and Firm First Name <u>Jim/Keith</u> Last Name Firm <u>Giles Engineering</u>			Date Drilling Started <u>03/02/15</u>	Date Drilling Completed <u>03/03/15</u>	Drilling Method Direct Push
WI Unique Well No.	DNR Well ID No.	Well Name	Final Static Water Level Feet	Surface Elevation Feet MSL	Borehole Diameter <u>3</u> inches
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/>	State Plane <u>399793.43</u> N, <u>2144097.02</u> E	S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat _____	Long _____	Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> S Feet <input type="checkbox"/> E <input type="checkbox"/> W	
SW 1/4 of _____ 1/4 of Section <u>5</u> , T <u>7</u> NR <u>10</u> <input checked="" type="checkbox"/> E <input type="checkbox"/> W					
Facility ID <u>113125320</u>	County <u>Dane</u>	County Code <u>13</u>	Civil Town/City or Village <u>Madison</u>		

Number and Type	Length All. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/Comments
									Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	P 200	
1	48		0	0-4'/ 0.0-0.6' Concrete. 0.6-4.0' Silty Clay: Grading into clay with some silt (at 2.6'), silt decreases with depth medium stiff, low to moderate plasticity with depth, light brownish gray grades to reddish brown at 2.6' slightly moist.				0.6-2 2.5						
2	45.6		4	4-8'/ 4.0-7.0' Clay: Little to some silt, medium stiff, low to no plasticity, grayish brown, slightly moist to dry with depth. 7.0-7.8' Sand; Trace to little gravel, very fine to fine, poorly sorted, loose, little yellowish brown, dry.				2-4 0.8						
3	36		8	8-12'/ 8.0-11.0' Sand; Trace to little gravel, very fine to fine, poorly sorted, loose, little yellowish brown, dry, becomes slightly moist to moist at 10.4'. Refusal at 13.5				4-7 1.3						
			10					7-7.8 0.9						
								8-10 0.6						
								10-11 0.2						

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	$\phi D/D$	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	43.2		12	12-16'/ 12.0-15.0' Sand: Little to some gravel and rock fragments, loose, very fine to fine, poorly sorted, light yellowish brown, dry. 15.0-15.6' Clayey, Sand: Little large rock fragments, dense, very fine to fine, poorly sorted, dark yellowish brown, slightly moist.				12-14 6.4					
5	33.6		14					14-15 1.9					
5	33.6		16	16-20'/ 16.0-18.6' Sand: Little to some rock fragments, loose to medium dense, very fine to fine poorly sorted, rock fragments increase with depth light yellowish brown to yellowish brown, dry to slightly moist. 18.6-18.8' Rock Fragments.				15-15.6 1.2					
6	36		18					16-18 2.8					
6	36		20	20-23'/ 20.0-21.4' Rock Fragments. 21.4-23.0' Clayey Sand: Clay content increasing with depth, little large rock fragments, increasing with depth, very fine to fine, poorly sorted, medium dense to dense, dark yellowish brown, moist. Refusal at 23				18-18.8 1.1					
			22					20-21 5.2					
			24					21-22 1.6					
			26					22-23 1.2					
			28										

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp				License/Permit/Monitoring Number				Boring Number B-199							
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Jim/Keith Last Name Firm Giles Engineering				Date Drilling Started 03/03/15		Date Drilling Completed 03/03/15		Drilling Method Direct Push							
WI Unique Well No.		DNR Well ID No.	Well Name	Final Static Water Level Feet		Surface Elevation Feet MSL		Borehole Diameter 3 inches							
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399745.11 N, 2144103.56 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat _____ SW 1/4 of _____ 1/4 of Section 5 , T 7 (N.R. 10 <input checked="" type="checkbox"/> E <input type="checkbox"/> W Long _____				Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W											
Facility ID 113125320		County Dane	County Code 13	Civil Town/City or Village Madison											
Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit				USCS	Graphic Log	Well Diagram	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)										PID/FID	Compressive Strength	Moisture Content	Liquid Limit	
1	48		0	0-4'/ 0.0-0.7' Concrete. 0.7-1.0' Void 1.0-1.2' Concrete: Refusal, struck exiting subfloor. 1.2-4.0' Silty Clay: Silt content decreasing with depth, soft to medium stiff, low plasticity, dark gray grading to dark brown.							1.2-2 17.2				
2	39.6		4	4-8'/ 4.0-5.6' Silty Clay: Silt content decreasing with depth, soft to medium stiff, low plasticity, dark gray grading to dark brown, stained gray 5.0-5.6, strong odor. 5.6-6.8' Clayey Sand: Trace fine gravel, loose to medium dense, poorly sorted, dark brown, stained dark gray 5.6-6.6'. 6.8-7.3' Sand: Trace clay, trace rock fragments, very fine to fine, poorly sorted, loose, light yellowish brown, dry.							4-6 30.5				
3	34.8		8	8-12'/ 8.0-10.9' Sand: Little rock fragments, trace clay, loose to medium dense, density increases with depth, very fine to fine, poorly sorted, little yellowish to light reddish brown, dark brown 8.3-8.7, dry to slightly moist.							8-10 27.6				
			10								10-10.9 28.4				

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Number and Type	Length All. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties					RQD/ Comments
								RID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	33.6		12	12-16'/ 12.0-14.8' Sand: Little large rock fragments throughout trace to little silt, very fine to fine, loose, poorly sorted, light reddish brown, slightly moist.				12-14 27.8					
5	32.4		14					14-14.8 27.8					
			16	16-19'/ 16.0-18.7' Sand: Little large rock fragments throughout trace to little silt, very fine to fine, loose, poorly sorted, light reddish brown, slightly moist.				16-18 30.6					
			18					18-18.7 26.2					
			20										
			22										
			24										
			26										
			28										

Route to: Watershed/Wastewater Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp				License/Permit/Monitoring Number				Boring Number B-200					
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Chip/Joel Last Name Firm Giles Engineering				Date Drilling Started 03/03/15		Date Drilling Completed 03/05/15		Drilling Method Direct Push					
WI Unique Well No.		DNR Well ID No.	Well Name	Final Static Water Level ____ Feet		Surface Elevation ____ Feet MSL		Borehole Diameter 3 inches					
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399724.07 N, 2144102.19 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat _____		Lat _____		Long _____		Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> S <input type="checkbox"/> E <input type="checkbox"/> W							
SW 1/4 of _____ 1/4 of Section 5 , T 7 NR 10 <input checked="" type="checkbox"/> E <input type="checkbox"/> W		County Dane		County Code 13	Civil Town/City or Village Madison								
Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit		USCS	Graphic Log	Well Diagram	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)								PID/FID	Compressive Strength	Moisture Content	Liquid Limit	
1	48		0	0-4'/ 0.0-0.7' Concrete. Second subfloor encountered at approximately 1.0'. 0.0-0.9' Concrete. 0.9-4.0' Silty Clay: Medium stiff to stiff, low plasticity, silt content decreases with depth, dark brown to yellowish brown with depth.					0.9-2 5.2				
2	46.8		4	4-8'/ 4.0-6.4' Silty Clay: Soft to medium stiff to stiff, low plasticity, silt content decreases with depth, dark brown to yellowish brown with depth, strong odor. 5.4-6.2' stained dark gray appears greasy. 6.4-7.5' Sand: Little gravel, trace silt, very fine to fine, loose, poorly sorted, light yellowish brown, gray 7.5-7.9' dry.					4-5.4 7.2				
3	45.6		8	8-12'/ 8.0-11.8' Sand: Little gravel, trace silt, very fine to fine, loose, poorly sorted, light yellowish brown, gray, dry, rock fragments 9.9-10.3'.					8-10 6.8				
			10						10-11.8 7.8				

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties				RQD/Comments	
Number and Type	Length All & Recovered (in)							PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	24		12	12-14'/ Sand: Little gravel, trace silt, very fine to fine, loose, poorly sorted, light yellowish brown, gray, dry, rock fragments. Refusal at 14'.				12-14 11.6					
5	36		14	14-16'/ Sand: Little gravel, trace silt, very fine to fine, loose, poorly sorted, light yellowish brown, gray, dry, little rock fragments.				14-16 11.6					
6	43.2		16	16-20'/ 16.0-19.6' Sand: Little to some rock fragments, trace silt increasing with depth, loose to medium dense, very fine to fine, poorly sorted, light yellowish brown, dry. 19.6-20' Sand: Little to some rock fragments, trace silt increasing with depth, loose to medium dense, very fine to fine, poorly sorted, light yellowish brown, dry.				16-18 11.9					
7	42		20	20-23.5'/ 20.0-23.5' Sand: Little to some rock fragments, trace silt increasing with depth, loose to medium dense, very fine to fine, poorly sorted, light yellowish brown, dry, trace to little interbedded clay, little large rock fragments, dry to moist. Refusal at 23.5'.				20-22 4.8					
			24					22-23.5 15.3					
			26										
			28										

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 2

Facility/Project Name Madison-Kipp				License/Permit/Monitoring Number				Boring Number B-201							
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Jim/Keith Last Name Firm Giles Engineering				Date Drilling Started 03/03/15		Date Drilling Completed 03/03/15		Drilling Method Direct Push							
WI Unique Well No.		DNR Well ID No.	Well Name	Final Static Water Level Feet		Surface Elevation Feet MSL		Borehole Diameter 3 inches							
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399700.82 N, 2144061.66 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat <input type="checkbox"/> SW 1/4 of <input type="checkbox"/> 1/4 of Section 5 , T 7 (N.R. 10 <input checked="" type="checkbox"/> E W Long <input type="checkbox"/> Feet <input type="checkbox"/> S <input type="checkbox"/> Feet <input type="checkbox"/> W				Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W											
Facility ID 113125320		County Dane	County Code 13	Civil Town/City or Village Madison											
Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit				USCS	Graphic Log	Well Diagram	Soil Properties				RQD/Comments
Number and Type	Length All. & Recovered (in)											Compressive Strength	Moisture Content	Liquid Limit	
1	48	0	0-4' 0.0-0.6' Concrete. 0.6-1.2' Silty Clay: Soft to medium stiff, no plasticity, crumbly, dark brownish gray, slightly moist. 1.2-4.0' Clay: Some silt, medium to stiff to stiff, low plasticity, hardness increases with depth, yellowish brown.				0.6-2 1.5								
2	45.6	4	4-8' 4.0-5.2' Clay: Some silt, medium to stiff to stiff, low plasticity, hardness increases with depth, yellowish brown. 5.2-6.0' Clay: Little silt, trace sand, soft, moderate plasticity, brownish gray, slightly moist. 6.0-7.2' Sandy Clay: Grading to clayey, sand, soft, low to no plasticity, brownish gray, slightly moist. 7.2-7.8' Sand: Trace clay, loose, very fine to fine, poorly sorted, light reddish brown, slightly moist.				2-4 1.2								
3	33.6	8	8-11' 8.0-9.3' Sand: Trace clay, loose, very fine to fine, poorly sorted, light reddish brown, slightly moist. 9.3-11.0' Sand: Some rock fragments, trace gravel, loose to medium dense, fine to coarse poorly sorted, light yellowish brown with black glass fragments at 9.5-9.9'. Refusal at 11'.				4-5.2 1.7								
		10					5.2-6 4.9								
							6-7.2 9.4								
							7.2-7.8 18.1								
							8-9.3 17.3								
							9.3-11 15.1								

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample Number and Type	Length All. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties				RQD/ Comments	
								PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
4	36		12	12-16'/ 12.0-15.0' Sand: Trace clay increasing with depth, trace to little rock fragments increasing with depth, loose to medium dense, poorly sorted, very fine to fine, light yellowish to reddish brown, dry to slightly moist, odor, stained areas at 12.6-13.0'.				12-13 29.7					
5	40.8		14					13-14 26.7					
			16	16-19'/ 16.0-19.0' Sand: Trace clay increasing with depth, trace to little rock fragments increasing with depth, loose to medium dense, poorly sorted, very fine to fine, light yellowish to reddish brown, dry to slightly moist, odor, stained areas at 16.5-17.0', slightly moist, trace intermixed clay nodules.				14-15 23.5					
			18					16-17 26.8					
			20					17-18 21.9					
			22					18-19 23.7					
			24										
			26										
			28										

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Page 1 of 3

Facility/Project Name Madison-Kipp				License/Permit/Monitoring Number			Boring Number B-202/MW-28					
Boring Drilled By: Name of crew chief (first, last) and Firm First Name Chip/Joel Last Name Firm Giles Engineering				Date Drilling Started 03/04/15		Date Drilling Completed 03/04/15		Drilling Method Hollow Stem Auger				
WI Unique Well No.		DNR Well ID No.	Well Name SB-202/MW-28	Final Static Water Level Feet		Surface Elevation Feet MSL		Borehole Diameter 3 inches				
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input type="checkbox"/> State Plane 399666.77 N, 2144113.37 E S <input type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> Lat _____				Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E SW 1/4 of _____ 1/4 of Section 5 , T 7 (NR 10 <input checked="" type="checkbox"/> E W Long _____ Feet <input type="checkbox"/> S <input type="checkbox"/> W								
Facility ID 113125320		County Dane	County Code 13	Civil Town/City or Village Madison								
Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties				RQD/ Comments
Number and Type	Length All. & Recovered (in)							PID/FID	Compressive Strength	Moisture Content	Liquid Limit	
1			0	Concrete.				0.2-0.9 1.1				
2	10.8			1-2' 0.0-0.2' Fill, Sand and Gravel. 0.2-0.9' Silty Clay: Stiff, low plasticity, dark reddish brown, dry.								
3	4.8		2	2-4' 2.0-2.4' Silty Clay: Stiff, low plasticity, dark reddish brown, dry, clay, some silt.				2-2.4 0.8				
4	24		4	4-6' 4.0-4.8' Silty Clay: Stiff, low plasticity, dark reddish brown, dry, clay, some silt, trace little sand. 4.8-6.0' Sand: Trace to little clay, trace intermixed clay nodules, very fine to fine, poorly sorted, loose to medium dense, reddish brown slightly moist.				4-5 0.8				
5	16.8		6	6-8' 6.0-7.0' Sand: Trace clay and gravel, trace intermixed clay nodules, very fine to fine, poorly sorted, loose to medium dense, reddish brown slightly moist. 7.0-7.4' Sand: Trace clay and gravel, trace intermixed clay nodules, very fine to fine, poorly sorted, loose to medium dense, reddish brown slightly moist.				5-6 0.7				
6	16.8		8	8-10' 8.0-9.4' Sand: Trace to little gravel, trace slag, loose, very fine to fine, poorly sorted, light yellowish brown, dry.				6-7.4 0.6				
7	7.2		10	10-12' 10.0-10.6' Sand: Trace to little gravel, trace slag,				8-9.4 0.8				
I hereby certify that the information on this form is true and correct to the best of my knowledge.												

Signature

Firm **ARCADIS**
126 N. Jefferson St., Suite 400
Milwaukee, WI (414) 276-7742

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties					RQD/Comments
Number and Type	Length All. & Recovered (in)							PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
				loose, very fine to fine, poorly sorted, light yellowish brown, dry, trace gravel.									
8	10.8	12		12-14'/ 12.0-12.5' Fragmented rock, micaceous limestone. 12.5-12.9' Sand: Little clay, trace gravel/rock fragments, very fine to fine, poorly sorted, loose to medium dense, light reddish brown, dry.				12-12.9 2.2					
9	16.8	14		14-16'/ 14.0-15.4' Sand: Little clay, trace gravel/rock fragments, very fine to fine, poorly sorted, loose to medium dense, light reddish brown, dry, large rock fragments 14-14.7'.				14-15.4 2.1					
10	22.8	16		16-18'/ 16.0-17.9' Sand: Little clay, trace gravel/rock fragments, very fine to fine, poorly sorted, loose to medium dense, light reddish brown, dry, large rock fragments 16.1-16.6' and 16.9-17.2'.				16-17 2.3					
11	--	18		18-20'/ No recovery.				17-17.9 1.3					
12	13.2	20		20-22'/ 20.0-21.1' Sand: Little rock fragments and gravel, trace clay, very fine to fine, poorly sorted, sub-rounded, loose to medium dense, light reddish brown, dry.				20-21.1 1.1					
13	13.2	22		22-24'/ 22.0-22.4' Rock Fragments. 22.4-23.1' Sand and Clay: Trace to little rock fragments, soft to medium stiff, no to low plasticity, clay content decreases with depth, light reddish brown, moist.				22-23.1 2.5					
14	22.8	24		24-26'/ 24.0-24.4' Rock Fragments. 24.4-25.4' Sand: Little silt, little rock fragments, medium dense, very fine to fine, poorly sorted, light reddish brown, dry to slightly moist.				24-25.4 2.1					
15	9.6	26		26-28'/ 26.0-26.8' Sand: Little silt, little rock fragments, medium dense, very fine to fine, poorly sorted, light reddish brown, dry to slightly moist, little clay, trace silt.				26-26.8 2.1					
16	8.4	28		28-30'/ 28.0-28.7' Sand: Little rock fragments/gravel, trace silt, loose, very fine, poorly sorted, light reddish				28-28.7 2.1					

Sample		Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	Soil Properties				RQD/ Comments	
Number and Type	Length All. & Recovered (in)							PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plastic Limit	
17	--		30	brown, slightly moist to moist.									
18	14.4		32	30-32'/ No recovery.									
			34	32-34'/ Refusal rock.									
			36										
			38										
			40										
			42										
			44										
			48										

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

 Verification Only of Fill and Seal

Route to:

 Drinking Water Watershed/Wastewater Remediation/Redevelopment Waste Management Other:

1. Well Location Information

County
DaneWI Unique Well No.
Removed Well

Hicap #

Latitude / Longitude (Degrees and Minutes)

Method Code (see instructions)

2. Facility / Owner Information

Facility Name
Madison KippCommon Well Name
B-196

Facility ID (FID or PWS)

113125320

License/Permit/Monitoring #

1/4 / 1/4 1/4 SW Section Township Range E
or Gov't Lot # 5 7 N 10 W

Well Street Address

201 Waubesa Street

Well City, Village or Town

Madison

Well ZIP Code

53704

Subdivision Name

Lot #

Reason For Removal From Service

WI Unique Well # of Replacement Well

Soil Boring

3. Well/Drillhole/Borehole Information

 Monitoring Well
 Water Well
 Borehole / DrillholeOriginal Construction Date (mm/dd/yyyy)
03/03/2015If a Well Construction Report is available,
please attach.

Construction Type:

 Drilled Driven (Sandpoint) Dug
 Other (specify): _____

Formation Type:

 Unconsolidated Formation Bedrock

Total Well Depth From Groundsurface (ft.)

18.5

Casing Diameter (in.)

Lower Drillhole Diameter (in.)

3

Casing Depth (ft.)

Was well annular space grouted?

 Yes No Unknown

If yes, to what depth (feet)?

Depth to Water (feet)

4. Pump, Liner, Screen, Casing & Sealing Material

- | | | | |
|---------------------------------------------------------------------------------------|-----------------------------------------|----------------------------------------|-----------------------------------------|
| Pump and piping removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Liner(s) removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Screen removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Casing left inplace? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Was casing cut off below surface? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Did sealing material rise to surface? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> N/A |
| Did material settle after 24 hours? | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No | <input type="checkbox"/> N/A |
| If yes, was hole retopped? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| If bentonite chips were used, were they hydrated with water from a known safe source? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> N/A |

Required Method of Placing Sealing Material

 Conductor Pipe-Gravity Conductor Pipe-Pumped
 Screened & Poured Other (Explain): _____

Sealing Materials

 Neat Cement Grout Clay-Sand Slurry (11 lb./gal. wt.)
 Sand-Cement (Concrete) Grout Bentonite-Sand Slurry " "
 Concrete Bentonite Chips

For Monitoring Wells and Monitoring Well Boreholes Only:

 Bentonite Chips Bentonite - Cement Grout
 Granular Bentonite Bentonite - Sand Slurry

5. Material Used to Fill Well / Drillhole

Granular Bentonite

From (ft.)	To (ft.)	No. Yards, Sacks Sealant or Volume (circle one)	Mix Ratio or Mud Weight
Surface	18.5	0.91 ft ³	

6. Comments

7. Supervision of Work

Name of Person or Firm Doing Filling & Sealing
ARCADIS

License #

Date of Filling & Sealing (mm/dd/yyyy)
03/03/2015DNR Use Only
Date Received Noted ByStreet or Route
126 N. Jefferson Street, Suite 400

Telephone Number

414-276-7742

Comments

City Milwaukee

State WI

ZIP Code 53202

Signature of Person Doing Work

Date Signed

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

Verification Only of Fill and Seal

Route to:

- Drinking Water
 Waste Management

- Watershed/Wastewater
 Other:

- Remediation/Redevelopment

1. Well Location Information

County Dane	WI Unique Well No. Removed Well	Hicap #			
Latitude / Longitude (Degrees and Minutes)		Method Code (see instructions)			
1/4 / 1/4 or Gov't Lot #	1/4 SW	Section 5	Township 7 N	Range 10	<input checked="" type="checkbox"/> E <input type="checkbox"/> W

Well Street Address

201 Waubesa Street

Well City, Village or Town Madison	Well ZIP Code 53704
---------------------------------------	------------------------

Subdivision Name	Lot #
------------------	-------

Reason For Removal From Service Soil Boring	WI Unique Well # of Replacement Well
------------------------------------------------	--------------------------------------

3. Well/Drillhole/Borehole Information

<input type="checkbox"/> Monitoring Well <input type="checkbox"/> Water Well <input checked="" type="checkbox"/> Borehole / Drillhole	Original Construction Date (mm/dd/yyyy) 03/02/2015
If a Well Construction Report is available, please attach.	

Construction Type:

- Drilled Driven (Sandpoint) Dug
 Other (specify): _____

Formation Type:

- Unconsolidated Formation Bedrock

Total Well Depth From Groundsurface (ft.) 17.5	Casing Diameter (in.)
---------------------------------------------------	-----------------------

Lower Drillhole Diameter (in.) 3	Casing Depth (ft.)
-------------------------------------	--------------------

Was well annular space grouted? Yes No Unknown

If yes, to what depth (feet)?	Depth to Water (feet)
-------------------------------	-----------------------

5. Material Used to Fill Well / Drillhole

Granular Bentonite

2. Facility / Owner Information

Facility Name Madison Kipp	Common Well Name B-197
-------------------------------	---------------------------

Facility ID (FID or PWS)

113125320

License/Permit/Monitoring #

Original Well Owner

Present Well Owner

Mark Meunier

Mailing Address of Present Owner
201 Waubesa Street

City of Present Owner Madison	State WI	ZIP Code 53704
----------------------------------	-------------	-------------------

4. Pump, Liner, Screen, Casing & Sealing Material

- | | | | |
|---------------------------------------------------------------------------------------|-----------------------------------------|----------------------------------------|-----------------------------------------|
| Pump and piping removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Liner(s) removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Screen removed? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Casing left inplace? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Was casing cut off below surface? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| Did sealing material rise to surface? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> N/A |
| Did material settle after 24 hours? | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No | <input type="checkbox"/> N/A |
| If yes, was hole retopped? | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input checked="" type="checkbox"/> N/A |
| If bentonite chips were used, were they hydrated with water from a known safe source? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> N/A |

Required Method of Placing Sealing Material

- | | |
|----------------------------------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Conductor Pipe-Gravity | <input type="checkbox"/> Conductor Pipe-Pumped |
| <input checked="" type="checkbox"/> Screened & Poured
(Bentonite Chips) | <input type="checkbox"/> Other (Explain): _____ |

Sealing Materials

- | | |
|-------------------------------------------------------|-------------------------------------------------------------|
| <input type="checkbox"/> Neat Cement Grout | <input type="checkbox"/> Clay-Sand Slurry (11 lb./gal. wt.) |
| <input type="checkbox"/> Sand-Cement (Concrete) Grout | <input type="checkbox"/> Bentonite-Sand Slurry " " |
| <input type="checkbox"/> Concrete | <input type="checkbox"/> Bentonite Chips |

For Monitoring Wells and Monitoring Well Boreholes Only:

- | | |
|--------------------------------------------------------|---------------------------------------------------|
| <input type="checkbox"/> Bentonite Chips | <input type="checkbox"/> Bentonite - Cement Grout |
| <input checked="" type="checkbox"/> Granular Bentonite | <input type="checkbox"/> Bentonite - Sand Slurry |

From (ft.)	To (ft.)	No. Yards, Sacks Sealant of Volume (circle one)	Mix Ratio or Mud Weight
Surface	17.5	0.86 ft ³	

6. Comments

7. Supervision of Work

Name of Person or Firm Doing Filling & Sealing
ARCADIS

Street or Route
126 N. Jefferson Street, Suite 400

City Milwaukee State WI ZIP Code 53202 Signature of Person Doing Work

DNR Use Only

Date Received Noted By

Comments

Date Signed

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

 Verification Only of Fill and Seal

Route to:

 Drinking Water Watershed/Wastewater Remediation/Redevelopment Waste Management Other: _____**1. Well Location Information**County
DaneWI Unique Well No.
Removed Well

Hicap #

Latitude / Longitude (Degrees and Minutes) Method Code (see instructions)

° _____ N
° _____ W1/4 / 1/4 1/4 SW Section Township Range E
or Gov't Lot # 5 7 N 10 W

Well Street Address

201 Waubesa Street

Well City, Village or Town

Madison

Well ZIP Code

53704

Subdivision Name

Lot #

Reason For Removal From Service

WI Unique Well # of Replacement Well

Soil Boring

3. Well/Drillhole/Borehole Information Monitoring Well
 Water Well
 Borehole / DrillholeOriginal Construction Date (mm/dd/yyyy)
03/02/2015If a Well Construction Report is available,
please attach.

Construction Type:

 Drilled Driven (Sandpoint) Dug
 Other (specify): _____

Formation Type:

 Unconsolidated Formation Bedrock

Total Well Depth From Groundsurface (ft.)

23

Casing Diameter (in.)

Lower Drillhole Diameter (in.)

3

Casing Depth (ft.)

Was well annular space grouted?

 Yes No Unknown

If yes, to what depth (feet)?

Depth to Water (feet)

5. Material Used to Fill Well / Drillhole

Granular Bentonite

From (ft.)	To (ft.)	No. Yards, Sacks Sealant of Volume (circle one)	Mix Ratio or Mud Weight
Surface	23	1.13 ft ³	

6. Comments**7. Supervision of Work**

Name of Person or Firm Doing Filling & Sealing

ARCADIS

Street or Route

126 N. Jefferson Street, Suite 400

City Milwaukee

State

WI

ZIP Code

53202

Signature of Person Doing Work

DNR Use Only

Date Received

Noted By

Comments

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

Verification Only of Fill and Seal

Route to:

- Drinking Water
 Waste Management

- Watershed/Wastewater
 Other:

- Remediation/Redevelopment

1. Well Location Information

County Dane	WI Unique Well No. Removed Well	Hicap #
Latitude / Longitude (Degrees and Minutes)		Method Code (see instructions)
1/4 / 1/4 or Gov't Lot #	1/4 SW 5	Section Township Range E N W

Well Street Address

201 Waubesa Street

Well City, Village or Town Madison	Well ZIP Code 53704
---------------------------------------	------------------------

Subdivision Name

Lot #

Reason For Removal From Service
Soil Boring

WI Unique Well # of Replacement Well

— — — — —

3. Well/Drillhole/Borehole Information

- Monitoring Well
 Water Well
 Borehole / Drillhole

Original Construction Date (mm/dd/yyyy)
03/03/2015

If a Well Construction Report is available,
please attach.

Construction Type:

- Drilled Driven (Sandpoint) Dug
 Other (specify): _____

Formation Type:

- Unconsolidated Formation Bedrock

Total Well Depth From Groundsurface (ft.)
19

Lower Drillhole Diameter (in.)
3

Was well annular space grouted? Yes No Unknown

If yes, to what depth (feet)?
Depth to Water (feet)

5. Material Used to Fill Well / Drillhole

Granular Bentonite

From (ft.)	To (ft.)	No. Yards, Sacks Sealant of Volume (circle one)	Mix Ratio or Mud Weight
Surface	19	0.93 ft ³	

6. Comments

7. Supervision of Work

Name of Person or Firm Doing Filling & Sealing
ARCADIS

License #

Date of Filling & Sealing (mm/dd/yyyy)
03/03/2015

DNR Use Only

Date Received Noted By

Street or Route
126 N. Jefferson Street, Suite 400

Telephone Number

414-276-7742

Comments

City Milwaukee

State WI

ZIP Code 53202

Signature of Person Doing Work

Date Signed

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

Verification Only of Fill and Seal

Route to:

Drinking Water

Watershed/Wastewater

Remediation/Redevelopment

Waste Management

Other: _____

1. Well Location Information

County Dane	WI Unique Well No. Removed Well _____	Hicap # _____	
Latitude / Longitude (Degrees and Minutes) _____._____._____._____._____._____. ° N ° W		Method Code (see instructions) _____	
1/4 / 1/4 or Gov't Lot #	1/4 SW Section 5	Township 7 N	Range 10 E <input checked="" type="checkbox"/>

Well Street Address

201 Waubesa Street

Well City, Village or Town Madison	Well ZIP Code 53704
----------------------------------------------	-------------------------------

Subdivision Name	Lot #
------------------	-------

Reason For Removal From Service Soil Boring	WI Unique Well # of Replacement Well _____
-------------------------------------------------------	-----------------------------------------------

3. Well/Drillhole/Borehole Information

<input type="checkbox"/> Monitoring Well	Original Construction Date (mm/dd/yyyy) 03/03/2015
<input type="checkbox"/> Water Well	If a Well Construction Report is available, please attach.
<input checked="" type="checkbox"/> Borehole / Drillhole	

Construction Type:

<input checked="" type="checkbox"/> Drilled	<input type="checkbox"/> Driven (Sandpoint)	<input type="checkbox"/> Dug
<input type="checkbox"/> Other (specify): _____		

Formation Type:

<input checked="" type="checkbox"/> Unconsolidated Formation	<input type="checkbox"/> Bedrock
--------------------------------------------------------------	----------------------------------

Total Well Depth From Groundsurface (ft.) 23.5	Casing Diameter (in.)
----------------------------------------------------------	-----------------------

Lower Drillhole Diameter (in.) 3	Casing Depth (ft.)
--------------------------------------------	--------------------

Was well annular space grouted? Yes No Unknown

If yes, to what depth (feet)?	Depth to Water (feet)
-------------------------------	-----------------------

5. Material Used to Fill Well / Drillhole

Granular Bentonite

2. Facility / Owner Information

Facility Name Madison Kipp	Common Well Name B-200
--------------------------------------	----------------------------------

Facility ID (FID or PWS)

113125320

License/Permit/Monitoring #

Original Well Owner

Present Well Owner

Mark Meunier

Mailing Address of Present Owner

201 Waubesa Street

City of Present Owner Madison	State WI	ZIP Code 53704
-----------------------------------------	--------------------	--------------------------

4. Pump, Liner, Screen, Casing & Sealing Material

Pump and piping removed?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Liner(s) removed?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Screen removed?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Casing left inplace?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Was casing cut off below surface?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Did sealing material rise to surface?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Did material settle after 24 hours?	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A
If yes, was hole retopped?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
If bentonite chips were used, were they hydrated with water from a known safe source?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A

Required Method of Placing Sealing Material

Conductor Pipe-Gravity Conductor Pipe-Pumped

Screened & Poured (Bentonite Chips) Other (Explain): _____

Sealing Materials

<input type="checkbox"/> Neat Cement Grout	<input type="checkbox"/> Clay-Sand Slurry (11 lb./gal. wt.)
<input type="checkbox"/> Sand-Cement (Concrete) Grout	<input type="checkbox"/> Bentonite-Sand Slurry " "
<input type="checkbox"/> Concrete	<input type="checkbox"/> Bentonite Chips

For Monitoring Wells and Monitoring Well Boreholes Only:

<input type="checkbox"/> Bentonite Chips	<input type="checkbox"/> Bentonite - Cement Grout
<input checked="" type="checkbox"/> Granular Bentonite	<input type="checkbox"/> Bentonite - Sand Slurry

From (ft.)	To (ft.)	No. Yards, Sacks Sealant or Volume (circle one)	Mix Ratio or Mud Weight
Surface	23.5	1.15 ft³	

6. Comments

7. Supervision of Work

Name of Person or Firm Doing Filling & Sealing ARCADIS	License #	Date of Filling & Sealing (mm/dd/yyyy) 03/05/2015
------------------------------------------------------------------	-----------	-------------------------------------------------------------

DNR Use Only

Date Received _____ Noted By _____

Street or Route
126 N. Jefferson Street, Suite 400

Telephone Number
414-276-7742

Comments

Signature of Person Doing Work

Date Signed

Notice: Completion of this report is required by chs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

Verification Only of Fill and Seal

Route to:

Drinking Water

Watershed/Wastewater

Remediation/Redevelopment

Waste Management

Other:

1. Well Location Information

County Dane	WI Unique Well No. Removed Well	Hicap #			
Latitude / Longitude (Degrees and Minutes)		Method Code (see instructions)			
1/4 N or Gov't Lot #	1/4 SW	Section 5	Township 7 N	Range 10	<input checked="" type="checkbox"/> E <input type="checkbox"/> W

Well Street Address

201 Waubesa Street

Well City, Village or Town Madison	Well ZIP Code 53704
----------------------------------------------	-------------------------------

Subdivision Name

Reason For Removal From Service
Soil Boring

WI Unique Well # of Replacement Well

3. Well/Drillhole/Borehole Information

<input type="checkbox"/> Monitoring Well	Original Construction Date (mm/dd/yyyy) 03/03/2015
<input type="checkbox"/> Water Well	If a Well Construction Report is available, please attach.
<input checked="" type="checkbox"/> Borehole / Drillhole	

Construction Type:

Drilled Driven (Sandpoint) Dug
 Other (specify): _____

Formation Type:

Unconsolidated Formation Bedrock

Total Well Depth From Groundsurface (ft.)
19

Lower Drillhole Diameter (in.)
3

Was well annular space grouted? Yes No Unknown

If yes, to what depth (feet)? Depth to Water (feet)

5. Material Used to Fill Well / Drillhole

Granular Bentonite

From (ft.)	To (ft.)	No. Yards, Sacks Sealant or Volume (circle one)	Mix Ratio or Mud Weight
Surface	19	0.93 ft³	

6. Comments

7. Supervision of Work

Name of Person or Firm Doing Filling & Sealing
ARCADIS

DNR Use Only

Date Received Noted By

Street or Route
126 N. Jefferson Street, Suite 400

Telephone Number

414-276-7742

Comments

City **Milwaukee**

State **WI**

ZIP Code **53202**

Signature of Person Doing Work

Date Signed

ARCADIS

Attachment C

**Well Construction and Well
Development Form**

Facility/Project Name Madision-Kipp		Local Grid Location of Well ft. <input type="checkbox"/> N. <input type="checkbox"/> S. ft. <input type="checkbox"/> E. <input type="checkbox"/> W.	Well Name MW-28
Facility License, Permit or Monitoring Number 113125320		Local Grid Origin Lat. _____ Long _____ or St. Plane 399666.77 ft. N. 2144113.37 ft. E.	Wis. Unique Well Number DNR Well Number
Type of Well	Well Code /	Section Location of Waste/Source SW 1/4 of 1/4 of Sec 5 T. 7 N R 10 E. W.	Date Well Installed 03/04/2015
Distance from Waste/ Source _____ ft.	Enf. Stds. Apply <input type="checkbox"/>	Location of Well Relative to Waste/Source <input type="checkbox"/> Upgradient <input type="checkbox"/> Sidegradient <input type="checkbox"/> Downgradient <input type="checkbox"/> Not Known	Well Installed by: Name (first, last) and Firm Chip and Joel Giles Engineering
A. Protective pipe, top elevation 874.30 ft. MSL	B. Well casing, top elevation 874.05 ft. MSL	C. Land surface elevation 874.30 ft. MSL	D. Surface seal, bottom 873.30 ft MSL or 1 ft.

12. USCS classification of soil near screen:
 GP GM GC GW SW SP
 SM SC ML MH CL CH
 Bedrock

13. Sieve analysis attached? Yes No

14. Drilling method used:
 Rotary 50
 Hollow Stem Auger 41
 Other --

15. Drilling fluid used: Water 0.2 Air 0.1
 Drilling Mud 0.3 None 9.9

16. Drilling additives used? Yes No
 Describe _____

17. Source of Water (attached analysis if required):
City of Madison Public Water

E. Bentonite seal, top
855.60 ft. MSL or **23.7** ft.

F. Fine sand, top
855.60 ft. MSL or **23.7** ft.

G. Filter pack, top
849.60 ft. MSL or **24.7** ft.

H. Screen joint, top
846.60 ft. MSL or **27.7** ft.

I. Well bottom
836.60 ft. MSL or **37.7** ft.


J. Filter pack, bottom
ft. MSL or ft.

K. Borehole bottom
834.30 ft. MSL or **40** ft.

L. Borehole diameter _____ in.

M. O.D. well casing _____ in.

N. I.D. well casing _____ in.



1. Cap and lock? Yes No
2. Protective cover pipe:
 a. Inside diameter: _____ in.
 b. Length: _____ ft.
 c. Material:
 Steel 0.4
 Other --
- d. Additional protection?
 If yes, describe: _____
3. Surface seal: Bentonite 3.0
 Concrete 0.1
 Other --
4. Material between well casing and protective pipe:
 Bentonite 3.0
 Annular space seal --
 Other --
5. Annular space seal:
 a. Granular Bentonite 3.3
 b. _____ Lbs/gal mud weight..... Bentonite-sand slurry 3.5
 c. _____ Lbs/gal mud weight..Bentonite-cement grout 3.1
 d. _____ % Bentonite..... Bentonite-cement grout 5.0
 e. _____ Ft³ volume added for any of the above
- f. How installed:
 Tremie 0.1
 Tremie pumped 0.2
 Gravity 0.8
6. Bentonite seal:
 a. Granular Bentonite 3.3
 b. 1/4 in. 3/8 in. 1/2 in. bentonite pellets 3.2
 c. _____ Other --
7. Fine sand Material: Manufacturer, product name and mesh size
 a. _____
 b. Volume added _____ ft³ --
8. Filter pack material: Manufacturer, product name and mesh size
 a. _____
 b. Volume added _____ ft³ --
9. Well casing: Flush threaded PVC schedule 40 2.3
 Flush threaded PVC schedule 80 2.4
 Other --
10. Screen material: **PVC Sch.**
 a. Screen type:
 Factory cut 1.1
 Continuous slot 0.1
 Other --
- b. Manufacturer _____
 c. Slot size: _____
 d. Slotted length: **0.010** in.
10.0 ft.
11. Backfill material (below filter pack):
 None 14
 Other --

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature:	Firm: ARCADIS 126 N. Jefferson Street Milwaukee, WI (414) 276-7742
------------	--------------------------------------------------------------------------

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Madison-Kipp	County Name Dane	Well Name MW-28
Facility License, Permit or Monitoring Number	County Code 13	Wis. Unique Well Number DNR Well Number

1. Can this well be purged dry?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Before Development	After Development
2. Well development method		11. Depth to Water (from top of well casing)	a. <u>27.27</u> ft.
surged with bailer and bailed	<input type="checkbox"/> 41	Date	<u>03/06/2015</u>
surged with bailer and pumped	<input type="checkbox"/> 61	mm/dd/yyyy	<u>mm/dd/yyyy</u>
surged with block and bailed	<input type="checkbox"/> 42	Time	c. <u>09:40</u> <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.
surged with block and pumped	<input checked="" type="checkbox"/> 62		<u>11:30</u> <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.
surged with block, bailed and pumped	<input type="checkbox"/> 70	12. Sediment in well bottom	<u>0.0</u> inches
compressed air	<input type="checkbox"/> 20	13. Water Clarity	Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe) <u>Cloudy</u>
bailed only	<input type="checkbox"/> 10		Clear <input checked="" type="checkbox"/> 20 Turbid <input type="checkbox"/> 25 (Describe) <u>Clear</u>
pumped only	<input type="checkbox"/> 51		
pumped slowly	<input type="checkbox"/> 50		
Other _____	<input type="checkbox"/> --		
3. Time spent developing well	<u>110</u> min.		
4. Depth of well (from top of well casing)	<u>37.98</u> ft.		
5. Inside diameter of well	<u>2.00</u> in.		
6. Volume of water in filter pack and well casing	<u>14.5</u> gal.		
7. Volume of water removed from well	<u>32</u> gal.	Fill in if drilling fluids were used and well is at solid waste facility:	
8. Volume of water added (if any)	<u>0.0</u> gal.	14. Total suspended solids	<u> </u> mg/l <u> </u> mg/l
9. Source of water added _____		15. COD	<u> </u> mg/l <u> </u> mg/l
10. Analysis performed on water added? (If yes, attach results)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	16. Well developed by: Name (first, last) and Firm First Name: <u>Jay</u> Last Name: <u>Read</u>	
17. Additional comments on development:	<p>ARCADIS purged additional groundwater prior to first sampling event.</p>		

Name and Address of Facility Contact/Owner/Responsible Party First Name: <u>Alina</u> Last Name: <u>Satkoski</u>	I hereby certify that the above information is true and correct to the best of my knowledge.
Facility/Firm: <u>Madison-Kipp</u>	Signature: <u></u>
Street: <u>201 Waubesa Street</u>	Print Name: <u>Jay Read</u>
City/State/Zip: <u>Madison, WI 53704</u>	Firm: <u>ARCADIS U.S., Inc.</u>

NOTE: See instructions for more information including a list of country codes and well type codes.

ARCADIS

Attachment D

Wipe Sampling Log

Attachment D
Wipe Sample Log

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation

Grid #	Wipe Type					Sample ID	Sample Location	Sample Date	Sample Time
	Wall	Column	Floor	Machine horz.	Dup. vert.				
1	X					MKC-WIPE01-WALL	white wall at bottom of stairs next to cafeteria door/emergency fire blanket (vertical surface)	3/4/15	1102
		X				MKC-WIPE01-COLUMN	blue support column next to cafeteria door/emergency fire blanket (vertical surface)	3/4/15	1051
		X				MKC-WIPE01-FLOOR	black rough concrete floor in die storage #2 area (horizontal surface)	3/4/15	1059
			X			MKC-WIPE01-M1HORZ	rear end of Machine 1 - hydraulic tank (horizontal surface)	3/4/15	1010
				X		MKC-WIPE01-M1VERT	front end of Machine 1 - shot barrel block (vertical surface)	3/4/15	1004
		X				MKC-WIPE01-FLOOR2	break room tile floor (23 tiles in from west and 12 tiles in from north)	4/2/15	0750
2	X					MKC-WIPE02-WALL	white wall next to emergency eye wash station (vertical surface)	3/4/15	1117
		X				MKC-WIPE02-COLUMN	yellow support column east of Machine 1 (vertical surface)	3/4/15	1108
			X			MKC-WIPE02-FLOOR	black rough concrete floor along base of wall of repair room (horizontal surface)	3/4/15	1113
				X		MKC-WIPE02-FLOOR2	black rough concrete floor south of double doors and west of furnace in aisle way	4/2/15	0810
3	X					MKC-WIPE03-WALL	white wall next to emergency eye wash station (vertical surface)	3/4/15	1155
		X				MKC-WIPE03-COLUMN	unpainted column south of 55-gal steel drum storage (vertical surface)	3/4/15	1144
			X			MKC-WIPE03-FLOOR	black rough concrete floor along base of secondary containment of 55-gal steel drum storage (horizontal surface)	3/4/15	1152
				X		MKC-WIPE03-M2HORZ	front end of M2 - c-frame (horizontal surface)	3/4/15	1019
					X	MKC-WIPE03-M2VERT	front end of M2 - shot barrel block (vertical surface)	3/4/15	1015
				X		MKC-WIPE03-M3HORZ	rear end of M3 - hydraulic tank (horizontal surface)	3/4/15	1028
					X	MKC-WIPE03-M3VERT	front end of M3 - shot barrel block (vertical surface)	3/4/15	1024
					X	MKC-WIPE03-DUP	front end of M2 - shot barrel block (vertical surface)	3/4/15	1017
						MKC-WIPE03-FLOOR2	black rough concrete floor 9 feet from center of pallet rack along west wall	4/2/15	0820
						MKC-WIPE03-FLOOR3	black rough concrete floor 27 feet west of yellow guardrail in center aisle way	4/2/15	0830
						MKC-WIPE03-FLOOR4	black rough concrete floor 4 feet south of north wall	4/2/15	0835

Attachment D
Wipe Sample Log

Building Interior Polychlorinated Biphenyl Investigation Summary
201 Waubesa Street
Madison-Kipp Corporation

Grid #	Wipe Type					Sample ID	Sample Location	Sample Date	Sample Time
	Wall	Column	Floor	Machine horz.	Dup. vert.				
4	X					MKC-WIPE04-WALL	white wall at bottom of stairs (vertical surface)	3/4/15	1124
		X				MKC-WIPE04-COLUMN	yellow support column east of M3 (vertical surface)	3/4/15	1129
			X			MKC-WIPE04-FLOOR	black rough concrete floor in aisleway between pressure washing area and repair room (horizontal surface)	3/4/15	1135
					X	MKC-WIPE04-DUP	black rough concrete floor in aisleway between pressure washing area and repair room (horizontal surface)	3/4/15	1137
5	X					MKC-WIPE05-WALL	white wall west of M7 (vertical surface)	3/4/15	1207
		X				MKC-WIPE05-COLUMN	blue support column between M6 and M7 (vertical surface)	3/4/15	1213
			X			MKC-WIPE05-FLOOR	black rough concrete floor along base of M6 near column (horizontal surface)	3/4/15	1219
				X		MKC-WIPE05-FLOOR2	black rough concrete floor 8 feet east of electrical panel	4/2/15	0845
6	X					MKC-WIPE06-WALL	white wall southwest of M21 (vertical surface)	3/4/15	1424
		X				MKC-WIPE06-COLUMN	yellow support column near exit door (vertical surface)	3/4/15	1426
			X			MKC-WIPE06-FLOOR	black rough concrete floor at rear end of M21 (horizontal surface)	3/4/15	1420
				X		MKC-WIPE06-M21HORZ	rear end of M21 - pump block (horizontal surface)	3/4/15	1038
					X	MKC-WIPE06-M21VERT	front end of M21 - shot barrel block (vertical surface)	3/4/15	1034
7	X					MKC-WIPE07-WALL	white wall at intersection of west-east and north-south aisleway west of M10 (vertical surface)	3/4/15	1323
		X				MKC-WIPE07-COLUMN	blue support column between M9 and M10 (vertical surface)	3/4/15	1227
			X			MKC-WIPE07-FLOOR	black rough concrete floor along base of M11 (horizontal surface)	3/4/15	1326
8	X					MKC-WIPE08-WALL	white exterior wall of building (vertical surface)	3/4/15	1411
		X				MKC-WIPE08-COLUMN	yellow support column near exit door (vertical surface)	3/4/15	1406
			X			MKC-WIPE08-FLOOR	black rough concrete floor at rear end of M31 (horizontal surface)	3/4/15	1408
9	X					MKC-WIPE09-WALL	white wall of "water pit" (vertical surface)	3/4/15	1332
		X				MKC-WIPE09-COLUMN	white support column at intersection of west-east and north-south aisleway (vertical surface)	3/4/15	1338
			X			MKC-WIPE09-FLOOR	black rough concrete floor at rear end of M13 (horizontal surface)	3/4/15	1343
10	X					MKC-WIPE10-WALL	white wall of office near exit door (vertical surface)	3/4/15	1352
		X				MKC-WIPE10-COLUMN	blue support column between M14 and M15 (vertical surface)	3/4/15	1355
			X			MKC-WIPE10-FLOOR	black rough concrete floor in 30-gal fiber drum storage (horizontal surface)	3/4/15	1358

ARCADIS

Attachment E

Laboratory Reports



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 09, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 03/02/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser
Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Accreditation	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SB-198 (1-2)	A151002-01	Soil	03/02/2015	03/02/2015
SB-198 (4-5)	A151002-02	Soil	03/02/2015	03/02/2015
Dup-1	A151002-03	Soil	03/02/2015	03/02/2015
SB-198 (7-8)	A151002-04	Soil	03/02/2015	03/02/2015
SB-198 (9-10)	A151002-05	Soil	03/02/2015	03/02/2015
SB-197 (2-3)	A151002-06	Soil	03/02/2015	03/02/2015
SB-197 (5-6)	A151002-07	Soil	03/02/2015	03/02/2015
SB-197 (6-7)	A151002-08	Soil	03/02/2015	03/02/2015
SB-197 (9-10)	A151002-09	Soil	03/02/2015	03/02/2015
SB-197 (14-15)	A151002-10	Soil	03/02/2015	03/02/2015

CASE NARRATIVE

Sample Receipt Information:

10 samples were received on 3/2/2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (1-2)

A151002-01 (Soil)

Date Sampled
03/02/2015 13:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	8.8	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
PCB-1221	ND	4.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
PCB-1232	ND	3.3	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
PCB-1242	1900	5.2	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	D
PCB-1248	ND	6.3	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
PCB-1254	ND	5.2	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
PCB-1260	ND	2.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	
Total PCBs	1900	8.8	120	mg/kg dry	1000	03/04/2015	03/06/2015 01:36	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127

03/04/2015 03/06/2015 01:36 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119

03/04/2015 03/06/2015 01:36 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	84.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (4-5)

A151002-02 (Soil)

Date Sampled

03/02/2015 13:40

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	4.5	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
PCB-1221	ND	2.5	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
PCB-1232	ND	1.7	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
PCB-1242	910	2.7	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	D
PCB-1248	ND	3.2	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
PCB-1254	ND	2.7	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
PCB-1260	ND	1.5	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	
Total PCBs	910	4.5	61	mg/kg dry	500	03/04/2015	03/06/2015 02:02	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 02:02 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 02:02 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	82.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Dup-1

A151002-03 (Soil)

Date Sampled

03/02/2015 00:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	8.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
PCB-1221	ND	4.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
PCB-1232	ND	3.4	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
PCB-1242	2300	5.3	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	D
PCB-1248	ND	6.4	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
PCB-1254	ND	5.3	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
PCB-1260	ND	2.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	
Total PCBs	2300	8.9	120	mg/kg dry	1000	03/04/2015	03/06/2015 03:21	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 03:21 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 03:21 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	83.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (7-8)

A151002-04 (Soil)

Date Sampled

03/02/2015 13:50

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.031	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
PCB-1221	ND	0.017	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
PCB-1232	ND	0.012	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
PCB-1242	3.6	0.018	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	D
PCB-1248	ND	0.022	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
PCB-1254	ND	0.018	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
PCB-1260	ND	0.0099	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	
Total PCBs	3.6	0.031	0.41	mg/kg dry	4	03/04/2015	03/06/2015 03:47	EPA 8082A	D

Surrogate: Decachlorobiphenyl

66.7 % 59.1-127

03/04/2015 03:47

EPA 8082A

D

Surrogate: Tetrachloro-meta-xylene

84.8 % 77.4-119

03/04/2015 03:47

EPA 8082A

D

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	96.6	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (9-10)

A151002-05 (Soil)

Date Sampled

03/02/2015 14:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.077	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
PCB-1221	ND	0.043	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
PCB-1232	ND	0.029	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
PCB-1242	13	0.046	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	D
PCB-1248	ND	0.055	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
PCB-1254	ND	0.046	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
PCB-1260	ND	0.025	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	
Total PCBs	13	0.077	1.0	mg/kg dry	10	03/04/2015	03/06/2015 04:13	EPA 8082A	D

Surrogate: Decachlorobiphenyl

71.1 %

59.1-127

03/04/2015

03/06/2015 04:13

EPA 8082A

D

Surrogate: Tetrachloro-meta-xylene

90.7 %

77.4-119

03/04/2015

03/06/2015 04:13

EPA 8082A

D

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	95.8	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (2-3)

A151002-06 (Soil)

Date Sampled

03/02/2015 14:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.090	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
PCB-1221	ND	0.050	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
PCB-1232	ND	0.034	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
PCB-1242	21	0.053	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	D
PCB-1248	ND	0.064	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
PCB-1254	ND	0.053	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
PCB-1260	ND	0.029	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	
Total PCBs	21	0.090	1.2	mg/kg dry	10	03/04/2015	03/06/2015 04:39	EPA 8082A	D

Surrogate: Decachlorobiphenyl

73.3 %

59.1-127

03/04/2015

03/06/2015 04:39

EPA 8082A

D

Surrogate: Tetrachloro-meta-xylene

91.9 %

77.4-119

03/04/2015

03/06/2015 04:39

EPA 8082A

D

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	82.3	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (5-6)

A151002-07 (Soil)

Date Sampled

03/02/2015 14:40

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	4.2	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
PCB-1221	ND	2.4	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
PCB-1232	ND	1.6	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
PCB-1242	1600	2.5	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	D
PCB-1248	ND	3.0	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
PCB-1254	ND	2.5	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
PCB-1260	ND	1.4	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	
Total PCBs	1600	4.2	57	mg/kg dry	500	03/04/2015	03/06/2015 13:20	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 13:20 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 13:20 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	87.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (6-7)

A151002-08 (Soil)

Date Sampled

03/02/2015 14:50

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	3.8	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
PCB-1221	ND	2.1	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
PCB-1232	ND	1.4	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
PCB-1242	1200	2.3	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	D
PCB-1248	ND	2.7	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
PCB-1254	ND	2.3	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
PCB-1260	ND	1.2	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	
Total PCBs	1200	3.8	51	mg/kg dry	500	03/04/2015	03/06/2015 13:46	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 13:46 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 13:46 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	97.6	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (9-10)

A151002-09 (Soil)

Date Sampled

03/02/2015 14:55

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	3.8	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
PCB-1221	ND	2.1	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
PCB-1232	ND	1.4	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
PCB-1242	1200	2.3	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	D
PCB-1248	ND	2.7	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
PCB-1254	ND	2.3	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
PCB-1260	ND	1.2	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	
Total PCBs	1200	3.8	52	mg/kg dry	500	03/04/2015	03/06/2015 07:41	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 07:41 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 07:41 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	96.8	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (14-15)

A151002-10 (Soil)

Date Sampled

03/02/2015 15:05

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	16	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
PCB-1221	ND	8.6	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
PCB-1232	ND	5.9	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
PCB-1242	4000	9.3	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	D
PCB-1248	ND	11	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
PCB-1254	ND	9.3	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
PCB-1260	ND	5.1	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	
Total PCBs	4000	16	210	mg/kg dry	2000	03/04/2015	03/06/2015 08:07	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127

03/04/2015 03/06/2015 08:07 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119

03/04/2015 03/06/2015 08:07 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	95.0	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control

ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A503009 - EPA 3570

Blank (A503009-BLK1)		Prepared: 03/04/2015 Analyzed: 03/06/2015 01:10				
PCB-1016	ND	0.10	mg/kg wet			
PCB-1221	ND	0.10	mg/kg wet			
PCB-1232	ND	0.10	mg/kg wet			
PCB-1242	ND	0.10	mg/kg wet			
PCB-1248	ND	0.10	mg/kg wet			
PCB-1254	ND	0.10	mg/kg wet			
PCB-1260	ND	0.10	mg/kg wet			
Total PCBs	ND	0.10	mg/kg wet			
Surrogate: Decachlorobiphenyl	0.130		mg/kg wet	0.1584	82.2	59.1-127
Surrogate: Tetrachloro-meta-xylene	0.113		mg/kg wet	0.1200	94.0	77.4-119

LCS (A503009-BS1)

		Prepared: 03/04/2015 Analyzed: 03/06/2015 00:44				
PCB-1254	0.927	0.10	mg/kg wet	1.000	92.7	76.4-124
Surrogate: Decachlorobiphenyl	0.130		mg/kg wet	0.1584	81.9	59.1-127
Surrogate: Tetrachloro-meta-xylene	0.120		mg/kg wet	0.1200	100	77.4-119

Matrix Spike (A503009-MS1)

		Source: A151002-02 Prepared: 03/04/2015 Analyzed: 03/06/2015 02:28				
PCB-1242	798	61	mg/kg dry	906	61.9-148	M1, D
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1927	59.1-127	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1460	77.4-119	DO

Matrix Spike Dup (A503009-MSD1)

		Source: A151002-02 Prepared: 03/04/2015 Analyzed: 03/06/2015 02:55				
PCB-1242	720	61	mg/kg dry	906	61.9-148	20 M1, D
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1927	59.1-127	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1460	77.4-119	DO



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Classical Chemistry Parameters - Quality Control
ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch A503010 - % Solids

Duplicate (A503010-DUP1)	Source: A151002-01	Prepared: 03/04/2015	Analyzed: 03/05/2015 08:15
% Solids	82.3	0.00 % by Weight	84.2 2.28 20



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

- M1 Spike recoveries were not evaluated because of elevated levels of the spiked analyte in the parent sample.
- DO Diluted out.
- D Data reported from a dilution
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
- RPD Relative Percent Difference



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 1

Project Number: W1001368

Project Name: Madison Kipp

Project Location: Madison, WI

Turn Around (circle one): Normal Rush

If Rush, Report Due Date:

Sampled By (Print): Jay Read

Lab Work Order #:

A151002

Mail Report To: Chris Kubacki

Company: ARCADES

Address:

E-mail Address: chris.kubacki@arcades-ws.com

Invoice To: " " "

Company:

Address:

Analyses Requested

Preservation Codes

Total # of Containers
Matrix

PCBs 6082
PCBs homolog

Comments

Lab ID
Receipt Time

SB-198 (1-2)	3/2/15	13:30	SO	1	X				01
SB-198 (4-5)	3/2/15	13:40	SO	2	X		MS/MSD		02
DUP-1	3/2/15	-	SO	1	X		Duplicate		03
SB-198 (2-8)	3/2/15	13:50	SO	1	X				04
SB-198 (9-10)	3/2/15	14:00	SO	1	X				05
SB-197 (2-3)	3/2/15	14:30	SO	1	X X		per client HOLD		06
SB-197 (5-6)	3/2/15	14:40	SO	1	X X		HOMOLOG		07
SB-197 (6-7)	3/2/15	14:50	SO	1	X X				08
SB-197 (9-10)	3/2/15	14:55	SO	1	X X				09
SB-197 (14-15)	3/2/15	15:05	SO	1	X X				10

Preservation Codes

A=None B=HCL C=H₂SO₄
D=HNO₃ E=EnCore F=Methanol
G=NaOH O=Other (Indicate)

Relinquished By:

ARCADeS

Date:

3/2/15

Time:

1552

Received By:

Jay A. Kipp

Date:

3/2/15

Time:

1552

Relinquished By:

Date:

Time:

Received By:

Date:

Time:

Matrix Codes

A=Air S=Soil W=Water O=Other

Custody Seal: Present/Absent

Intact/Not Intact

Seal #'s

Receipt Temp:

Temp Blank Y N

On ice



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 09, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 03/03/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser
Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Accreditation	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SB-196 (1-2)	A151005-01	Soil	03/03/2015	03/03/2015
SB-196 (5-6)	A151005-02	Soil	03/03/2015	03/03/2015
SB-196 (8-9)	A151005-03	Soil	03/03/2015	03/03/2015
SB-196 (9-10)	A151005-04	Soil	03/03/2015	03/03/2015
SB-196 (12-13)	A151005-05	Soil	03/03/2015	03/03/2015
SB-196 (16.3-17.3)	A151005-06	Soil	03/03/2015	03/03/2015
SB-201 (0.6-1.6)	A151005-07	Soil	03/03/2015	03/03/2015
SB-201 (5-6)	A151005-08	Soil	03/03/2015	03/03/2015
SB-201 (6.8-7.8)	A151005-09	Soil	03/03/2015	03/03/2015
SB-201 (9-10)	A151005-10	Soil	03/03/2015	03/03/2015

CASE NARRATIVE

Sample Receipt Information:

10 samples were received on 3/3/2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (1-2)

A151005-01 (Soil)

Date Sampled
03/03/2015 09:15

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.79	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
PCB-1221	ND	0.44	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
PCB-1232	ND	0.30	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
PCB-1242	86	0.47	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	D
PCB-1248	ND	0.56	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
PCB-1254	ND	0.47	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
PCB-1260	ND	0.26	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	
Total PCBs	86	0.79	11	mg/kg dry	100	03/04/2015	03/06/2015 09:26	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127

03/04/2015 03/06/2015 09:26 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119

03/04/2015 03/06/2015 09:26 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	93.9	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (5-6)

A151005-02 (Soil)

Date Sampled

03/03/2015 09:25

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	18	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
PCB-1221	ND	9.8	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
PCB-1232	ND	6.7	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
PCB-1242	2500	10	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	D
PCB-1248	ND	13	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
PCB-1254	ND	10	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
PCB-1260	ND	5.7	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	
Total PCBs	2500	18	240	mg/kg dry	2000	03/04/2015	03/06/2015 09:52	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 09:52 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 09:52 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	83.9	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (8-9)

A151005-03 (Soil)

Date Sampled

03/03/2015 09:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	39	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
PCB-1221	ND	22	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
PCB-1232	ND	15	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
PCB-1242	4800	23	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	D
PCB-1248	ND	28	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
PCB-1254	ND	23	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
PCB-1260	ND	13	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	
Total PCBs	4800	39	530	mg/kg dry	5000	03/04/2015	03/06/2015 10:18	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 10:18 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 10:18 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	94.9	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (9-10)

A151005-04 (Soil)

Date Sampled

03/03/2015 09:35

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	7.7	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
PCB-1221	ND	4.3	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
PCB-1232	ND	2.9	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
PCB-1242	2300	4.6	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	D
PCB-1248	ND	5.5	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
PCB-1254	ND	4.6	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
PCB-1260	ND	2.5	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	
Total PCBs	2300	7.7	100	mg/kg dry	1000	03/04/2015	03/06/2015 10:44	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 10:44 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 10:44 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	96.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (12-13)

A151005-05 (Soil)

Date Sampled

03/03/2015 09:40

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	7.9	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
PCB-1221	ND	4.4	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
PCB-1232	ND	3.0	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
PCB-1242	2200	4.7	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	D
PCB-1248	ND	5.7	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
PCB-1254	ND	4.7	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
PCB-1260	ND	2.6	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	
Total PCBs	2200	7.9	110	mg/kg dry	1000	03/04/2015	03/06/2015 12:54	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 12:54 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 12:54 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	93.4	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-196 (16.3-17.3)
A151005-06 (Soil)

Date Sampled
03/03/2015 10:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	16	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
PCB-1221	ND	8.7	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
PCB-1232	ND	5.9	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
PCB-1242	3200	9.3	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	D
PCB-1248	ND	11	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
PCB-1254	ND	9.3	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
PCB-1260	ND	5.1	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	
Total PCBs	3200	16	210	mg/kg dry	2000	03/04/2015	03/06/2015 14:13	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 14:13 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 14:13 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	94.6	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (0.6-1.6)

A151005-07 (Soil)

Date Sampled

03/03/2015 10:50

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.0091	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1221	ND	0.0051	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1232	ND	0.0035	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1242	1.2	0.0054	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1248	ND	0.0065	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1254	ND	0.0054	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
PCB-1260	ND	0.0030	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A
Total PCBs	1.2	0.0091	0.12	mg/kg dry	1	03/04/2015	03/06/2015 08:33	EPA 8082A

Surrogate: Decachlorobiphenyl 104 % 59.1-127 03/04/2015 03/06/2015 08:33 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 106 % 77.4-119 03/04/2015 03/06/2015 08:33 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	80.9	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (5-6)

A151005-08 (Soil)

Date Sampled

03/03/2015 11:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	0.35	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
PCB-1221	ND	0.19	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
PCB-1232	ND	0.13	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
PCB-1242	68	0.21	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	D
PCB-1248	ND	0.25	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
PCB-1254	ND	0.21	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
PCB-1260	ND	0.11	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	
Total PCBs	68	0.35	4.7	mg/kg dry	40	03/04/2015	03/06/2015 08:59	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 08:59 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 08:59 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	85.2	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (6.8-7.8)

A151005-09 (Soil)

Date Sampled

03/03/2015 11:25

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	3.2	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
PCB-1221	ND	1.8	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
PCB-1232	ND	1.2	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
PCB-1242	720	1.9	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	D
PCB-1248	ND	2.3	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
PCB-1254	ND	1.9	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
PCB-1260	ND	1.0	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	
Total PCBs	720	3.2	44	mg/kg dry	400	03/04/2015	03/06/2015 14:38	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 14:38 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 14:38 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	91.7	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (9-10)

A151005-10 (Soil)

Date Sampled

03/03/2015 11:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503009

PCB-1016	ND	3.0	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
PCB-1221	ND	1.7	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
PCB-1232	ND	1.1	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
PCB-1242	890	1.8	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	D
PCB-1248	ND	2.2	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
PCB-1254	ND	1.8	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
PCB-1260	ND	0.98	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	
Total PCBs	890	3.0	41	mg/kg dry	400	03/04/2015	03/06/2015 15:04	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 59.1-127 03/04/2015 03/06/2015 15:04 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 77.4-119 03/04/2015 03/06/2015 15:04 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503010

% Solids	98.1	0.00	% by Weight	1	03/04/2015	03/05/2015 08:15	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control

ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A503009 - EPA 3570

Blank (A503009-BLK1)		Prepared: 03/04/2015 Analyzed: 03/06/2015 01:10				
PCB-1016	ND	0.10	mg/kg wet			
PCB-1221	ND	0.10	mg/kg wet			
PCB-1232	ND	0.10	mg/kg wet			
PCB-1242	ND	0.10	mg/kg wet			
PCB-1248	ND	0.10	mg/kg wet			
PCB-1254	ND	0.10	mg/kg wet			
PCB-1260	ND	0.10	mg/kg wet			
Total PCBs	ND	0.10	mg/kg wet			
Surrogate: Decachlorobiphenyl	0.130		mg/kg wet	0.1584	82.2	59.1-127
Surrogate: Tetrachloro-meta-xylene	0.113		mg/kg wet	0.1200	94.0	77.4-119

LCS (A503009-BS1)

		Prepared: 03/04/2015 Analyzed: 03/06/2015 00:44				
PCB-1254	0.927	0.10	mg/kg wet	1.000	92.7	76.4-124
Surrogate: Decachlorobiphenyl	0.130		mg/kg wet	0.1584	81.9	59.1-127
Surrogate: Tetrachloro-meta-xylene	0.120		mg/kg wet	0.1200	100	77.4-119

Matrix Spike (A503009-MS1)

		Source: A151002-02 Prepared: 03/04/2015 Analyzed: 03/06/2015 02:28				
PCB-1242	798	61	mg/kg dry	906	61.9-148	M1, D
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1927	59.1-127	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1460	77.4-119	DO

Matrix Spike Dup (A503009-MSD1)

		Source: A151002-02 Prepared: 03/04/2015 Analyzed: 03/06/2015 02:55				
PCB-1242	720	61	mg/kg dry	906	61.9-148	20 M1, D
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1927	59.1-127	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1460	77.4-119	DO



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Classical Chemistry Parameters - Quality Control
ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A503010 - % Solids

Duplicate (A503010-DUP1)	Source: A151002-01	Prepared: 03/04/2015	Analyzed: 03/05/2015 08:15							
% Solids	82.3	0.00 % by Weight		84.2		2.28		20		

Batch A503015 - % Solids

Duplicate (A503015-DUP1)	Source: A151008-01	Prepared: 03/06/2015	Analyzed: 03/07/2015 10:30							
% Solids	94.9	0.00 % by Weight		95.2		0.315		20		




2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

- M1 Spike recoveries were not evaluated because of elevated levels of the spiked analyte in the parent sample.
- DO Diluted out.
- D Data reported from a dilution
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
- RPD Relative Percent Difference



Environmental Chemistry
Consulting Services, Inc.
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 21 of 1
PJR

Project Number: WI001368		Lab Work Order #:		Mail Report To: Chris Kubacki				
		A151005		Company: ARCADIS				
Project Name: Madison Kipp		Analyses Requested		Address:				
Project Location: Madison, WI		Preservation Codes		E-mail Address: chris.kubacki@arcadis-us.com				
Turn Around (circle one): Normal Rush		Matrix	Total # of Containers	Invoice To:				
If Rush, Report Due Date:				Comments		Company:	Address:	
Sampled By (Print): Jay Read								
Sample Description	Collection		Comments	Lab ID	Lab Receipt Time			
	Date	Time						
SB-196 (1-2)	3/3/15	09:15	50	1 X	01			
SB-196 (5-6)		09:25	1	1 X	02			
SB-196 (8-9)		09:30	1	1 X	03			
SB-196 (9-10)		09:35	1	1 X	04			
SB-196 (12-13)		09:40	1	1 X	05			
SB-196 (16.3-17.3)		10:00	1	1 X	06			
SB-201 (0.6-1.6)		10:50	1	1 X	07			
SB-201 (5-6)		11:00	1	1 X	08			
SB-201 (6-8-7.8)		11:25	1	1 X	09			
SB-201 (9-10)		11:30	1	1 X	10			
Preservation Codes		Relinquished By:	Date: 3/3/15	Time: 1343	Received By:	Date: 3/3/15	Time: 1343	
A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)		/ ARCADIS						
Matrix Codes		Custody Seal: Present/Absent	Intact/Not Intact	Seal #'s	Receipt Temp:			
A=Air S=Soil W=Water O=Other		Shipped Via:			Temp Blank	Y	N	



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 11, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 03/04/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser
Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Accreditation	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SB-198 (12-13)	A151008-01	Soil	03/03/2015	03/04/2015
Dup-2	A151008-02	Soil	03/03/2015	03/04/2015
SB-198 (16-17)	A151008-03	Soil	03/03/2015	03/04/2015
SB-198 (20.4-21.4)	A151008-04	Soil	03/03/2015	03/04/2015
SB-198 (22-23)	A151008-05	Soil	03/03/2015	03/04/2015
SB-202 (1-2)	A151008-06	Soil	03/04/2015	03/04/2015
SB-202 (4-5)	A151008-07	Soil	03/04/2015	03/04/2015
SB-202 (8-9)	A151008-08	Soil	03/04/2015	03/04/2015
SB-202 (10-10.6)	A151008-09	Soil	03/04/2015	03/04/2015
SB-202 (12-12.9)	A151008-10	Soil	03/04/2015	03/04/2015
SB-202 (16-17)	A151008-11	Soil	03/04/2015	03/04/2015
SB-202 (20-21)	A151008-12	Soil	03/04/2015	03/04/2015
SB-202 (22-23)	A151008-13	Soil	03/04/2015	03/04/2015
SB-202 (24.4-25.4)	A151008-14	Soil	03/04/2015	03/04/2015
SB-202 (28-28.7)	A151008-15	Soil	03/04/2015	03/04/2015
SB-197 (16.5-17.5)	A151008-16	Soil	03/04/2015	03/04/2015

CASE NARRATIVE

Sample Receipt Information:

16 samples were received on 3/4/2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (12-13)

A151008-01 (Soil)

Date Sampled
03/03/2015 13:55

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.31	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
PCB-1221	ND	0.17	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
PCB-1232	ND	0.12	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
PCB-1242	63	0.18	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	D
PCB-1248	ND	0.22	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
PCB-1254	ND	0.18	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
PCB-1260	ND	0.10	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	
Total PCBs	63	0.31	4.2	mg/kg dry	40	03/06/2015	03/09/2015 13:50	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138

03/06/2015 03/09/2015 13:50 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142

03/06/2015 03/09/2015 13:50 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	95.2	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Dup-2

A151008-02 (Soil)

Date Sampled

03/03/2015 00:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.78	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
PCB-1221	ND	0.43	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
PCB-1232	ND	0.30	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
PCB-1242	150	0.46	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	D
PCB-1248	ND	0.56	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
PCB-1254	ND	0.46	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
PCB-1260	ND	0.25	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	
Total PCBs	150	0.78	11	mg/kg dry	100	03/06/2015	03/09/2015 14:15	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/06/2015 03/09/2015 14:15 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/06/2015 03/09/2015 14:15 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	94.9	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (16-17)

A151008-03 (Soil)

Date Sampled

03/03/2015 14:15

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.81	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
PCB-1221	ND	0.45	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
PCB-1232	ND	0.31	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
PCB-1242	220	0.48	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	D
PCB-1248	ND	0.58	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
PCB-1254	ND	0.48	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
PCB-1260	ND	0.26	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	
Total PCBs	220	0.81	11	mg/kg dry	100	03/06/2015	03/09/2015 14:40	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/06/2015 03/09/2015 14:40 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/06/2015 03/09/2015 14:40 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	91.2	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (20.4-21.4)
A151008-04 (Soil)

Date Sampled
03/03/2015 14:40

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.80	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
PCB-1221	ND	0.44	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
PCB-1232	ND	0.30	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
PCB-1242	220	0.47	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	D
PCB-1248	ND	0.57	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
PCB-1254	ND	0.47	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
PCB-1260	ND	0.26	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	
Total PCBs	220	0.80	11	mg/kg dry	100	03/06/2015	03/09/2015 15:05	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/06/2015 03/09/2015 15:05 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/06/2015 03/09/2015 15:05 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	93.1	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-198 (22-23)

A151008-05 (Soil)

Date Sampled

03/03/2015 14:45

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0084	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
PCB-1221	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
PCB-1232	ND	0.0032	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
PCB-1242	0.052	0.0050	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	J
PCB-1248	ND	0.0060	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
PCB-1254	ND	0.0050	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
PCB-1260	ND	0.0027	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	
Total PCBs	0.052	0.0084	0.11	mg/kg dry	1	03/06/2015	03/09/2015 16:20	EPA 8082A	J

Surrogate: Decachlorobiphenyl

109 %

66.3-138

03/06/2015

03/09/2015 16:20

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

103 %

61.6-142

03/06/2015

03/09/2015 16:20

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	87.8	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (1-2)

A151008-06 (Soil)

Date Sampled

03/04/2015 11:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0088	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
PCB-1221	ND	0.0049	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
PCB-1232	ND	0.0033	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
PCB-1242	0.052	0.0052	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	J
PCB-1248	ND	0.0063	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
PCB-1254	ND	0.0052	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
PCB-1260	ND	0.0029	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	
Total PCBs	0.052	0.0088	0.12	mg/kg dry	1	03/06/2015	03/09/2015 18:26	EPA 8082A	J

Surrogate: Decachlorobiphenyl

112 %

66.3-138

03/06/2015

03/09/2015 18:26

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

107 %

61.6-142

03/06/2015

03/09/2015 18:26

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	84.0	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



**2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax**

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (4-5)

A151008-07 (Soil)

Date Sampled

03/04/2015 11:05

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0093	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1221	ND	0.0052	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1232	ND	0.0035	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1242	0.68	0.0055	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1248	ND	0.0067	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1254	ND	0.0055	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
PCB-1260	ND	0.0030	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A
Total PCBs	0.68	0.0093	0.13	mg/kg dry	1	03/06/2015	03/09/2015 18:51	EPA 8082A

Surrogate: Tetrachloro-meta-xylene 98.7 % 61.6-142 03/06/2015 03/09/2015 18:51 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids **79.6** 0.00 % by Weight 1 03/06/2015 03/07/2015 10:30 SM 2540B



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (8-9)

A151008-08 (Soil)

Date Sampled

03/04/2015 11:10

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0082	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
PCB-1221	ND	0.0045	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
PCB-1232	ND	0.0031	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
PCB-1242	0.011	0.0049	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	J
PCB-1248	ND	0.0059	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
PCB-1254	ND	0.0049	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
PCB-1260	ND	0.0027	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	
Total PCBs	0.011	0.0082	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:16	EPA 8082A	J

Surrogate: Decachlorobiphenyl

104 %

66.3-138

03/06/2015

03/09/2015 19:16

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

105 %

61.6-142

03/06/2015

03/09/2015 19:16

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	90.2	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (10-10.6)

A151008-09 (Soil)

Date Sampled

03/04/2015 11:20

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0079	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
PCB-1221	ND	0.0044	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
PCB-1242	0.025	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	J
PCB-1248	ND	0.0056	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
PCB-1260	ND	0.0026	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	
Total PCBs	0.025	0.0079	0.11	mg/kg dry	1	03/06/2015	03/09/2015 19:41	EPA 8082A	J

Surrogate: Decachlorobiphenyl

102 %

66.3-138

03/06/2015

03/09/2015 19:41

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

103 %

61.6-142

03/06/2015

03/09/2015 19:41

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	94.1	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (12-12.9)

A151008-10 (Soil)

Date Sampled

03/04/2015 11:25

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0078	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1221	ND	0.0043	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1242	ND	0.0046	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1248	ND	0.0056	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1254	ND	0.0046	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
PCB-1260	ND	0.0025	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A
Total PCBs	ND	0.0078	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:06	EPA 8082A

Surrogate: Decachlorobiphenyl 110 % 66.3-138 03/06/2015 03/09/2015 20:06 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 107 % 61.6-142 03/06/2015 03/09/2015 20:06 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	94.7	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (16-17)

A151008-11 (Soil)

Date Sampled

03/04/2015 11:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0078	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1221	ND	0.0043	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1242	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1248	ND	0.0056	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
PCB-1260	ND	0.0025	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A
Total PCBs	ND	0.0078	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:31	EPA 8082A

Surrogate: Decachlorobiphenyl 107 % 66.3-138 03/06/2015 03/09/2015 20:31 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 102 % 61.6-142 03/06/2015 03/09/2015 20:31 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	94.3	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (20-21)

A151008-12 (Soil)

Date Sampled

03/04/2015 11:40

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0079	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1221	ND	0.0044	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1242	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1248	ND	0.0057	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
PCB-1260	ND	0.0026	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A
Total PCBs	ND	0.0079	0.11	mg/kg dry	1	03/06/2015	03/09/2015 20:56	EPA 8082A

Surrogate: Decachlorobiphenyl 94.9 % 66.3-138 03/06/2015 03/09/2015 20:56 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 95.1 % 61.6-142 03/06/2015 03/09/2015 20:56 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	93.5	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (22-23)

A151008-13 (Soil)

Date Sampled

03/04/2015 11:50

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0082	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1221	ND	0.0045	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1232	ND	0.0031	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1242	ND	0.0049	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1248	ND	0.0058	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1254	ND	0.0049	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
PCB-1260	ND	0.0026	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A
Total PCBs	ND	0.0082	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:21	EPA 8082A

Surrogate: Decachlorobiphenyl 91.4 % 66.3-138 03/06/2015 03/09/2015 21:21 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 103 % 61.6-142 03/06/2015 03/09/2015 21:21 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	90.6	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (24.4-25.4)
A151008-14 (Soil)

Date Sampled
03/04/2015 12:05

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0080	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1221	ND	0.0044	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1242	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1248	ND	0.0057	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
PCB-1260	ND	0.0026	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A
Total PCBs	ND	0.0080	0.11	mg/kg dry	1	03/06/2015	03/09/2015 21:46	EPA 8082A

Surrogate: Decachlorobiphenyl

94.7 %

66.3-138

03/06/2015

03/09/2015 21:46

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

105 %

61.6-142

03/06/2015

03/09/2015 21:46

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	92.7	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-202 (28-28.7)

A151008-15 (Soil)

Date Sampled

03/04/2015 12:10

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	0.0080	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1221	ND	0.0044	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1242	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1248	ND	0.0057	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
PCB-1260	ND	0.0026	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A
Total PCBs	ND	0.0080	0.11	mg/kg dry	1	03/06/2015	03/09/2015 22:11	EPA 8082A

Surrogate: Decachlorobiphenyl 86.8 % 66.3-138 03/06/2015 03/09/2015 22:11 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 97.4 % 61.6-142 03/06/2015 03/09/2015 22:11 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	92.9	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (16.5-17.5)
A151008-16 (Soil)

Date Sampled
03/04/2015 13:55

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503014

PCB-1016	ND	3.1	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
PCB-1221	ND	1.7	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
PCB-1232	ND	1.2	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
PCB-1242	890	1.8	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	D
PCB-1248	ND	2.2	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
PCB-1254	ND	1.8	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
PCB-1260	ND	1.0	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	
Total PCBs	890	3.1	42	mg/kg dry	400	03/06/2015	03/09/2015 13:25	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/06/2015 03/09/2015 13:25 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/06/2015 03/09/2015 13:25 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503015

% Solids	96.3	0.00	% by Weight	1	03/06/2015	03/07/2015 10:30	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control

ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A503014 - EPA 3570

Blank (A503014-BLK1)		Prepared: 03/06/2015 Analyzed: 03/09/2015 13:00				
PCB-1016	ND	0.10	mg/kg wet			
PCB-1221	ND	0.10	mg/kg wet			
PCB-1232	ND	0.10	mg/kg wet			
PCB-1242	ND	0.10	mg/kg wet			
PCB-1248	ND	0.10	mg/kg wet			
PCB-1254	ND	0.10	mg/kg wet			
PCB-1260	ND	0.10	mg/kg wet			
Total PCBs	ND	0.10	mg/kg wet			
Surrogate: Decachlorobiphenyl	0.104		mg/kg wet	0.1200	86.6	66.3-138
Surrogate: Tetrachloro-meta-xylene	0.123		mg/kg wet	0.1200	103	61.6-142

LCS (A503014-BS1)

		Prepared: 03/06/2015 Analyzed: 03/09/2015 12:35				
PCB-1254	0.935	0.10	mg/kg wet	1.000	93.5	74-128
Surrogate: Decachlorobiphenyl	0.105		mg/kg wet	0.1200	87.9	66.3-138
Surrogate: Tetrachloro-meta-xylene	0.125		mg/kg wet	0.1200	104	61.6-142

Matrix Spike (A503014-MS1)

		Source: A151008-03 Prepared: 03/06/2015 Analyzed: 03/09/2015 15:30				
PCB-1242	209	11	mg/kg dry	222	61.9-148	M1, D
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1316	66.3-138	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1316	61.6-142	DO

Matrix Spike Dup (A503014-MSD1)

		Source: A151008-03 Prepared: 03/06/2015 Analyzed: 03/09/2015 15:55				
PCB-1242	158	11	mg/kg dry	222	61.9-148	20
Surrogate: Decachlorobiphenyl	ND		mg/kg dry	0.1316	66.3-138	DO
Surrogate: Tetrachloro-meta-xylene	ND		mg/kg dry	0.1316	61.6-142	DO



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Classical Chemistry Parameters - Quality Control
ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-------

Batch A503015 - % Solids

Duplicate (A503015-DUP1) Source: A151008-01 Prepared: 03/06/2015 Analyzed: 03/07/2015 10:30
% Solids 94.9 0.00 % by Weight 95.2 0.315 20




2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

- X Precision for the matrix spike duplicate, laboratory control sample duplicate or lab duplicate was outside of control limits.
- M1 Spike recoveries were not evaluated because of elevated levels of the spiked analyte in the parent sample.
- J Analyte was detected but is below the reporting limit. The concentration is estimated.
- DO Diluted out.
- D Data reported from a dilution
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
- RPD Relative Percent Difference




**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 1

Project Number:	WI001368
Project Name:	Madison Wipp
Project Location:	Madison WI
Turn Around (circle one):	Normal Rush
If Rush, Report Due Date:	
Sampled By (Print):	J. Read

Sample Description	Collection		Matrix	Total # of Containers	Analyses Requested	Preservation Codes	Comments	Lab ID	Lab Receipt Time
	Date	Time							
SB-198 (12-13)	3/3/15	13:15	SO	1	X	PCBs 6082		01	
DUP-2				1	X		Duplicate	02	
SB-198 (16-17)		14:15		2	X		MS/MSD	03	
SB-198 (20.4-21.4)		14:40		1	X			04	
SB-198 (22-23)		14:45		1	X			05	
SB-202 (1-2)	3/4/15	11:00		1	Y			06	
SB-202 (4-5)		11:05		1	X			07	
SB-202 (8-9)		11:10		1	X			08	
SB-202 (10-10.6)		11:20		1	X			09	
SB-202 (12-12.9)		11:25		1	X			10	
Preservation Codes	Relinquished By:		Date:	Time:	Received By:		Date:	Time:	
A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)			3/4/15	1509			3/4	1509	
Matrix Codes	Custody Seal: Present/Absent		Intact/Not Intact	Seal #'s	Receipt Temp:				
A=Air S=Soil W=Water O=Other	Shipped Via:				Temp Blank	Y	N		



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 2 of 2



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 12, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are revised analytical results for the samples received by the laboratory on 03/05/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser
Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Ac	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SB-201 (12-13)	A151011-01	Soil	03/04/2015	03/05/2015
SB-201 (16-17)	A151011-02	Soil	03/04/2015	03/05/2015
SB-200 (1-2)	A151011-03	Soil	03/05/2015	03/05/2015
SB-200 (5.2-6.2)	A151011-04	Soil	03/05/2015	03/05/2015
SB-200 (6.9-7.9)	A151011-05	Soil	03/05/2015	03/05/2015
SB-200 (10.8-11.8)	A151011-06	Soil	03/05/2015	03/05/2015
SB-200 (13-14)	A151011-07	Soil	03/05/2015	03/05/2015
SB-200 (16-17)	A151011-08	Soil	03/05/2015	03/05/2015
SB-200 (18-19)	A151011-09	Soil	03/05/2015	03/05/2015
Dup-3	A151011-10	Soil	03/05/2015	03/05/2015
SB-200 (22.5-23.5)	A151011-11	Soil	03/05/2015	03/05/2015
SB-199 (1.2-2.2)	A151011-12	Soil	03/05/2015	03/05/2015
SB-199 (5-6)	A151011-13	Soil	03/05/2015	03/05/2015
SB-199 (6.3-7.3)	A151011-14	Soil	03/05/2015	03/05/2015
SB-199 (9.9-10.9)	A151011-15	Soil	03/05/2015	03/05/2015
SB-199 (12-13)	A151011-16	Soil	03/05/2015	03/05/2015
SB-199 (16-17)	A151011-17	Soil	03/05/2015	03/05/2015
SB-199 (17.7-18.7)	A151011-18	Soil	03/05/2015	03/05/2015

CASE NARRATIVE

Sample Receipt Information:

18 samples were received on 3/5/2015. Samples were received at 0.8 degrees Celsius. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.

Reason for Revised Report

This report was revised to remove the reported surrogate recoveries for sample A151011-03. Surrogates are not reported for samples analyzed at an initial dilution of greater than 1:10 and are qualified as diluted out. This report should replace "A 151011 FINAL 03 12 2015 1139".



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (12-13)

Date Sampled

A151011-01 (Soil)

03/04/2015 15:05

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	7.7	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
PCB-1221	ND	4.3	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
PCB-1232	ND	2.9	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
PCB-1242	1300	4.6	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	D
PCB-1248	ND	5.5	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
PCB-1254	ND	4.6	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
PCB-1260	ND	2.5	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	
Total PCBs	1300	7.7	100	mg/kg dry	1000	03/09/2015	03/10/2015 13:56	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 13:56 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 13:56 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	96.4	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-201 (16-17)

A151011-02 (Soil)

Date Sampled
03/04/2015 15:25

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	8.3	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
PCB-1221	ND	4.6	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
PCB-1232	ND	3.1	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
PCB-1242	2900	4.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	D
PCB-1248	ND	5.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
PCB-1254	ND	4.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
PCB-1260	ND	2.7	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	
Total PCBs	2900	8.3	110	mg/kg dry	1000	03/09/2015	03/10/2015 14:21	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 14:21 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 14:21 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	89.5	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (1-2)

A151011-03 (Soil)

Date Sampled
03/05/2015 09:15

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	1.8	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
PCB-1221	ND	0.99	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
PCB-1232	ND	0.67	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
PCB-1242	ND	1.1	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
PCB-1248	210	1.3	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	D
PCB-1254	ND	1.1	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
PCB-1260	ND	0.58	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	
Total PCBs	210	1.8	24	mg/kg dry	200	03/09/2015	03/10/2015 15:13	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 15:13 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 15:13 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	83.0	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (5.2-6.2)

A151011-04 (Soil)

Date Sampled
03/05/2015 09:20

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	1.7	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
PCB-1221	ND	0.93	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
PCB-1232	ND	0.64	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
PCB-1242	ND	1.0	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
PCB-1248	200	1.2	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	D
PCB-1254	ND	1.0	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
PCB-1260	ND	0.55	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	
Total PCBs	200	1.7	23	mg/kg dry	200	03/09/2015	03/10/2015 17:22	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 17:22 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 17:22 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	87.8	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (6.9-7.9)

A151011-05 (Soil)

Date Sampled
03/05/2015 09:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	3.1	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
PCB-1221	ND	1.7	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
PCB-1232	ND	1.2	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
PCB-1242	910	1.8	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	D
PCB-1248	ND	2.2	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
PCB-1254	ND	1.8	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
PCB-1260	ND	1.0	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	
Total PCBs	910	3.1	42	mg/kg dry	400	03/09/2015	03/10/2015 17:47	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 17:47 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 17:47 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	95.5	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (10.8-11.8)
A151011-06 (Soil)

Date Sampled
03/05/2015 09:35

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	0.30	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
PCB-1221	ND	0.17	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
PCB-1232	ND	0.11	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
PCB-1242	97	0.18	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	D
PCB-1248	ND	0.22	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
PCB-1254	ND	0.18	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
PCB-1260	ND	0.098	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	
Total PCBs	97	0.30	4.1	mg/kg dry	40	03/09/2015	03/10/2015 13:06	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 13:06 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 13:06 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	97.5	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (13-14)

A151011-07 (Soil)

Date Sampled
03/05/2015 10:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	7.7	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
PCB-1221	ND	4.3	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
PCB-1232	ND	2.9	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
PCB-1242	1500	4.6	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	D
PCB-1248	ND	5.5	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
PCB-1254	ND	4.6	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
PCB-1260	ND	2.5	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	
Total PCBs	1500	7.7	100	mg/kg dry	1000	03/09/2015	03/10/2015 18:12	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 18:12 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 18:12 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	96.1	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (16-17)

A151011-08 (Soil)

Date Sampled
03/05/2015 10:10

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	8.3	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
PCB-1221	ND	4.6	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
PCB-1232	ND	3.1	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
PCB-1242	1700	4.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	D
PCB-1248	ND	5.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
PCB-1254	ND	4.9	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
PCB-1260	ND	2.7	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	
Total PCBs	1700	8.3	110	mg/kg dry	1000	03/09/2015	03/10/2015 19:27	EPA 8082A	D

Surrogate: Decachlorobiphenyl

Preparation Batch: A503027

Surrogate: Tetrachloro-meta-xylene

Preparation Batch: A503027

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	89.6	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (18-19)

Date Sampled

A151011-09 (Soil)

03/05/2015 10:20

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	0.0078	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1221	ND	0.0043	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1232	ND	0.0029	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1242	1.0	0.0046	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1248	ND	0.0056	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1254	ND	0.0046	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
PCB-1260	ND	0.0025	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A
Total PCBs	1.0	0.0078	0.11	mg/kg dry	1	03/09/2015	03/10/2015 11:51	EPA 8082A

Surrogate: Decachlorobiphenyl

99.2 %

66.3-138

03/09/2015

03/10/2015 11:51

EPA 8082A

Surrogate: Tetrachloro-meta-xylene

99.1 %

61.6-142

03/09/2015

03/10/2015 11:51

EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	94.9	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Dup-3

A151011-10 (Soil)

Date Sampled
03/05/2015 00:00

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	0.0078	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1221	ND	0.0043	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1232	ND	0.0030	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1242	1.7	0.0047	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1248	ND	0.0056	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1254	ND	0.0047	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
PCB-1260	ND	0.0025	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A
Total PCBs	1.7	0.0078	0.11	mg/kg dry	1	03/09/2015	03/10/2015 12:16	EPA 8082A

Surrogate: Decachlorobiphenyl

103 %

66.3-138

03/09/2015 03/10/2015 12:16 EPA 8082A

Surrogate: Tetrachloro-meta-xylene

98.2 %

61.6-142

03/09/2015 03/10/2015 12:16 EPA 8082A

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	94.6	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-200 (22.5-23.5)

A151011-11 (Soil)

Date Sampled
03/05/2015 10:30

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	1.6	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
PCB-1221	ND	0.87	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
PCB-1232	ND	0.59	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
PCB-1242	360	0.93	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	D
PCB-1248	ND	1.1	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
PCB-1254	ND	0.93	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
PCB-1260	ND	0.51	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	
Total PCBs	360	1.6	21	mg/kg dry	200	03/09/2015	03/10/2015 19:52	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 19:52 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 19:52 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	94.8	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (1.2-2.2)

A151011-12 (Soil)

Date Sampled
03/05/2015 10:50

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	18	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
PCB-1221	ND	10	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
PCB-1232	ND	6.8	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
PCB-1242	4500	11	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	D
PCB-1248	ND	13	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
PCB-1254	ND	11	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
PCB-1260	ND	5.8	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	
Total PCBs	4500	18	240	mg/kg dry	2000	03/09/2015	03/10/2015 20:17	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 20:17 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 20:17 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	82.1	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (5-6)

A151011-13 (Soil)

Date Sampled
03/05/2015 10:55

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	8.9	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
PCB-1221	ND	4.9	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
PCB-1232	ND	3.4	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
PCB-1242	1500	5.3	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	D
PCB-1248	ND	6.4	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
PCB-1254	ND	5.3	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
PCB-1260	ND	2.9	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	
Total PCBs	1500	8.9	120	mg/kg dry	1000	03/09/2015	03/10/2015 20:42	EPA 8082A	D

Surrogate: Decachlorobiphenyl

Surrogate: Tetrachloro-meta-xylene

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	83.1	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (6.3-7.3)

A151011-14 (Soil)

Date Sampled
03/05/2015 11:05

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	8.0	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
PCB-1221	ND	4.4	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
PCB-1232	ND	3.0	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
PCB-1242	1500	4.8	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	D
PCB-1248	ND	5.8	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
PCB-1254	ND	4.8	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
PCB-1260	ND	2.6	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	
Total PCBs	1500	8.0	110	mg/kg dry	1000	03/09/2015	03/10/2015 21:07	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 21:07 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 21:07 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	92.2	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (9.9-10.9)

A151011-15 (Soil)

Date Sampled
03/05/2015 11:15

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	16	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
PCB-1221	ND	8.7	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
PCB-1232	ND	5.9	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
PCB-1242	4600	9.3	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	D
PCB-1248	ND	11	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
PCB-1254	ND	9.3	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
PCB-1260	ND	5.1	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	
Total PCBs	4600	16	210	mg/kg dry	2000	03/09/2015	03/10/2015 23:13	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 23:13 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 23:13 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	94.6	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
----------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (12-13)

A151011-16 (Soil)

Date Sampled
03/05/2015 14:55

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	0.66	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
PCB-1221	ND	0.36	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
PCB-1232	ND	0.25	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
PCB-1242	120	0.39	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	D
PCB-1248	ND	0.47	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
PCB-1254	ND	0.39	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
PCB-1260	ND	0.21	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	
Total PCBs	120	0.66	8.9	mg/kg dry	80	03/09/2015	03/10/2015 13:31	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 13:31 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 13:31 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	89.9	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

Revised Report

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (16-17)

A151011-17 (Soil)

Date Sampled
03/05/2015 15:10

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	1.6	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
PCB-1221	ND	0.88	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
PCB-1232	ND	0.60	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
PCB-1242	410	0.95	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	D
PCB-1248	ND	1.1	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
PCB-1254	ND	0.95	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
PCB-1260	ND	0.52	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	
Total PCBs	410	1.6	22	mg/kg dry	200	03/09/2015	03/10/2015 23:38	EPA 8082A	D

Surrogate: Decachlorobiphenyl

% 66.3-138 03/09/2015 03/10/2015 23:38 EPA 8082A DO

Surrogate: Tetrachloro-meta-xylene

% 61.6-142 03/09/2015 03/10/2015 23:38 EPA 8082A DO

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	92.7	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (17.7-18.7)

A151011-18 (Soil)

Date Sampled
03/05/2015 15:15

Analyte	Result	Limit of Detection	Limit of Quantitation	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	--------------------	-----------------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503027

PCB-1016	ND	0.016	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
PCB-1221	ND	0.0086	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
PCB-1232	ND	0.0059	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
PCB-1242	3.5	0.0092	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	D
PCB-1248	ND	0.011	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
PCB-1254	ND	0.0092	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
PCB-1260	ND	0.0050	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	
Total PCBs	3.5	0.016	0.21	mg/kg dry	2	03/09/2015	03/10/2015 12:41	EPA 8082A	D

Surrogate: Decachlorobiphenyl

83.3 %

66.3-138

03/09/2015

03/10/2015 12:41

EPA 8082A

D

Surrogate: Tetrachloro-meta-xylene

99.0 %

61.6-142

03/09/2015

03/10/2015 12:41

EPA 8082A

D

Classical Chemistry Parameters

Preparation Batch: A503026

% Solids	95.2	0.00	% by Weight	1	03/09/2015	03/11/2015 09:00	SM 2540B
-----------------	-------------	------	-------------	---	------------	------------------	----------



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control

ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC %REC	RPD Limits	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	-----------	------------	-----------	-------

Batch A503027 - EPA 3570

Blank (A503027-BLK1)

Prepared: 03/09/2015 Analyzed: 03/10/2015 11:26

PCB-1016	ND	0.10	mg/kg wet						
PCB-1221	ND	0.10	mg/kg wet						
PCB-1232	ND	0.10	mg/kg wet						
PCB-1242	ND	0.10	mg/kg wet						
PCB-1248	ND	0.10	mg/kg wet						
PCB-1254	ND	0.10	mg/kg wet						
PCB-1260	ND	0.10	mg/kg wet						
Total PCBs	ND	0.10	mg/kg wet						
<i>Surrogate: Decachlorobiphenyl</i>	0.113		mg/kg wet	0.1200		94.0	66.3-138		
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.110		mg/kg wet	0.1200		91.6	61.6-142		

LCS (A503027-BS1)

Prepared: 03/09/2015 Analyzed: 03/10/2015 11:01

PCB-1254	0.890	0.10	mg/kg wet	1.000		89.0	74-128		
<i>Surrogate: Decachlorobiphenyl</i>	0.105		mg/kg wet	0.1200		87.3	66.3-138		
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.104		mg/kg wet	0.1200		86.9	61.6-142		

Matrix Spike (A503027-MS1)

Source: A151011-07 Prepared: 03/09/2015 Analyzed: 03/10/2015 18:37

PCB-1242	1510	100	mg/kg dry	1530		61.9-148	D
PCB-1254	ND	100	mg/kg dry	1.040	ND	50.3-155	DO, M1
<i>Surrogate: Decachlorobiphenyl</i>	ND		mg/kg dry	0.1249		66.3-138	DO
<i>Surrogate: Tetrachloro-meta-xylene</i>	ND		mg/kg dry	0.1249		61.6-142	DO

Matrix Spike Dup (A503027-MSD1)

Source: A151011-07 Prepared: 03/09/2015 Analyzed: 03/10/2015 19:02

PCB-1242	1480	100	mg/kg dry	1530		61.9-148	20	D
PCB-1254	ND	100	mg/kg dry	1.040	ND	50.3-155	20	DO, M1
<i>Surrogate: Decachlorobiphenyl</i>	ND		mg/kg dry	0.1249		66.3-138	DO	
<i>Surrogate: Tetrachloro-meta-xylene</i>	ND		mg/kg dry	0.1249		61.6-142	DO	



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Classical Chemistry Parameters - Quality Control

ECCS

Analyte	Result	Limit of Quantitation	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A503026 - % Solids

Duplicate (A503026-DUP1) Source: A151011-07 Prepared: 03/09/2015 Analyzed: 03/11/2015 09:00
% Solids 95.5 0.00 % by Weight 96.1 0.613 20



Revised Report

2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

M1	Spike recoveries were not evaluated because of elevated levels of the spiked analyte in the parent sample.
DO	Diluted out.
D	Data reported from a dilution
ND	Analyte NOT DETECTED at or above the reporting limit
NR	Not Reported
dry	Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
RPD	Relative Percent Difference




**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 1

 Madison, WI 53718 608-221-8700 (phone) 608-221-4889 (fax)		Lab Work Order #: A151011		Mail Report To: Chris Kubacki Company: ARCADIS Address: Milwaukee			
Project Number: WZ001368		Analyses Requested					
Project Name: Madison Kipp		Preservation Codes					
Project Location: Madison, WI		A	A				
Turn Around (circle one): Normal Rush		Matrix Total # of Containers	PCBs <small>6082</small> <small>PCBs, lead, Ag</small>	E-mail Address: chris.kubacki@arcadis-us.com Invoice To: cc cc Company: Address:			
If Rush, Report Due Date:							
Sampled By (Print): J. Read							
Sample Description	Collection		Comments	Lab ID	Lab Receipt Time		
	Date	Time					
SB-201 (12-13)	3/4/15	15:05	SD	1	X		01
SB-201 (16-17)	3/4/15	15:25		1	X		02
SB-200 (1-2)	3/5/15	0915		1	X		03
SB-200 (5-2-6-2)		0920		1	X		04
SB-200 (6-9-7-9)		0930		1	X		05
SB-200 (10.8-11.8)		0935		1	X		06
SB-200 (13-14) MG/MSD		10:00		2	X	MS/MSD	07
SB-200 (16-17)		10:10		1	X		08
SB-200 (18-19)		10:20		1	X		09
DUP-3	✓	-	↓	1	X	Duplicate	10
Preservation Codes A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)		Relinquished By:  Date: 3/5/15 Time: 1623		Received By:  Date: 3/5 Time: 1623		Date: 3/5	Time: 1623
Matrix Codes A=Air S=Soil W=Water O=Other		Custody Seal: Present/Absent Present Intact/Not Intact Intact Seal #'s		Receipt Temp: 80C S/N 130492013 Temp Blank (Y) N Exp. 08-09-15			
		Shipped Via: PICK-UP					



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 2 of 1

Project Number: W1001368		Lab Work Order #: A151011				Mail Report To: Chris Kubacki			
Project Name: Madison Kipp		Analyses Requested				Company: ARCADIS			
Project Location: Madison, WI		Preservation Codes				Address: Milwaukee			
Turn Around (circle one): Normal <input checked="" type="radio"/> Rush		Matrix	Total # of Containers	PCB ₁ PCB ₂ PCB ₃ homolog			E-mail Address: chris.kubacki@arcadis-us.com		
If Rush, Report Due Date:							Comments		
Sampled By (Print): J. Read							Company:		
Sample Description		Collection	Date	Time	Matrix	Total # of Containers	Comments	Lab ID	Lab Receipt Time
SB-200 (22.5-23.5)		3/5/15	10:30	50		1 X		11	
SB-199 (1.2-2.2)			10:50			1 XX	hold homolog	12	
SB-199 (5-6)			10:55			1 XX		13	
SB-199 (6-3-7-3)			11:05			1 XX		14	
SB-199 (9-9-10.9)			11:15			1 XX		15	
SB-199 (12-13)			14:55			1 XX		16	
SB-199 (16-17)			15:10			1 XX		17	
SB-199 (17.7-18.7)		↓	15:15	↓		1 XX		18	
								19	Temp
Preservation Codes A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)		Relinquished By: <i>J. Read</i>			Date: 3/5/15	Time: 1625	Received By: <i>John</i>	Date: 3/5	Time: 1623
Matrix Codes A=Air S=Soil W=Water O=Other		Relinquished By:			Date:	Time:	Received By:	Date:	Time:
		Custody Seal: Present/Absent Intact/Not Intact Seal #'s			Receipt Temp: 0.8°C				
		Shipped Via: Pickup			Temp Blank (Y) N				



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 31, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 03/17/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser
Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Ac	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
SB-197 (14-15)	A151210-01	Soil	03/02/2015	03/17/2015
SB-199 (9.9-10.9)	A151210-02	Soil	03/05/2015	03/17/2015

CASE NARRATIVE

Sample Receipt Information:

PCB homolog analysis was added to the samples in this work order on March 17, 2015 by client via email. Samples were removed from the refrigerator and re-logged in on this work order. Samples were originally received on March 2, 2015 and March 5, 2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-197 (14-15)

A151210-01 (Soil)

Date Sampled

03/02/2015 15:05

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ALS Group USA, Corp-NY

160.3 Modified

Preparation Batch: NA

Solids, Total	93.8	1	%	1		03/19/2015 14:04	160.3
							Modified

680

Preparation Batch: 231550

Decachlorobiphenyls, Total	ND	110000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Dichlorobiphenyls, Total	360000	21000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Heptachlorobiphenyls, Total	ND	64000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Hexachlorobiphenyls, Total	ND	43000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Monochlorobiphenyls, Total	ND	21000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Nonachlorobiphenyls, Total	ND	85000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Octachlorobiphenyls, Total	ND	64000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Pentachlorobiphenyls, Total	190000	43000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Tetrachlorobiphenyls, Total	1100000	43000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680
Trichlorobiphenyls, Total	920000	21000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:00	680



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

SB-199 (9.9-10.9)

Date Sampled

A151210-02 (Soil)

03/05/2015 11:15

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ALS Group USA, Corp-NY

160.3 Modified

Preparation Batch: NA

Solids, Total	96.7	1	%	1		03/19/2015 14:04	160.3	
---------------	-------------	---	---	---	--	------------------	-------	--

680

Preparation Batch: 231550

Decachlorobiphenyls, Total	ND	100000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Dichlorobiphenyls, Total	350000	20000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Heptachlorobiphenyls, Total	ND	62000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Hexachlorobiphenyls, Total	ND	42000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Monochlorobiphenyls, Total	ND	20000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Nonachlorobiphenyls, Total	ND	83000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Octachlorobiphenyls, Total	ND	62000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Pentachlorobiphenyls, Total	210000	42000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Tetrachlorobiphenyls, Total	1200000	42000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680
Trichlorobiphenyls, Total	880000	20000	ug/Kg dry	2000	03/19/2015	03/20/2015 11:30	680



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC %REC	Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	-----------	--------	---------	-----------	-------




2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

ND	Analyte NOT DETECTED at or above the reporting limit
NR	Not Reported
dry	Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
RPD	Relative Percent Difference



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 1

A151210

Project Number: W1001368		Lab Work Order #: <u>A151002</u>		Mail Report To: Chris Kubacki					
Project Name: Madison Kipp				Company: ARCADIS					
Project Location: Madison, WI		Analyses Requested		Address:					
Turn Around (circle one): <u>Normal</u> Rush		Preservation Codes		E-mail Address: chris.kubacki@arcadis-us.com					
If Rush, Report Due Date:				Invoice To: "					
Sampled By (Print): Jay Reed				Company:					
				Address:					
Sample Description	Collection		Matrix	Total # of Containers	Comments	Lab ID	Lab Receipt Time		
	Date	Time							
SB-198 (1-2)	3/2/15	13:30	SO	1	X	01			
SB-198 (4-5)	3/2/15	13:40	SO	2	X	02	MS/MSD		
DUP-1	3/2/15	-	SO	1	X	03	Duplicate		
SB-198 (2-8)	3/2/15	13:50	SO	1	X	04			
SB-198 (9-10)	3/2/15	14:00	SO	1	X	05			
SB-197 (2-3)	3/2/15	14:30	SO	1	XX	06	per client HOLD		
SB-197 (5-6)	3/2/15	14:40	SO	1	XX	07	Homolog		
SB-197 (6-7)	3/2/15	14:50	SO	1	XX	08			
SB-197 (9-10)	3/2/15	14:55	SO	1	XX	09			
SB-197 (14-15)	3/2/15	15:05	SO	1	XX	10	Release for Homolog 3/11/15 01		
Preservation Codes		Relinquished By: <u>Jay Reed / ARCADIS</u>		Date: 3/2/15	Time: 1552	Received By: <u>Kris-Jean Kelly</u>	Date: 3/2/15	Time: 1552	
A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)		Relinquished By:		Date:	Time:	Received By:	Date:	Time:	
Matrix Codes		Custody Seal: Present/Absent		Intact/Not Intact		Seal #'s	Receipt Temp:		
A=Air S=Soil W=Water O=Other		Shipped Via: hand del.					Temp Blank Y N in ice		

Download this form at www.eccsmobilelab.com.

WHITE - REPORT COPY YELLOW - LABORATORY COPY PINK - SAMPLER/SUBMITTER

Rev. 11/08



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 2 of 1

Project Number: W1001368		Lab Work Order #: A151210		Mail Report To: Chris Kubacki				
Project Name: Madison Kipp				Company: ARCADIS				
Project Location: Madison, WI				Address: Milwaukee				
Turn Around (circle one): <input checked="" type="radio"/> Normal <input type="radio"/> Rush		Analyses Requested		E-mail Address: chris.kubacki@arcadis-us.com				
If Rush, Report Due Date:		Preservation Codes		Invoice To:				
Sampled By (Print): J. Read		A A		Company:				
Sample Description	Collection		Matrix	Total # of Containers	Comments	Lab ID	Lab Receipt Time	
	Date	Time						
SB-200 (22.5-23.5)	3/5/15	10:30	SO	1	X	11		
SB-199 (1.2-2.2)		10:50		1	XX	12	hold homolog	
SB-199 (5-6)		10:55		1	XX	13		
SB-199 (6.3-7.3)		11:05		1	XX	14		
SB-199 (9.9-10.9)		11:15		1	XX	15	Released for Homolog 3/17/15 02	
SB-199 (12-13)		14:55		1	XX	16		
SB-199 (16-17)		15:10		1	XX	17		
SB-199 (17.7-18.7)	↓	15:15	↓	1	XX	18		
						19	Temp	
Preservation Codes A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)		Relinquished By:		Date: 3/5/15	Time: 1623	Received By:	Date: 3/5	Time: 1623
Matrix Codes A=Air S=Soil W=Water O=Other		Relinquished By:		Date:	Time:	Received By:	Date:	Time:
		Custody Seal: Present/Absent		Intact/Not Intact		Seal #'s	Receipt Temp: 0, 8°C	
		Shipped Via: Pickup					Temp Blank <input checked="" type="radio"/> Y N	

Download this form at www.eccsmobilelab.com.

WHITE - REPORT COPY YELLOW - LABORATORY COPY PINK - SAMPLER/SUBMITTER

Rev. 11/08



ALS Environmental
ALS Group USA, Corp
1565 Jefferson Rd, Building 300, Suite 360
Rochester, NY 14623
T: 585-288-5380
F: 585-288-8475
www.alsglobal.com

March 25, 2015

Analytical Report for Service Request No: R1501887

Ms. Jessica Esser
ECCS Nationwide Mobile Laboratories
2525 Advance Road
Madison, WI 53718

Laboratory Results for: Madison Kipp - Madison WI

Dear Ms. Esser:

Enclosed are the results of the sample(s) submitted to our laboratory on March 18, 2015. For your reference, these analyses have been assigned our service request number **R1501887**.

All analyses were performed according to our laboratory's quality assurance program. The test results meet requirements of the NELAP standards except as noted in the case narrative report. All results are intended to be considered in their entirety, and ALS Environmental is not responsible for use of less than the complete report. Results apply only to the items submitted to the laboratory for analysis and individual items (samples) analyzed, as listed in the report. The measurement uncertainty of the results included in this report is within that expected when using the prescribed method(s) for analysis of these samples, and represented by Laboratory Control Sample control limits. Any events, such as QC failures, which may add to the uncertainty are explained in the report narrative..

Please contact me if you have any questions. My extension is 7472. You may also contact me via email at Janice.Jaeger@alsglobal.com.

Respectfully submitted,

ALS Group USA Corp. dba ALS Environmental

A handwritten signature in black ink, appearing to read "Janice Jaeger".

Janice Jaeger
Project Manager

Page 1 of 13

ALS Environmental

Client: ECCS Nationwide Mobile Laboratories
Service Request No.: R1501887
Project: Madison Kipp
Date Received: 3/18/15
Sample Matrix: Soil
Project/Case No.:

CASE NARRATIVE

All analyses were performed consistent with the quality assurance program of ALS Environmental. This report contains analytical results for samples designated for Tier II data deliverables. When appropriate to the method, method blank results have been reported with each analytical test. Surrogate recoveries have been reported for all applicable organic analyses. Additional quality control analyses reported herein include: Laboratory Control Sample (LCS).

Sample Receipt

Soil samples were received for analysis at ALS Environmental on 3/18/15. The samples were received in good condition and consistent with the accompanying chain of custody form. All sampling activities performed by ALS personnel have been in accordance with "ALS Field Procedures and Measurements Manual" or by client specifications. The samples were stored in a refrigerator between 1°C and 6°C upon receipt at the laboratory.

Homologues

Two soil samples were analyzed for Homologues by method 680.

All initial and continuing calibration criteria were met for all analytes.

All Laboratory Control Sample/ Laboratory Control Sample Duplicate (LCS/LCSD) recoveries were within limits.

A151210-01 was received outside the recommended holding time of 14 days as noted by the “*”. The sample was extracted as soon as possible upon receipt.

Site specific QC was not requested for these samples.

All surrogate standard recoveries were diluted out and have been flagged with a "D".

The Method blanks associated with these samples were free of contamination except for a low level detection for Dichlorobiphenyls. No data was affected.

All samples were analyzed within recommended holding times.

No other analytical or QC problems were encountered.

00002

CASE NARRATIVE

This report contains analytical results for the following samples:
Service Request Number: R1501887

<u>Lab ID</u>	<u>Client ID</u>
R1501887-001	A151210-01
R1501887-002	A151210-02



REPORT QUALIFIERS AND DEFINITIONS

- U** Analyte was analyzed for but not detected. The sample quantitation limit has been corrected for dilution and for percent moisture, unless otherwise noted in the case narrative.
- J** Estimated value due to either being a Tentatively Identified Compound (TIC) or that the concentration is between the MRL and the MDL. Concentrations are not verified within the linear range of the calibration. For DoD: concentration >40% difference between two GC columns (pesticides/Aroclors).
- B** Analyte was also detected in the associated method blank at a concentration that may have contributed to the sample result.
- E** Inorganics- Concentration is estimated due to the serial dilution was outside control limits.
- E** Organics- Concentration has exceeded the calibration range for that specific analysis.
- D** Concentration is a result of a dilution, typically a secondary analysis of the sample due to exceeding the calibration range or that a surrogate has been diluted out of the sample and cannot be assessed.
- * Indicates that a quality control parameter has exceeded laboratory limits. Under the "Notes" column of the Form I, this qualifier denotes analysis was performed out of Holding Time.
- H** Analysis was performed out of hold time for tests that have an "immediate" hold time criteria.
- # Spike was diluted out.
- + Correlation coefficient for MSA is <0.995.
- N Inorganics- Matrix spike recovery was outside laboratory limits.
- N Organics- Presumptive evidence of a compound (reported as a TIC) based on the MS library search.
- S Concentration has been determined using Method of Standard Additions (MSA).
- W Post-Digestion Spike recovery is outside control limits and the sample absorbance is <50% of the spike absorbance.
- P Concentration >40% (25% for CLP) difference between the two GC columns.
- C Confirmed by GC/MS
- Q DoD reports: indicates a pesticide/Aroclor is not confirmed ($\geq 100\%$ Difference between two GC columns).
- X See Case Narrative for discussion.
- MRL Method Reporting Limit. Also known as:
LOQ Limit of Quantitation (LOQ)
The lowest concentration at which the method analyte may be reliably quantified under the method conditions.
- MDL Method Detection Limit. A statistical value derived from a study designed to provide the lowest concentration that will be detected 99% of the time. Values between the MDL and MRL are estimated (see J qualifier).
- LOD Limit of Detection. A value at or above the MDL which has been verified to be detectable.
- ND Non-Detect. Analyte was not detected at the concentration listed. Same as U qualifier.



Rochester Lab ID # for State Certifications¹

NELAP Accredited	Maine ID #NY0032	New Hampshire ID # 294100 A/B
Connecticut ID # PH0556	Nebraska Accredited	
Delaware Accredited	Nevada ID # NY-00032	North Carolina #676
DoD ELAP #65817	New Jersey ID # NY004	Pennsylvania ID# 68-786
Florida ID # E87674	New York ID # 10145	Rhode Island ID # 158
Illinois ID #200047		Virginia #460167

¹ Analyses were performed according to our laboratory's NELAP-approved quality assurance program and any applicable state or agency requirements. The test results meet requirements of the current NELAP/TNI standards or state or agency requirements, where applicable, except as noted in the laboratory case narrative provided. For a specific list of accredited analytes, refer to <http://www.alsglobal.com/en/Our-Services/Life-Sciences/Environmental/Downloads/North-America-Downloads>

ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil
Sample Name: A151210-01
Lab Code: R1501887-001

Service Request: R1501887
Date Collected: 3/2/15 1505
Date Received: 3/18/15
Basis: As Received

General Chemistry Parameters

Analyte Name	Method	Result Q	Units	MRL	Dilution Factor	Date Extracted	Date Analyzed	Note
Solids, Total	160.3 Modified	93.8	Percent	1.0	1	NA	3/19/15 14:04	

ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil

Service Request: R1501887
Date Collected: 3/2/15 1505
Date Received: 3/18/15
Date Extracted: 3/19/15
Date Analyzed: 3/20/15 11:00

Sample Name: A151210-01
Lab Code: R1501887-001

Units: µg/Kg
Basis: Dry
Percent Solids: 93.8

Pesticides and PCBs in Water and Soil/Sediment by Gas Chromatography/Mass Spectrometry

Analytical Method: 680
Prep Method: EPA 3541
Data File Name: I:\ACQUDATA\S973B\DATA\032015\DK783.D\

Analysis Lot: 437114
Extraction Lot: 231550
Instrument Name: R-MS-52
Dilution Factor: 2000

CAS No.	Analyte Name	Result Q	MRL	Note
27323-18-8	Monochlorobiphenyls, Total	21000 U	21000	*
25512-42-9	Dichlorobiphenyls, Total	360000	21000	*
25323-68-6	Trichlorobiphenyls, Total	920000	21000	*
26914-33-0	Tetrachlorobiphenyls, Total	1100000	43000	*
25429-29-2	Pentachlorobiphenyls, Total	190000	43000	*
26601-64-9	Hexachlorobiphenyls, Total	43000 U	43000	*
28655-71-2	Heptachlorobiphenyls, Total	64000 U	64000	*
55722-26-4	Octachlorobiphenyls, Total	64000 U	64000	*
53742-07-7	Nonachlorobiphenyls, Total	85000 U	85000	*
2051-24-3	Decachlorobiphenyls, Total	110000 U	110000	*

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
gamma-BHC (Lindane)	0 *	40-135	3/20/15 11:00	D
4,4'-DDT	0 *	22-175	3/20/15 11:00	D



ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil
Sample Name: A151210-02
Lab Code: R1501887-002

Service Request: R1501887
Date Collected: 3/5/15 1115
Date Received: 3/18/15
Basis: As Received

General Chemistry Parameters

Analyte Name	Method	Result Q	Units	MRL	Dilution Factor	Date Extracted	Date Analyzed	Note
Solids, Total	160.3 Modified	96.7	Percent	1.0	1	NA	3/19/15 14:04	

ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil

Service Request: R1501887
Date Collected: 3/5/15 11:15
Date Received: 3/18/15
Date Extracted: 3/19/15
Date Analyzed: 3/20/15 11:30

Sample Name: A151210-02
Lab Code: R1501887-002

Units: µg/Kg
Basis: Dry
Percent Solids: 96.7

Pesticides and PCBs in Water and Soil/Sediment by Gas Chromatography/Mass Spectrometry

Analytical Method: 680
Prep Method: EPA 3541
Data File Name: I:\ACQUDATA\5973B\DATA\032015\DK784.D\

Analysis Lot: 437114
Extraction Lot: 231550
Instrument Name: R-MS-52
Dilution Factor: 2000

CAS No.	Analyte Name	Result Q	MRL	Note
27323-18-8	Monochlorobiphenyls, Total	20000 U	20000	
25512-42-9	Dichlorobiphenyls, Total	350000	20000	
25323-68-6	Trichlorobiphenyls, Total	880000	20000	
26914-33-0	Tetrachlorobiphenyls, Total	1200000	42000	
25429-29-2	Pentachlorobiphenyls, Total	210000	42000	
26601-64-9	Hexachlorobiphenyls, Total	42000 U	42000	
28655-71-2	Heptachlorobiphenyls, Total	62000 U	62000	
55722-26-4	Octachlorobiphenyls, Total	62000 U	62000	
53742-07-7	Nonachlorobiphenyls, Total	83000 U	83000	
2051-24-3	Decachlorobiphenyls, Total	100000 U	100000	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
gamma-BHC (Lindane)	0 *	40-135	3/20/15 11:30	D
4,4'-DDT	0 *	22-175	3/20/15 11:30	D

ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
 Project: Madison Kipp - Madison WI
 Sample Matrix: Soil
 Sample Name: Method Blank
 Lab Code: R1501887-MB
 Service Request: R1501887
 Date Collected: NA
 Date Received: NA
 Basis: As Received

General Chemistry Parameters

Analyte Name	Method	Result Q	Units	MRL	Dilution Factor	Date Extracted	Date Analyzed	Note
Solids, Total	160.3 Modified	1.0 U	Percent	1.0	1	NA	3/19/15 14:04	



ALS Group USA, Corp. dba ALS Environmental

Analytical Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil

Service Request: R1501887
Date Collected: NA
Date Received: NA
Date Extracted: 3/19/15
Date Analyzed: 3/20/15 08:35

Sample Name: Method Blank
Lab Code: RQ1502629-01

Units: µg/Kg
Basis: Dry

Pesticides and PCBs in Water and Soil/Sediment by Gas Chromatography/Mass Spectrometry

Analytical Method: 680
Prep Method: EPA 3541
Data File Name: I:\ACQUADATA\5973B\DATA\032015\DK778.D\

Analysis Lot: 437114
Extraction Lot: 231550
Instrument Name: R-MS-52
Dilution Factor: 1

CAS No.	Analyte Name	Result Q	MRL	Note
27323-18-8	Monochlorobiphenyls, Total	0.33 U	0.33	
25512-42-9	Dichlorobiphenyls, Total	0.43	0.33	
25323-68-6	Trichlorobiphenyls, Total	0.33 U	0.33	
26914-33-0	Tetrachlorobiphenyls, Total	0.67 U	0.67	
25429-29-2	Pentachlorobiphenyls, Total	0.67 U	0.67	
26601-64-9	Hexachlorobiphenyls, Total	0.67 U	0.67	
28655-71-2	Heptachlorobiphenyls, Total	1.0 U	1.0	
55722-26-4	Octachlorobiphenyls, Total	1.0 U	1.0	
53742-07-7	Nonachlorobiphenyls, Total	1.3 U	1.3	
2051-24-3	Dccachlorobiphenyls, Total	1.7 U	1.7	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
gamma-BHC (Lindane)	67	40-135	3/20/15 08:35	
4,4'-DDT	90	22-175	3/20/15 08:35	

ALS Group USA, Corp. dba ALS Environmental

QA/QC Report

Client: ECCS Nationwide Mobile Laboratories
Project: Madison Kipp - Madison WI
Sample Matrix: Soil

Service Request: R1501887
Date Analyzed: 3/20/15

Lab Control Sample Summary

Pesticides and PCBs in Water and Soil/Sediment by Gas Chromatography/Mass Spectrometry

Analytical Method: 680
Prep Method: EPA 3541

Units: $\mu\text{g/Kg}$
Basis: Dry

Extraction Lot: 231550

Analyte Name	Lab Control Sample			Duplicate Lab Control Sample					
	RQ1502629-02			RQ1502629-03					
	Result	Spike Amount	% Rec	Result	Spike Amount	% Rec	% Rec Limits	RPD	RPD Limit
Monochlorobiphenyls, Total	8.33	16.7	50	8.00	16.7	48	10 - 108	4	30
Dichlorobiphenyls, Total	8.67	16.7	52	9.00	16.7	54	13 - 121	4	30
Trichlorobiphenyls, Total	8.67	16.7	52	8.67	16.7	52	25 - 118	<1	30
Tetrachlorobiphenyls, Total	17.0	33.3	51	17.3	33.3	52	19 - 119	2	30
Pentachlorobiphenyls, Total	17.7	33.3	53	18.0	33.3	54	15 - 168	2	30
Hexachlorobiphenyls, Total	17.7	33.3	53	17.3	33.3	52	10 - 180	2	30
Heptachlorobiphenyls, Total	27.0	50.0	54	26.3	50.0	53	15 - 181	3	30
Octachlorobiphenyls, Total	26.3	50.0	53	26.3	50.0	53	25 - 150	<1	30
Decachlorobiphenyls, Total	41.0	83.3	49	44.0	83.3	53	39 - 137	7	30

Results flagged with an asterisk (*) indicate values outside control criteria.

Percent recoveries and relative percent differences (RPD) are determined by the software using values in the calculation which have not been rounded.



SUBCONTRACT ORDER

ECCS

A151210

R1501887
ECCS Nationwide Mobile Laboratories
Madison Kipp - Madison WI

5

SENDING LABORATORY:

ECCS
2525 Advance Road
Madison, WI 53718
Phone: 608.221.8700
Fax: 608.221.4889
Project Manager: Jessica Esser

RECEIVING LABORATORY:

ALS Group USA, Corp-NY
1565 Jefferson Road
Rochester, NY 14623
Phone :(585) 288-5380
Fax: (585) 288-8475

Turn around Time: Normal Rush

Project Name: Madison Kipp - Madison, WI

		Laboratory ID	Comments
Lab ID: A151210-01	Soil	Sampled: 03/02/2015 15:05	<input type="text"/>
Subcontracted Analysis			PCB Homolog (680)
Containers Supplied:	03_4oz WM Amber Glass		
Lab ID: A151210-02	Soil	Sampled: 03/05/2015 11:15	<input type="text"/>
Subcontracted Analysis			PCB Homolog (680)
Containers Supplied:			

Kari-Anne Kippin 3/17/15 3/18/15 0935
Released By Date Received By Date
Kari-Anne Kippin *3/17/15* *3/18/15* *0935*

Released By Date Received By Date
Kari-Anne Kippin *3/17/15* *3/18/15* *0935*

00012 Page 1 of 1



Cooler Receipt and Preservation Check Form

R1501887 5
ECCS Nationwide Mobile Laboratories
Madison Kipp - Madison WI

Project/Client ECCS Folder Number R15-1887

Cooler received on 3/18/15 by: R

COURIER: ALS UPS FEDEX VELOCITY CLIENT

1	Were Custody seals on outside of cooler?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	5a	Perchlorate samples have required headspace?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N <input checked="" type="checkbox"/> NA
2	Custody papers properly completed (ink, signed)?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	5b	Did VOA vials, Alk, or Sulfide have sig* bubbles?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N <input checked="" type="checkbox"/> NA
3	Did all bottles arrive in good condition (unbroken)?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	6	Where did the bottles originate? <u>ALS/ROC</u>	<input checked="" type="checkbox"/> CLIENT
4	Circle: <u>Wet Ice</u> Dry Ice Gel packs present?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	7	Soil VOA received as:	Bulk Encore 5035set <input checked="" type="checkbox"/> NA

8. Temperature Readings Date: 3/18/15 Time: 0949 ID: R# IR#4 From: Temp Blank Sample Bottle

Observed Temp (°C)	<u>1.8</u>						
Correction Factor (°C)	<u>-</u>						
Corrected Temp (°C)	<u>1.8</u>						
Within 0-6°C?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N					

If out of Temperature, note packing/ice condition: Ice melted Poorly Packed Same Day Rule

& Client Approval to Run Samples: Standing Approval Client aware at drop-off Client notified by: _____

All samples held in storage location:	<u>R-002</u>	by	<u>R</u>	on	<u>3/18/15</u>	at	<u>0950</u>
5035 samples placed in storage location:		by		on		at	

PC Secondary Review: MMS 3/18/15

Cooler Breakdown: Date: 3/18/15 Time: 1405 by: R

1. Were all bottle labels complete (i.e. analysis, preservation, etc.)? YES NO
2. Did all bottle labels and tags agree with custody papers? YES NO
3. Were correct containers used for the tests indicated? YES NO
4. Air Samples: Cassettes / Tubes Intact Canisters Pressurized Tedlar® Bags Inflated N/A

Explain any discrepancies:

pH	Reagent	Yes	No	Lot Received	Exp	Sample ID	Vol. Added	Lot Added	Final pH
≥12	NaOH								
≤2	HNO ₃								
≤2	H ₂ SO ₄								
<4	NaHSO ₄								
Residual Chlorine (-)	For CN Phenol and 522			If +, contact PM to add Na ₂ S ₂ O ₃ (CN), ascorbic (phenol).					
	Na ₂ S ₂ O ₃	-	-						
	ZnAcetate	-	-						
	HCl	**	**						

**Not to be tested before analysis – pH tested and recorded by VOAs on a separate worksheet

Yes=All samples OK

No=Samples were preserved at The lab as listed

PM OK to Adjust:

Bottle lot numbers: 101314-13N4

Other Comments:

* limited volume

PC Secondary Review: MMS 3/24/15 Significant air bubbles: VOA > 5-6 mm : WC > 1 in. diameter

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING



ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Chicago

2417 Bond Street

University Park, IL 60484

Tel: (708)534-5200

TestAmerica Job ID: 500-93379-1

Client Project/Site: MadisonKipp Corp WI001368.0024.00001

For:

ARCADIS U.S., Inc.

126 North Jefferson Street

Suite 400

Milwaukee, Wisconsin 53202

Attn: Chris Kubacki

Therese Hargraves

Authorized for release by:

3/25/2015 5:04:12 PM

Therese Hargraves, Project Manager I

therese.hargraves@testamericainc.com

Designee for

Sandie Fredrick, Project Manager II

(920)261-1660

sandie.fredrick@testamericainc.com

LINKS

Review your project
results through

Total Access

Have a Question?

Ask
The
Expert

Visit us at:

www.testamericainc.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

Table of Contents

Cover Page	1
Table of Contents	2
Case Narrative	3
Detection Summary	4
Method Summary	5
Sample Summary	6
Client Sample Results	7
Definitions	8
QC Association	9
Surrogate Summary	10
QC Sample Results	11
Chronicle	12
Certification Summary	13
Chain of Custody	14
Receipt Checklists	15

Case Narrative

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Job ID: 500-93379-1

Laboratory: TestAmerica Chicago

Narrative

**Job Narrative
500-93379-1**

Comments

No additional comments.

Receipt

The sample was received on 3/17/2015 10:00 AM; the sample arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 3.2° C.

GC Semi VOA

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Field Service / Mobile Lab

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Organic Prep

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Detection Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Client Sample ID: MW-28

Lab Sample ID: 500-93379-1

No Detections.

This Detection Summary does not include radiochemical test results.

TestAmerica Chicago

Method Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Method	Method Description	Protocol	Laboratory
8082	Polychlorinated Biphenyls (PCBs) by Gas Chromatography	SW846	TAL CHI

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL CHI = TestAmerica Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Sample Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
500-93379-1	MW-28	Water	03/13/15 12:40	03/17/15 10:00

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

TestAmerica Chicago

Client Sample Results

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Client Sample ID: MW-28

Lab Sample ID: 500-93379-1

Date Collected: 03/13/15 12:40

Matrix: Water

Date Received: 03/17/15 10:00

Method: 8082 - Polychlorinated Biphenyls (PCBs) by Gas Chromatography - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	<0.068		0.40	0.068	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1221	<0.20		0.40	0.20	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1232	<0.20		0.40	0.20	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1242	<0.20		0.40	0.20	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1248	<0.20		0.40	0.20	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1254	<0.20		0.40	0.20	ug/L		03/18/15 11:26	03/19/15 08:33	1
PCB-1260	<0.071		0.40	0.071	ug/L		03/18/15 11:26	03/19/15 08:33	1
Surrogate							Prepared	Analyzed	Dil Fac
Tetrachloro-m-xylene	62			50 - 120			03/18/15 11:26	03/19/15 08:33	1
DCB Decachlorobiphenyl	86			29 - 126			03/18/15 11:26	03/19/15 08:33	1

Definitions/Glossary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Glossary

Abbreviation These commonly used abbreviations may or may not be present in this report.

□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

QC Association Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

GC Semi VOA

Prep Batch: 280198

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-93379-1	MW-28	Dissolved	Water	3510C	
LCS 500-280198/2-A	Lab Control Sample	Total/NA	Water	3510C	
LCSD 500-280198/3-A	Lab Control Sample Dup	Total/NA	Water	3510C	
MB 500-280198/1-A	Method Blank	Total/NA	Water	3510C	

Analysis Batch: 280241

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
500-93379-1	MW-28	Dissolved	Water	8082	280198
LCS 500-280198/2-A	Lab Control Sample	Total/NA	Water	8082	280198
LCSD 500-280198/3-A	Lab Control Sample Dup	Total/NA	Water	8082	280198
MB 500-280198/1-A	Method Blank	Total/NA	Water	8082	280198

Surrogate Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Method: 8082 - Polychlorinated Biphenyls (PCBs) by Gas Chromatography

Matrix: Water

Prep Type: Total/NA

Lab Sample ID	Client Sample ID	Percent Surrogate Recovery (Acceptance Limits)				
		TCX2 (50-120)	DCB2 (29-126)			
LCS 500-280198/2-A	Lab Control Sample	88	91			
LCSD 500-280198/3-A	Lab Control Sample Dup	91	80			
MB 500-280198/1-A	Method Blank	88	69			

Surrogate Legend

TCX = Tetrachloro-m-xylene

DCB = DCB Decachlorobiphenyl

Method: 8082 - Polychlorinated Biphenyls (PCBs) by Gas Chromatography

Matrix: Water

Prep Type: Dissolved

		Percent Surrogate Recovery (Acceptance Limits)			
Lab Sample ID	Client Sample ID	TCX2 (50-120)	DCB2 (29-126)		
500-93379-1	MW-28	62	86		

Surrogate Legend

TCX = Tetrachloro-m-xylene

DCB = DCB Decachlorobiphenyl

QC Sample Results

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Method: 8082 - Polychlorinated Biphenyls (PCBs) by Gas Chromatography

Lab Sample ID: MB 500-280198/1-A

Matrix: Water

Analysis Batch: 280241

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 280198

Analyte	MB	MB	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier									
PCB-1016	<0.067		0.40		0.067	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1221	<0.20		0.40		0.20	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1232	<0.20		0.40		0.20	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1242	<0.20		0.40		0.20	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1248	<0.20		0.40		0.20	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1254	<0.20		0.40		0.20	ug/L			03/18/15 11:26	03/18/15 15:37	1
PCB-1260	<0.070		0.40		0.070	ug/L			03/18/15 11:26	03/18/15 15:37	1

Surrogate	MB	MB	%Recovery	Qualifier	Limits			Prepared	Analyzed	Dil Fac
	Result	Qualifier								
Tetrachloro-m-xylene	88		50 - 120					03/18/15 11:26	03/18/15 15:37	1
DCB Decachlorobiphenyl	69		29 - 126					03/18/15 11:26	03/18/15 15:37	1

Lab Sample ID: LCS 500-280198/2-A

Matrix: Water

Analysis Batch: 280241

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 280198

Analyte	MB	MB	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	Limits	%Rec.
	Result	Qualifier								
PCB-1016			4.00	3.35		ug/L		84	70 - 130	
PCB-1260			4.00	3.60		ug/L		90	70 - 130	
Surrogate	MB	MB	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	Limits	%Rec.
	Result	Qualifier								
Tetrachloro-m-xylene	88		50 - 120							
DCB Decachlorobiphenyl	91		29 - 126							

Lab Sample ID: LCSD 500-280198/3-A

Matrix: Water

Analysis Batch: 280241

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Prep Batch: 280198

Analyte	LCSD	LCSD	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	Limits	RPD	Limit
	Result	Qualifier									
PCB-1016			4.00	3.72		ug/L		93	70 - 130	10	20
PCB-1260			4.00	3.62		ug/L		90	70 - 130	0	20
Surrogate	LCSD	LCSD	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	Limits	RPD	Limit
	Result	Qualifier									
Tetrachloro-m-xylene	91		50 - 120								
DCB Decachlorobiphenyl	80		29 - 126								

TestAmerica Chicago

Lab Chronicle

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Client Sample ID: MW-28

Lab Sample ID: 500-93379-1

Date Collected: 03/13/15 12:40

Matrix: Water

Date Received: 03/17/15 10:00

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Dissolved	Prep	3510C			280198	03/18/15 11:26	SML	TAL CHI
Dissolved	Analysis	8082		1	280241	03/19/15 08:33	GMO	TAL CHI

Laboratory References:

TAL CHI = TestAmerica Chicago, 2417 Bond Street, University Park, IL 60484, TEL (708)534-5200

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Certification Summary

Client: ARCADIS U.S., Inc.

Project/Site: MadisonKipp Corp WI001368.0024.00001

TestAmerica Job ID: 500-93379-1

Laboratory: TestAmerica Chicago

The certifications listed below are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
Wisconsin	State Program	5	999580010	08-31-15

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

TestAmerica Chicago

ID#:

CHAIN OF CUSTODY & LABORATORY ANALYSIS REQUEST FORM

Page 1 of 1

Lab Work Order #

500-93379

Send Results to:	Contact & Company Name: Chris Kubacki ARCADIS			Telephone: 414.276.7742	Preservative E								Keys Preservation Key: A. H ₂ SO ₄ B. HCl C. HNO ₃ D. NaOH E. None F. Other: _____ G. Other: _____ H. Other: _____ 10. Other: _____
	Address: 126 N. Jefferson St. #400	Fax: 414.276.7603	City: Milwaukee State: WI Zip: 53202	E-mail Address: Chris.Kubacki@arcadis-us.com	Filtered (✓) ✓	# of Containers 2	Container Information 9						
PARAMETER ANALYSIS & METHOD													
 500-93379 COC													
<i>PCBS-Dissolved</i> <i>Method 8082</i>													
<i>NDD</i>													
<i>3/13/15 1240</i>													
<i>W 2</i>													
<i>SO - Soil</i> <i>SE - Sediment</i> <i>NL - NAPL/OIL</i> <i>W - Water</i> <i>SL - Sludge</i> <i>SW - Sample Wipe</i> <i>T - Tissue</i> <i>A - Air</i> <i>Other: _____</i>													
REMARKS													
<input type="checkbox"/> Special QA/QC Instructions(✓):													
Special Instructions/Comments:													

Laboratory Information and Receipt		Relinquished By		Received By		Relinquished By		Laboratory Received By	
Lab Name: TestAmerica	Cooler Custody Seal (✓)	Printed Name: Nicole Duder	Printed Name:	Printed Name:	Printed Name: Sherri Scott	Printed Name:	Printed Name: Sherri Scott		
<input checked="" type="checkbox"/> Cooler packed with ice (✓)	<input type="checkbox"/> Intact <input type="checkbox"/> Not Intact	Signature: <i>NDD</i>	Signature:	Signature:	Signature: <i>TA-CHE</i>	Signature:	Signature: <i>TA-CHE</i>		
Specify Turnaround Requirements: Standard	Sample Receipt: ARCADIS	Firm:	Firm/Courier:	Firm/Courier:	Date/Time:	Date/Time:	Date/Time:		
Shipping Tracking #: 8000 76004 8628	Condition/Cooler Temp: 312	Date/Time: 3/16/2015 1701	Date/Time:	Date/Time:	3/17/15 1000	PINK - Retained by ARCADIS			

Login Sample Receipt Checklist

Client: ARCADIS U.S., Inc.

Job Number: 500-93379-1

Login Number: 93379

List Source: TestAmerica Chicago

List Number: 1

Creator: Scott, Sherri L

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	3.2
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

March 13, 2015

Chris Kubacki
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 03/04/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser

Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Accreditation	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MKC-WIPE01-WALL	A151009-01	Wipe	03/04/2015	03/04/2015
MKC-WIPE01-COLUMN	A151009-02	Wipe	03/04/2015	03/04/2015
MKC-WIPE01-FLOOR	A151009-03	Wipe	03/04/2015	03/04/2015
MKC-WIPE01-M1HORZ	A151009-04	Wipe	03/04/2015	03/04/2015
MKC-WIPE01-M1VERT	A151009-05	Wipe	03/04/2015	03/04/2015
MKC-WIPE02-WALL	A151009-06	Wipe	03/04/2015	03/04/2015
MKC-WIPE02-COLUMN	A151009-07	Wipe	03/04/2015	03/04/2015
MKC-WIPE02-FLOOR	A151009-08	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-WALL	A151009-09	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-COLUMN	A151009-10	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-FLOOR	A151009-11	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-M2HORZ	A151009-12	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-M2VERT	A151009-13	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-M3HORZ	A151009-14	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-M3VERT	A151009-15	Wipe	03/04/2015	03/04/2015
MKC-WIPE03-DUP	A151009-16	Wipe	03/04/2015	03/04/2015
MKC-WIPE04-WALL	A151009-17	Wipe	03/04/2015	03/04/2015
MKC-WIPE04-COLUMN	A151009-18	Wipe	03/04/2015	03/04/2015
MKC-WIPE04-FLOOR	A151009-19	Wipe	03/04/2015	03/04/2015
MKC-WIPE04-DUP	A151009-20	Wipe	03/04/2015	03/04/2015
MKC-WIPE05-WALL	A151009-21	Wipe	03/04/2015	03/04/2015
MKC-WIPE05-COLUMN	A151009-22	Wipe	03/04/2015	03/04/2015
MKC-WIPE05-FLOOR	A151009-23	Wipe	03/04/2015	03/04/2015
MKC-WIPE06-WALL	A151009-24	Wipe	03/04/2015	03/04/2015
MKC-WIPE06-COLUMN	A151009-25	Wipe	03/04/2015	03/04/2015
MKC-WIPE06-FLOOR	A151009-26	Wipe	03/04/2015	03/04/2015
MKC-WIPE07-WALL	A151009-27	Wipe	03/04/2015	03/04/2015
MKC-WIPE07-COLUMN	A151009-28	Wipe	03/04/2015	03/04/2015
MKC-WIPE07-FLOOR	A151009-29	Wipe	03/04/2015	03/04/2015
MKC-WIPE06-M21HORZ	A151009-30	Wipe	03/04/2015	03/04/2015
MKC-WIPE06-M21VERT	A151009-31	Wipe	03/04/2015	03/04/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MKC-WIPE09-WALL	A151009-32	Wipe	03/04/2015	03/04/2015
MKC-WIPE09-COLUMN	A151009-33	Wipe	03/04/2015	03/04/2015
MKC-WIPE09-FLOOR	A151009-34	Wipe	03/04/2015	03/04/2015
MKC-WIPE08-WALL	A151009-35	Wipe	03/04/2015	03/04/2015
MKC-WIPE08-COLUMN	A151009-36	Wipe	03/04/2015	03/04/2015
MKC-WIPE08-FLOOR	A151009-37	Wipe	03/04/2015	03/04/2015
MKC-WIPE10-WALL	A151009-38	Wipe	03/04/2015	03/04/2015
MKC-WIPE10-COLUMN	A151009-39	Wipe	03/04/2015	03/04/2015
MKC-WIPE10-FLOOR	A151009-40	Wipe	03/04/2015	03/04/2015

CASE NARRATIVE

Sample Receipt Information:

40 samples were received on 3/4/2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.

Continuing Calibration Verification (CCV):

The HC footnote on samples A151009-23, A151009-26, A151009-29, A151009-30 and A151009-34 states that there was a high CCV recovery for PCB-1248. The upper control limit is 120% and the recovery was 122%.

CCV also indicates a potential high bias for PCB-1242 for samples A151009-03, A151009-04, A151009-11, A151009-19 and A151009-20. Samples were less than the reporting limit for this analyte so no further action is required.

CCV also indicates a potential high bias for PCB-1260 for samples A151009-23, A151009-26, A151009-28 through A151009-30 and A151009-34 through A151009-40. Samples were less than the reporting limit for this analyte so no further action is required.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE01-WALL
A151009-01 (Wipe)

Date Sampled
03/04/2015 11:02

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 00:53	EPA 8082A

Surrogate: Decachlorobiphenyl 92.8 % 60-140 03/09/2015 03/11/2015 00:53 EPA 8082A

Surrogate: Tetrachloro-meta-xylene 89.8 % 60-140 03/09/2015 03/11/2015 00:53 EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE01-COLUMN

Date Sampled
03/04/2015 10:51

A151009-02 (Wipe)

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1242	0.81	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
Total PCBs	0.81	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:18	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.0 %	60-140		03/09/2015	03/11/2015 01:18	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		97.7 %	60-140		03/09/2015	03/11/2015 01:18	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE01-FLOOR
A151009-03 (Wipe)

Date Sampled
03/04/2015 10:59

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1248	11	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
Total PCBs	11	0.15	ug/Wipe	1	03/09/2015	03/11/2015 10:53	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		87.7 %	60-140		03/09/2015	03/11/2015 10:53	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		104 %	60-140		03/09/2015	03/11/2015 10:53	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE01-M1HORZ

Date Sampled

A151009-04 (Wipe)

03/04/2015 10:10

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1248	1.3	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
Total PCBs	1.3	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:21	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		91.2 %	60-140		03/09/2015	03/11/2015 11:21	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		109 %	60-140		03/09/2015	03/11/2015 11:21	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE01-M1VERT

Date Sampled

A151009-05 (Wipe)

03/04/2015 10:04

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 01:43	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		85.9 %	60-140		03/09/2015	03/11/2015 01:43	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		93.0 %	60-140		03/09/2015	03/11/2015 01:43	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE02-WALL

A151009-06 (Wipe)

Date Sampled
03/04/2015 11:17

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1242	0.76	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
Total PCBs	0.76	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:08	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		94.7 %	60-140		03/09/2015	03/11/2015 02:08	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		98.7 %	60-140		03/09/2015	03/11/2015 02:08	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE02-COLUMN

Date Sampled

A151009-07 (Wipe)

03/04/2015 11:08

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1242	0.65	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
Total PCBs	0.65	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:33	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		83.0 %	60-140		03/09/2015	03/11/2015 02:33	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		88.1 %	60-140		03/09/2015	03/11/2015 02:33	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE02-FLOOR
A151009-08 (Wipe)

Date Sampled
03/04/2015 11:13

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1248	6.3	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
Total PCBs	6.3	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:48	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		75.8 %	60-140		03/09/2015	03/11/2015 08:48	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		91.0 %	60-140		03/09/2015	03/11/2015 08:48	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-WALL

Date Sampled

A151009-09 (Wipe)

03/04/2015 11:55

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 02:58	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		95.9 %	60-140		03/09/2015	03/11/2015 02:58	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		101 %	60-140		03/09/2015	03/11/2015 02:58	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-COLUMN

Date Sampled

A151009-10 (Wipe)

03/04/2015 11:44

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1242	0.35	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
Total PCBs	0.35	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:03	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.6 %	60-140		03/09/2015	03/11/2015 05:03	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		95.9 %	60-140		03/09/2015	03/11/2015 05:03	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-FLOOR
A151009-11 (Wipe)

Date Sampled
03/04/2015 11:52

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
PCB-1221	ND	3.0	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
PCB-1232	ND	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
PCB-1242	ND	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
PCB-1248	120	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	D
PCB-1254	ND	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
PCB-1260	ND	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	
Total PCBs	120	1.5	ug/Wipe	10	03/09/2015	03/11/2015 12:46	EPA 8082A	D
<i>Surrogate: Decachlorobiphenyl</i>		90.6 %	60-140		03/09/2015	03/11/2015 05:28	EPA 8082A	
<i>Surrogate: Tetrachloro-meta-xylene</i>		102 %	60-140		03/09/2015	03/11/2015 05:28	EPA 8082A	



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-M2HORZ

Date Sampled

A151009-12 (Wipe)

03/04/2015 10:19

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 05:54	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		99.3 %	60-140		03/09/2015	03/11/2015 05:54	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		102 %	60-140		03/09/2015	03/11/2015 05:54	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-M2VERT

Date Sampled

A151009-13 (Wipe)

03/04/2015 10:15

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:18	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		101 %	60-140		03/09/2015	03/11/2015 06:18	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		105 %	60-140		03/09/2015	03/11/2015 06:18	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-M3HORZ

Date Sampled
03/04/2015 10:28

A151009-14 (Wipe)

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1248	3.9	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
Total PCBs	3.9	0.15	ug/Wipe	1	03/09/2015	03/11/2015 06:43	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		98.6 %	60-140		03/09/2015	03/11/2015 06:43	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		95.0 %	60-140		03/09/2015	03/11/2015 06:43	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-M3VERT

Date Sampled

A151009-15 (Wipe)

03/04/2015 10:24

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:08	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.9 %	60-140		03/09/2015	03/11/2015 07:08	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		104 %	60-140		03/09/2015	03/11/2015 07:08	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE03-DUP

Date Sampled

A151009-16 (Wipe)

03/04/2015 10:17

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:33	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		99.3 %	60-140		03/09/2015	03/11/2015 07:33	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		103 %	60-140		03/09/2015	03/11/2015 07:33	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE04-WALL

Date Sampled

A151009-17 (Wipe)

03/04/2015 11:24

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 07:58	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.5 %	60-140		03/09/2015	03/11/2015 07:58	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		103 %	60-140		03/09/2015	03/11/2015 07:58	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE04-COLUMN

Date Sampled

A151009-18 (Wipe)

03/04/2015 11:29

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 08:23	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		95.0 %	60-140		03/09/2015	03/11/2015 08:23	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		101 %	60-140		03/09/2015	03/11/2015 08:23	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE04-FLOOR
A151009-19 (Wipe)

Date Sampled
03/04/2015 11:35

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1248	7.8	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
Total PCBs	7.8	0.15	ug/Wipe	1	03/09/2015	03/11/2015 11:50	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		77.0 %	60-140		03/09/2015	03/11/2015 11:50	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		96.3 %	60-140		03/09/2015	03/11/2015 11:50	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE04-DUP

A151009-20 (Wipe)

Date Sampled
03/04/2015 11:37

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503029

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1248	4.4	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
Total PCBs	4.4	0.15	ug/Wipe	1	03/09/2015	03/11/2015 12:18	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		86.2 %	60-140		03/09/2015	03/11/2015 12:18	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		103 %	60-140		03/09/2015	03/11/2015 12:18	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE05-WALL

Date Sampled

A151009-21 (Wipe)

03/04/2015 12:07

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/12/2015 23:58	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		94.9 %	60-140		03/09/2015	03/12/2015 23:58	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		96.0 %	60-140		03/09/2015	03/12/2015 23:58	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE05-COLUMN

Date Sampled
03/04/2015 12:13

A151009-22 (Wipe)

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:24	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		99.2 %	60-140		03/09/2015	03/13/2015 00:24	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		105 %	60-140		03/09/2015	03/13/2015 00:24	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE05-FLOOR
A151009-23 (Wipe)

Date Sampled
03/04/2015 12:19

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1248	3.7	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
Total PCBs	3.7	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:01	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		107 %	60-140		03/09/2015	03/13/2015 10:01	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		95.0 %	60-140		03/09/2015	03/13/2015 10:01	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE06-WALL

Date Sampled

A151009-24 (Wipe)

03/04/2015 14:24

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 00:49	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		94.7 %	60-140		03/09/2015	03/13/2015 00:49	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		103 %	60-140		03/09/2015	03/13/2015 00:49	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE06-COLUMN

Date Sampled

A151009-25 (Wipe)

03/04/2015 14:26

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:14	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		102 %	60-140		03/09/2015	03/13/2015 01:14	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		113 %	60-140		03/09/2015	03/13/2015 01:14	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE06-FLOOR

A151009-26 (Wipe)

Date Sampled
03/04/2015 14:20

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1248	3.7	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
Total PCBs	3.7	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:26	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.1 %	60-140		03/09/2015	03/13/2015 10:26	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		92.3 %	60-140		03/09/2015	03/13/2015 10:26	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE07-WALL

Date Sampled

A151009-27 (Wipe)

03/04/2015 13:23

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 01:39	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		115 %	60-140		03/09/2015	03/13/2015 01:39	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		106 %	60-140		03/09/2015	03/13/2015 01:39	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE07-COLUMN

Date Sampled

A151009-28 (Wipe)

03/04/2015 12:27

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1248	0.96	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
Total PCBs	0.96	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:40	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		107 %	60-140		03/09/2015	03/13/2015 06:40	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		101 %	60-140		03/09/2015	03/13/2015 06:40	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE07-FLOOR
A151009-29 (Wipe)

Date Sampled
03/04/2015 13:26

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1248	4.2	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
Total PCBs	4.2	0.15	ug/Wipe	1	03/09/2015	03/13/2015 10:51	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		101 %	60-140		03/09/2015	03/13/2015 10:51	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		105 %	60-140		03/09/2015	03/13/2015 10:51	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE06-M21HORZ
A151009-30 (Wipe)

Date Sampled
03/04/2015 10:38

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1248	1.5	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A
Total PCBs	1.5	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:16	EPA 8082A

Surrogate: Decachlorobiphenyl

97.6 % 60-140 03/09/2015 03/13/2015 11:16 EPA 8082A

Surrogate: Tetrachloro-meta-xylene

99.3 % 60-140 03/09/2015 03/13/2015 11:16 EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE06-M21VERT

Date Sampled

A151009-31 (Wipe)

03/04/2015 10:34

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:04	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		92.6 %	60-140		03/09/2015	03/13/2015 02:04	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		85.8 %	60-140		03/09/2015	03/13/2015 02:04	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE09-WALL

Date Sampled

A151009-32 (Wipe)

03/04/2015 13:32

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1248	0.33	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
Total PCBs	0.33	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:29	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		80.2 %	60-140		03/09/2015	03/13/2015 02:29	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		87.9 %	60-140		03/09/2015	03/13/2015 02:29	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE09-COLUMN

Date Sampled

A151009-33 (Wipe)

03/04/2015 13:38

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 02:54	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		125 %	60-140		03/09/2015	03/13/2015 02:54	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		108 %	60-140		03/09/2015	03/13/2015 02:54	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE09-FLOOR

Date Sampled

A151009-34 (Wipe)

03/04/2015 13:43

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1248	3.9	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
Total PCBs	3.9	0.15	ug/Wipe	1	03/09/2015	03/13/2015 11:41	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		96.9 %	60-140		03/09/2015	03/13/2015 11:41	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		102 %	60-140		03/09/2015	03/13/2015 11:41	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE08-WALL

Date Sampled

A151009-35 (Wipe)

03/04/2015 14:11

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:00	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		126 %	60-140		03/09/2015	03/13/2015 05:00	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		108 %	60-140		03/09/2015	03/13/2015 05:00	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE08-COLUMN

Date Sampled
03/04/2015 14:06

A151009-36 (Wipe)

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:25	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		120 %	60-140		03/09/2015	03/13/2015 05:25	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		108 %	60-140		03/09/2015	03/13/2015 05:25	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE08-FLOOR
A151009-37 (Wipe)

Date Sampled
03/04/2015 14:08

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1248	4.8	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
Total PCBs	4.8	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:05	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		81.9 %	60-140		03/09/2015	03/13/2015 07:05	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		73.9 %	60-140		03/09/2015	03/13/2015 07:05	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE10-WALL

Date Sampled

A151009-38 (Wipe)

03/04/2015 13:52

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 05:50	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		125 %	60-140		03/09/2015	03/13/2015 05:50	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		105 %	60-140		03/09/2015	03/13/2015 05:50	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE10-COLUMN

Date Sampled

A151009-39 (Wipe)

03/04/2015 13:55

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1248	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
Total PCBs	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 06:15	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		131 %	60-140		03/09/2015	03/13/2015 06:15	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		112 %	60-140		03/09/2015	03/13/2015 06:15	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

MKC-WIPE10-FLOOR
A151009-40 (Wipe)

Date Sampled
03/04/2015 13:58

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A503030

PCB-1016	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1221	ND	0.30	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1232	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1242	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1248	2.4	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1254	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
PCB-1260	ND	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
Total PCBs	2.4	0.15	ug/Wipe	1	03/09/2015	03/13/2015 07:30	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		112 %	60-140		03/09/2015	03/13/2015 07:30	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		104 %	60-140		03/09/2015	03/13/2015 07:30	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control

ECCS

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC %REC	Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	-----------	--------	---------	-----------	-------

Batch A503029 - EPA 3580A

Blank (A503029-BLK1)

Prepared: 03/09/2015 Analyzed: 03/11/2015 00:28

PCB-1016	ND	0.15	ug/Wipe							
PCB-1221	ND	0.30	ug/Wipe							
PCB-1232	ND	0.15	ug/Wipe							
PCB-1242	ND	0.15	ug/Wipe							
PCB-1248	ND	0.15	ug/Wipe							
PCB-1254	ND	0.15	ug/Wipe							
PCB-1260	ND	0.15	ug/Wipe							
Total PCBs	ND	0.15	ug/Wipe							
<i>Surrogate: Decachlorobiphenyl</i>	0.871		ug/Wipe	0.9000		96.7	60-140			
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.841		ug/Wipe	0.9000		93.5	60-140			

LCS (A503029-BS1)

Prepared: 03/09/2015 Analyzed: 03/11/2015 00:03

PCB-1254	14.0	0.15	ug/Wipe	15.00		93.3	70-130			
<i>Surrogate: Decachlorobiphenyl</i>	0.827		ug/Wipe	0.9000		91.9	60-140			
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.811		ug/Wipe	0.9000		90.1	60-140			

Batch A503030 - EPA 3580A

Blank (A503030-BLK1)

Prepared: 03/09/2015 Analyzed: 03/12/2015 23:33

PCB-1016	ND	0.15	ug/Wipe							
PCB-1221	ND	0.30	ug/Wipe							
PCB-1232	ND	0.15	ug/Wipe							
PCB-1242	ND	0.15	ug/Wipe							
PCB-1248	ND	0.15	ug/Wipe							
PCB-1254	ND	0.15	ug/Wipe							
PCB-1260	ND	0.15	ug/Wipe							
Total PCBs	ND	0.15	ug/Wipe							
<i>Surrogate: Decachlorobiphenyl</i>	0.940		ug/Wipe	0.9000		104	60-140			
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.870		ug/Wipe	0.9000		96.7	60-140			

LCS (A503030-BS1)

Prepared: 03/09/2015 Analyzed: 03/12/2015 23:08

PCB-1254	13.6	0.15	ug/Wipe	15.00		90.9	70-130			
<i>Surrogate: Decachlorobiphenyl</i>	0.889		ug/Wipe	0.9000		98.8	60-140			
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.835		ug/Wipe	0.9000		92.7	60-140			




2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Chris Kubacki

Notes and Definitions

- HC Results may be biased high because of high continuing calibration verification (CCV).
- D Data reported from a dilution
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
- RPD Relative Percent Difference



Environmental Chemistry
Consulting Services, Inc.
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 4

Project Number: W1001368

Project Name: Madison-Kipp - Wipe Sampling

Project Location: Madison, WI

Turn Around (circle one): Normal Rush

If Rush, Report Due Date:

Sampled By (Print): Trenna Seilheimer (ARCADIS)

Lab Work Order #:

A151009

Mail Report To: Trenna Seilheimer

Company: ARCADIS

Address: 25 N Jefferson St Ste 400

Milwaukee, WI

E-mail Address: trenna.seilheimer@arcadis-us.com

Invoice To: same as above

Company:

Address:

Sample Description	Collection		Matrix	Total # of Containers	PCB Analysis	Comments	Lab ID	Lab Receipt Time
	Date	Time						
MKC-WIPE01-WALL	3/4/15	1102	O	1	X		01	
MKC-WIPE01-COLUMN	3/4/15	1051	O	1	X		02	
MKC-WIPE01-FLOOR	3/4/15	1059	O	1	X		03	
MKC-WIPE01-M1 HOPZ	3/4/15	1010	O	1	X		04	
MKC-WIPE01-M1 VERT	3/4/15	1004	O	1	X		05	
MKC-WIPE02-WALL	3/4/15	1117	O	1	X		06	
MKC-WIPE02-COLUMN	3/4/15	1108	O	1	X		07	
MKC-WIPE02-FLOOR	3/4/15	1113	O	1	X		08	
MKC-WIPE03-WALL	3/4/15	1155	O	1	X		09	
MKC-WIPE03-COLUMN	3/4/15	1144	O	1	X		10	

Preservation Codes

A=None B=HCL C=H₂SO₄
D=HNO₃ E=EnCore F=Methanol
G=NaOH O=Other (Indicate)

Relinquished By:

Date:

3/4/15

Time:

1545

Received By:

Date:

3/4/15

Time:

1545

Relinquished By:

Date:

Time:

Received By:

Date:

Time:

Matrix Codes

A=Air S=Soil W=Water O=Other

Custody Seal: Present/Absent


Intact/Not Intact

Seal #'s

Receipt Temp: on ice

Shipped Via: Walk-In

Temp Blank Y N



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 2 of 4

Project Number: W1001368

Project Name: Madison - Kipp - Wipe Sampling

Project Location: Madison, WI

Turn Around (circle one): Normal Rush

If Rush, Report Due Date:

Sampled By (Print):

Lab Work Order #:

A151009

Mail Report To:

Company:

Address:

Analyses Requested

Preservation Codes

A

PCB Analyzer

E-mail Address:

Invoice To:

Company:

Address:

Sample Description	Collection		Matrix	Total # of Containers	PCB Analyzer		Comments	Lab ID	Lab Receipt Time
	Date	Time							
MKC-WIPE03 - FLOOR	3/4/15	1152	O	1	X			11	
MKC-WIPE03 - M2HORZ	3/4/15	1019	O	1	X			12	
MKC-WIPE03 - M2VERT	3/4/15	1015	O	1	X			13	
MKC-WIPE03 - M3HORZ	3/4/15	1028	O	1	X			14	
MKC-WIPE03 - M3VERT	3/4/15	1024	O	1	X			15	
MKC-WIPE03 - DUP	3/4/15	1017	O	1	X			16	
MKC-WIPE04 - WALL	3/4/15	1124	O	1	X			17	
MKC-WIPE04 - COLUMN	3/4/15	1129	O	1	X			18	
MKC-WIPE04 - FLOOR	3/4/15	1135	O	1	X			19	
MKC-WIPE04 - DUP	3/4/15	1137	O	1	X			20	

Preservation Codes

A=None B=HCL C=H₂SO₄
D=HNO₃ E=EnCore F=Methanol
G=NaOH O=Other (Indicate)

Relinquished By:

JL

Date:

3/4/15

Time:

1545

Received By:

Johnna Conner

Date:

3-4-15

Time:

1545

Relinquished By:

Date:

Time:

Received By:

Date:

Time:

Matrix Codes

A=Air S=Soil W=Water O=Other

Custody Seal: Present Absent


Intact/Not Intact

Seal #'s

Shipped Via: Walk-in

Receipt Temp: On ice

Temp Blank Y N




**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 3 of 4

 Madison, WI 53718 608-221-8700 (phone) 608-221-4889 (fax)		Lab Work Order #: A151009		Mail Report To: Company:			
Project Number: W1001368		Analyses Requested		Address:			
Project Name: Madison-Kipp - Wipe Sampling		Preservation Codes					
Project Location: Madison, WI		A		E-mail Address:			
Turn Around (circle one): <input checked="" type="radio"/> Normal <input type="radio"/> Rush		PCB Analyzer		Invoice To:			
If Rush, Report Due Date:				Company:			
Sampled By (Print):				Address:			
Sample Description	Collection		Matrix	Total # of Containers	Comments	Lab ID	Lab Receipt Time
	Date	Time					
MKC-WIPE05-WALL	3/4/15 1207	1207	0	1	X		21
MKC-WIPE05-COLUMN	1213	1213	0	1	X		22
MKC-WIPE05-FLOOR	1219	1219	0	1	X		23
MKC-WIPE06-WALL	1424	1424	0	1	X		24
MKC-WIPE06-COLUMN	1426	1426	0	1	X		25
MKC-WIPE06-FLOOR	1420	1420	0	1	X		26
MKC-WIPE07-WALL	1323	1323	0	1	X		27
MKC-WIPE07-COLUMN	1227	1227	0	1	X		28
MKC-WIPE07-FLOOR	1326	1326	0	1	X		29
MKC-WIPE06-MZ1 HDRZ	1038	1038	0	1	X		30
Preservation Codes A=None B=HCL C= H_2SO_4 D= HNO_3 E=EnCore F=Methanol G=NaOH O=Other (Indicate)		Relinquished By: <i>JL</i>		Date: 3/4/15 Time: 1545	Received By: <i>Jessica Anna</i>	Date: 3-4-15 Time: 1545	
		Relinquished By:		Date: Time:	Received By:	Date: Time:	
Matrix Codes A=Air S=Soil W=Water O=Other		Custody Seal: Present/Absent Intact/Not Intact Seal #'s		Receipt Temp: <i>On ice</i> Temp Blank Y N			
		Shipped Via: <i>Walk-in</i>					



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 4 of 4

 Madison, WI 53718 608-221-8700 (phone) 608-221-4889 (fax)		Lab Work Order #: <i>A151009</i>		Mail Report To:				
Project Number: W1001368		Analyses Requested		Company:				
Project Name: Madison-Kipp - Wipe Sampling		Preservation Codes		Address:				
Project Location: Madison, WI		A		E-mail Address:				
Turn Around (circle one): <input checked="" type="radio"/> Normal <input type="radio"/> Rush		PCB Analyzer 		Invoice To:				
If Rush, Report Due Date:				Company:				
Sampled By (Print):				Address:				
Sample Description	Collection		Matrix	Total # of Containers	Comments	Lab ID	Lab Receipt Time	
	Date	Time						
MKC-WIPE06-M21 VERT	3/4/15	1034	O	1	X		31	
MKC-WIPE09-WALL	3/4/15	1332	O	1	X		32	
MKC-WIPE09-COLUMN	3/4/15	1338	O	1	X		33	
MKC-WIPE09-FLOOR	3/4/15	1343	O	1	X		34	
MKC-WIPE08-WALL	3/4/15	1411	O	1	X		35	
MKC-WIPE08-COLUMN	3/4/15	1406	O	1	X		36	
MKC-WIPE08-FLOOR	3/4/15	1408	O	1	X		37	
MKC-WIPE10-WALL	3/4/15	1352	O	1	X		38	
MKC-WIPE10-COLUMN	3/4/15	1355	O	1	X		39	
MKC-WIPE10-FLOOR	3/4/15	1358	O	1	X		40	
Preservation Codes A=None B=HCL C=H ₂ SO ₄ D=HNO ₃ E=EnCore F=Methanol G=NaOH O=Other (Indicate)	Relinquished By: <i>JW</i>			Date: 3/4/15	Time: 1545	Received By: <i>Jessica Goss</i>	Date: 3/4/15	Time: 1545
	Relinquished By:			Date:	Time:	Received By:	Date:	Time:
Matrix Codes A=Air S=Soil W=Water O=Other	Custody Seal: Present/Absent			Intact/Not Intact		Seal #'s	Receipt Temp: On Ice	
	Shipped Via: Walk-In						Temp Blank Y N	



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

April 03, 2015

Trenna Seilheimer
ARCADIS
126 N Jefferson St., Ste 400
Milwaukee, WI 53202
RE: Madison Kipp - Madison, WI

Enclosed are the analytical results for the samples received by the laboratory on 04/02/2015.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. These results are in compliance with the 2009 NELAC Standards and the appropriate agencies listed below, unless otherwise noted in the case narrative. This analytical report should be reproduced in its entirety.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Jessica Esser

Project Manager

Certification List		Expires	
DODELAP	DOD ELAP Accreditation (A2LA)	3269.01	03/31/2016
ILEPA	Illinois Secondary NELAP Accreditation	003174	04/30/2015
KDHE	Kansas Secondary NELAP Accreditation	E-10384	04/30/2015
LELAP	Louisiana Primary NELAP Accreditation	04165	06/30/2015
NJDEP	New Jersey Secondary NELAP Accreditation	WI004	06/30/2015
ODEQ	Oklahoma Department of Environmental Quality Accreditation	2014-153	08/31/2015
WDNR	Wisconsin Certification under NR 149	113289110	08/31/2015



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MKC-WIPE01-FLOOR2	A151407-01	Wipe	04/02/2015	04/02/2015
MKC-WIPE02-FLOOR2	A151407-02	Wipe	04/02/2015	04/02/2015
MKC-WIPE03-FLOOR2	A151407-03	Wipe	04/02/2015	04/02/2015
MKC-WIPE03-FLOOR3	A151407-04	Wipe	04/02/2015	04/02/2015
MKC-WIPE03-FLOOR4	A151407-05	Wipe	04/02/2015	04/02/2015
MKC-WIPE05-FLOOR2	A151407-06	Wipe	04/02/2015	04/02/2015

CASE NARRATIVE

Sample Receipt Information:

6 samples were received on 4/2/2015. Samples were received on ice. Samples were received in acceptable condition.

Please see the chain of custody (COC) document at the end of this report for additional information.

Continuing Calibration Verification (CCV):

CCV indicates a potential high bias for PCB-1016 and PCB-1242 for samples A151407-01 through A151407-06. Samples were less than the reporting limit for these analytes so no further action is required.



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE01-FLOOR2

Date Sampled

A151407-01 (Wipe)

04/02/2015 07:50

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1248	1.2	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A
Total PCBs	1.2	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:10	EPA 8082A

Surrogate: Decachlorobiphenyl

80.2 % 60-140 04/02/2015 04/03/2015 07:10 EPA 8082A

Surrogate: Tetrachloro-meta-xylene

95.1 % 60-140 04/02/2015 04/03/2015 07:10 EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE02-FLOOR2

Date Sampled

A151407-02 (Wipe)

04/02/2015 08:10

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1248	3.0	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
Total PCBs	3.0	0.50	ug/Wipe	1	04/02/2015	04/03/2015 07:35	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		91.8 %	60-140		04/02/2015	04/03/2015 07:35	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		107 %	60-140		04/02/2015	04/03/2015 07:35	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE03-FLOOR2

Date Sampled

A151407-03 (Wipe)

04/02/2015 08:20

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1248	13	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
Total PCBs	13	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:00	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		60.7 %	60-140		04/02/2015	04/03/2015 08:00	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		104 %	60-140		04/02/2015	04/03/2015 08:00	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE03-FLOOR3

Date Sampled

A151407-04 (Wipe)

04/02/2015 08:30

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1248	6.9	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
Total PCBs	6.9	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:25	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		74.4 %	60-140		04/02/2015	04/03/2015 08:25	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		102 %	60-140		04/02/2015	04/03/2015 08:25	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE03-FLOOR4

Date Sampled

A151407-05 (Wipe)

04/02/2015 08:35

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1248	6.0	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
Total PCBs	6.0	0.50	ug/Wipe	1	04/02/2015	04/03/2015 08:50	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		73.6 %	60-140		04/02/2015	04/03/2015 08:50	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		102 %	60-140		04/02/2015	04/03/2015 08:50	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

MKC-WIPE05-FLOOR2

Date Sampled

A151407-06 (Wipe)

04/02/2015 08:45

Analyte	Result	Reporting Limit	Units	Dilution	Prepared	Analyzed	Method	Qualifiers
---------	--------	-----------------	-------	----------	----------	----------	--------	------------

ECCS

Polychlorinated Biphenyls by EPA Method 8082

Preparation Batch: A504010

PCB-1016	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1221	ND	1.0	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1232	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1242	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1248	14	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1254	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
PCB-1260	ND	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
Total PCBs	14	0.50	ug/Wipe	1	04/02/2015	04/03/2015 09:15	EPA 8082A
<i>Surrogate: Decachlorobiphenyl</i>		75.6 %	60-140		04/02/2015	04/03/2015 09:15	EPA 8082A
<i>Surrogate: Tetrachloro-meta-xylene</i>		97.8 %	60-140		04/02/2015	04/03/2015 09:15	EPA 8082A



2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

Polychlorinated Biphenyls by EPA Method 8082 - Quality Control
ECCS

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	---------	-----------	-------

Batch A504010 - EPA 3580A

Blank (A504010-BLK1)

PCB-1016	ND	0.50	ug/Wipe							
PCB-1221	ND	1.0	ug/Wipe							
PCB-1232	ND	0.50	ug/Wipe							
PCB-1242	ND	0.50	ug/Wipe							
PCB-1248	ND	0.50	ug/Wipe							
PCB-1254	ND	0.50	ug/Wipe							
PCB-1260	ND	0.50	ug/Wipe							
Total PCBs	ND	0.50	ug/Wipe							
<i>Surrogate: Decachlorobiphenyl</i>	0.870		ug/Wipe	0.9000		96.7		60-140		
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.957		ug/Wipe	0.9000		106		60-140		

LCS (A504010-BS1)

PCB-1260	13.6	0.50	ug/Wipe	15.00		90.8		70-130		
<i>Surrogate: Decachlorobiphenyl</i>	0.920		ug/Wipe	0.9000		102		60-140		
<i>Surrogate: Tetrachloro-meta-xylene</i>	0.947		ug/Wipe	0.9000		105		60-140		




2525 Advance Road
Madison, WI 53718
608.221.8700 Phone
608.221.4889 Fax

ARCADIS
126 N Jefferson St., Ste 400
Milwaukee WI, 53202

Project: Madison Kipp - Madison, WI
Project Number: W1001368
Project Manager: Trenna Seilheimer

Notes and Definitions

ND	Analyte NOT DETECTED at or above the reporting limit
NR	Not Reported
dry	Sample results reported on a dry weight basis. If the word 'dry' does not appear after the units, results are reported on an as-is basis.
RPD	Relative Percent Difference



**Environmental Chemistry
Consulting Services, Inc.**
2525 Advance Road
Madison, WI 53718
608-221-8700 (phone)
608-221-4889 (fax)

CHAIN OF CUSTODY

Page 1 of 1



SAMPLE RECEIPT REPORT

15040032

Pace Analytical Services, Inc.
 2190 Technology Drive
 Schenectady, NY 12308
 Phone: 518.346.4592
 Fax: 518.381.6055

CLIENT: ARCADIS
PROJECT: WI001368.0022.00001 MADISON KIPP
LRF: 15040032
REPORT: ANALYTICAL REPORT
EDD: YES
LRF TAT: *2 DAY*

RECEIVED DATE: 04/02/2015 09:20
SHIPPED VIA: FEDEX ^{1,2}
SHIPPING ID: 801702172756
NUMBER OF COOLERS: 1
CUSTODY SEAL INTACT: YES
COOLER STATUS: CHILLED
TEMPERATURE(S): ⁵3.5 °C

SAMPLE SEALS INTACT: NA
SAMPLES PRESERVED PER METHOD GUIDANCE: YES
³ **SAMPLES REC'D IN HOLDTIME:** YES
DISPOSAL: BY LAB (45 DAYS)
COC DISCREPANCY: NO

COMMENTS:

CLIENT ID (LAB ID)	TAT-DUE Date ⁴	DATE-TIME SAMPLED	MATRIX	METHOD	TEST DESCRIPTION	QC REQUEST
MKC-AIR01 (AS06704)	*2 DAY* 04-06-15	04/01/2015 15:30	PF10	EPA TO-10A	PCB Analysis (TO-10A)	
MKC-AIR02 (AS06705)	*2 DAY* 04-06-15	04/01/2015 15:45	PF10	EPA TO-10A	PCB Analysis (TO-10A)	
MKC-AIR03 (AS06706)	*2 DAY* 04-06-15	04/01/2015 15:55	PF10	EPA TO-10A	PCB Analysis (TO-10A)	

¹The pH preservation check of Oil and Grease (Method 1664) and Total Organic Carbon (Method 5310B) are performed as soon as possible after sample receipt and may not be included in this report.

²The pH preservation check of aqueous volatile samples is not performed until after the analysis of the sample to maintain zero headspace and is not included in this report.

³Samples received for pH analysis are not marked as a hold time exceedance here. SW-846 methods suggests analysis to be done within 15 minutes of sample collection. Because of transportation time it is not possible for the laboratory to perform the test in that time. Sample Certificates of Analysis reports are noted as such.

⁴Samples arriving at the laboratory after 4:00 pm are assigned a due date as if they arrived the following business day unless other arrangements have been made.

The due date represents the date the lab report is expected to be completed on or before 5:00 pm (EST) for the date specified.

⁵All samples which require thermal preservation shall be considered acceptable when received greater than 6 degrees Celsius if they are collected on the same day as received and there is evidence that the chilling process has begun, such as arrival on ice. Control limits are between 0-6 Degrees Celsius. Control limits do not apply for metals analysis.

Reporting Parameters and Lists

EPA TO-10A - PCB Analysis (TO-10A) - (ug/m³)

Aroclor 1016
 Aroclor 1221
 Aroclor 1232
 Aroclor 1242
 Aroclor 1248
 Aroclor 1254
 Aroclor 1260
 Total PCB Amount > RL (\$)

GC - PCB

5



Analytical Sample Results

Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: MKC-AIR01
Lab Sample ID: 15040032-01 (AS06704)

Collection Date: 04/01/2015 15:30
Sample Matrix: POLYURETHANE FOAM
Received Date: 04/02/2015 09:20
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10F-1368-8	EPA Method TO-10A	04/03/2015 14:30	MCA	NA	NA	Phenomenex, Zebron ZB-1MS, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	2.40m ³	5.00 mL	NA

Analyte	CAS No.	Result (ug/m ³)	PQL	Dilution Factor	Flags	File ID
Aroclor 1016	12674-11-2	ND	0.0417	1.00	U	GC10F-1368-8
Aroclor 1221	11104-28-2	ND	0.0417	1.00	U	GC10F-1368-8
Aroclor 1232	11141-16-5	ND	0.0417	1.00	U	GC10F-1368-8
Aroclor 1242	53469-21-9	0.0553	0.0417	1.00		GC10F-1368-8
Aroclor 1248	12672-29-6	ND	0.0417	1.00	U	GC10F-1368-8
Aroclor 1254	11097-69-1	ND	0.0417	1.00	U	GC10F-1368-8
Aroclor 1260	11096-82-5	ND	0.0417	1.00	U	GC10F-1368-8
Total PCB Amount > RL (\$)	1336-36-3	0.0553		1.00		GC10F-1368-8

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	89.3	60.0-120		GC10F-1368-8
Decachlorobiphenyl	2051-24-3	99.6	60.0-120		GC10F-1368-8
Tetrachloro-meta-xylene	877-09-8	91.8	60.0-120		GC10B-1354-8
Decachlorobiphenyl	2051-24-3	108	60.0-120		GC10B-1354-8

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

Note: Concentration results based upon client supplied air volumes.

(\$) NYSDOH does not currently offer certification for this analyte.



Analytical Sample Results

Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: MKC-AIR02
Lab Sample ID: 15040032-02 (AS06705)

Collection Date: 04/01/2015 15:45
Sample Matrix: POLYURETHANE FOAM
Received Date: 04/02/2015 09:20
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10B-1354-9	EPA Method TO-10A	04/03/2015 14:43	MCA	NA	NA	Phenomenex, Zebron ZB-5, 20 m, 0.18 mm ID, 0.18 µm
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	2.40m³	5.00 mL	NA

Analyte	CAS No.	Result (ug/m³)	PQL	Dilution Factor	Flags	File ID
Aroclor 1016	12674-11-2	ND	0.0417	1.00	U	GC10B-1354-9
Aroclor 1221	11104-28-2	ND	0.0417	1.00	U	GC10B-1354-9
Aroclor 1232	11141-16-5	ND	0.0417	1.00	U	GC10B-1354-9
Aroclor 1242	53469-21-9	0.0525	0.0417	1.00		GC10B-1354-9
Aroclor 1248	12672-29-6	ND	0.0417	1.00	U	GC10B-1354-9
Aroclor 1254	11097-69-1	ND	0.0417	1.00	U	GC10B-1354-9
Aroclor 1260	11096-82-5	ND	0.0417	1.00	U	GC10B-1354-9
Total PCB Amount > RL (\$)	1336-36-3	0.0525		1.00		GC10B-1354-9

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	87.8	60.0-120		GC10F-1368-9
Decachlorobiphenyl	2051-24-3	99.5	60.0-120		GC10F-1368-9
Tetrachloro-meta-xylene	877-09-8	91.5	60.0-120		GC10B-1354-9
Decachlorobiphenyl	2051-24-3	109	60.0-120		GC10B-1354-9

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

Note: Concentration results based upon client supplied air volumes.

(\$) NYSDOH does not currently offer certification for this analyte.



Analytical Sample Results

Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: MKC-AIR03
Lab Sample ID: 15040032-03 (AS06706)

Collection Date: 04/01/2015 15:55
Sample Matrix: POLYURETHANE FOAM
Received Date: 04/02/2015 09:20
Percent Solid: N/A

Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10B-1354-10 EPA Method TO-10A	04/03/2015 14:55	MCA	NA	NA	Phenomenex, Zebron ZB-5, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397 TO-10A	04/02/2015 14:00	MH	2.40m ³	5.00 mL	NA

Analyte	CAS No.	Result (ug/m ³)	PQL	Dilution Factor	Flags	File ID
Aroclor 1016	12674-11-2	ND	0.0417	1.00	U	GC10B-1354-10
Aroclor 1221	11104-28-2	ND	0.0417	1.00	U	GC10B-1354-10
Aroclor 1232	11141-16-5	ND	0.0417	1.00	U	GC10B-1354-10
Aroclor 1242	53469-21-9	0.0841	0.0417	1.00		GC10B-1354-10
Aroclor 1248	12672-29-6	ND	0.0417	1.00	U	GC10B-1354-10
Aroclor 1254	11097-69-1	ND	0.0417	1.00	U	GC10B-1354-10
Aroclor 1260	11096-82-5	ND	0.0417	1.00	U	GC10B-1354-10
Total PCB Amount > RL (\$)	1336-36-3	0.0841		1.00		GC10B-1354-10

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	83.6	60.0-120		GC10F-1368-10
Decachlorobiphenyl	2051-24-3	96.6	60.0-120		GC10F-1368-10
Tetrachloro-meta-xylene	877-09-8	89.5	60.0-120		GC10B-1354-10
Decachlorobiphenyl	2051-24-3	105	60.0-120		GC10B-1354-10

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

Note: Concentration results based upon client supplied air volumes.

(\$) NYSDOH does not currently offer certification for this analyte.

Quality Control Samples (Lab)



Quality Control Results

Method Blank

Job Number: 15040032

Pace Analytical Services, Inc.

2190 Technology Drive

Schenectady, NY 12308

Phone: 518.346.4592

Fax: 518.381.6055

Client: ARCADIS

Project: WI001368.0022.00001 MADISON KIPP

Client Sample ID: Method Blank (AS06704B)

Lab Sample ID: PBLK-30

Collection Date: N/A

Sample Matrix: POLYURETHANE FOAM

Received Date: N/A

Percent Solid: N/A

Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1: Prep 1:	GC10B-1354-5 30397	EPA Method TO-10A TO-10A	04/03/2015 13:52 04/02/2015 14:00	MCA MH	NA 0.00m³	NA 5.00 mL NA
						Phenomenex, Zebtron ZB-5, 20 m, 0.18 mm ID, 0.18 µm

Analyte	CAS No.	Result (ug)	PQL	Dilution Factor	Flags	File ID
Aroclor 1016	12674-11-2	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1221	11104-28-2	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1232	11141-16-5	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1242	53469-21-9	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1248	12672-29-6	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1254	11097-69-1	ND	0.100	1.00	U	GC10B-1354-5
Aroclor 1260	11096-82-5	ND	0.100	1.00	U	GC10B-1354-5
Total PCB Amount > RL (\$)	1336-36-3	ND		1.00	U	GC10B-1354-5

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	92.1	60.0-120		GC10B-1354-5
Decachlorobiphenyl	2051-24-3	107	60.0-120		GC10B-1354-5

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\$) NYSDOH does not currently offer certification for this analyte.

6



Quality Control Results

Method Blank

Job Number: 15040032

Pace Analytical Services, Inc.

2190 Technology Drive

Schenectady, NY 12308

Phone: 518.346.4592

Fax: 518.381.6055

Client: ARCADIS

Project: WI001368.0022.00001 MADISON KIPP

Client Sample ID: Method Blank (AS06704B)

Lab Sample ID: PBLK-30

Collection Date: N/A

Sample Matrix: POLYURETHANE FOAM

Received Date: N/A

Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10F-1368-5	EPA Method TO-10A	04/03/2015 13:52	MCA	NA	NA	Phenomenex, Zebron ZB-1MS, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	0.00m ³	5.00 mL	NA

Analyte	CAS No.	Result (ug)	PQL	Dilution Factor	Flags	File ID
Aroclor 1016	12674-11-2	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1221	11104-28-2	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1232	11141-16-5	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1242	53469-21-9	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1248	12672-29-6	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1254	11097-69-1	ND	0.100	1.00	U	GC10F-1368-5
Aroclor 1260	11096-82-5	ND	0.100	1.00	U	GC10F-1368-5
Total PCB Amount > RL (\$)	1336-36-3	ND		1.00	U	GC10F-1368-5

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	88.2	60.0-120		GC10F-1368-5
Decachlorobiphenyl	2051-24-3	99.9	60.0-120		GC10F-1368-5

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\$) NYSDOH does not currently offer certification for this analyte.

6



**Quality Control Results
Lab Control Sample (LCS)**

Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: Lab Control Sample (AS06704L)
Lab Sample ID: LCS-30

Collection Date: N/A
Sample Matrix: POLYURETHANE FOAM
Received Date: N/A
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10B-1354-6	EPA Method TO-10A	04/03/2015 14:05	MCA	NA	NA	Phenomenex, Zebtron ZB-5, 20 m, 0.18 mm ID, 0.18 µm
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	0.00m³	5.00 mL	NA

Analyte Spiked	CAS No.	Added (ug)	LCS (ug)	LCS % Rec.	Q ¹	Limits (%)
Aroclor 1242	53469-21-9	1.00	0.979	97.9		70.0-130

¹Qualifier column where '*' denotes value outside the control limits. Note: RPD criteria does not apply if either the sample and duplicate sample are not detected.

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	95.8	60.0-120		GC10B-1354-6
Decachlorobiphenyl	2051-24-3	107	60.0-120		GC10B-1354-6

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\\$) NYSDOH does not currently offer certification for this analyte.



Quality Control Results
Lab Control Sample (LCS)
Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: Lab Control Sample (AS06704L)
Lab Sample ID: LCS-30

Collection Date: N/A
Sample Matrix: POLYURETHANE FOAM
Received Date: N/A
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10F-1368-6	EPA Method TO-10A	04/03/2015 14:05	MCA	NA	NA	Phenomenex, Zebron ZB-1MS, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	0.00m ³	5.00 mL	NA

Analyte Spiked	CAS No.	Added (ug)	LCS (ug)	LCS % Rec.	Q ¹	Limits (%)
Aroclor 1242	53469-21-9	1.00	0.952	95.2		70.0-130

¹Qualifier column where '*' denotes value outside the control limits. Note: RPD criteria does not apply if either the sample and duplicate sample are not detected.

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	91.0	60.0-120		GC10F-1368-6
Decachlorobiphenyl	2051-24-3	103	60.0-120		GC10F-1368-6

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\\$) NYSDOH does not currently offer certification for this analyte.



Quality Control Results
Lab Control Sample - Duplicate (LCSD)
Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: Lab Control Sample - Duplicate (AS06704S)
Lab Sample ID: LCSD-30

Collection Date: N/A
Sample Matrix: POLYURETHANE FOAM
Received Date: N/A
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10B-1354-7	EPA Method TO-10A	04/03/2015 14:17	MCA	NA	NA	Phenomenex, Zebtron ZB-5, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	0.00m ³	5.00 mL	NA

Analyte Spiked	CAS No.	Added (ug)	LCSD (ug)	LCSD % Rec.	Q ¹	Limits (%)	Precision		
							LCS % Rec.	RPD	Q ¹ (%)
Aroclor 1242	53469-21-9	1.00	0.969	96.9	70.0-130	97.9	1.03		20

¹Qualifier column where '*' denotes value outside the control limits. Note: RPD criteria does not apply if either the sample and duplicate sample are not detected.

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	93.1	60.0-120		GC10B-1354-7
Decachlorobiphenyl	2051-24-3	104	60.0-120		GC10B-1354-7

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\\$) NYSDOH does not currently offer certification for this analyte.



Quality Control Results
Lab Control Sample - Duplicate (LCSD)
Job Number: 15040032

Pace Analytical Services, Inc.
2190 Technology Drive
Schenectady, NY 12308
Phone: 518.346.4592
Fax: 518.381.6055

Client: ARCADIS
Project: WI001368.0022.00001 MADISON KIPP
Client Sample ID: Lab Control Sample - Duplicate (AS06704S)
Lab Sample ID: LCSD-30

Collection Date: N/A
Sample Matrix: POLYURETHANE FOAM
Received Date: N/A
Percent Solid: N/A

	Batch ID	Method	Date	Analyst	Init Wt./Vol.	Final Vol.	Column
Analysis 1:	GC10F-1368-7	EPA Method TO-10A	04/03/2015 14:17	MCA	NA	NA	Phenomenex, Zebron ZB-1MS, 20 m, 0.18 mm ID, 0.18 μ m
Prep 1:	30397	TO-10A	04/02/2015 14:00	MH	0.00m ³	5.00 mL	NA

Analyte Spiked	CAS No.	Added (ug)	Precision				LCS % Rec.	RPD	Q ¹	Limits (%)
			LCSD (ug)	LCSD % Rec.	Q ¹	Limits (%)				
Aroclor 1242	53469-21-9	1.00	0.966	96.6	70.0-130	95.2	1.46			20

¹Qualifier column where '*' denotes value outside the control limits. Note: RPD criteria does not apply if either the sample and duplicate sample are not detected.

Surrogate	CAS No.	% Recovery	Limits (%)	Q ¹	File ID
Tetrachloro-meta-xylene	877-09-8	89.6	60.0-120		GC10F-1368-7
Decachlorobiphenyl	2051-24-3	95.3	60.0-120		GC10F-1368-7

¹Qualifier column where '*' denotes value outside the control limits or 'D' denotes value was diluted.

ND: Denotes analyte not detected at a concentration greater than the PQL.

PQL (Practical Quantitation Limit). Denotes lowest analyte concentration reportable for the sample.

(\\$) NYSDOH does not currently offer certification for this analyte.