



SIGNED		DRAWN	
PEB		GYV	
PROJECT NO. B1076-950158			
DATE 4-10-15			
SHEET NO. S206			

[illegible]

1. TYP. MASONRY DETAILS - SEE DET. 1/5601.
2. MASONRY LINTELS - SEE DET. 2/5601 FOR C.M.U. LINTELS & DET. 3/5601 FOR STEEL LINTELS. LINTELS IN NON-BRG. PARTITION WALLS SHALL BE MASONRY - SEE SCHEDULE.
3. TYP. C.M.U. WALL CONSTRUCTION - SEE DET. 4/5601.
4. PRECAST SLAB OPENING - SEE DET. 5/5601.
5. HOUSEKEEPING DASH AT PRECAST PLANK - SEE DET. 6/5601.
6. TYP. PRECAST LINTEL - SEE DET. 7/5601 & 8/5601.
7. INTERIOR MASONRY WALL REINF. - #5 @ 48"o.c.
8. NON-BEARING C.M.U. AT PRECAST PLANK - SEE DET. 9/5601.
9. EQUIPMENT EYEHOOK - SEE DET. 19/5602

NORTH 