

ALTERNATE NO. 1

PIPELINE CONSTRUCTION

ELIGIBLE ITEMS

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
1	8" gravity sewer, Class 2400, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	43,779 LF	\$ <u>14.63</u>	\$ <u>640,486.77</u>
(Unit Price In Written Words)				
2	8" gravity sewer, Class 2400, 6-8 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	28,066 LF	\$ <u>15.85</u>	\$ <u>444,846.1</u>
(Unit Price In Written Words)				
3	8" gravity sewer, Class 2400, 8-10 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	15,547 LF	\$ <u>17.21</u>	\$ <u>267,563.87</u>
(Unit Price In Written Words)				
4	8" gravity sewer, Class 2400, 10-12 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	7,743 LF	\$ <u>18.54</u>	\$ <u>143,555.22</u>
(Unit Price In Written Words)				
5	8" gravity sewer, Class 2400, 12-14 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	4,426 LF	\$ <u>21.16</u>	\$ <u>93,654.16</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
6	8" gravity sewer, Class 2400, 14-16 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	2,401 LF	\$ <u>23.93</u>	\$ <u>57,455.93</u>

(Unit Price In Written Words)

7	8" gravity sewer, Class 2400, 16-18 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	1,946 LF	\$ <u>30.40</u>	\$ <u>59,158.40</u>
---	--	----------	-----------------	---------------------

(Unit Price In Written Words)

8	8" gravity sewer, Class 2400, 18-20 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	750 LF	\$ <u>37.13</u>	\$ <u>27,847.50</u>
---	--	--------	-----------------	---------------------

(Unit Price In Written Words)

9	8" gravity sewer, Class 2400, 20-22 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	276 LF	\$ <u>43.83</u>	\$ <u>12,097.08</u>
---	--	--------	-----------------	---------------------

(Unit Price In Written Words)

10	8" gravity sewer, Class 2400, 22-24 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	61 LF	\$ <u>50.53</u>	\$ <u>3,082.33</u>
----	--	-------	-----------------	--------------------

(Unit Price In Written Words)

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
11	8" gravity sewer, Class 2400, 24-26 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>14 LF</u>	<u>\$57.28</u>	<u>\$801.92</u>
(Unit Price In Written Words)				
12	8" gravity sewer, Class 3300, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>241 LF</u>	<u>\$15.68</u>	<u>\$3778.88</u>
(Unit Price In Written Words)				
13	10" gravity sewer, Class 2400, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>3,131 LF</u>	<u>\$16.69</u>	<u>52,256.39</u> \$
(Unit Price In Written Words)				
14	10" gravity sewer, Class 2400, 6-8 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>3,011 LF</u>	<u>\$18.56</u>	<u>55,884.16</u> \$
(Unit Price In Written Words)				
15	10" gravity sewer, Class 2400, 8-10 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>903 LF</u>	<u>\$20.47</u>	<u>18,484.41</u> \$
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
16	10" gravity sewer, Class 2400, 10-12 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	350 LF	\$ <u>23.34</u>	\$ <u>8169-</u>
(Unit Price In Written Words)				
17	10" gravity sewer, Class 2400, 12-14 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	109 LF	\$ <u>27.26</u>	\$ <u>2971.34</u>
(Unit Price In Written Words)				
18	12" gravity sewer, Class 2400, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	3,792 LF	\$ <u>20.23</u>	\$ <u>76,712.16</u>
(Unit Price In Written Words)				
19	12" gravity sewer, Class 2400, 6-8 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	3,149 LF	\$ <u>21.53</u>	\$ <u>67,797.97</u>
(Unit Price In Written Words)				
20	12" gravity sewer, Class 2400, 8-10 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	2,575 LF	\$ <u>23.34</u>	\$ <u>60,100.50</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
21	12" gravity sewer, Class 2400, 10-12 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	680 LF	\$ <u>25.40</u>	<u>17,272.-</u>
(Unit Price In Written Words)				
22	12" gravity sewer, Class 2400, 12-14 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	378 LF	\$ <u>28.35</u>	<u>10,716.30</u>
(Unit Price In Written Words)				
23	12" gravity sewer, Class 2400, 14-16 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	493 LF	\$ <u>31.09</u>	<u>15,327.37</u>
(Unit Price In Written Words)				
24	12" gravity sewer, Class 2400, 16-18 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	627 LF	\$ <u>34.80</u>	<u>21,819.60</u>
(Unit Price In Written Words)				
25	12" gravity sewer, Class 2400, 18-20 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	127 LF	\$ <u>40.68</u>	<u>5,166.36</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
26	12" gravity sewer, Class 2400, 20-22 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving, and excluding permanent paving.	<u>40 LF</u>	\$ <u>46.48</u>	<u>1859.20</u>
(Unit Price In Written Words)				
27	12" gravity sewer, Class 2400, 22-24 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving, and excluding permanent paving.	<u>66 LF</u>	\$ <u>52.28</u>	<u>3450.48</u>
(Unit Price In Written Words)				
28	12" gravity sewer, Class 3300, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving, and excluding permanent paving.	<u>296 LF</u>	\$ <u>20.14</u>	<u>5961.44</u>
(Unit Price In Written Words)				
29	14" gravity sewer, Class 2400, 0-6 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>356 LF</u>	\$ <u>23.28</u>	<u>8287.68</u>
(Unit Price In Written Words)				
30	14" gravity sewer, Class 2400, 6-8 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>643 LF</u>	\$ <u>27-</u>	<u>17,361</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
31	14" gravity sewer, Class 2400, 8-10 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	884 LF	\$ <u>30.25</u>	26,741- \$
(Unit Price In Written Words)				
32	14" gravity sewer, Class 2400, 10-12 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	803 LF	\$ <u>33.50</u>	26,900.50 \$
(Unit Price In Written Words)				
33	14" gravity sewer, Class 2400, 12-14 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	189 LF	\$ <u>36.20</u>	6841.80 \$
(Unit Price In Written Words)				
34	14" gravity sewer, Class 2400, 14-16 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	205 LF	\$ <u>38.96</u>	7986.80 \$
(Unit Price In Written Words)				
35	14" gravity sewer, Class 2400, 16-18 feet deep, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	34 LF	\$ <u>42.22</u>	1,435.48 \$
(Unit Price In Written Words)				

Item No.	Description	Estimated Quantity	Unit Price	Total Price
36	8", Class 150, cement lined, cast iron, force main, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>11,544</u> <u>12,455</u> LF	<u>\$22.50</u>	<u>259,740</u> \$

↑ blocking

(Unit Price In Written Words)

37	10", Class 150, cement lined, cast iron, force main, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	<u>4366</u> <u>2,282</u> LF	<u>\$27.50</u>	<u>120,065</u> \$
----	--	--------------------------------	----------------	----------------------

↑ blocking

(Unit Price In Written Words)

38	8" x 4" Wye, complete in place.	<u>704 Ea.</u>	<u>\$17.50</u>	<u>12,320-</u> \$
----	---------------------------------	----------------	----------------	----------------------

(Unit Price In Written Words)

39	10" x 4" Wye, complete in place.	<u>19 Ea.</u>	<u>\$27.50</u>	<u>522.50</u> \$
----	----------------------------------	---------------	----------------	---------------------

(Unit Price In Written Words)

40	12" x 4" Wye, complete in place.	<u>80 Ea.</u>	<u>\$27.50</u>	<u>\$2200-</u> \$
----	----------------------------------	---------------	----------------	----------------------

(Unit Price In Written Words)

41	8" x 6" Wye, complete in place.	<u>2 Ea.</u>	<u>\$20-</u>	<u>\$40-</u> \$
----	---------------------------------	--------------	--------------	--------------------

(Unit Price In Written Words)

42	4" PVC, Class 160, force main, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving, and excluding permanent paving.	<u>3,046 LF</u>	\$	\$
---------------	--	----------------------------	---------------	---------------

(Unit Price In Written Words)

43	4" PVC, Class 160, force main, complete in place including pipe, excavation, stone bedding, stone backfill, temporary paving, and excluding permanent paving.	<u>270 LF</u>	\$	\$
---------------	--	--------------------------	---------------	---------------

(Unit Price In Written Words)

Item No.	Description	Estimated Quantity	Unit Price	Total Price
44	6", Class 150, cement lined, cast iron, force main, complete in place, including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	15,015 10,562 LF	\$ 17.50	262,762.50

blocking

(Unit Price In Written Words)

45	6", Class 150, cement lined, cast iron, force main, complete in place, including pipe, excavation, stone bedding, stone backfill, temporary paving and excluding permanent paving.	935 LF	\$	\$
---------------	---	-------------------	---------------	---------------

(Unit Price In Written Words)

46	Precast concret manholes, 0-6 feet deep, complet with base, frame, and cover.	505 Ea.	\$ 550	277,750-
----	---	---------	--------	----------

(Unit Price In Written Words)

47	Manhole extra depth over six feet complete in place.	1,151. 7 VF	\$ 45	51,795-
----	--	-------------	-------	---------

(Unit Price In Written Words)

48	Drop manhole connections, complete.	268 VF	\$ 45	12060-
----	-------------------------------------	--------	-------	--------

(Unit Price In Written Words)

49	Additional allowance for difference in cost between standard manhole frame and covers and watertight manhole frame and covers.	10 Ea.	\$ 150	\$1,500-
----	--	--------	--------	----------

(Unit Price In Written Words)

50	Sheeting and shoring left in place at direction of Engineer.	65 MBM	\$ 200	\$13,000
----	--	--------	--------	----------

(Unit Price In Written Words)

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
51	Miscellaneous mass concrete including concrete cradle for gravity sewer line or as directed by Engineer.	<u>70 CY</u>	<u>\$ 65</u>	<u>\$4550</u>
(Unit Price In Written Words)				
52	10" Air release valve chambers for four inch force main complete with piping, chamber, cover, valves, fittings, pipe saddles, excavation and backfill.	<u>4 Ea.</u>	<u>\$ 750-</u>	<u>\$3000-</u>
(Unit Price In Written Words)				
53	Air release valve chambers for six (6) inch force main complete with piping, chamber, cover, valves, fittings, pipe saddles, excavation and backfill.	<u>5 Ea.</u>	<u>\$ 550</u>	<u>2750-</u>
(Unit Price In Written Words)				
54	Air release valve chambers for eight (8) inch force main complete with piping, chamber, cover, valves, fittings, pipe saddles, excavation and backfill.	<u>4 EA.</u>	<u>\$ 650</u>	<u>\$2600-</u>
(Unit Price In Written Words)				
55	Connections to existing manholes complete with all fittings, concrete, etc.	<u>4 Ea.</u>	<u>\$ 250-</u>	<u>\$1000-</u>
(Unit Price In Written Words)				
56	Reinforced concrete base course, 10-inch thick for State roads.	<u>76 SY</u>	<u>\$ 16</u>	<u>1216</u>
(Unit Price In Written Words)				

Item No.	Description	Estimated Quantity	Unit Price	Total Price
57	Bituminous concrete binder course (ID-2A) 2" thick, State roads.	6,152 SY	\$ <u>11.40</u>	<u>70,132.80</u>
(Unit Price In Written Words)				
58	Bituminous concrete, ID-2A, wearing course, 1" thick, State roads.	6,152 SY	\$ <u>6-</u>	<u>36,912-</u>
(Unit Price In Written Words)				
59	Pavement replacement, CP-2 Township roads and driveways.	12,172 SY	\$ <u>6-</u>	<u>73,032-</u>
(Unit Price In Written Words)				
60	Improved shoulder replacement.	3,030 SY	\$ <u>3.50</u>	<u>10,605-</u>
(Unit Price In Written Words)				
61	Shoulder replacement (original material) for Township roads.	3,400 SY	\$ <u>1-</u>	<u>\$ 3,400-</u>
(Unit Price In Written Words)				
62	2-RC stone (6" thick) driveway replacement, complete.	775 SY	\$ <u>1.10</u>	<u>852.50</u>
(Unit Price In Written Words)				
63	6" force main 6" concrete encasement.	93 LF	\$ <u>22.50</u>	<u>2092.50</u>
(Unit Price In Written Words)				
64	8" force main, 6" concrete encasement.	15 LF	\$ <u>27-</u>	<u>\$ 405</u>
(Unit Price In Written Words)				
65	8" gravity sewer, 6" concrete encasement. (Miscellaneous Plan Sheets)	698 LF	\$ <u>27</u>	<u>18,846-</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
66	10" gravity sewer, 6" concrete encasement. (Miscellaneous Plan Sheets)	<u>161 LF</u>	<u>\$ 30-</u>	<u>\$ 4830-</u>
(Unit Price In Written Words)				
67	14" gravity sewer 6" concrete encasement.	<u>25 LF</u>	<u>\$ 40-</u>	<u>\$ 1,000</u>
(Unit Price In Written Words)				
68	Compacted select fill, complete in place, excluding topsoil and seeding (Plan Sheet No. 95).	<u>475 CY</u>	<u>\$ 5-</u>	<u>\$ 2,375</u>
(Unit Price In Written Words)				
69	Commerce Street metering station, complete in place, including flow nozzle, electrical wiring and all related items (Plan Sheet No. 2 and Detail Sheet No. 20 of Contract No. 1).	<u>Lump Sum</u>	<u>\$ 10,000</u>	<u>\$ 10,000</u>
(Unit Price In Written Words)				
70	Provide and install 24-inch CMP, 14 ga., complete in place as shown on Plan Sheet No. 14.	<u>42 LF</u>	<u>\$ 60-</u>	<u>\$ 2520-</u>
(Unit Price In Written Words)				
71	Provide and install 36" CMP, 14 gal, complete in place as shown on Plan Sheet No. 95.	<u>55 LF</u>	<u>\$ 75</u>	<u>\$ 4125</u>
(Unit Price In Written Words)				
72	Furnish and install stream crossing between but not including MH #L-2 and MH #1-3, complete with 53 LF + 12" cement lined ductile iron pipe, two supporting piers and all other items indicated.	<u>Lump Sum</u>	<u>\$ 6514</u>	<u>\$ 6514</u>
(Unit Price In Written Words)				

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
73	Furnish and install 18" corrugated metal storm sewer pipe, 16 gauge, complete in place as shown on Plan Sheet No. 15.	<u>54 LF</u>	<u>\$ 40-</u>	<u>\$ 2,160-</u>
(Unit Price In Written Words)				
74	Furnish and install 36" corrugated metal storm sewer pipe, 16 gauge, complete in place as shown on Plan Sheet No. 21.	<u>38 LF</u>	<u>\$ 75-</u>	<u>\$ 2,850-</u>
(Unit Price In Written Words)				
75	Furnish and install fill embankments complete in place compacted to 90% of optimum compaction to include 490 CY as shown on Plan Sheet No. 15 2450 CY as shown on Plan Sheet No. 21.	<u>2,940 CY</u>	<u>\$ 5-</u>	<u>\$ 14,700</u>
(Unit Price In Written Words)				
76	Provide for the relocation of 690 ± LF of 6" PVC water line north berm of U.S. Route #30 between Sta. 38 + 35 ± and Sta. 45 + 25 ±.	<u>Lump Sum</u>	<u>\$</u>	<u>\$ 5,000-</u>
(Unit Price In Written Words)				
77	Provide and install 4" thick (Min.) of topsoil, seedings, fertilizer, and mulch covering on all disturbed vegetative areas.	<u>79,960 SY</u>	<u>\$ 3.50</u>	<u>\$ 279,860-</u>
(Unit Price In Written Words)				
78	Provide and relocate the water service line in the east berm of L.R. #340 between Sta. 5 + 75 ± and Sta. 7 + 75 ±.	<u>Lump Sum</u>	<u>\$</u>	<u>\$ 5,000</u>
(Unit Price In Written Words)				

ALTERNATE NO. 1

PIPELINE CONSTRUCTIONINELIGIBLE ITEMS

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
1	4" service laterals complete in place including excavation, backfill, water-tight plugs, drop connection, testing, and restoration of unpaved surfaces or temporary paving, but, excluding permanent paving.	16,200 15,908 LF	\$ 10-	159,080-
(Unit Price In Written Words)				
2	6" service laterals complet in place including excavation, backfill, water-tight plugs, frop connection, testing, and restoration of unpaved surfaces or temporary paving, but, excluding permanent paving.	40 LF	\$ 15-	\$ 600-
(Unit Price In Written Words)				
3 3	Bituminous concrete binder course (ID-2A) 2" thick, State roads.	250 250 SY	\$ 11.40	2850-
(Unit Price In Written Words)				
4 4	Bituminous concrete, ID-2A, wearing course, 1" thick, State roads.	250 250 SY	\$ 6-	\$ 1500-
(Unit Price In Written Words)				
5 5	Pavement replacement, CP-2 Township roads and driveways.	750 750 SY	\$ 6-	\$ 1,500-
(Unit Price In Written Words)				
6 6	Improved shoulder replacement.	1,674 1,674 SY	\$ 3.50	\$ 5859-
(Unit Price In Written Words)				
7 7	Shoulder replacement (original material) for Township roads.	1200 1200 SY	\$ 1-	\$ 1200-
(Unit Price In Written Words)				
8 8	2-RC stone (6" thick) driveway replacement, complete.	200 200 SY	\$ 1.10	\$ 220-

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
79	Relocate and/or replace any trees, shrubs, fences, walls, signs, and all other items which conflict with the Contract work.	<u>Lump Sum</u>	\$ <u> </u>	\$ <u>5000</u>
<u>(Unit Price In Written Words)</u>				
80	Construction stake-out.	<u>131,585 LF</u>	\$ <u>0.10</u>	<u>13,158.50</u>
<u>(Unit Price In Written Words)</u>				
81	Television inspection of gravity sewer lines (the Owner reserves the right to eliminate all television inspection or to require television inspection.	<u>57,000 LF</u>	\$ <u>0.25</u>	<u>14,250-</u>
<u>(Unit Price In Written Words)</u>				
Total Contract Alternate No. 1 - Eligible Items		\$	<u>3,922,191</u>	<u>3,892,322.40</u>
<u>(In Words)</u>				

ALTERNATE NO. 1

PIPELINE CONSTRUCTION

INELIGIBLE ITEMS

Item No.	Description	Estimated Quantity	Unit Price	Total Price
1	4" service laterals complete in place including excavation, backfill, water-tight plugs, drop connection, testing, and restoration of unpaved surfaces or temporary paving, but, excluding permanent paving.	16,208 LF	\$	\$
(Unit Price In Written Words)				
2	6" service laterals complete in place including excavation, backfill, water-tight plugs, drop connection, testing, and restoration of unpaved surfaces or temporary paving, but, excluding permanent paving.	40 LF	\$	\$
(Unit Price In Written Words)				

Total Contract Alternate No. 1 - Ineligible Items \$ 172,809-

(In Words)

Type of Piping Selected:

Gravity Pipelines: _____

Pressure Sewer Pipelines: _____

Contract Alternate No. 1

Eligible Items (Total brought forward) \$ ~~3,922,191~~ 3,892,322.40

Ineligible Items (Total) \$ _____

Total Bid - Contract Alternate No. 1 \$ ~~\$ 4,045,000~~ 4,065,131.40

(In Words)

DATE: _____

BIDDER: _____

ADDRESS: _____

SIGNED: _____

TITLE: _____

no page 15

DER
Water Quality Management

1992-1993

HARRISBURG REGION