

**ATTACHMENT J-0200000-05 - EXHIBIT LINE ITEM NUMBERS
AWARD N40085-13-D-5203**

CLIN 0002 - IDIQ BASE YEAR

PROVIDE UNIT PRICES FOR INDEFINITE DELIVERY INDEFINITE QUANTITY WORK
IN ACCORDANCE WITH SECTION C, SPEC ITEM 4
ELINs A700 through A711

<u>CLIENT</u>	<u>SHORT</u>		<u>EST</u>	<u>UNIT OF</u>	<u>UNIT</u>	<u>TOTAL</u>
<u>ELIN</u>	<u>DESCRIPTION</u>	<u>FULL DESCRIPTION</u>	<u>QTY</u>	<u>ISSUE</u>	<u>PRICE</u>	<u>AMOUNT</u>
Spec Item 3.1 Improved Grounds						
A700	Mowing and Trimming - Prestige Areas - Level I-1	This requirement will be ordered when mowing a specified area of the Maintenance Level I-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. All mowers shall have bags or containers to collect lawn clippings while the grass is being cut. Policing and trimming shall be accomplished in these areas. Mowing shall be accomplished in such a manner that the finished product is neat in appearance and free from scalping, rutting, bruising or rough cutting. Edging and growth removal will be performed for this level of service. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered.	15	AC		
A701	Mowing and Trimming - Prestige Areas - Level I-2	This requirement will be ordered when mowing a specified area of the Maintenance Level I-2 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		
A702	Mowing and Trimming Road Shoulders - Level SI-1	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Areas shall be mowed to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area includes ammunition supply areas utility buildings and road shoulders. Utility buildings shall be mowed inside the fence, 20 feet around the outside of the fenced area and 15 feet wide along access roads leading to these areas. Mowing warning signs will be used and made visible to traffic traveling on road ways in both directions. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	300	AC		
A703	Mowing and Trimming Road Shoulders - Level SI-4	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-4 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area is located in the ammunition supply point, Old Landfill Sneads Ferry Road and Piney Green Road Landfill. Mowing and trimming is required including areas maintained outside the fence. Some Policing may be required. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	200	AC		
A704	Mowing and Trimming - Level SI-5	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-5 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		

(b) (4)

A705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	200	AC
A706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	300	AC
A707	Mowing and Trimming - Level SI-10	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-10 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements The Contractor shall cut grass by bush hog/track type vehicles Henderson Pond, Hickory Pond, and Old Landfill Pond, shall be cut during mowing/maintenance Any fallen limbs and other debris (including garbage) shall be removed Debris may be disposed of at the Base Sanitary Landfill Trees and structures (monuments, sign posts) within the 50-foot mowing area shall be trimmed around using weed eater type equipment Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	20	AC
A708	Edging Level I-1A	All sidewalks, curbing, and similar items in Maintenance Level I-1 areas shall be edged monthly in conjunction with end of month mowing Edging shall be performed the same day as the mowing, Edging shall be accomplished with a heavy-duty commercial edger, gasoline motor driven, designed specifically for the intended purpose and subject to approval by the contracting Officer Edging shall establish a gap, ¼ to ½ inch wide and 1 to 1 ½ inches deep between lawn surface and concrete surfaces If a lawn surface is higher than a paved surface, making mechanical edging impractical, the Contractor shall establish a straight lawn edge, by performing vertical cuts with a spade or a flat Pointed shovel, cutting the turf down to the pavement edge, then removing the cut turf All soil, turf and debris resulting from the edging operation shall be removed from the work site, and properly disposed of, by the end of each working day in which the edging was performed Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday, for every 1000 linear feet ordered	100,000	LF
A709	Growth Removal Level I-1B	The Contractor shall remove all weeds or growth in existing joints and cracks of pavement curbs and sidewalks in all area as specified All growth shall be removed and leveled with existing pavement, curbs or sidewalks Contractor shall ensure pavement, curbs and sidewalks are not damaged during the removal process Process shall not be considered complete until the debris has been removed and the pavement, sidewalks, and curbs are clean Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday for every 1000 linear feet ordered	75,000	LF
A710	Plant Long Leaf Seedlings	Plant long leaf seedlings	300,000	EA

TOTAL IDIQ LINE ITEMS - A700 THROUGH A710

\$ 242,091 30

(b) (4)

ATTACHMENT J-0200000-05 - EXHIBIT LINE ITEM NUMBERS
AWARD N40085-13-D-5203

CLIN 0004 - OPTION YEAR 1 Indefinite Delivery Indefinite Quantity Work

PROVIDE UNIT PRICES FOR INDEFINITE DELIVERY INDEFINITE QUANTITY WORK
 IN ACCORDANCE WITH SECTION C, SPEC ITEM 4
 ELINs B700 through B711

<u>CLIENT</u> <u>ELIN</u>	<u>SHORT</u> <u>DESCRIPTION FULL DESCRIPTION</u>	<u>EST</u> <u>QTY</u>	<u>UNIT</u> <u>ISSUE</u>	<u>UNIT</u> <u>PRICE</u>	<u>TOTAL</u> <u>AMOUNT</u>
Spec Item 3.1 Improved Grounds					
B700	Mowing and Trimming Prestige Areas Level I-1	This requirement will be ordered when mowing a specified area of the Maintenance Level I-1 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 2 inches All mowers shall have bags or containers to collect lawn clippings while the grass is being cut Policing and trimming shall be accomplished in these areas Mowing shall be accomplished in such a manner that the finished product is neat in appearance and free from scalping, rutting, bruising or rough cutting Edging and growth removal will be performed for this level of service The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work	15	AC	
B701	Mowing and Trimming -	This requirement will be ordered when mowing a specified area of the Maintenance Level I-2 areas This requirement shall be ordered when	100	AC	
B702	Mowing and Trimming Road Shoulders - Level SI-1	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-1 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Areas shall be mowed to a height of 3 inches Equipment used in this area will be equipped with fire arrestors This area includes ammunition supply areas utility buildings and road shoulders Utility buildings shall be mowed inside the fence, 20 feet around the outside of the fenced area and 15 feet wide along access roads leading to these areas Mowing warning signs will	300	AC	
B704	Mowing and Trimming - Level SI-5	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-5 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Grass shall be cut to a height of 2 inches Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows Policing and trimming shall be accomplished in these areas Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100	AC	
B705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	200	AC	

(b) (4)

(b) (4)

B705 (P00004)	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	100	AC
B706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	300	AC
B706 (P00004)	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100	AC
B707	Mowing and Trimming - Level SI-10	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-10 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements The Contractor shall cut grass by bush hog/track type vehicles Henderson Pond, Hickory Pond, and Old Landfill Pond, shall be cut during mowing/maintenance Any fallen limbs and other debris (including garbage) shall be removed Debris may be disposed of at the Base Sanitary Landfill Trees and structures (monuments, sign posts) within the 50-foot mowing area shall be trimmed around using weed eater type equipment Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered, upon	20	AC
B708	Edging Level I-1A	All sidewalks, curbing, and similar items in Maintenance Level I-1 areas shall be edged monthly in conjunction with end of month mowing Edging shall be performed the same day as the mowing, Edging shall be accomplished with a heavy-duty commercial edger, gasoline motor driven, designed specifically for the intended purpose and subject to approval by the contracting Officer Edging shall establish a gap, ¼ to ½ inch wide and 1 to 1 ½ inches deep between lawn surface and concrete surfaces If a lawn surface is higher than a paved surface, making mechanical edging impractical, the Contractor shall establish a straight lawn edge, by performing vertical cuts with a space or a flat Pointed shovel, cutting the turf down to the pavement edge, then removing the cut turf All soil, turf and debris resulting from the edging operation shall be removed from the work site, and properly disposed of, by the end of each working day in which the edging was performed Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within	100,000	LF
B709	Growth Removal Level I-1B	The Contractor shall remove all weeds or growth in existing joints and cracks of pavement curbs and sidewalks in all area as specified This requirement shall be done on a monthly basis in conjunction with the edging process All growth shall be removed and leveled with existing pavement, curbs or sidewalks Contractor shall ensure pavement, curbs and sidewalks are not damaged during the removal process Process shall not be considered complete until the debris has been removed and the pavement, sidewalks, and curbs are clean Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement	75,000	LF

B710	Plant Long Leaf Seedlings	Plant long leaf seedlings	300,000	EA
B711 (P00004)	Mowing - Level SI-7	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-7 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	10	AC
B712 (P00004)	Mowing - Level SI-9	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-9 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	500	AC

(b) (4)

TOTAL IDIQ LINE ITEMS - B700 THROUGH B710

\$ 337,370.35

**ATTACHMENT J-0200000-05 - EXHIBIT LINE ITEM NUMBERS
AWARD N40085-13-D-5203**

CLIN 0006 - OPTION YEAR 2 Indefinite Delivery Indefinite Quantity Work

PROV DE UNIT PRICES FOR INDEFINITE DELIVERY NDEFINITE QUANTITY WORK
IN ACCORDANCE WITH SECTION C, SPEC ITEM 4
ELINs C700 through C711

<u>CLIENT</u>	<u>SHORT</u>		<u>EST</u>	<u>UNIT OF</u>	<u>UNIT</u>	<u>TOTAL</u>
<u>ELIN</u>	<u>DESCRIPTION</u>	<u>FULL DESCRIPTION</u>	<u>QTY</u>	<u>ISSUE</u>	<u>PRICE</u>	<u>AMOUNT</u>
Spec Item 3.1 Improved Grounds						
C700	Mowing and Trimming - Prestige Areas - Level I-1	This requirement will be ordered when mowing a specified area of the Maintenance Level I-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. All mowers shall have bags or containers to collect lawn clippings while the grass is being cut. Policing and trimming shall be accomplished in these areas. Mowing shall be accomplished in such a manner that the finished product is neat in appearance and free from scalping, rutting, bruising or rough cutting. Edging and growth removal will be performed for this level of service. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered.	15	AC		
C701	Mowing and Trimming - Prestige Areas - Level I-2	This requirement will be ordered when mowing a specified area of the Maintenance Level I-2 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		
C702	Mowing and Trimming Road Shoulders - Level SI-1	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Areas shall be mowed to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area includes ammunition supply areas utility buildings and road shoulders. Utility buildings shall be mowed inside the fence, 20 feet around the outside of the fenced area and 15 feet wide along access roads leading to these areas. Mowing warning signs will be used and made visible to traffic traveling on road ways in both directions. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	300	AC		
C703	Mowing and Trimming Road Shoulders - Level SI-4	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-4 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area is located in the ammunition supply point, Old Landfill Sneads Ferry Road and Piney Green Road Landfill. Mowing and trimming is required including areas maintained outside the fence. Some Policing may be required. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	200	AC		
C704	Mowing and Trimming - Level SI-5	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-5 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		

(b) (4)

(b) (4)

C705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	200	AC
C705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	100	AC
C706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	300	AC
C706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100	AC
C707	Mowing and Trimming - Level SI-10	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-10 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements The Contractor shall cut grass by bush hog/track type vehicles Henderson Pond, Hickory Pond, and Old Landfill Pond, shall be cut during mowing/maintenance Any fallen limbs and other debris (including garbage) shall be removed Debris may be disposed of at the Base Sanitary Landfill Trees and structures (monuments, sign posts) within the 50-foot mowing area shall be trimmed around using weed eater type equipment Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered upon	20	AC
C708	Edging Level I-1A	All sidewalks, curbing, and similar items in Maintenance Level I-1 areas shall be edged monthly in conjunction with end of month mowing Edging shall be performed the same day as the mowing, Edging shall be accomplished with a heavy-duty commercial edger, gasoline motor driven, designed specifically for the intended purpose and subject to approval by the contracting Officer Edging shall establish a gap, ¼ to ½ inch wide and 1 to 1 ½ inches deep between lawn surface and concrete surfaces If a lawn surface is higher than a paved surface, making mechanical edging impractical, the Contractor shall establish a straight lawn edge, by performing vertical cuts with a space or a flat Pointed shovel, cutting the turf down to the pavement edge, then removing the cut turf All soil, turf and debris resulting from the edging operation shall be removed from the work site, and properly disposed of, by the end of each working day in which the edging was performed Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday, for every 1000 linear feet ordered	100,000	LF
C709	Growth Removal Level I-1B	The Contractor shall remove all weeds or growth in existing joints and cracks of pavement curbs and sidewalks in all area as specified This requirement shall be done on a monthly basis in conjunction with the edging process All growth shall be removed and leveled with existing pavement, curbs or sidewalks Contractor shall ensure pavement, curbs and sidewalks are not damaged during the removal process Process shall not be considered complete until the debris has been removed and the pavement, sidewalks, and curbs are clean Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday for every 1000 linear feet ordered	75,000	LF
C710	Plant Long Leaf Seedlings	Plant long leaf seedlings	300,000	EA

(b) (4)

C711	Mowing - Level SI-7	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-7 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	10	AC
C712	Mowing - Level SI-9	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-9 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	500	AC

TOTAL IDIQ LINE ITEMS - C700 THROUGH C710

\$ 343,996.40

ATTACHMENT J-0200000-05 - EXHIBIT LINE ITEM NUMBERS
AWARD N40085-13-D-5203

CLIN 0008 - OPTION YEAR 3 Indefinite Delivery Indefinite Quantity Work

PROV DE UNIT PRICES FOR INDEFINITE DELIVERY INDEFINITE QUANTITY WORK
 N ACCORDANCE WITH SECTION C, SPEC ITEM 4
 ELINs D700 through D711

CLIENT	SHORT		EST	UNIT OF	UNIT	TOTAL
ELIN	DESCRIPTION	FULL DESCRIPTION	QTY	ISSUE	PRICE	AMOUNT
Spec Item 3.1 Improved Grounds						
D700	Mowing and Trimming Prestige Areas - Level I-1	This requirement will be ordered when mowing a specified area of the Maintenance Level I-1 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 2 inches All mowers shall have bags or containers to collect lawn clippings while the grass is being cut Policing and trimming shall be accomplished in these areas Mowing shall be accomplished in such a manner that the finished product is neat in appearance and free from scalping, rutting, bruising or rough cutting Edging and growth removal will be performed for this level of service The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	15		AC	
D701	Mowing and Trimming - Prestige Areas - Level I-2	This requirement will be ordered when mowing a specified area of the Maintenance Level I-2 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 2 inches Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows Policing and trimming shall be accomplished in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100		AC	
D702	Mowing and Trimming Road Shoulders - Level SI-1	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-1 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Areas shall be mowed to a height of 3 inches Equipment used in this area will be equipped with fire arrestors This area includes ammunition supply areas utility buildings and road shoulders Utility buildings shall be mowed inside the fence, 20 feet around the outside of the fenced area and 15 feet wide along access roads leading to these areas Mowing warning signs will be used and made visible to traffic traveling on road ways in both directions Policing and trimming shall be accomplished in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Policing and trimming is included	300		AC	
D703	Mowing and Trimming Road Shoulders - Level SI-4	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-4 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches Equipment used in this area will be equipped with fire arrestors This area is located in the ammunition supply point, Old Landfill Sneads Ferry Road and Piney Green Road Landfill Mowing and trimming is required including areas maintained outside the fence Some Policing may be required The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Policing and trimming is included	200		AC	
D704	Mowing and Trimming - Level SI-5	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-5 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Grass shall be cut to a height of 2 inches Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows Policing and trimming shall be accomplished in these areas Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100		AC	
D705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	200		AC	
D705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	100		AC	

(b) (4)

(b) (4)

D706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02. No trimming is required in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	300	AC
D706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02. No trimming is required in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC
D707	Mowing and Trimming - Level SI-10	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-10 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. The Contractor shall cut grass by bush hog/track type vehicles. Henderson Pond, Hickory Pond, and Old Landfill Pond, shall be cut during mowing/maintenance. Any fallen limbs and other debris (including garbage) shall be removed. Debris may be disposed of at the Base Sanitary Landfill. Trees and structures (monuments, sign posts) within the 50-foot mowing area shall be trimmed around using weed eater type equipment. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	20	AC
D708	Edging Level I-1A	All sidewalks, curbing, and similar items in Maintenance Level I-1 areas shall be edged monthly in conjunction with end of month mowing. Edging shall be performed the same day as the mowing. Edging shall be accomplished with a heavy-duty commercial edger, gasoline motor driven, designed specifically for the intended purpose and subject to approval by the contracting Officer. Edging shall establish a gap, ¼ to ½ inch wide and 1 to 1 ½ inches deep between lawn surface and concrete surfaces. If a lawn surface is higher than a paved surface, making mechanical edging impractical, the Contractor shall establish a straight lawn edge, by performing vertical cuts with a spade or a flat pointed shovel, cutting the turf down to the pavement edge, then removing the cut turf. All soil, turf and debris resulting from the edging operation shall be removed from the work site, and properly disposed of, by the end of each working day in which the edging was performed. Debris may be disposed of at the Base Sanitary Landfill. The Contractor shall complete this requirement within one workday, for every 1000 linear feet ordered.	100,000	LF
D709	Growth Removal Level I-1B	The Contractor shall remove all weeds or growth in existing joints and cracks of pavement curbs and sidewalks in all areas as specified. This requirement shall be done on a monthly basis in conjunction with the edging process. All growth shall be removed and leveled with existing pavement, curbs or sidewalks. Contractor shall ensure pavement, curbs and sidewalks are not damaged during the removal process. Process shall not be considered complete until the debris has been removed and the pavement, sidewalks, and curbs are clean. Debris may be disposed of at the Base Sanitary Landfill. The Contractor shall complete this requirement within one workday for every 1000 linear feet ordered.	75,000	LF
D710	Plant Long Leaf Seedlings	Plant long leaf seedlings	300,000	EA
D711	Mowing - Level SI-7	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-7 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02. No trimming is required in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered.	10	AC
D712	Mowing - Level SI-9	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-9 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02. No trimming is required in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered.	500	AC

TOTAL IDIQ LINE ITEMS - D700 THROUGH D710

\$ 350,936.55

**ATTACHMENT J-0200000-05 - EXHIBIT LINE ITEM NUMBERS
AWARD N40085-13-D-5203**

CLIN 0010 - OPTION YEAR 4 Indefinite Delivery Indefinite Quantity Work

PROVIDE UNIT PRICES FOR INDEFINITE DELIVERY INDEFINITE QUANTITY WORK
IN ACCORDANCE WITH SECTION C, SPEC ITEM 4
ELINs E700 through E711

<u>CLIENT</u>	<u>SHORT</u>		<u>EST</u>	<u>UNIT OF</u>	<u>UNIT</u>	<u>TOTAL</u>
<u>ELIN</u>	<u>DESCRIPTION</u>	<u>FULL DESCRIPTION</u>	<u>QTY</u>	<u>ISSUE</u>	<u>PRICE</u>	<u>AMOUNT</u>
Spec Item 3.1 Improved Grounds						
E700	Mowing and Trimming Prestige Areas Level I-1	This requirement will be ordered when mowing a specified area of the Maintenance Level I-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. All mowers shall have bags or containers to collect lawn clippings while the grass is being cut. Policing and trimming shall be accomplished in these areas. Mowing shall be accomplished in such a manner that the finished product is neat in appearance and free from scalping, rutting, bruising or rough cutting. Edging and growth removal will be performed for this level of service. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered.	15	AC	(b) (4)	
E701	Mowing and Trimming - Prestige Areas - Level I-2	This requirement will be ordered when mowing a specified area of the Maintenance Level I-2 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		
E702	Mowing and Trimming Road Shoulders - Level SI-1	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-1 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Areas shall be mowed to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area includes ammunition supply areas utility buildings and road shoulders. Utility buildings shall be mowed inside the fence, 20 feet around the outside of the fenced area and 15 feet wide along access roads leading to these areas. Mowing warning signs will be used and made visible to traffic traveling on road ways in both directions. Policing and trimming shall be accomplished in these areas. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	300	AC		
E703	Mowing and Trimming Road Shoulders - Level SI-4	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-4 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. Grass shall be cut to a height of 3 inches. Equipment used in this area will be equipped with fire arrestors. This area is located in the ammunition supply point, Old Landfill Sneads Ferry Road and Piney Green Road Landfill. Mowing and trimming is required including areas maintained outside the fence. Some Policing may be required. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Policing and trimming is included.	200	AC		
E704	Mowing and Trimming - Level SI-5	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-5 areas. This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements. Grass shall be cut to a height of 2 inches. Clippings shall be removed when they may cause damage to the grass or present an unsightly appearance such as when left covering the cut grass, in clumps or windrows. Policing and trimming shall be accomplished in these areas. Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work. The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered. Trimming is included.	100	AC		

(b) (4)

E705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	200	AC
E705	Mowing Semi Improved - Level SI-6	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-6 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be cut to a height of 3 inches, at the range/training areas specified in Attachment J-1503050-02 Mowing / bush hogging and trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	100	AC
E706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	300	AC
E706	Mowing and Trimming - Level SI-8	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-8 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	100	AC
E707	Mowing and Trimming - Level SI-10	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-10 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements The Contractor shall cut grass by bush hog/track type vehicles Henderson Pond, Hickory Pond, and Old Landfill Pond, shall be cut during mowing/maintenance Any fallen limbs and other debris (including garbage) shall be removed Debris may be disposed of at the Base Sanitary Landfill Trees and structures (monuments, sign posts) within the 50-foot mowing area shall be trimmed around using weed eater type equipment Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered Trimming is included	20	AC
E708	Edging Level I-1A	All sidewalks, curbing, and similar items in Maintenance Level I-1 areas shall be edged monthly in conjunction with end of month mowing Edging shall be performed the same day as the mowing, Edging shall be accomplished with a heavy-duty commercial edger, gasoline motor driven, designed specifically for the intended purpose and subject to approval by the contracting Officer Edging shall establish a gap, ¼ to ½ inch wide and 1 to 1 ½ inches deep between lawn surface and concrete surfaces If a lawn surface is higher than a paved surface, making mechanical edging impractical, the Contractor shall establish a straight lawn edge, by performing vertical cuts with a spade or a flat Pointed shovel, cutting the turf down to the pavement edge, then removing the cut turf All soil, turf and debris resulting from the edging operation shall be removed from the work site, and properly disposed of, by the end of each working day in which the edging was performed Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday, for every 1000 linear feet ordered	100,000	LF
E709	Growth Removal Level I-A2	The Contractor shall remove all weeds or growth in existing joints and cracks of pavement curbs and sidewalks in all area as specified This requirement shall be done on a monthly basis in conjunction with the edging process All growth shall be removed and leveled with existing pavement, curbs or sidewalks Contractor shall ensure pavement, curbs and sidewalks are not damaged during the removal process Process shall not be considered complete until the debris has been removed and the pavement, sidewalks, and curbs are clean Debris may be disposed of at the Base Sanitary Landfill The Contractor shall complete this requirement within one workday for every 1000 linear feet ordered	75,000	LF

E710	Plant Long Leaf Seedlings	Plant long leaf seedlings	300,000	EA
E711	Mowing - Level SI-7	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-7 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	10	AC
E712	Mowing - Level SI-9	This requirement will be ordered when mowing a specified area of the Maintenance Level SI-9 areas This requirement shall be ordered when additional cutting is needed in portions of areas where scheduled cutting is performed or other areas not identified in the fixed price requirements Services will not be accepted as complete unless all work requirements have been satisfactorily performed in each location of work Grass shall be bush hogged to a height of 3 inches at the range/training areas as specified in Attachment J-1503050-02 No trimming is required in these areas The Contractor shall have one working day for each 10 acres ordered, upon receipt of the work authorization to complete the work ordered	500	AC

TOTAL IDIQ LINE ITEMS - E700 THROUGH E710

\$ 358,349.65

(b) (4)