NAME OF PAGE ON SIDEBAR: FY2014 Stormwater BMP Projects

TITLE OF PROJECT: Nitrogen Reducing Stormwater BMP Projects on Cape Cod, Massachusetts



Funded by to Program (SNECWRP) for 2015 funds, two communities were selected <a href="mailto:for direct assistance projects to to-design and construct a stormwater best management practice (BMP) for that will treatment of for nitrogen. Each of these communities currently have waterbodies that are impaired for nitrogen. Construction will take place during the spring of 2015.

The first BMP to be constructed will be an innovative <u>subsurface</u> gravel wetland <u>nitrogen</u> retrofit constructed on a parcel of land <u>at that intercepts runoff discharging into</u> Hyannis Inner Harbor in Barnstable, MA. The BMP will intercept stormwater runoff discharging from the Town's municipal separate storm sewer system (MS4) to Hyannis Inner Harbor, a waterbody listed as impaired for total <u>nitrogen</u> and fecal coliform. This BMP will be designed to treat a 0.3 inch design storm from an approximate 6.9 - 8.4 acres of MS4 catchment (approx. 3.5 – 4.2 acres impervious surface).

The second BMP, a <u>surface</u> gravel wetland retrofit, will be <u>constructed</u> on a <u>currently</u> nudeveloped parcel of land along Oyster Pond Furlong, in Chatham, MA. This BMP will also that will intercept stormwater runoff from the Town's MS4 before being discharged into Oyster Pond in Chatham, MA, a waterbody similarly listed as impaired for nutrients and pathogens. The BMP will be designed to treat an approximate 16.9 - 18.4 acres of MS4 catchment (approx. 5.7 - 6.4 acres impervious surface).

In part because stormwater runoff requires anaerobic conditions to treat nitrogen, both of these BMPs are innovative by their nature and/or application.

Tentative Project Schedule (Spring 2015)

Formatted: Font: Italic

Formatted: Font: Italic

BMP Site	Tentative Start Date	<u>Task</u>	<u>Status</u>
Gateway	April <u>612</u> - 1 <u>0</u> 8	Pre-ConstructionKick-off	<u>completed</u>
Marina		meeting	
		Equipment mobilization and	In progress
(Hyannis, MA)		materials stockpiling; site	
		surveying and staking;	
		sediment controls	
		Mobilization	
	April 19 -25	Topsoil Removal,	Ongoing Not yet
		excavation and grading	started
		Geotextile Lining and Stone	Scheduled Not yet
		Placement	started [KAREN,
			CHANGE THE REST TO
			"Scheduled".
	April 26 – May 2	Piping and structure	Not yet started
		placement	
		Wetland soil, loam, seed,	Not yet started
		topsoil, seeding	
		Cleanup and demobilization	Not yet started
Oyster Pond	May 17 - 23	Kickoff meeting	
Furlong		Mobilization	Not yet started
U		Erosion controls, site	Not yet started
(Chatham, MA)		clearing, topsoil removal	
	May 24 - 30	Excavation and Grading	Not yet started
	May 31 – June 6	Geotextile lining and stone	Not yet started
		placement	
	June 7 - 13	Wetland soil, loam, seed,	Not yet started
		topsoil, seeding	
	June 14 <u>-</u> 20	Cleanup & demobilization	Not yet started
	October 11 - 17	Piping and structure placement	Not yet started
	October 18 - 24	Cleanup & demobilization	Not yet started

Pictures:

- Gateway Marina Site (Hyannis Inner Harbor, Hyannis, MA) \rightarrow link to Barnstable Picture Page
- Oyster Pond Furlong Site (Oyster Pond, Chatham, MA) → link to Chatham picture page

<u>Downloads:</u> [LYNNE WILL PROBABLY WANT THIS TO READ SOMETHING LIKE "PROJECT LITERATURE" OR SOMETHING, BUT I THINK ITS FINE FOR NOW. LET OTHER FOLKS, LIKE PAUL, JOHANNA AND LYNNE DECIDE B/C THEY WILL MORE LIKELY THAN NOT BE MORE INTERESTED IN HOW IT LOOKS AND READS]

- Gateway Marina (Barnstable) 60% Design → link to design
- Oyster Pond Furlong (Chatham) 60% Design → link to design

Formatted: Font: Not Bold

WE'RE GOING TO WANT TO ADD MORE HERE, SUCH AS THE FINAL T1SM, PERHAPS OUR PWS, THE LITERATURE REVIEDW WHICH I EXPECT TO SEE SOON, THE FINAL DESIGN, ETC. BUT FOR NOW, THIS LOOKS GOOD.

Contacts:

USEPA Project Technical Lead:

Ray Cody (cody.ray@epa.gov)

Surface Water Branch, Office of Ecosystem Protection

Phone: (617) 918 - 1366

USEPA SNECWRP Coordinator:

Karen Simpson (simpson.karen@epa.gov)

Watersheds and Nonpoint Source Unit, Office of Ecosystem Protection

Phone: (617) 918 - 1672

PROJECT PARTNERS:

<u>Town of Barnstable</u>

Dale Saad, Ph.D.

Senior Project Manager

Water and Sewer

Barnstable DPW

382 Falmouth Road

Hyannis, MA 02601

Phone 508-790-6400 X4941

Town of Chatham

Robert A. Duncanson, Ph.D.

Director of Health & Natural Resources

Town of Chatham, 261 George Ryder Road, Chatham, MA 02633

(508) 945-5165 FAX (508) 945-5163

SUGGEST add Cape Cod Commission here

MAYBE add MassDEP here? I can check with Fred Civian and get back to you.

Formatted: Font: Not Bold