
LSASD Project ID: 23-0016

# Sampling and Analysis Plan Bluestone Coke, LLC

Location: 3500 35th Avenue North Birmingham, Alabama 35207

**Project Date(s): November 28-December 2, 2022** 

Final SAP Approval Date: November 17, 2022



Hazardous Waste Section Field Services Branch Laboratory Services & Applied Science Division USEPA – Region 4 980 College Station Road Athens, Georgia 30605-2720

The ANSI National Accreditation Board attests that U.S. EPA Region 4 Laboratory Services and Applied Science Division fulfills the requirements of ISO/IEC 17025:2017 ANAB Forensic Testing & Calibration AR 3125:2019 in the field of Forensic Testing. The activities contained in this report fall within the scope of accreditation, Certificate Number: AT-2628. Expires 08 June 2024.





#### **Project Requestor:**

James H. Smith
Corrective Action Specialist
RCRA Corrective Action Section
RCRA Programs and Cleanup Branch
Land, Chemicals and Redevelopment
Division
US Environmental Protection Agency Region 4
Sam Nunn Atlanta Federal Center
61 Forsyth Street SW
Atlanta, GA 30303

•	

**Analytical Support:** 

Laboratory Services and Applied Science Division Laboratory Services Branch 980 College Station Road Athens, GA 30605

Approvals:
------------

LSASD Project Leader:

Art Masters Hazardous Waste Section Field Services Branch	Date
Approving Official:	
Malcolm Grieve Technical Reviewer Hazardous Waste Section Field Services Branch	Date

This Sampling and Analysis Plan (SAP) is designed to be used in conjunction with the *Applied Science Branch Quality Assurance Project Plan* December 2019.

Liza Montalvo, Supervisor

Hazardous Waste Section Field Services Branch

Date

SECTION A: Project Planning Elements					
A1. Distribution List					
Recipient	Organization	Address/Email			
James H. Smith	RCRA Corrective Action Section RCRA Programs and Cleanup Branch Land, Chemicals and Redevelopment Division US Environmental Protection Agency - Region 4	James H. Smith Corrective Action Specialist RCRA Corrective Action Section RCRA Programs and Cleanup Branch Land, Chemicals and Redevelopment Division US Environmental Protection Agency - Region 4 Sam Nunn Atlanta Federal Center 61 Forsyth Street SW Atlanta, GA 30303  Smith.JamesH@epa.gov			
	42 P :				
Toom Mouthough		et Personnel  Personnel			
Team Members <sup>1</sup>	Organization	Responsibilities			
Art Masters	LSASD/FSB/HWS	Project Leader, Sampling			
Paula Whiting	LSASD/FSB/HWS	Site Safety Officer, Sampling			
Daniel McCay	LSASD/FSB/HWS	Sampling			
Morris Flexner	LSASD/FSB/WQS	Sampling			
Dina Constantinides	Serco, Inc	Contractor, Sampling Support			
Pete Kalla	LSASD/FSB/WQS	Sampling			
Jim Smith	LCRD	Project Requestor			
Kevin Greaney	LCRD	Technical Assistance			

<sup>&</sup>lt;sup>1</sup>Project Leader and all Task Leaders assisting with this project have been deemed competent by LSASD management to conduct the tasks required to fulfill the prescribed goals.

#### A3. Site Description and Background Information

In the late 1980's, a RCRA Facility Assessment (RFA) was conducted at the Sloss Industries Coke plant, now known as Bluestone Coke, LLC. During that RFA, 39 Solid Waste Management Units (SWMUs) were identified. Corrective Action measures are currently being implemented on some SWMUs at the facility.

#### A4. Problem Definition

During EPA's Human Health Risk Assessors review of the SWMU management area (SMA) 3 Coke Manufacturing Plant Corrective Measures Study dated October 21, 2021, a data gap was identified that is essential to completing human health risk evaluation. During the RFI process surficial soil samples, 0-1 foot, were not taken and in order to fill these data gaps, the Land, Chemicals and Redevelopment Division (LCRD) has requested that the Laboratory Services & Applied Science Division (LSASD) take 25 soil samples across SMA 3 and at the following locations associated with Quench Towers A: SWMU 1A (Quench Towers & Sumps), SWMU 2A (Quench Tower Pump Basin), SWMU 3A (Old Quench Tower Settling Basin); Quench Towers B: SWMU 1B (Quench Towers & Sumps), SWMU 2B (Quench Tower Pump Basin); SWMU 5 (Coal Tar Storage Drainage System); SWMU 6 (Diesel Tank Spill Area); SWMU 7 (Coal Tar Collection Sump in #1 Pump House); SWMU 8 (Flushing Liquor Decanter); SWMU 9 (Flushing Liquor Decanter Sump); SWMU 10 (Coal Tar Decanter for #3 & #4 Coke Batteries); SWMU 11 (Coal Tar Decanter for Coke Battery #5); and SWMU 12 (Coal Tar Decanter for #1 and #2 Coke Batteries); SWMU 37 (BTF Sewers Sump) (Figure 3). LCRD requested these samples to expedite human health risk evaluation and corrective action.

#### A5. Project Description, Goals, and Study Boundaries

Surficial soil samples (0"-12") will be collected as grab samples from the 25 locations identified by LCRD. These locations are listed in Table 1. Due to the presence of significant amounts of gravel at many of the locations, samples collected may be sieved to remove the large gravel particles and render enough fine soil material for analysis. LSASD will attempt to obtain the sample for volatile organic analysis (VOCs) prior to sieving. Samples will be analyzed at LSASD for VOCs, semi volatile organic compounds (SVOC), polycyclic aromatic compounds (PAH), and metals. LSASD will attempt to obtain sufficient sample material to provide split samples for the facility or their representative. The facility will need to provide their own sample containers.

### **A6.** Applicable Regulatory Information

Data from the sampling will be compared to the Regional Screening Levels (RSLs) for industrial soil.

#### A7. Decision(s) to be made based on data

The facility will submit a plan for corrective measures, if needed, and this data will assist LCRD in evaluating any subsequent proposals. LCRD, in conjunction with Region 4 risk assessors, will determine what action to take based upon the results.

SECTION B: Data Generation, Acquisition, and Reporting					
Will samples or physical evidence be collected:		▼ Yes – If yes, complete all subsections in Section B.			
		□ No -	If no, no action needed for B1, B2, B3 or B4, proceed to B5.		
B1. Sampling Design/Information Inputs					
Sample Media	Total Number of San	nples	Analyses		
			VOCs EPA Method 5035, 8260C		
g - ti	25		SVOCs EPA Method 8270D		
Soil 25		PAH Method 8270D			
			Metals EPA Methods 200.1, 6010		
	B2. Samplin	g Handl	ing and Custody		
As outlined in the <i>Applied Science Branch Quality Assurance Project Plan</i> , all samples will be handled and custody maintained in accordance with the LSASD Laboratory Services Branch Laboratory Operations and Quality Assurance Manual, LSASD Operating Procedure for Sample and Evidence Management, SESDPROC-005, and SESD Operating Procedure for Packing, Labeling and Shipping of Environmental and Waste Samples, SESDPROC-209.					
Will a Chai	n-of-Custody be produced?	⊠ Yes			
win a Cham-of-Custody be produced?		□ No	□ No		

During the duration of the event, have preparations been made to ensure that custody is maintained? <i>Custody of a sample or physical evidence is defined as:</i>	⊠ Yes
<ul> <li>It is in the actual possession of an investigator</li> <li>It is in the view of an investigator, after being in their physical possession</li> <li>It was in the physical possession of an investigator and then they secured it to prevent tampering</li> <li>It is placed in a designated secure area</li> </ul>	□ No
B3. Quality Control	
Field quality control measures will be in accordance with the LSASD Operating Procedure for Field S Quality Control, SESDPROC-011.  Field quality control samples include the following: At least one sample will be designated as a matrix duplicate (MS/MSD).	, 0
Laboratory quality control measures are specified in the LSASD Laboratory Services Branch Laboratory Operations and Quality Assurance Manual.	ory
B4. Analytical Methods and Support	
Samples will be analyzed by the EPA/Region 4 LSASD laboratory in Athens, GA in accordance with Laboratory Services Branch Laboratory Operations and Quality Assurance Manual. Specific analytics include:	

VOCs EPA Method 5035, 8260C SVOCs EPA Method 8270D PAH Method 8270D Metals EPA Methods 200.1, 6010 Laboratory Turn-Around-Time Requested: 35 Days  $\boxtimes$ Non-Routine Reporting Levels **ARE NOT** Required, No Further Action. **Reporting Levels:** Non-Routine Reporting Levels **ARE** Required, List Below. Non-Routine Reporting Levels: □ Yes **Waste Samples Anticipated:** ⊠ No

	□ Unknown
If answer is yes, specify laboratory to receive samples: (i.e., LSASD, commercial lab vis bank card or PR, subcontracted via START/RA	ACS/REPA 5)

#### **B5. Sampling and Measurement Procedures** Sampling and measurement activities will be in accordance to the LSASD operating procedures. The following field procedures will be followed during this study, check all that apply: (Last Update: 8/12/2021) Field Measurement Procedures\* LSASD/SESDPROC-Revision Field pH Measurement 100 R5 Field Specific Conductance Measurement 101 R7 Field Temperature Measurement 102 R5 Field Turbidity Measurement 103 R4 Groundwater Level and Well Depth Measurement 105 R4 Field Measurement of Dissolved Oxygen 106 R4 Field X-Ray Fluorescence (XRF) Measurement 107 R4 П Wastewater Flow Measurement 109 R5 X Global Positioning System 110 R5 In-Situ Water Quality Monitoring 111 R4 Field Measurement of Total Residual Chlorine 112 **R6** Field Measurement of Oxidation-Reduction Potential (ORP) 113 R2 Field Sampling Procedures\* LSASD/SESDPROC-Revision **Sediment Sampling** 200 R4 Surface Water Sampling 201 R4 X 300 Soil Sampling R4 **Groundwater Sampling** 301 R4 $\boxtimes$ Waste Sampling 302 R4 Ambient Air Sampling 303 R5 305 Potable Water Supply Sampling R4 Wastewater Sampling 306 R5 Soil Gas Sampling 307 R4

<sup>\*</sup>If procedures allow for different sampling and measurement methods, the utilized method(s) must be identified in the project description section. Additionally, verify procedure revision numbers before issuance of SAP.

Section C: Reporting				
C1. Reporting				
Estimated Report Completion Date: February 3, 2023				
Is a Provisional Data Release Anticipated?	□ Yes			
is a Frovisional Data Release Anticipateu:	⊠ No			
Provisional data refers to final analytical and field measurement data assessment by the project leader prior to the issuance of a provided prior to the completion of the LSASD final report only and the analytical data have been released as final from the LSA and/or the LSASD Quality Assurance Section, for non-LSASD g by electronic or hard copy with official correspondence from the Procedure for Report Preparation and Distribution (SESDPRO)	final field investigation report. Provisional data may be if LSASD management approves the release of the information ASD Laboratory Services Branch, for LSASD generated data, enerated data. Release of provisional data will be transmitted to Section Chief in accordance with the LSASD Operating			
Additional Comments: A memorandum detailing sampling transmitted to Pesticide Enforcement in lieu of a report.	g activities and observations will be prepared and			

## **Site Figures and Tables**

Table 1 Proposed Sample IDs

Station	Sample ID
ID	•
QTA	QTA-SS-04
SMU01A	SMU01A-SS-01
SMU02A	SMU02A-SS-02
SMU03A	SMU03A-SS-03
QT2B	QT2B-SS-01
SMU01B	SMU01B-SS-03
SMU02B	SMU02B-SS-02
SMU05A	SMU05A-SS-01
SMU05B	SMU05B-SS-02
SMU06	SMU06-SS-01
SMU78	SMU78-SS-01
SMU09	SMU09-SS-01
SMU10A	SMU10A-SS-01
SMU10B	SMU10B-SS-02
SMU11A	SMU11A-SS-01
SMU11B	SMU11B-SS-02
SMU12	SMU12-SS-01
SMU37	SMU37-SS-01
SMA3A	SMA3A-SS-01
SMA3B	SMA3B-SS-02
SMA3C	SMA3C-SS-03
SMA3D	SMA3D-SS-04
SMA3E	SMA3E-SS-05
SMA3F	SMA3F-SS-06
SMA3G	SMA3G-SS-07

**Table 2 Sample Information** 

Bluestone Coke	Sample	Station ID	Sample ID	Latitude GPS	Longitude GPS	Matrix Description	Notes	Soil Sampling
SMA 3 SWMUs				Accuracy +-13 feet	Accuracy +- 13 feet			Location Figure #
Quench Tower A	SS-04	QTA	QTA-SS-04	33.5626N	-86.8038W	Coke breeze		1
SWMU 1A	SS-01	SMU01A	SMU01A-SS-01	33.5629N	-86.8040W	Soil and gravel	outside railroad tracks	1
SWMU 2A	SS-02	SMU02A	SMU02A-SS-02	33.5627N	-86.8037W	Dirt and gravel		1
SWMU 3A	SS-03	SMU03A	SMU03A-SS-03	33.5630N	-86.8037W	Gravel soil coke breeze		1
Quench Tower 2B	SS-01	QT2B	QT2B-SS-01	33.56715N	-86.80021W	Gravel and coke breeze	15 feet from Middle of Quench Tower B	2
SWMU 1B	SS-03	SMU01B	SMU01B-SS-03	33.5665N	-86.8001W	Black soil coke breeze	15 feet from pipe	2
SWMU 2B	SS-02	SMU02B	SMU02B-SS-02	33.56715N	-86.80021W	Coke breeze/coal fines/soil	GPS taken 25 feet from actual sample location below along railroad cut.	2
SWMU 5	SS-01	SMU05A	SMU05A-SS-01	33.5630N	-86.8028W	Grass/soil	Between concrete tank foundations	3
SWMU 5	SS-02	SMU05B	SMU05B-SS-02	33.56323N	-86.80261W	Grass/soil	East of second tank ring foundation	3
SWMU 6	SS-01	SMU06	SMU06-SS-01	33.56546N	-86.80266W	Coke breeze, gravel, fine dust		4
SWMU 7/8	SS-01	SMU78	SMU78-SS-01	33.5637N	-86.8021W	Grass and soil	Corner of building and secondary containment	3,5
SWMU 9	SS-01	SMU09	SMU09-SS-01	33.55410N	-86.80190W	gravel		5
SWMU 10	SS-01	SMU10A	SMU10A-SS-01	33.56522N	-86.801103W	Gravel and dirt	2 pipes but below 1 foot in depth	6
SWMU 10	SS-02	SMU10B	SMU10B-SS-02	33.56539N	-86.80089	Gravel and dirt	Corner of concrete curb	6
SWMU 11	SS-01	SMU11A	SMU11A-SS-01	33.56553N	-86.80061W	Soil and gravel		6
SWMU 11	SS-02	SMU11B	SMU11B-SS-02	33.56557N	-86.80070W	Gravel and dirt	Pipes are well below one foot in depth	6
SWMU 12	SS-01	SMU12	SMU12-SS-01	33.56414N	-86.80189W	Gravel and grass	Two samples for 9 and 12 are close	5
SWMU 37	SS-01	SMU37	SMU37-SS-01	33.56778N	-86.79948	Soil	Sample should be taken 10 feet closer to sump. Location is 27 feet from sump.	8
SMA 3	SS-01	SMA3A	SMA3A-SS-01	33.56584N	-86.80058W	Gravel coke breeze	Between concrete ties	7
SMA 3	SS-02	SMA3B	SMA3B-SS-02	33.56469N	-86.80163W			7
SMA 3	SS-03	SMA3C	SMA3C-SS-03	33.56555N	-86.80008W	Grass/soil		6
SMA 3	SS-04	SMA3D	SMA3D-SS-04	33.5636N	-86.8026W	Gravel and dirt		3
SMA 3	SS-05	SMA3E	SMA3E-SS-05	33.5631N	-86.8033W	Gravel soil grass		3
SMA 3	SS-06	SMA3F	SMA3F-SS-06	33.56707N	-86.80013W	Soil	Next to tank	2
SMA 3	SS-07	SMA3G	SMA3G-SS-07	33.56495N	-86.80124W	Soil gravel dust coke breeze	125 feet south of SWMU 10 SS-01	6




Figure 2



Figure 3



Figure 4




Figure 5



Figure 6




Figure 7




Figure 8

