LEASE NO. GS-11P-LDC00638
BUILDING NO. DC-0685

Warehouse Lease
GSA TEMPLATE FORM L201WH (10/2021)

A. This Lease is made and entered into between

Terreno V Street, LLC

(Lessor), whose principal place of business is 101 Montgomery Street, San Francisco, CA 94104, and whose interest in the Property described herein is that of Fee Owner, and

The United States of America

(Government), acting by and through the designated representative of the General Services Administration (GSA), upon the terms and conditions set forth herein.

B. Witnesseth: The parties hereto, for the consideration hereinafter mentioned, covenant and agree as follows:

Lessor hereby leases to the Government the Premises described herein, being all or a portion of the Property located at

3035 V Street, NE, Washington, DC 20018

and more fully descr bed in Section 1 and Exh bit **A,** together with rights to the use of parking and other areas as set forth herein, to be used for such purposes as determined by GSA.

C. LEASE TERM

To Have and To Hold the said Premises with its appurtenances for the term beginning upon acceptance of the Premises as required by this Lease and continuing for a period of

15 Years, 10 Years Firm,

subject to termination and renewal rights as may be hereinafter set forth. The commencement date of this Lease, along with any applicable termination and renewal rights, shall be more specifically set forth in a Lease Amendment upon substantial completion and acceptance of the Space by the Government.

In Witness Whereof, the parties to this Lease evidence their agreement to all terms and conditions set forth herein by their signatures below, to be effective as of the date of delivery of the fully executed Lease to the Lessor.

FOR THE LESSOR:

(b) (6) [redacted]

Name: Cody Saunders

Title: Senior Vice President

Entity: Terreno Realty Corp.

Date: 6/9/2022

FOR THE GOVERNMENT:

(b) (6) [redacted]

Name: Lynn Abram

Title: Lease Contracting Officer

General Services Administration, Public Buildings Service

Date: 6/30/2022

WITNESSED FOR THE LESSOR BY:

(b) (6) [redacted]

Name: Hayes Graham

Title: Vice President

Date: 6/9/2022

The information collection requirements contained in this Solicitation/Contract, that are not required by regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

SECTION 1 THE PREMISES, RENT, AND OTHER TERMS 5
1.01 THE PREMISES (WAREHOUSE) (OCT 2016) 5
1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014) 5
1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014) 6
1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014) 6
1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014) 6
1.06 RENT AND OTHER CONSIDERATION (WAREHOUSE) (OCT 2021) 6
1.07 BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016) 7
1.08 TERMINATION RIGHTS (OCT 2016) 7
1.09 RENEWAL RIGHTS (OCT 2016) 7
1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2021) 8
1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011) 8
1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016) 8
1.13 TENANT IMPROVEMENT FEE SCHEDULE (OCT 2020) 8
1.14 ~~BUILDING SPECIFIC AMORTIZED CAPITAL (SEP 2012)~~ INTENTIONALLY DELETED 8
1.15 ~~BUILDING SPECIFIC AMORTIZED CAPITAL RENTAL ADJUSTMENT (SEP 2013)~~ INTENTIONALLY DELETED 8
1.16 PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2021) 8
1.17 REAL ESTATE TAX BASE (SEP 2013) 9
1.18 OPERATING COST BASE (OCT 2016) 9
1.19 ~~RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)~~ INTENTIONALLY DELETED 9
1.20 ~~HOURLY OVERTIME HVAC RATES (OCT 2016)~~ INTENTIONALLY DELETED 9
1.21 ~~ADJUSTMENT FOR REDUCED SERVICES (OCT 2018)~~ INTENTIONALLY DELETED 9
1.22 ~~BUILDING IMPROVEMENTS (MAR 2016)~~ INTENTIONALLY DELETED 9
1.23 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAR 2012) 9
1.24 LESSOR'S UNIQUE ENTITY IDENTIFIER (OCT 2021) 9

SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS 10
2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016) 10
2.02 AUTHORIZED REPRESENTATIVES (OCT 2016) 11
2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018) 11
2.04 WAIVER OF RESTORATION (OCT 2021) 11
2.05 PAYMENT OF BROKER (OCT 2021) 11
2.06 CHANGE OF OWNERSHIP/NOVATION (OCT 2021) 11
2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012) 12
2.08 ADJUSTMENT FOR VACANT PREMISES (OCT 2017) 13
2.09 OPERATING COSTS ADJUSTMENT (JUN 2012) 13
2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012) 14
2.11 ~~RELOCATION ASSISTANCE ACT (APR 2011)~~ INTENTIONALLY DELETED 14

SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS 15
3.01 ~~LABOR STANDARDS (OCT 2016)~~ INTENTIONALLY DELETED 15
3.02 WORK PERFORMANCE (JUN 2012) 15
3.03 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (OCT 2019) 15
3.04 CONSTRUCTION WASTE MANAGEMENT (OCT 2021) 15
3.05 WOOD PRODUCTS (OCT 2019) 15
3.06 ADHESIVES AND SEALANTS (OCT 2019) 15
3.07 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016) 16
3.08 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012) 16
3.09 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014) 16
3.10 VESTIBULES (OCT 2020) 16
3.11 MEANS OF EGRESS (WAREHOUSE) (MAY 2015) 16
3.12 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014) 17
3.13 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014) 17
3.14 ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016) 17
3.15 ELEVATORS (WAREHOUSE) (OCT 2020) 18
3.16 ~~FLAGPOLE (SEP 2013)~~ INTENTIONALLY DELETED 18
3.17 DEMOLITION (JUN 2012) 18
3.18 ACCESSIBILITY (FEB 2007) 18
3.19 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014) 19
3.20 DOORS: IDENTIFICATION (APR 2011) 19
3.21 WINDOWS (OCT 2020) 19
3.22 PARTITIONS: GENERAL (OCT 2019) 19
3.23 PARTITIONS: PERMANENT (OCT 2019) 19
3.24 INSULATION: THERMAL, ACOUSTIC, AND HVAC (OCT 2019) 19
3.25 WALL FINISHES—SHELL (SEP 2015) 20
3.26 PAINTING—SHELL (OCT 2019) 20
3.27 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (OCT 2019) 20
3.28 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014) 21
3.29 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011) 21

3.30 BUILDING SYSTEMS (APR 2011) 21
3.31 ELECTRICAL—SHELL (WAREHOUSE) (OCT 2019)....21
3.32 ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)....21
3.33 PLUMBING (JUN 2012) 21
3.34 DRINKING FOUNTAINS (WAREHOUSE) (OCT 2018)....21
3.35 RESTROOMS (WAREHOUSE) (OCT 2021) 22
3.36 PLUMBING FIXTURES: WATER CONSERVATION (OCT 2019) 22
3.37 JANITOR CLOSETS (SEP 2015) 23
3.38 HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2021)....23
3.39 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000) 23
3.40 ~~TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)~~ INTENTIONALLY DELETED 24
3.41 LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2020)....24
3.42 ACOUSTICAL REQUIREMENTS (JUN 2012) 24
3.43 ~~ENERGY EFFICIENCY AND CONSERVATION FOR NEW CONSTRUCTION (SEP 2010)~~ INTENTIONALLY DELETED 24
3.44 ~~SECURITY FOR NEW CONSTRUCTION (AUG 2021)~~ INTENTIONALLY DELETED 24
3.45 ~~SEISMIC SAFETY FOR NEW CONSTRUCTION (OCT 2020)~~ INTENTIONALLY DELETED 25
3.46 ~~FIRE PROTECTION FOR NEW CONSTRUCTION (WAREHOUSE) (MAY 2015)~~ INTENTIONALLY DELETED....25
3.47 INDOOR AIR QUALITY DURING CONSTRUCTION (OCT 2021) 25
3.48 SYSTEMS COMMISSIONING (OCT 2021) 25
3.49 LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)....25
3.50 EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014) 26
3.51 MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)....26
3.52 ~~DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)~~ INTENTIONALLY DELETED 27
3.53 ~~NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS – LEASE (SEP 2014)~~ INTENTIONALLY DELETED....27

SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES....28
4.01 ~~SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2020)~~ INTENTIONALLY DELETED 28
4.02 CONSTRUCTION DOCUMENTS (SEP 2012)....28
4.03 ~~TENANT IMPROVEMENTS PRICE PROPOSAL (OCT 2020)~~ INTENTIONALLY DELETED 28
4.04 ~~BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2015)~~ INTENTIONALLY DELETED 28
4.05 ~~GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2021)~~ INTENTIONALLY DELETED....28
4.06 ~~CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (OCT 2020)~~ INTENTIONALLY DELETED....28
4.07 ~~PROGRESS REPORTS (OCT 2020)~~ INTENTIONALLY DELETED....28
4.08 ~~ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)~~ INTENTIONALLY DELETED 28
4.09 ~~CONSTRUCTION INSPECTIONS (SEP 2015)~~ INTENTIONALLY DELETED 28
4.10 ~~LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (OCT 2021)~~ INTENTIONALLY DELETED....28
4.11 ~~AS-BUILT DRAWINGS (OCT 2021)~~ INTENTIONALLY DELETED....28
4.12 ~~LIQUIDATED DAMAGES (JUN 2012)~~ INTENTIONALLY DELETED....28
4.13 ~~SEISMIC RETROFIT (SEP 2013)~~ INTENTIONALLY DELETED 28
4.14 GOVERNMENT PROJECT MANAGEMENT SYSTEM (OCT 2021) 28

SECTION 5 TENANT IMPROVEMENT COMPONENTS....29
5.01 ~~TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)~~ INTENTIONALLY DELETED 29
5.02 ~~FINISH SELECTIONS (SEP 2015)~~ INTENTIONALLY DELETED 29
5.03 WINDOW COVERINGS (WAREHOUSE) (JUN 2012) 29
5.04 DOORS: SUITE ENTRY (OCT 2019) 29
5.05 DOORS: INTERIOR (OCT 2019)....29
5.06 DOORS: HARDWARE (SEP 2013)....29
5.07 DOORS: IDENTIFICATION (JUN 2012) 29
5.08 PARTITIONS: SUBDIVIDING (OCT 2020)....29
5.09 CEILINGS—TI (WAREHOUSE) (OCT 2019)....30
5.10 WALL FINISHES (OCT 2019)....30
5.11 ~~PAINTING—TI (OCT 2019)~~ INTENTIONALLY DELETED....30
5.12 ~~FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2019)~~ INTENTIONALLY DELETED....30
5.13 ~~HEATING AND AIR CONDITIONING – TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED....30
5.14 ~~ELECTRICAL: DISTRIBUTION – TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED 30
5.15 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)....30
5.16 ~~TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)~~ INTENTIONALLY DELETED....30
5.17 ~~DATA DISTRIBUTION (OCT 2020)~~ INTENTIONALLY DELETED....30
5.18 ~~ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (OCT 2020)~~ INTENTIONALLY DELETED 30
5.19 ~~LIGHTING: INTERIOR AND PARKING – TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED 30
5.20 ~~LOADING DOCKS – TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED 30
5.21 ~~AUTOMATIC FIRE SPRINKLER SYSTEM – TI (OCT 2016)~~ INTENTIONALLY DELETED....30

SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM....32
6.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014) 32
6.02 UTILITIES SEPARATE FROM RENTAL/BUILDING OPERATING PLAN (OCT 2020)....32
6.03 ~~UTILITY CONSUMPTION REPORTING (OCT 2016)~~ INTENTIONALLY DELETED....32

6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2020) 32
6.05 ~~OVERTIME HVAC USAGE (OCT 2020)~~ INTENTIONALLY DELETED 33
6.06 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014) 33
6.07 ~~SELECTION OF CLEANING PRODUCTS (OCT 2021)~~ INTENTIONALLY DELETED 33
6.08 ~~SELECTION OF PAPER PRODUCTS (OCT 2021)~~ INTENTIONALLY DELETED 33
6.09 SNOW REMOVAL (WAREHOUSE) (OCT 2020) 33
6.10 MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014) 33
6.11 MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016) 33
6.12 ASBESTOS ABATEMENT (OCT 2021) 34
6.13 ONSITE LESSOR MANAGEMENT (APR 2011) 34
6.14 IDENTITY VERIFICATION OF PERSONNEL (OCT 2021) 34
6.15 SCHEDULE OF PERIODIC SERVICES (OCT 2020) 34
6.16 LANDSCAPING (OCT 2019) 35
6.17 LANDSCAPE MAINTENANCE (APR 2011) 35
6.18 RECYCLING—WAREHOUSE (OCT 2021) 35
6.19 ~~RANDOLPH SHEPPARD COMPLIANCE (SEP 2013)~~ INTENTIONALLY DELETED 35
6.20 SAFEGUARDING AND DISSEMINATION OF CONTROLLED UNCLASSIFIED INFORMATION (CUI) BUILDING INFORMATION (FEB 2020) 35
6.21 INDOOR AIR QUALITY (OCT 2019) 36
6.22 RADON IN AIR (OCT 2016) 37
6.22 ~~RADON IN WATER (JUN 2012)~~ INTENTIONALLY DELETED 37
6.23 HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014) 37
6.24 MOLD (OCT 2021) 37
6.25 OCCUPANT EMERGENCY PLANS (OCT 2020) 37
6.26 ~~FLAG DISPLAY (OCT 2016)~~ INTENTIONALLY DELETED 37
6.27 PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014) 37
6.28 TRASH DUMPSTER SERVICE (WAREHOUSE) – GOVERNMENT PROVIDED (OCT 2016) 38
6.29 ACCESS TO BUILDING INFORMATION (MAY 2014) 38

SECTION 7 ADDITIONAL TERMS AND CONDITIONS 39
7.01 SECURITY REQUIREMENTS (OCT 2016) 39
7.02 MODIFIED LEASE PARAGRAPHS (OCT 2016) 39
7.03 ADDENDUM TO GSA FORM 3517B, GENERAL CLAUSES, NO FEDERALLY ELECTED OFFICIALS TO BENEFIT (OCT 2018) 39
7.04 PROVISIONAL ACCEPTANCE (FEB 2021) 39
7.05 AS-EXISTING CONDITION (MAY 2022) 40

SECTION 1 THE PREMISES, RENT, AND OTHER TERMS

1.01 THE PREMISES (WAREHOUSE) (OCT 2016)

The Premises are descr bed as follows:

A. Warehouse and Related Space: **27,100** rentable square feet yielding **26,755** ANSI/BOMA Office Area (ABOA) square feet (SF) of warehouse Space, as depicted on the floor plan(s) attached hereto as Exhibit **A**.

B. Common Area Factor: The Common Area Factor (CAF), defined under Section 2 of the Lease, is established as **1.289479** percent. This factor, rounded to the nearest whole percentage, shall be used for purposes of rental adjustments in accordance with the Payment Clause of the General Clauses.

1.02 EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)

The Government shall have exclusive or non-exclusive (as identified) right to the use of Appurtenant Areas, and shall have the right to post Rules and Regulations Governing Conduct on Federal Property, Title 41, CFR, Part 102-74, Subpart C within such areas. The Government will coordinate with Lessor to ensure signage is consistent with Lessor's standards. Appurtenant to the Premises and included in the Lease are rights to use the following:

A. Automobile Parking:
25 parking spaces for passenger vehicles as depicted on the plan attached hereto as Exh bit **B** of which **25** spaces shall be marked as reserved for the exclusive use of the Government. In addition, the Lessor shall provide any additional automobile parking spaces as required by the applicable code of the local government entity having jurisdiction over the Property. All spaces must be secured and lit in accordance with the Security Requirements set forth in this Lease. The cost of this parking shall be included as part of the rental consideration.

B. INTENTIONALLY DELETED

C. Delivery Route:
(1) At least one unobstructed route having no steps or abrupt changes in level shall connect with all access ble elements, spaces, buildings, and courses of passage. The minimum clear width of a route shall be 36 inches. If a route is less than 60 inches in width then it shall have level passing zones, spaced at no more than 200 feet apart, measuring a minimum of 60 inches by 60 inches.

(2) Objects projecting from walls with their leading edges between 27 and 80 inches above the finished floor shall protrude no more than 4 inches into an accessible route. Freestanding objects mounted on posts or pylons may overhang 12 inches maximum from 27 to 80 inches above the ground or the finished floor. Objects mounted with their leading edges at or below 27 inches above the finished floor may protrude any distance. However, no protruding objects shall reduce the clear width of an accessible route or maneuvering space. If vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches, a barrier to warn blind or visually impaired persons shall be provided.

(3) Mechanical rooms and spaces which are not normally frequented by the public or occupants and are not part of an access ble or emergency route are excepted and need not be accessible.

(4) Gratings in a route surface shall have spaces no wider than ½ inch in one direction and shall be placed so that the long dimension of openings is perpendicular to the dominant direction of travel.

D. Delivery Ramps:
(1) Any part of an accessible route with a slope greater than 1 foot rise in 20 feet shall be considered a ramp. Where ramps are necessary, they shall have a non-slip surface with a slope no greater than 1 foot rise in 12 feet. Ramps must have a minimum clear width of 3 feet with level landings at the top and bottom of each ramp run. Each landing shall be at least 5 feet in length and as wide as any ramp run leading into it. The maximum rise for any run shall be 30 inches. Intermediate landings for turning ramps shall measure a minimum of 5 feet by 5 feet.

(2) Lessor shall provide handrails complying with "HANDRAILS" (36 CFR 1191) on both sides of all ramps with a vertical rise greater than 6 inches. Ramps with drop-offs shall have curbs (minimum 2 inches high), walls, railings or projecting surfaces. Lessor shall provide curb ramps wherever an accessible route crosses a curb. Curb ramps shall not interfere with walks or vehicular traffic. The maximum slope of a curb ramp shall be a 1 inch rise per 12 inch run. The maximum length of a curb ramp shall be 6 feet with a minimum width of 36 inches, exclusive of flared sides. If no other alternative is feasible, accessible platform lifts may be used in lieu of a ramp or elevator. Lifts shall have accessible controls and clearances, shall comply with applicable safety regulations, and should facilitate unassisted entry and exit.

E. Antennas, Satellite Dishes, and Related Transmission Devices:
(1) Space located on the roof of the Building sufficient in size for the installation and placement of telecommunications equipment,

(2) the right to access the roof of the Building, and

(3) use of all Building areas (e.g., chases, plenums, etc.) necessary for the use, operation, and maintenance of such telecommunications equipment at all times during the term of this Lease.

F. Loading Docks. See "LOADING DOCKS SHELL WAREHOUSE" paragraph in Section 3 of this Lease.

1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)

At a minimum, a truck turning radius of **53 feet** sized for **tractor trailer** trucks shall be provided and maintained at all times for all loading docks designed for such sized trucks. One-way design for service traffic is **preferred** in order to avoid the need for large turning areas.

1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)

A minimum of **21,081** ABOA SF must have a clear ceiling height of **18** feet **0** inches, measured from floor to the lowest obstruction, with the balance of the space maintaining a clear ceiling height of a minimum of **9** feet. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided.

1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)

The following minimum requirements apply to this Lease:

Bay Width: **24' 0"** (the distance from one side of the bay to the other side of the bay in linear feet and inches)
Bay Depth: **38' 0"** (the distance from the front of the bay to the back of the bay in linear feet and inches)
Column Spacing: Columns shall be **18' 0"** linear feet apart from one another

1.06 RENT AND OTHER CONSIDERATION (WAREHOUSE) (OCT 2021)

A. The Government shall pay the Lessor annual rent, payable in monthly installments in arrears, at the following rates:

	FIRM TERM YEARS 1-5	FIRM TERM YEARS 6-10
	ANNUAL RENT	ANNUAL RENT
SHELL RENT[1]	$485,361.00	$535,496.00
OPERATING COSTS[2]	(b) (4)	
TENANT IMPROVEMENTS RENT[3]		
TOTAL ANNUAL RENT[4]	**$563,556.93**	**$613,691.93**

[1]Shell rent calculation:
(Firm Term Years 1-5) **$17.91** per RSF multiplied by the RSF stated under Paragraph 1.01
(Firm Term Years 6-10) **$19.76** per RSF multiplied by the RSF stated under Paragraph 1.01

(b) (4)

B. INTENTIONALLY DELETED

C. INTENTIONALLY DELETED

D. INTENTIONALLY DELETED.

E. INTENTIONALLY DELETED .

F. Rent is subject to adjustment based upon the final Tenant Improvement (TI) cost to be amortized in the rental rate, as agreed upon by the parties subsequent to the Lease Award Date.

H. If the Government leases the Premises for less than a full calendar month, then rent shall be prorated based on the actual number of days leased for that month.

I. Rent shall be paid to Lessor by electronic funds transfer in accordance with the provisions of the General Clauses. Rent shall be payable using the EFT information contained in the System for Award Management (SAM). In the event the EFT information changes, the Lessor shall be respons ble for providing the updated information to SAM. Failure by the Lessor to maintain an active registration in SAM may result in delay of rental payments until such time as the SAM registration is activated.

J. Lessor shall provide to the Government, in exchange for the payment of rental and other specified consideration, the following:

1. The leasehold interest in the Property described herein in the paragraph entitled "The Premises."

2. All costs, expenses, and fees to perform the work required for acceptance of the Premises in accordance with this Lease, including all costs for labor, materials, and equipment, professional fees, contractor fees, attorney fees, permit fees, inspection fees, and similar such fees, and all related expenses;

3. Performance or satisfaction of all other obligations set forth in this Lease; and all services, utilities (with the exclusion of **electricity, gas, water, janitorial, and trash removal**), maintenance required for the proper operation of the Property, the Building, and the Leased Premises, in accordance with the terms of the Lease, including, but not limited to, all inspections, modifications, repairs, replacements and improvements required to be made thereto to meet the requirements of this Lease. The Government shall be responsible for paying the cost of **electricity, gas, water, janitorial, and trash removal** directly to the utility provider. The Lessor shall ensure that such utilities are separately metered. The Lessor shall provide and install as part of shell rent, separate meters for utilities. Sub-meters are not acceptable. The Lessor shall furnish in writing to the LCO, prior to occupancy by the Government, a record of the meter numbers and verification that the meters measure Government usage only. Proration is not permissible. In addition, an automatic control system shall be provided to assure compliance with heating and air conditioning requirements.

K. For succeeding Leases with an incumbent Lessor where the Government is currently in occupancy and possession of the leased Premises and where the Lease requires the Lessor to perform alterations using either the TIA or BSAC, the amortized tenant improvement rent and/or BSAC rent will not commence until the alterations are complete and accepted by the Government. Upon acceptance of these improvements, the Government will commence payment of the tenant improvement and/or BSAC rent as stipulated under the Lease, in addition to payment of the tenant improvement and/or BSAC rent for the period starting from the Lease Term Commencement Date to the date of tenant improvement/BSAC acceptance by the Government (such rent payment will not include any additional interest). Alternatively, the Government may elect to re-amortize the tenant improvements/BSAC over the remaining Firm Term of the Lease, at the amortization rate stipulated in the Lease. In the event the Government does not use all the TIA or BSAC, then the rental payments will be adjusted in accordance with the provisions of the Lease (e.g., de-amortization).

1.07 BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016)

A. **CBRE, INC.** (Broker) is the authorized real estate Broker representing GSA in connection with this Lease transaction. The total amount of the Commission is (b) (4) and is earned upon Lease execution, payable according to the Commission Agreement signed between the Lessor and Broker. Only (b) (4) of the Commission will be payable to **CBRE, INC.** with the remaining (b) (4), which is the Commission Credit, to be credited to the shell rental portion of the annual rental payments due and owing to fully recapture this Commission Credit. The reduction in shell rent shall commence with the first month of the rental payments and continue until the credit has been fully recaptured in equal monthly installments over the shortest time practicable.

B. Notwithstanding the "Rent and Other Consideration" paragraph of this Lease, the shell rental payments due and owing under this Lease shall be reduced to recapture fully this Commission Credit. The reduction in shell rent shall commence with the first month of the rental payments and continue as indicated in this schedule for adjusted Monthly Rent:

Month **1** Shell Rental Payment **$40,446.75** minus prorated Commission Credit of $(b) (4) adjusted **1st** Month's Shell Rent.*

Month **2** Shell Rental Payment **$40,446.75** minus prorated Commission Credit of (b) (4) adjusted **2nd** Month's Shell Rent.*

Month **3** Shell Rental Payment **$40,446.75** minus prorated Commission Credit of (b) (4) adjusted **3rd** Month's Shell Rent.*

Month **4** Shell Rental Payment **$40,446.75** minus prorated Commission Credit of (b) (4) adjusted **4th** Month's Shell Rent.*

* Subject to change based on adjustments outlined under the paragraph "Rent and Other Consideration."

1.08 TERMINATION RIGHTS (OCT 2016)

The Government may terminate this Lease, in whole or in parts, at any time effective after the Firm Term of this Lease, by providing not less than **180** days' prior written notice to the Lessor. The effective date of the termination shall be the day following the expiration of the required notice period or the termination date set forth in the notice, whichever is later. No rental shall accrue after the effective date of termination.

1.09 RENEWAL RIGHTS (OCT 2016)

A. This Lease may be renewed at the option of the Government for a term of **5 YEARS** at the following rental rate(s):

	OPTION TERM, YEARS 11—15	
	ANNUAL RENT	ANNUAL RATE / RSF
SHELL RENTAL RATE	**$639,560.00**	**$23.60**
OPERATING COSTS	OPERATING COST BASE SHALL CONTINUE FROM THE EFFECTIVE YEAR OF THE LEASE. OPTION TERM IS SUBJECT TO CONTINUING ANNUAL ADJUSTMENTS.	

provided notice is given to the Lessor at least **120** days before the end of the original Lease term or any extension thereof; all other terms and conditions of this Lease, as same may have been amended, shall remain in full force and effect during any renewal term.

B. Termination rights outlined "Termination Rights" paragraph apply to all renewal terms.

1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2021)

The following documents are attached to and made part of the Lease:

DOCUMENT NAME	EXHIBIT	NO. OF PAGES
FLOOR PLAN(S)	A	2
PARKING PLAN(S)	B	1
SITE PLAN(S)	C	1
AGENCY SPECIAL REQUIREMENTS	D	20
SECURITY REQU REMENTS	E	14
GSA FORM 3517B GENERAL CLAUSES	F	17
SMALL BUSINESS SUBCONTRACTING PLAN	G	12
REVISION(S) TO LEASE ISSUED UNDER RLP AMENDMENT NUMBER(S) I	H	1
LISTING OF TERRENO V STREET, LLC TAX PARCELS	I	1

1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)

The Tenant Improvement Allowance (TIA) for purposes of this Lease is (b) (4) [redacted]. The TIA is the amount that the Lessor shall make available for the Government to be used for TIs. This amount is amortized in the rent over the Firm Term of this Lease at an (b) (4) [redacted]

1.12 TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016)

A. The Government, at its sole discretion, shall make all decisions as to the use of the TIA. The Government may use all or part of the TIA. The Government may return to the Lessor any unused portion of the TIA in exchange for a decrease in rent according to the agreed-upon amortization rate over the Firm Term.

B. The Government may elect to make lump sum payments for any or all work covered by the TIA. That part of the TIA amortized in the rent shall be reduced accordingly. At any time after occupancy and during the Firm Term of the Lease, the Government, at its sole discretion, may elect to pay lump sum for any part or all of the remaining unpaid amortized balance of the TIA. If the Government elects to make a lump sum payment for the TIA after occupancy, the payment of the TIA by the Government will result in a decrease in the rent according to the amortization rate over the Firm Term of the Lease.

C. If it is anticipated that the Government will spend more than the identified TIA, the Government may elect to:

1. Reduce the TI requirements;

2. Pay lump sum for the overage upon substantial completion in accordance with the "Acceptance of Space and Certificate of Occupancy" paragraph;

3. Negotiate an increase in the rent.

1.13 TENANT IMPROVEMENT FEE SCHEDULE (OCT 2020)

For pricing TI costs, the following rates shall apply for the initial build-out of the Space.

	INITIAL BUILD-OUT
ARCHITECT/ENGINEER (A/E) FEES ($ PER ABOA SF OR % OF TI CONSTRUCTION COSTS)	(b) (4) [redacted]
LESSOR'S PROJECT MANAGEMENT FEE (% OF TI CONSTRUCTION COSTS)	

1.14 ~~BUILDING SPECIFIC AMORTIZED CAPITAL (SEP 2012)~~ INTENTIONALLY DELETED

1.15 ~~BUILDING SPECIFIC AMORTIZED CAPITAL RENTAL ADJUSTMENT (SEP 2013)~~ INTENTIONALLY DELETED

1.16 PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2021)

A. As of the Lease Award Date, the Government's Percentage of Occupancy, as defined in the "Real Estate Tax Adjustment" paragraph of this Lease is 3.3 percent. The Percentage of Occupancy is derived by dividing the total Government Space of 27,100 RSF by the total Building space of 821,410 RSF. The tax parcel numbers associated with this lease are outlined in Exh bit I: Listing of Terreno V Street, LLC Tax Parcels.

B. All relevant tax adjustment documentation (e.g. copies of paid tax receipts, invoices) must be submitted online via the GSA Real Estate Tax Portal at RET.GSA.GOV or a successor portal.

1.17 REAL ESTATE TAX BASE (SEP 2013)

The Real Estate Tax Base, as defined in the "Real Estate Tax Adjustment" paragraph of the Lease is $**63,859.41**. Tax adjustments shall not occur until the tax year following lease commencement has passed.

1.18 OPERATING COST BASE (OCT 2016)

The parties agree, for the purpose of applying the paragraph titled "Operating Costs Adjustment," that the Lessor's base rate for operating costs shall be (b) (4) [redacted]

1.19 ~~RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)~~ INTENTIONALLY DELETED

1.20 ~~HOURLY OVERTIME HVAC RATES (OCT 2016)~~ INTENTIONALLY DELETED

1.21 ~~ADJUSTMENT FOR REDUCED SERVICES (OCT 2018)~~ INTENTIONALLY DELETED

1.22 ~~BUILDING IMPROVEMENTS (MAR 2016)~~ INTENTIONALLY DELETED

1.23 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (MAR 2012)

If the Lessor is a qualified HUBZone small business concern (SBC) that did not waive the price evaluation preference then as required by 13 C.F.R. 126.700, the HUBZone SBC must spend at least 50% of the cost of the contract incurred for personnel on its own employees or employees of other qualified HUBZone SBC's and must meet the performance of the work requirements for subcontracting in 13 C.F.R. § 125.6(c). If the Lessor is a HUBZone joint venture, the aggregate of the qualified HUBZone SBC's to the joint venture, not each concern separately, must perform the applicable percentage of work required by this clause.

1.24 LESSOR'S UNIQUE ENTITY IDENTIFIER (OCT 2021)

Lessor's Unique Entity Identifier (UEI)

UEI-DUNS: (b) (6) [redacted]

UEI-SAM: (b) (6) [redacted]

SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS

2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016)

Unless otherwise specifically noted, all terms and conditions set forth in this Lease shall be interpreted by reference to the following definitions, standards, and formulas:

A. Appurtenant Areas. Appurtenant Areas are defined as those areas and facilities on the Property that are not located within the Premises, but for which rights are expressly granted under this Lease, or for which rights to use are reasonably necessary or reasonably anticipated with respect to the Government's enjoyment of the Premises and express appurtenant rights (such as parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease).

B. Broker. If GSA awarded this Lease using a contract real estate broker, Broker shall refer to GSA's broker.

C. Building. Building(s) situated on the Property in which the Premises are located.

D. Commission Credit. If GSA awarded this Lease using a Broker, and the Broker agreed to forego a percentage of its commission to which it is entitled in connection with the award of this Lease, the amount of this credit is referred to as the "Commission Credit."

E. Common Area Factor. The "Common Area Factor" (CAF) is a conversion factor determined by the Building owner and applied by the owner to the ABOA SF to determine the RSF for the leased Space. The CAF is expressed as a percentage of the difference between the amount of rentable SF and ABOA SF, divided by the ABOA SF. For example 11,500 RSF and 10,000 ABOA SF will have a CAF of 15% [(11,500 RSF-10,000 ABOA SF)/10,000 ABOA SF]. For the purposes of this Lease, the CAF shall be determined in accordance with the applicable ANSI/ BOMA standard for the type of space to which the CAF shall apply.

F. Contract. "Contract" shall mean this Lease.

G. Contractor. "Contractor" shall mean Lessor.

H. Days. All references to "day" or "days" in this Lease shall mean calendar days, unless specified otherwise.

I. FAR. All references to the FAR shall be understood to mean the Federal Acquisition Regulation, codified at 48 CFR Chapter 1.

J. Firm Term/Non-Firm Term. The Firm Term is that part of the Lease term that is not subject to termination rights. The Non-Firm Term is that part of the Lease term following the end of the Firm Term.

K. GSAR. All references to the GSAR shall be understood to mean the GSA supplement to the FAR, codified at 48 CFR Chapter 5.

L. Lease Term Commencement Date. The date on which the lease term commences.

M. Lease Award Date. The date the LCO executes the Lease and mails or otherwise furnishes written notification of the executed Lease to the successful Offeror (date on which the parties' obligations under the Lease begin).

N. Premises. Defined as the total Warehouse Area, Office Area, and other type of Space, together with all associated common areas, described in Section 1 of this Lease, and delineated by plan in the attached exhibit. Parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease are not included in the Premises.

O. Property. Defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas, wareyards, loading docks, aprons, loading ramps) to which the Government is granted rights.

P. Racking System Plan—A plan that at a minimum must include clear ceiling height requirement(s), aisle width(s), shelving depth(s) and type of material(s) to be stored . In addition such Plan shall identify locations and dimensions of storage of materials in packed piles, on pallets, in racks, or on shelves.

Q. Rentable Space or Rentable Square Feet (RSF). Rentable Space is the area for which a tenant is charged rent. It is determined by the Building owner and may vary by city or by building within the same city. The Rentable Space may include a share of Building support/common areas such as elevator lobbies, Building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The Rentable Space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts. Rentable Square Feet is calculated using the following formula for each type of Space (e.g., office, warehouse, etc.) included in the Premises: ABOA SF of Space x (1 + CAF) = RSF.

R. Space. The Space shall refer to that part of the Premises to which the Government has exclusive use, such as Office Area, or other type of Space. Parking areas, wareyards, loading docks, aprons, loading ramps to which the Government has rights under this Lease are not included in the Space.

S. Warehouse and office space. For the purposes of this Lease, Space shall be measured in accordance with the standard (Z65.1-1996) provided by American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) for Office Area, which means "the area

where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed." References to ABOA mean ANSI/BOMA Office Area.

T. Working Days. Working Days shall mean weekdays, excluding Saturdays and Sundays and Federal holidays.

2.02 AUTHORIZED REPRESENTATIVES (OCT 2016)

Signatories to this Lease shall have full authority to bind their respective principals with regard to all matters relating to this Lease. No other persons shall be understood to have any authority to bind their respective principals, except to the extent that such authority may be explicitly delegated by notice to the other party, or to the extent that such authority is transferred by succession of interest. The Government shall have the right to substitute its Lease Contracting Officer (LCO) by notice, without an express delegation by the prior LCO.

2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)

A. The Government may request the Lessor to provide alterations during the term of the Lease. Alterations will be ordered by issuance of a Lease Amendment, GSA Form 300, Order for Supplies or Services, or a tenant agency-approved form when specifically authorized to do so by the LCO. The General Services Administration Acquisition Manual ("GSAM") clause, 552.270-31, Prompt Payment, including its invoice requirements, shall apply to orders for alterations. All orders are subject to the terms and conditions of this Lease and may be placed by the LCO or a warranted contracting officer's representative (COR) in GSA or the tenant agency when specifically authorized to do so by the LCO, subject to the threshold limitation below.

B. Orders for alterations issued by an authorized COR are limited to no more than $250,000 (LCOs are not subject to this threshold). This threshold will change according to future adjustments of the simplified acquisition threshold (see FAR 2.101). The LCO will provide the Lessor with a list of tenant agency officials authorized to place orders and will specify any limitations on the authority delegated to tenant agency officials. The tenant agency officials are not authorized to deal with the Lessor on any other matters.

C. Payments for alterations ordered by the tenant agency under the authorization described in sub-paragraph B will be made directly by the tenant agency placing the order.

2.04 WAIVER OF RESTORATION (OCT 2021)

Lessor shall have no right to require the Government to restore the Premises upon expiration or earlier termination (full or partial) of the Lease, and waives all claims against the Government for:
a) waste, or,
b) damages or restoration arising from or related to:
(1) the Government's normal and customary use of the Premises during the term of the Lease (including any extensions thereof), as well as
(2) any initial or subsequent alteration to the Premises regardless of whether such alterations are performed by the Lessor or by the Government.

At its sole option, the Government may abandon property in the Space following expiration or earlier termination (full or partial) of the Lease, in which case the property will become the property of the Lessor and the Government will be relieved of any liability in connection therewith.

2.05 PAYMENT OF BROKER (OCT 2021)

If GSA awarded the Lease through its Broker, the Lessor shall pay GSA's Broker its portion of the commission according to the Commission Agreement signed between the Lessor and Broker. "Its portion of the commission" means the agreed-upon commission to GSA's Broker minus the Commission Credit specified in the Lease or Lease Amendment.

2.06 CHANGE OF OWNERSHIP/NOVATION (OCT 2021)

A. If during the term of the Lease, title to the Property is transferred or the Lessor changes its legal name, the Lessor and its successor shall comply with the requirements of FAR Subpart 42.12. If title is transferred, the Lessor shall notify the Government within five days of the transfer of title.

B. The Government and the Lessor may execute a Change of Name Agreement if the Lessor is changing only its legal name, and the Government's and the Lessor's respective rights and obligations remain unaffected.

C. If title to the Property is transferred, the Government, the original Lessor (Transferor), and the new owner or assignee (Transferee) shall execute a Novation Agreement providing for the transfer of Transferor's rights and obligations under the Lease to the Transferee. When executed on behalf of the Government, a Novation Agreement will be made part of the Lease via Lease Amendment.

D. In addition to all documents required by FAR 42.1204, the LCO may request additional information (e.g., copy of the deed, bill of sale, certificate of merger, contract, court decree, articles of incorporation, operation agreement, partnership certificate of good standing, etc.) from the Transferor or Transferee to verify the parties' representations regarding the transfer, and to determine whether the transfer of the Lease is in the Government's interest.

E. If the LCO determines that recognizing the Transferee as the Lessor will not be in the Government's interest, the Transferor shall remain fully liable to the Government for the Transferee's performance of obligations under the Lease, notwithstanding the transfer. Under no condition shall the Government be obligated to release the Transferor of obligations prior to (a) the rent commencement date; and (b) any amounts due and owing to the Government under the Lease have been paid in full or completely set off against the rental payments due under the Lease.

F. As a condition for being recognized as the Lessor and entitlement to receiving rent, the Transferee must register in the System for Award Management (SAM) for purposes of "All Awards" (See FAR 52.232-33), and complete all required representations and certifications within SAM. In

addition, for FSL III or above, the Transferee must also complete 552.270-33 Foreign Ownership and Financing Representation for High Security Leased Space. This representation must be completed annually.

G. If title to the Property is transferred, rent shall continue to be paid to the original Lessor, subject to the Government's rights as provided for in this Lease. The Government's obligation to pay rent to the Transferee shall commence on the effective date of the Lease Amendment incorporating the Novation Agreement. The Lease Amendment will not be issued until the Government has received all information reasonably required by the LCO, the Government has determined that recognizing the Transferee as the Lessor is in the Government's interest (which determination will be prompt and not unreasonably withheld), and the Transferee has met all conditions specified in sub-paragraph F. The original Lessor must maintain an active registration in SAM until the Novation process is complete.

2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012)

A. Purpose: This paragraph provides for adjustment in the rent (tax adjustment) to account for increases or decreases in Real Estate Taxes for the Property after the establishment of the Real Estate Tax Base, as those terms are defined herein. Tax adjustments shall be calculated in accordance with this paragraph.

B. Definitions: The following definitions apply to the use of the terms within this paragraph:

Property is defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas to which the Government is granted rights).

Real Estate Taxes are those taxes that are levied upon the owners of real property by a Taxing Authority (as hereinafter defined) of a state or local Government on an ad valorem basis to raise general revenue for funding the provision of government services. The term excludes, without limitation, special assessments for specific purposes, assessments for business improvement districts, and/or community development assessments.

Taxing Authority is a state, commonwealth, territory, county, city, parish, or political subdivision thereof, authorized by law to levy, assess, and collect Real Estate Taxes.

Tax Year refers to the 12-month period adopted by a Taxing Authority as its fiscal year for assessing Real Estate Taxes on an annual basis.

Tax Abatement is an authorized reduction in the Lessor's liability for Real Estate Taxes below that determined by applying the generally applicable real estate tax rate to the Fully Assessed (as hereinafter defined) valuation of the Property.

Unadjusted Real Estate Taxes are the full amount of Real Estate Taxes that would be assessed for the Property for one full Tax Year without regard to the Lessor's entitlement to any Tax Abatements (except if such Tax Abatement came into effect after the date of award of the Lease), and not including any late charges, interest or penalties. If a Tax Abatement comes into effect after the date of award of the Lease, "unadjusted Real Estate Taxes" are the full amount of Real Estate Taxes assessed for the Property for one full Tax Year, less the amount of such Tax Abatement, and not including any late charges, interest, or penalties.

Real Estate Tax Base is the unadjusted Real Estate Taxes for the first full Tax Year following the commencement of the Lease term. If the Real Estate Taxes for that Tax Year are not based upon a Full Assessment of the Property, then the Real Estate Tax Base shall be the Unadjusted Real Estate Taxes for the Property for the first full Tax Year for which the Real Estate Taxes are based upon a Full Assessment. Such first full Tax Year may be hereinafter referred to as the Tax Base Year. Alternatively, the Real Estate Tax Base may be an amount negotiated by the parties that reflects an agreed upon base for a Fully Assessed value of the Property.

The Property is deemed to be Fully Assessed (and Real Estate Taxes are deemed to be based on a Full Assessment) only when a Taxing Authority has, for the purpose of determining the Lessor's liability for Real Estate Taxes, determined a value for the Property taking into account the value of all improvements contemplated for the Property pursuant to the Lease, and issued to the Lessor a tax bill or other notice of levy wherein the Real Estate Taxes for the full Tax Year are based upon such Full Assessment. At no time prior to the issuance of such a bill or notice shall the Property be deemed Fully Assessed.

Percentage of Occupancy refers to that portion of the Property exclusively occupied or used by the Government pursuant to the Lease. For Buildings, the Percentage of Occupancy is determined by calculating the ratio of the RSF occupied by the Government pursuant to the Lease to the total RSF in the Building or Buildings so occupied, and shall not take into account the Government's ancillary rights including, but not limited to, parking or roof space for antennas (unless facilities for such ancillary rights are separately assessed). This percentage shall be subject to adjustment to take into account increases or decreases for Space leased by the Government or for rentable space on the Property.

C. Adjustment for changes in Real Estate Taxes. After the Property is Fully Assessed, the Government shall pay its share of any increases and shall receive its share of any decreases in the Real Estate Taxes for the Property, such share of increases or decreases to be referred to herein as "tax adjustment." The amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base, less the portion of such difference not paid due to a Tax Abatement (except if a Tax Abatement comes into effect after the date of award of the Lease). If a Tax Abatement comes into effect after the date of award of the Lease, the amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base. The Government shall pay the tax adjustment in a single annual lump sum payment to the Lessor. In the event that this tax adjustment results in a credit owed to the Government, the Government may elect to receive payment in the form of a rental credit or lump sum payment.

If the Property contains more than one separately assessed parcel, then more than one tax adjustment shall be determined based upon the Percentage of Occupancy, Real Estate Tax Base, and Real Estate Taxes for each respective parcel.

After commencement of the Lease term, the Lessor shall provide to the LCO copies of all real estate tax bills for the Property, all documentation of Tax Abatements, credits, or refunds, if any, and all notices which may affect the assessed valuation of the Property, for the Tax Year prior to the commencement of the Lease Term, and all such documentation for every year following. Lessor acknowledges that the LCO shall rely on the completeness and accuracy of these submissions in order to establish the Real Estate Tax Base and to determine tax adjustments. The LCO may memorialize the establishment of the Real Estate Tax Base by issuing a unilateral administrative lease amendment indicating the base year, the amount of the Real Estate Tax Base, and the Government's Percentage of Occupancy.

The Real Estate Tax Base is subject to adjustment when increases or decreases to Real Estate Taxes in any Tax Year are attributable to (a) improvements or renovations to the Property not required by this Lease, or (b) changes in net operating income for the Property not derived from this Lease. If either condition results in a change to the Real Estate Taxes, the LCO may re-establish the Real Estate Tax Base as the Unadjusted Real Estate Taxes for the Tax Year the Property is reassessed under such condition, less the amount by which the Unadjusted Real Estate Taxes for the Tax Year prior to reassessment exceeds the prior Real Estate Tax Base.

If this Lease includes any options to renew the term of the Lease, or be otherwise extended, the Real Estate Tax Base for determining tax adjustments during the renewal term or extension shall be the last Real Estate Tax Base established during the base term of the Lease.

If any Real Estate Taxes for the Property are retroactively reduced by a Taxing Authority during the term of the Lease, the Government shall be entitled to a proportional share of any tax refunds to which the Lessor is entitled, calculated in accordance with this Paragraph. Lessor acknowledges that it has an affirmative duty to disclose to the Government any decreases in the Real Estate Taxes paid for the Property during the term of the Lease. Lessor shall annually provide to the LCO all relevant tax records for determining whether a tax adjustment is due, irrespective of whether it seeks an adjustment in any Tax Year.

If the Lease terminates before the end of a Tax Year, or if rent has been suspended, payment for the real estate tax increase due because of this section for the Tax Year will be prorated based on the number of days that the Lease and the rent were in effect. Any credit due the Government after the expiration or earlier termination of the Lease shall be made by a lump sum payment to the Government or as a rental credit to any succeeding Lease, as determined in the LCO's sole discretion. Lessor shall remit any lump sum payment to the Government within 15 calendar days of payment or credit by the Taxing Authority to Lessor or Lessor's designee. If the credit due to the Government is not paid by the due date, interest shall accrue on the late payment at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978, as amended (41 USC § 611), that is in effect on the day after the due date. The interest penalty shall accrue daily on the amount of the credit and shall be compounded in 30-day increments inclusive from the first day after the due date through the payment date. The Government shall have the right to pursue the outstanding balance of any tax credit using all such collection methods as are available to the United States to collect debts. Such collection rights shall survive the expiration of this Lease.

In order to obtain a tax adjustment, the Lessor shall furnish the LCO with copies of all paid tax receipts, or other similar evidence of payment acceptable to the LCO, and a proper invoice (as descr bed in GSA Form 3517, General Clauses, 552.270-31, Prompt Payment) for the requested tax adjustment, including the calculation thereof. All such documents must be received by the LCO within 60 calendar days after the last date the real estate tax payment is due from the Lessor to the Taxing Authority without payment of penalty or interest. FAILURE TO SUBMIT THE PROPER INVOICE AND EVIDENCE OF PAYMENT WITHIN SUCH TIME FRAME SHALL CONSTITUTE A WAIVER OF THE LESSOR'S RIGHT TO RECEIVE A TAX ADJUSTMENT PURSUANT TO THIS PARAGRAPH FOR THE TAX YEAR AFFECTED.

Tax Appeals. If the Government occupies more than 50 percent of the Building by virtue of this and any other Government Lease(s), the Government may, upon reasonable notice, direct the Lessor to initiate a tax appeal, or the Government may elect to contest the assessed valuation on its own behalf or jointly on behalf of Government and the Lessor. If the Government elects to contest the assessed valuation on its own behalf or on behalf of the Government and the Lessor, the Lessor shall cooperate fully with this effort, including, without limitation, furnishing to the Government information necessary to contest the assessed valuation in accordance with the filing requirements of the Taxing Authority, executing documents, providing documentary and testimonial evidence, and verifying the accuracy and completeness of records. If the Lessor initiates an appeal at the direction of the Government, the Government shall have the right to approve the selection of counsel who shall represent the Lessor with regard to such appeal, which approval shall not be unreasonably withheld, conditioned or delayed, and the Lessor shall be entitled to a credit in the amount of its reasonable expenses in pursuing the appeal.

2.08 ADJUSTMENT FOR VACANT PREMISES (OCT 2017)

A. If the Government fails to occupy any portion of the leased Premises or vacates the Premises in whole or in part prior to expiration of the term of the Lease, the rental rate and the base for operating cost adjustments will be reduced using the figure specified in the "Rate for Adjustment for Vacant Leased Premises" paragraph of this Lease.

B. If no rate reduction has been established in this Lease, the rate will be reduced by that portion of the costs per ABOA SF of operating expenses not required to maintain the Space.

C. Said reduction shall occur after the Government gives 30 calendar days' prior notice to the Lessor and shall continue in effect until the Government occupies the vacant Premises or the Lease expires or is terminated.

2.09 OPERATING COSTS ADJUSTMENT (JUN 2012)

A. Beginning with the second year of the Lease and each year thereafter, the Government shall pay annual incremental adjusted rent for changes in costs for materials, maintenance, landscaping, and certain administrative expenses attributable to occupancy. The Lease is net of cleaning services, supplies, trash removal, water, sewer charges, heating and electricity and said costs will not be included in the Operating Costs Adjustment, pursuant to Lease section 1.06.J

B. The amount of adjustment will be determined by multiplying the base rate by the annual percent of change in the Cost of Living Index. The percent change will be computed by comparing the index figure published for the month prior to the Lease Term Commencement Date with the index

figure published for the month prior which begins each successive 12-month period. For example, a Lease which commences in June of 2005 would use the index published for May of 2005, and that figure would be compared with the index published for May of 2006, May of 2007, and so on, to determine the percent change. The Cost of Living Index will be measured by the Department of Labor revised Consumer Price Index for Urban Wage Earners and Clerical Workers (CPI-W), U.S. city average, all items, (1982 to 1984 = 100) published by the Bureau of Labor Statistics. Payment will be made with the monthly installment of fixed rent. Rental adjustments will be effective on the anniversary date of the Lease; however, payment of the adjusted rental rate will become due on the first workday of the second month following the publication of the Cost of Living Index for the month prior to the commencement of each 12-month period.

C. In the event of any decreases in the Cost of Living Index occurring during the term of the occupancy under the Lease, the rental amount will be reduced accordingly. The amount of such reductions will be determined in the same manner as increases in rent provided under this paragraph.

D. If the Government exercises an option to extend the Lease term at the same rate as that of the original term, the option price will be based on the adjustment during the original term. Annual adjustments will continue.

2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)

A. If the Lessor is a HUBZone small business concern (SBC) that did not waive the price evaluation preference, the Lessor shall provide a certification within 10 days after Lease award to the LCO (or representative designated by the LCO) that the Lessor was an eligible HUBZone SBC on the date of award. If it is determined within 20 days after award that a HUBZone SBC Offeror that has been awarded the Lease was not an elig ble HUBZone SBC at the time of award, and the HUBZone SBC Lessor failed to provide the LCO with information regarding a change to its HUBZone eligibility prior to award, then the Lease shall be subject, at the LCO's discretion, to termination, and the Government will be relieved of all obligations to the Lessor in such an event and not be liable to the Lessor for any costs, claims or damages of any nature whatsoever.

B. Within **10** days after Lease award, the Lessor shall provide to the LCO (or representative designated by the LCO) evidence of:

1. A firm commitment of funds in an amount sufficient to perform the work.

2. The names of at least two proposed construction contractors, as well as evidence of the contractors' experience, competency, and performance capabilities with construction similar in scope to that which is required herein.

3. The license or certification to practice in the state where the Building is located from the individual(s) and/or firm(s) providing architectural and engineering design services.

C. The Government shall have the right to withhold approval of design intent drawings (DIDs) until the conditions specified in sub-paragraphs A and B have been satisfied.

D. Within ten (10) calendar days after the LCO issues the Notice To Proceed (NTP) for TI construction, the Lessor shall provide to the LCO evidence of:

1. Award of a construction contract for TIs with a firm completion date. This date must be in accordance with the construction schedule for TIs as described in the "Schedule for Completion of Space" paragraph of this Lease.

2. Issuance of required permits for construction of the TIs.

2.11 ~~RELOCATION ASSISTANCE ACT (APR 2011)~~ INTENTIONALLY DELETED

SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS

3.01 ~~LABOR STANDARDS (OCT 2016)~~ INTENTIONALLY DELETED

3.02 WORK PERFORMANCE (JUN 2012)

All work in performance of this Lease shall be done by skilled workers or mechanics and shall be acceptable to the LCO. The LCO may reject the Lessor's workers 1) if such are unlicensed, unskilled, or otherwise incompetent, or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other government or private contracts.

3.03 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (OCT 2019)

A. Items and materials existing in the Premises, or to be removed from the Premises during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in re-furbished condition and shall meet the quality standards set forth by the Government in this Lease. In the absence of definitive quality standards, the Lessor is respons ble to confirm that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.

B. Unless waived by the LCO, the Lessor shall submit a reuse plan for leases 10,000 RSF or greater. The Government will not pay for existing fixtures and other TIs accepted in place. However, the Government will reimburse the Lessor, as part of the TIA, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the LCO.

3.04 CONSTRUCTION WASTE MANAGEMENT (OCT 2021)

For leases 10,000 RSF or greater, the requirements below apply:

A. Recycling construction waste is mandatory for initial space alterations for TIs and subsequent alterations under the Lease.

B. SUBMITTAL REQUIREMENT: Prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the LCO, may permit alternative means of disposal.

C. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility: Ceiling grid and tile, light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bu bs, duct work and HVAC equipment, wiring and electrical equipment, aluminum and/or steel doors and frames, hardware, drywall, steel studs, carpet, carpet backing, and carpet padding, wood, insulation, cardboard packaging, pallets, windows and glazing materials, all miscellaneous metals (as in steel support frames for filing equipment), and all other finish and construction materials.

D. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCBs) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with Federal and state laws and requirements concerning hazardous waste.

E. In addition to providing "one time" removal and recycling of large scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.

F. Construction materials recycling records shall be maintained by the Lessor and shall be access ble to the LCO. Records shall include materials recycled or land-filled, quantity, date, and identification of hazardous wastes.

3.05 WOOD PRODUCTS (OCT 2019)

A. Particle board, strawboard, and plywood materials used shall be free of formaldehyde or sufficiently aged prior to use such that indoor air levels in the finished leased space shall not exceed 0.016 parts per million (ppm) of formaldehyde..

B. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

C. For leases 10,000 RSF or greater, new installations of wood products shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at HTTP://WWW.WOOD-DATABASE.COM/WOOD-ARTICLES/RESTRICTED-AND-ENDANGERED-WOOD-SPECIES/ or https://www.fws.gov/international/plants/current-cites-listings-of-tree-species.html. In addition, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Stewardship Council United States (HTTPS://US.FSC.ORG/EN-US), or the Sustainable Forestry Initiative (HTTP://WWW.SFIPROGRAM.ORG/).

3.06 ADHESIVES AND SEALANTS (OCT 2019)

A. All adhesives employed (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no heavy metals and that do not result in indoor air levels above 0.016 parts per million (ppm) of formaldehyde. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

B. For leases 10,000 RSF or greater the Lessor is encouraged to use applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCURMENT and https://sftool.gov/greenprocurement/green-products/8/miscellaneous/1238/adhesives/0

3.07 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016)

A. The Building Shell shall be designed, constructed, and maintained in accordance with the standards set forth herein and completed prior to acceptance of Space. For pricing, fulfillment of all requirements not specifically designated as TIs, Building Specific Amortized Capital, Operating Costs, or other rent components as indicated shall be deemed included in the Shell Rent.

B. Base structure and Building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and service areas, shall be complete. Restrooms shall be complete and operational with an adequate number of fixtures for men and women to meet current local codes based on building occupancy and use. All newly installed Building shell components, including but not limited to, heating and ventilation, electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with TIs. Circulation corridors are provided as part of the base Building only on multi-tenanted buildings where the corridor is common to more than one tenant. In single tenant buildings, only the fire egress corridor(s) necessary to meet code is provided as part of the shell.

C. The Building Shell rental rate shall also include, but is not limited to, costs included listed under Section II of GSA Form 1217, Lessor's Annual Cost Statement, including insurance, taxes, lease commission and management, in addition to profit, reserve costs and loan financing for the Building.

3.08 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)

A. The Lessor shall be responsible for the professional quality, technical accuracy, and the coordination of all designs, drawings, specifications, and other services furnished by the Lessor under this contract. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services.

B. THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Government retains the right to review and approve many aspects of the Lessor's design, including without limitation, review of the Lessor's design and construction drawings, shop drawings, product data, finish samples, and completed base building and TI construction. Such review and approval is intended to identify potential design flaws, to minimize costly misdirection of effort, and to assist the Lessor in its effort to monitor whether such design and construction comply with applicable laws and satisfy all Lease requirements.

C. Neither the Government's review, approval or acceptance of, nor payment through rent of the services required under this contract, shall be construed to operate as a waiver of any rights under this contract or of any cause of action arising out of the performance of this contract, and the Lessor shall be and remain liable to the Government in accordance with applicable law for all damages to the Government caused by the Lessor's negligent performance of any of the services required under this Lease.

D. Design and construction and performance information is contained throughout several of the documents which comprise this Lease. The Lessor shall provide to space planners, architects, engineers, construction contractors, etc., all information required whether it is found in this Lease, special requirements and attachments, price lists, or design intent drawings. Reliance upon one of these documents to the exclusion of any other may result in an incomplete understanding of the scope of the work to be performed and/or services to be provided.

3.09 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)

The Building in which the leased Space is located shall be designed, built, and maintained in good condition, suitable for Lessee's use at all times, and in accordance with the requirements of this Lease.

3.10 VESTIBULES (OCT 2020)

A. Vestibules shall be provided at public entrances wherever entry to the Space is directly from the outside. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure. For measurement purposes, vestibules are considered building support space and not ABOA.

B. The Lessor shall provide permanent entryway systems (such as grilles or grates) to control dirt and particulates from entering the Building at all primary exterior entryways.

3.11 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)

A. Prior to occupancy, the Premises and any parking garage areas shall meet or will be upgraded to meet, either the applicable egress requirements in the National Fire Protection Association, Life Safety Code (NFPA 101), or the International Code Council, International Building Code (IBC), each current as of the Lease Award Date, or use an alternative approach or method that achieves an equivalent level of safety deemed acceptable by the Government.

B. The Space shall have unrestricted access to a minimum of two remote exits on each floor of Government occupancy.

C. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the IBC.

3.12 AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)

A. Any portion of the space located below-grade, including parking garage areas, and all areas in a building referred to as "hazardous areas" (defined in National Fire Protection Association (NFPA) 101) that are located within the entire Building (including non-Government areas) shall be protected by an automatic fire sprinkler system.

B. The entire warehouse building shall be protected throughout by an automatic fire sprinkler system(s) when the offered space exceeds 10,000 rentable square feet in area.

C. Automatic fire sprinkler system(s) shall be installed in accordance with the requirements of NFPA 13, Standard for the Installation of Sprinkler Systems that was in effect on the actual date of installation.

D. Automatic fire sprinkler system(s) shall be maintained in accordance with the requirements of NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-based Fire Protection Systems (current as of the Lease Award Date).

3.13 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)

A. A Building-wide fire alarm system shall be installed when the offered Space exceeds 40,000 square feet of RSF.

B. The fire alarm system shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code that was in effect on the actual date of installation.

C. Fire alarm systems shall be maintained in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date).

D. The fire alarm system shall transmit all fire alarm signals to the local fire department via any of the following means: directly to the local fire department, to the (911) public communications center, to a central station, to a remote supervising station, or to a proprietary supervising station.

E. If the Building's fire alarm control unit is over 25 years old as of the date of award of this Lease, Lessor shall install a new fire alarm system in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date), prior to Government acceptance and occupancy of the Space.

3.14 ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016)

A. Energy-related Requirements:

1. The Energy Independence and Security Act (EISA) establishes the following requirements for Government leases in Buildings that have not earned the ENERGY STAR® Label conferred by the Environmental Protection Agency (EPA) within one year prior to the due date for final proposal revisions ("most recent year").

2. If this Lease was awarded under any of EISA's Section 435 statutory exceptions, the Lessor shall either:

a. Earn the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding Lease); or

b. (i) Complete energy efficiency and conservation improvements if any, agreed to by Lessor in lieu of earning the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding lease); and

(ii) Obtain and publicly disclose the Building's current ENERGY STAR® score (using EPA's Portfolio Manager tool), unless the Lessor cannot access whole building utility consumption data, or there is no building category within Portfolio Manager to benchmark against, including spaces—

I. That are located in States with privacy laws that provide that utilities shall not provide such aggregated information to multitenant building owners; and

II. For which tenants do not provide energy consumption information to the commercial building owner in response to a request from the building owner. (A Federal agency that is a tenant of the space shall provide to the building owner, or authorize the owner to obtain from the utility, the energy consumption information of the space for the benchmarking and disclosure required by this subparagraph D).

III. That cannot be benchmarked (scored) using EPA's Portfolio Manager tool because of excessive vacancy; in which case Lessor agrees to obtain the score and publicly disclose it within 120 days of the eligibility to obtain a score using the EPA Portfolio Manager tool.

Note: "public disclosure" means posting the Energy Star® score on state or local websites in those areas that have applicable disclosure mandates, and reporting the score to the Government via Portfolio Manager. In the absence of an applicable state or local disclosure mandate, Lessor shall either generate and display the Energy Star® score in a public space at the building location or post the score on Lessor's or Lessor's Parent/Affiliate website.

3. If this Lease was awarded to a Building to be built or to a Building predominantly vacant as of the due date for final proposal revisions and was unable to earn the ENERGY STAR® label for the most recent year (as defined above) due to insufficient occupancy, but was able to demonstrate

sufficient evidence of capability to earn the ENERGY STAR® label, then Lessor must earn the ENERGY STAR® label within 18 months after occupancy by the Government.

4. The Lessor is encouraged to purchase at least 50 percent of the Government tenant's electricity from renewable sources.

B. Hydrology-related Requirements:

1. Per EISA Section 438, the sponsor of any development or redevelopment project involving a Federal facility with a footprint that exceeds 5,000 square feet shall use site planning, design, construction, and maintenance strategies for the property to maintain or restore, to the maximum extent technically feasible, the predevelopment hydrology of the Property with regard to the temperature, rate, volume, and duration of flow. If the Lessor proposes to satisfy the Government's space requirements through a development or redevelopment project, and the Government will be the sole or predominant tenant such that any other use of the Property will be functionally or quantitatively incidental to the Government's use, the Lessor is required to implement hydrology maintenance and restoration requirements as required by EISA Section 438.

a. For the purposes of applying EISA Section 438 in this Lease, "sponsor" shall mean "Lessor", and "exceeds 5,000 square feet" shall mean construction that disturbs 5,000 square feet or more of land area at the Property or on adjoining property to accommodate the Government's requirements, or at the Property for whatever reason. Information regarding implementation of the hydrology maintenance and restoration requirements can be found at: http://www.epa.gov/greeningepa/technical-guidance-implementing-stormwater-runoff-requirements-federal-projects

b. Lessor is required to implement these hydrology maintenance and restoration requirements to the maximum extent technically feasible, prior to acceptance of the Space, (or not later than one year after the Lease Award Date or Lease Term Commencement Date, whichever is later, of a succeeding or superseding lease). Additionally, this Lease requires EISA Section 438 storm water compliance not later than one year from the date of any applicable disturbance (as defined in EISA Section 438) of more than 5,000 square feet of ground area if such disturbance occurs during the term of the Lease if the Government is Government is the sole or predominant tenant. In the event the Lessor is required to comply with EISA Section 438, Lessor shall furnish the Government, prior to the filing for permits for the associated work, with a certification from Lessor's engineer that the design meets the hydrology maintenance and restoration requirements of EISA Section 438.

3.15 ELEVATORS (WAREHOUSE) (OCT 2020)

A. Lessor shall provide suitable passenger elevator and, when required by Government, freight elevator service to any portion of the Premises not having ground level access. Service shall be available during the normal hours of operation specified in this Lease. However, one passenger elevator and, when required by Government, one freight elevator shall be available at all times for Government use. When a freight elevator is required by the Government, it shall be accessible to the loading areas. When possible, Lessor shall provide Government with 24-hour advance notice if the service is to be interrupted for more than 1-1/2 hours. Lessor shall schedule normal service interruption outside of the Government's normal working hours. Lessor shall also use best efforts to minimize the frequency and duration of unscheduled interruptions.

B. Code: Elevators shall conform to the requirements of the American Society of Mechanical Engineers ASME A17.1/CSA B44, Safety Code for Elevators and Escalators that were in effect based on the elevator installation date code year. Elevators shall be provided with Phase I emergency recall operation and Phase II emergency in-car operation in accordance with ASME A17.1/CSA B44. Fire alarm initiating devices (e.g., smoke detectors) used to initiate Phase I emergency recall operation shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (actual date of installation). The elevators shall be inspected and maintained in accordance with the current edition of the ASME A17.2, Inspector's Manual for Elevators. Except for the reference to ASME A17.1 in ABAAS, Section F105.2.2, all elevators must meet ABAAS requirements for access bility in Sections 407, 408, and 409 of ABAAS.

C. Safety Systems: Elevators shall be equipped with telephones or other two-way emergency communication systems. The system used shall be marked and shall reach an emergency communication location staffed 24 hours per day, 7 days per week.

D. Speed: The passenger elevators shall have a capacity to transport in 5 minutes 15 percent of the normal population of all upper floors (based on 150 SF per person). Further, the dispatch interval between elevators during the up-peak demand period shall not exceed 35 seconds.

E. Interior Finishes: Passenger elevator cab walls must present a quality image and be sufficiently durable to withstand heavy use, Materials must be installed on removable panels or other replaceable devices to facilitate maintenance and renewal of finishes and shall be subject to approval by the LCO. Ceilings must be replaceable. In passenger elevators recessed down lights or indirect fixtures should be used. Passenger elevator cab floors shall be approved by the LCO and shall be carpet, wood, or high-quality resilient flooring materials. If carpet, use materials with low pile height and high density, and otherwise conform to the requirements of this lease, including sustainability requirements. Finishes for freight elevators must be very durable and easy to clean. Stainless steel walls and doors are preferred. Flooring must be sheet vinyl or resilient vinyl tile. Ceiling light fixtures must be recessed and protected from possible damage.

3.16 ~~FLAGPOLE (SEP 2013)~~ INTENTIONALLY DELETED

3.17 DEMOLITION (JUN 2012)

The Lessor shall remove existing abandoned electric, telephone, and data cabling and devices, as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

3.18 ACCESSIBILITY (FEB 2007)

The Building, leased Space, and areas serving the leased Space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

3.19 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)

A. Exterior Building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to TIs.

B. Exterior doors shall be weather tight and shall open outward. Hinges, pivots, and pins shall be installed in a manner which prevents removal when the door is closed and locked. These doors shall have a minimum clear opening of 32" clear wide x 80" high (per leaf). Doors shall be heavy duty, flush, (1) hollow steel construction, (2) solid core wood, or (3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be fully insulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall be of durable finish and shall have an aesthetically pleasing appearance acceptable to the LCO. The opening dimensions and operations shall conform to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements. Fire door assemblies shall be listed and labeled. Labels on fire door assemblies shall be maintained in a legible condition. Fire door assemblies and their accompanying hardware, including frames and closing devices shall be installed in accordance with the requirements of NFPA 80, Standard for Fire Doors and Other Opening Protectives. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the International Building Code (IBC) as of the Award Date of this Lease.

C. Exterior doors and all common area doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall or floor mounted) and silencers. All public use doors and restroom doors shall be equipped with kick plates. All doors shall have automatic door closers. All Building exterior doors shall have locking devices installed to reasonably deter unauthorized entry. The Lessor is encouraged to avoid the use of chrome-plated hardware.

D. There shall be unrestrictive access to a minimum of two remote exits on each floor of the Government's occupancy.

E. Loading docks shall have a roll-up coiling type door with lock.

3.20 DOORS: IDENTIFICATION (APR 2011)

All signage required in common areas unrelated to tenant identification shall be provided and installed by the Lessor.

3.21 WINDOWS (OCT 2020)

A. Office Space shall have windows in each exterior bay unless waived by the LCO.

B. All exterior window assemblies shall be weather resistant and weather tight. Operable windows that open shall be equipped with secure latches. Off-street, ground-level windows and those accessible from adjacent roofs, and other structures that can be opened must be fitted with a secure latch. Windows intended for use as a secondary means of egress must be openable from the egress side (e.g., inside) of the Building without the use of a key, tool, or special knowledge or effort for operation from the egress side.

3.22 PARTITIONS: GENERAL (OCT 2019)

A. Partitions in public areas shall be marble, granite, hardwood, or drywall covered with durable wall covering or high performance coating, or equivalent pre-approved by the LCO.

B. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building, the Lessor is encouraged to use materials for newly installed gypsum board meeting the applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False.

3.23 PARTITIONS: PERMANENT (OCT 2019)

A. Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor as part of shell rent as necessary to surround the Space, stairs, corridors, elevator shafts, restrooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by the applicable building code, fire code and ordinances adopted by the jurisdiction in which the Building is located (such as the International Building Code, etc.) current as of the Lease Award Date.

B. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building , the Lessor is encouraged to use materials for newly installed gypsum board meeting applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1735/wallboardgypsum-boarddrywall/0?addon=False.

3.24 INSULATION: THERMAL, ACOUSTIC, AND HVAC (OCT 2019)

A. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFCs), nor shall CFCs be used in the installation of the product.

B. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.

C. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.

D. All insulation shall contain low emitting volatiles and not result in indoor air levels above 0.016 parts per million (ppm) of formaldehyde..

E. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the Lease Award Date) adopted by the jurisdiction in which the Building is located.

F. For leases 10,000 RSF or greater, all insulation products shall meet applicable, statutory environmentally preferable criteria related to recovered material content as outlined in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/1/construction-materials/22/building-insulation/0.

3.25 WALL FINISHES—SHELL (SEP 2015)

A. All restrooms within the Building common areas of Government-occupied floors shall have 1) ceramic tile, recycled glass tile, or comparable wainscot from the finished floor to a minimum height of 4'-6" and 2) semigloss paint on remaining wall areas, or other finish approved by the Government.

B. All elevator areas that access the Space and hallways accessing the Space shall be covered with wall coverings not less than 20 ounces per square yard, high performance paint, or an equivalent.

3.26 PAINTING—SHELL (OCT 2019)

A. The Lessor shall bear the expense for all painting associated with the Building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Space shall be spackled and prime painted.. If any Building shell areas are already painted prior to TIs, then the Lessor shall repaint, at the Lessor's expense, as necessary during TIs.

B. The costs for cyclical painting requirements as outlined in Section 6 shall be included in the shell rent.

C. For leases 10,000 RSF or greater, primer shall meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False.

3.27 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (OCT 2019)

A. All adjoining floor areas shall be of a common level, and meet ASTM Standard E1155, with a minimum levelness of **Ff35** and **FL25**. Warehouse areas shall have a minimum live load capacity of **250** pounds per square foot. The Government may require Lessor to provide written certification of the floor load capacity, at no cost to the Government, by a registered Professional Engineer. The Government may also require calculations and structural drawings at no cost to the Government, by a registered Professional Engineer.

B. Warehouse floor surfacing shall have the appropriate surface performance for the operations being performed as outlined in the following table and as verified with in situ testing. The appropriate surface performance shall be maintained throughout the life of the lease term. Periodic in situ testing shall be performed at a frequency appropriate for the expected useful life of the floor attr bute required to be maintained:

	DUTY	APPLICATION	PERFORMANCE
a. Special	Unique requirements	One or more of the following attributes 1.Very heavy-duty operational or equipment traffic 2. Unique surface reflectance criteria 3. Anti slip/ anti skid 4. Chemical resistance 5. Anti static 6. Critical free movement floor 7. Critical defined movement floor 8.Critical dust control 9. Joint free	In addition to the Class 1-3 below Note: should one or more of the application attributes be critical for the performance of the required operation seek specialized help in tailoring the appropriate requirements)
b. Class 1	Very High Abrasion, steel wheel traffic and impact	Heavy-duty duty impact from pallets/ skid steer forks	<.1mm abrasion resistance Maintenance free joints
c. Class 2	High-abrasion steel wheel or hard wheel traffic	Medium—	<.3 mm abrasion resistance Maintenance free joints
d. Class 3	light abrasion—rubber tire and foot traffic	Light-duty	Dust free finish

b. Floor Hardeners, or coatings shall be utilized to achieve the wear performance for the appropriate duty class required in the above table. Coatings, such as polyurethanes membranes are only acceptable for class 3. Should hardeners be required then nano-lithium silicates or other environmentally friendly practices must be employed.
c. In situ abrasion resistance required of class 2 or 3 shall be determined in accordance with BS EN 13892-4: 2002

3.28 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)

A. Exposed interior floors in primary entrances and lobbies shall be marble, granite, or terrazzo. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, or terrazzo. Resilient flooring shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble, or carpet base.

B. Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all restroom and service areas of Government-occupied floors.

C. Any alternate flooring must be pre-approved by the LCO

D. The costs for cyclical carpet replacement requirements as outlined in Section 6 shall be included in the shell rent.

3.29 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)

The Lessor shall provide and operate all Building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in the office Space.

3.30 BUILDING SYSTEMS (APR 2011)

Whenever requested, the Lessor shall furnish to GSA as part of shell rent, a report by a registered professional engineer(s) showing that the Building and its systems as designed and constructed will satisfy the requirements of this Lease.

3.31 ELECTRICAL—SHELL (WAREHOUSE) (OCT 2019)

A. The Lessor shall be responsible for meeting the applicable requirements of local codes and ordinances. When codes conflict, the more stringent standard shall apply. The electrical panel supplying electrical service to the warehouse Space shall be located in an enclosed room. The enclosed room should only contain electrical infrastructure and not used for any other purpose. The enclosure must be located within the warehouse Space to be leased and not serve other non-leased facilities. The enclosure shall have door(s) fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch. The electrical distribution panels enclosed in the electrical room shall include: single-phase 120/240 volt service or 3-phase 120/208 volt for leased spaces under 10,000 RSF; 3-phase 120/208 volt service for leased spaces between 10,000 and 25,000 RSF; and 3-phase 277/480 volt and 3-phase 120/208 volt service for leased spaces over 25,000 RSF. A minimum of **150** amps at 120/240 volts per **4,000** rentable square feet of leased Space inclusive of lighting circuits (but assuming no air conditioning mechanical load) shall be provided to circuit breaker panel boxes in the Space.. All switchgear, fuses, and circuit breakers shall be plainly marked or labeled to identify circuits and/or equipment supplied through them. All office Space shall have , 4-wire with bond, 60 hertz electric service available. In no event shall such power distribution (not including lighting and HVAC) for the office Space fall below 4 watts per ABOA SF of Office area. Lessor must provide one watt per ABOA SF for electrical power distribution for warehouse areas.

B. Main power distr bution switchboards and distribution and lighting panel boards shall be circuit breaker type with copper buses that are properly rated to provide the calculated fault circuits. All power distribution panel boards shall be supplied with separate equipment ground buses. All power distribution equipment shall be required to handle the actual specified and projected loads and 10 percent spare load capacity. Distribution panels are required to accommodate circuit breakers for the actual calculated needs and 10 percent spare circuits that will be equivalent to the majority of other circuit breakers in the panel system. Fuses and circuit breakers shall be plainly marked or labeled to identify circuits or equipment supplied through them.

C. Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent. The Lessor shall provide duplex utility outlets in restrooms, corridors, and dispensing areas.

3.32 ADDITIONAL ELECTRICAL CONTROLS (JUN 2012)

If the Government pays separately for electricity, no more than 500 SF of office Space may be controlled by one switch or automatic light control for all office Space on the Government meter, whether through a building automation system, time clock, occupant sensor, or other comparable system acceptable to the LCO.

3.33 PLUMBING (JUN 2012)

The Lessor shall include the cost of plumbing in common areas. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for TIs, shall be included in the shell rent.

3.34 DRINKING FOUNTAINS (WAREHOUSE) (OCT 2018)

Lessor shall provide at least one chilled water fountain for the Premises. If more than one fountain is required by local building codes based on general warehouse use of the premises, they also shall be provided by Lessor as part of the shell rental. The fountains shall comply with Section F211 of the Architectural Barriers Act Accessibility Standard. Potable is defined as water meeting current EPA primary drinking water standards or more stringent,

applicable state or local regulations. The Lessor shall serve as first responder to any occupant complaints about drinking water. The Lessor shall promptly investigate any such complaints and implement the necessary controls to address the complaints and maintain potable water conditions.

3.35 RESTROOMS (WAREHOUSE) (OCT 2021)

A. For Warehouse Area, Lessor shall provide at its cost, restroom facilities which are handicap accessible, with an adequate number of fixtures for men and women to meet current local codes based on general warehousing use.

B. For Office Area within the Warehouse Building, if this Lease is satisfied by new construction or by renovations that include the construction of restrooms, Lessor shall provide water closets, sinks and urinals on each floor that is partially or fully occupied by the government per the schedule below. The schedule is per floor and based on a density of one person for each 135 ABOA SF, allocated as 50% women and 50% men. If future renovations requiring restroom construction occur during the term of this Lease, the number of fixtures then must meet the schedule as part of the major alterations.

ESTIMATED NUMBER OF EACH GENDER PER FLOOR	(WOMEN'S) WATER CLOSETS	(WOMEN'S) SINKS	(MEN'S) WATER CLOSETS	(MEN'S) URINALS	(MEN'S) SINKS
1 to 8	2	1	1	1	1
9 to 24	3	2	2	1	1
25 to 36	3	2	2	1	2
37 to 56	5	3	3	2	2
57 to 75	6	4	4	2	2
76 to 96	6	5	4	2	3
97 to 119	7	5	5	2	3
120 to 134	9	5	6	3	4
Above 135	3/40	1/24	1/20	1/40	1/30

C. If no new construction of a restroom is occurring, at a minimum, separate restroom facilities for men and women shall be provided with sufficient fixtures (water closets, sinks, and urinals) in accordance with local code or ordinances..

D. These facilities shall be located on each floor occupied by the Government in the Building, and shall be located so that employees will not be required to travel more than 200 feet on one floor to reach the restrooms. Each restroom shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.

E. Restrooms must meet ABAAS requirements as stated under this Lease.

F. Each main restroom shall contain the following:

1. A mirror and shelf above the lavatory.
2. A toilet paper dispenser in each water closet stall that will hold the equivalent of at least two standard-sized rolls and allow easy, unrestricted dispensing.
3. A coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories.
4. At least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories.
5. A coin-operated sanitary napkin dispenser in women's restrooms with a waste receptacle in each water closet stall.
6. A disposable toilet seat cover dispenser.
7. A counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground-fault interrupter-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
8. A floor drain.
9. New installed restroom partitions shall be made from recovered materials as listed in EPA's CPG.
10. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour. The exhaust fan systems shall be provided with a 24/7 seven day clock to allow programming.

3.36 PLUMBING FIXTURES: WATER CONSERVATION (OCT 2019)

For leases 10,000 RSF or greater, the specifications listed below apply:

1. New installations of plumbing fixtures,
2. Replacement of existing plumbing fixtures, or
3. Existing non-conforming fixtures where the Government occupies the full floor.

A. Water closets must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized.

B. Urinals must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized. Waterless urinals are acceptable.

C. Faucets must conform to EPA WaterSense or fixtures with equivalent flow rates must be utilized.

Information on EPA WaterSense fixtures can be found at HTTPS://WWW3.EPA.GOV/WATERSENSE/.

3.37 JANITOR CLOSETS (SEP 2015)

Janitor closets shall meet all local codes and ordinances. When not addressed by local code, Lessor shall provide containment drains plumbed for appropriate disposal of liquid wastes in spaces where water and chemical concentrate mixing occurs for maintenance purposes. Disposal is not permitted in restrooms.

3.38 HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2021)

A. Warehouse areas: Temperature control for all warehouse areas shall be provided by ceiling mounted heating equipment capable of maintaining a minimum temperature of 55 degrees Fahrenheit (with all doors closed) throughout the warehouse area during the heating season regardless of the outside temperature. Unit heaters shall be controlled by individual thermostats mounted in the area of the unit heaters, or controlled from a central master time clock of the 7-day type with a separate manual overdrive switch (12 hours) or other automatic means to permit setback of temperature at night and on weekends. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative. Central air rotation units will be acceptable if loading dock areas are equipped with unit heaters for direct heating over doors. In the warehouse area, unit heaters shall be mounted tight to the ceiling for maximum headroom. Lessor shall provide ventilation/air circulation in accordance with ANSI/ASHRAE 62.1, Ventilation for Acceptable Indoor Air Quality. Lessor shall follow the ASHRAE version that corresponds with how the HVAC system was designed to perform. At a minimum, Lessor must meet ASHRAE Standard 62.2004

B. Office Areas: Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all Building common areas. The Lessor shall provide conditioned air through medium pressure duct work at a rate of .75 cubic feet per minute per ABOA SF and systems shall be designed with sufficient systems capacity to meet all requirements in this Lease.

C. Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.

D. Equipment Performance. Temperature control for office Spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain Space temperature control over a range of internal load fluctuations of plus 0.5 W/SF to minus 1.5 W/SF from initial design requirements of the tenant.

E. Ductwork Re-use and Cleaning. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.

F. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the American National Standards Institute, American Society of Heating, Refrigeration and Air-Conditioning Engineers (ANSI/ASHRAE) Standard 62.1, Ventilation for Acceptable Indoor Air Quality that corresponds with how the HVAC system was designed to perform. At a minimum, Lessor must meet ASHRAE Standard 62.1-2004

G. Heating and air-conditioning air distribution systems (air handling units, VAV boxes, fan coil units, etc.) for the Space shall be equipped with particulate matter air filters that meet the Minimum Efficiency Reporting Value (MERV) specified in the ANSI/ASHRAE Standard 62.1 version referenced in sub-paragraph F above. Locations that do not meet the EPA National Ambient Air Quality Standards (NAAQS) for particulates (PM 10 or PM 2.5) must be equipped with additional filtration on outdoor air intakes as required in ANSI/ASHRAE Standard 62.1. NAAQS information can be found at HTTPS://WWW.EPA.GOV/GREEN-BOOK.

H. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour.

I. Where the Lessor proposes that the Government shall pay utilities, the following shall apply:

1. An automatic air or water economizer cycle shall be provided to all air handling equipment, and

2. The Building shall have a fully functional building automation system capable of control, regulation, and monitoring of all environmental conditioning equipment. The building automation system shall be fully supported by a service and maintenance contract.

J. Warehouse and Office areas: HVAC systems must conform to the locally approved building code.

K. For all refrigerant-containing equipment with over 50 pounds of ozone-depleting substances (including chlorofluorocarbons- CFCs or hydrochlorofluorocarbons- HCFCs), the Lessor shall comply with the U.S. Environmental Protection Agency (EPA)'s Significant New Alternative Policy (SNAP) Program for acceptable substitutes and alternatives to ozone-depleting substances when equipment is replaced, comes to its end of useful life, or when newly purchased. Upon request, the Lessor must provide to the Government the type of refrigerant used in chillers and HVAC systems, and the date by which the Lessor plans to replace ozone depleting substances with acceptable refrigerant substitutes in accordance with EPA's SNAP program.

3.39 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)

A. Sufficient space shall be provided on the floor(s) where the Government occupies Space for the purposes of terminating telecommunications service into the Building. The Building's telecommunications closets located on all floors shall be vertically-stacked. Telecommunications switch rooms, wire closets, and related spaces shall be enclosed. The enclosure shall not be used for storage or other purposes and shall have door(s) fitted with an automatic door-closer and deadlocking latch bolt with a minimum throw of 1/2 inch. The telephone closets shall include a telephone backboard.

B. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable Telecommunications Industry Association (TIA) and Electronic Industries Alliance (EIA) standards. These standards include the following:

1. TIA/EIA-568, Commercial Building Telecommunications Cabling Standard,
2. TIA/EIA 569, Commercial Building Standard for Telecommunications Pathways and Spaces,
3. TIA/EIA-570, Residential and Light Commercial Telecommunications Wiring Standard, and
4. TIA/EIA-607, Commercial Building Grounding and Bonding Requirements for Telecommunications Standard.

C. Telecommunications switch rooms, wire closets, and related spaces shall meet applicable NFPA standards. Bonding and grounding shall be in accordance with NFPA Standard 70, National Electrical Code, and other applicable NFPA standards and/or local code requirements.

3.40 ~~TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)~~ INTENTIONALLY DELETED

3.41 LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2020)

Warehouse/Storage Space & Overall:
A. Lessor shall provide a minimum lighting level of 10 foot-candles, as measured 30 inches above the floor, in aisles and open storage areas in the warehouse Space with the storage racks full. Lessor shall provide a minimum lighting level in the shipping and receiving areas of 30 foot-candles, when measured 30 inches above the floor. Lessor must provide lighting that is equivalent to the energy efficiency requirements in any office areas. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all non-office areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided as part of Shell Rent in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.

B. Occupancy Sensors: The Lessor shall provide ceiling mount occupancy sensors (over aisles and open areas), or scheduling controls through a building automation system (BAS) throughout the storage portion of the Space in order to reduce the hours that the lights are on when a particular area is unoccupied. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

C. Building Perimeter:
1. Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels, (especially at loading dock doors), shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 foot-candles for transition areas and at least 1 foot-candle at the surface throughout the parking lot. Wareyards (storage yards) require a minimum lighting level of 5 foot-candles (at ground level). Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 15:1 and a maximum to average uniformity ratio of 4:1.
2. If the leased space is 100 percent occupied by Government tenants, all exterior parking lot fixtures, including those illuminating a wareyard, shall be “Dark Sky” compliant with no property line trespass. .

D. Parking Structures: The minimum illuminance level for parking structures is 5 foot-candle as measured on the floor with a uniformity ratio of 10:1.

E. Parking Sensors: If the leased space is 100 percent occupied by Government tenants, exterior parking area and parking structure lighting shall be sensor or BAS controlled in order that it may be programmed to produce reduced lighting levels during non use. This non-use time period will normally be from 11:00 pm to 6:00 am.

F. Exterior Power Backup: Exterior egress, wa kway, parking lot, and parking structure lighting must have emergency power backup to provide for safe evacuation of the Building.

G. Video Surveillance System (VSS): Lighting shall be provided in such a manner to adequately support VSS operations, and not limit or preclude adequate fields of view.

3.42 ACOUSTICAL REQUIREMENTS (JUN 2012)

A. Reverberation Control. Private office and conference rooms using suspended acoustical ceilings shall have a noise reduction coefficient (NRC) of not less than 0.65 in accordance with ASTM C-423. Open office using suspended acoustical ceilings shall have an NRC of not less than 0.75. Private offices, conference rooms, and open offices using acoustical cloud or acoustical wall panels with a minimum of 70% coverage shall have an NRC of not less than 0.85.

B. Ambient Noise Control. Ambient noise from mechanical equipment shall not exceed noise criteria curve (NC) 35 in accordance with the ASHRAE Handbook of Fundamentals in offices and conference rooms; NC 40 in corridors, cafeterias, lobbies, and toilets; NC 50 in other spaces.

C. Noise Isolation. Rooms separated from adjacent spaces by ceiling high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

Conference rooms: NIC 40
Offices: NIC 35

D. Testing. The LCO may require, at Lessor’s expense, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.

3.43 ~~ENERGY EFFICIENCY AND CONSERVATION FOR NEW CONSTRUCTION (SEP 2010)~~ INTENTIONALLY DELETED

3.44 ~~SECURITY FOR NEW CONSTRUCTION (AUG 2021)~~ INTENTIONALLY DELETED

3.45 ~~SEISMIC SAFETY FOR NEW CONSTRUCTION (OCT 2020)~~ INTENTIONALLY DELETED

3.46 ~~FIRE PROTECTION FOR NEW CONSTRUCTION (WAREHOUSE) (MAY 2015)~~ INTENTIONALLY DELETED

3.47 INDOOR AIR QUALITY DURING CONSTRUCTION (OCT 2021)

A. The Lessor shall provide to the Government safety data sheets (SDS) or other appropriate documents upon request, but prior to installation or use for the following products, including but not limited to, adhesives, caulking, sealants, insulating materials, fireproofing or fire stopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finishes for wood surfaces, janitorial cleaning products, and pest control products.

B. The LCO may eliminate from consideration products with significant quantities of toxic, flammable, corrosive, or carcinogenic material and products with potential for harmful chemical emissions. Materials used often or in large quantities will receive the greatest amount of review.

C. Where demolition or construction work occurs adjacent to occupied Space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.

D. HVAC during Construction: If air handlers are used during construction, the Lessor shall provide filtration media with a MERV of 8 at each return air grill, as determined by ANSI/ ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size.

E. Flush-Out Procedure:

1. For leases 10,000 RSF or greater:

i. HVAC flush-out shall commence after construction ends and the Building has been completely cleaned. All interior finishes, such as millwork, doors, paint, carpet, acoustic tiles, and movable furnishings (e.g., workstations, partitions), must be installed, and major VOC punch list items must be finished.

ii. Prior to occupancy, Lessor shall install new filtration media and perform a building flush-out by supplying a total air volume of 14,000 cubic feet of outdoor air per square foot of gross floor area while maintaining an internal temperature of at least 60°F (15°C) and no higher than 80°F (27°C) and relative humidity no higher than 60%.

iii. If the LCO determines that occupancy is required before flush-out can be completed, the Space may be occupied only after delivery of a minimum of 3,500 cubic feet of outdoor air per square foot of gross floor area while maintaining an internal temperature of at least 60°F (15°C) and no higher than 80°F (27°C) and relative humidity no higher than 60%. Once the Space is occupied, it must be ventilated at a minimum rate of 0.30 cubic foot per minute (cfm) per square foot of outdoor air or greater. During each day of the flush-out period, ventilation must begin at least three hours before occupancy and continue during occupancy. These conditions must be maintained until a total of 14,000 cubic feet per square foot of outdoor air (4 270 liters of outdoor air per square meter) has been delivered to the space.

iv. The Lessor shall provide a signed statement explaining how all HVAC systems serving the leased Space will achieve the desired ventilation of the Space during the flush-out period.

2. For leases less than 10,000 RSF, the Lessor shall sufficiently flush-out or ventilate the area(s) following construction and prior to occupancy in order to remove any detectable odors or visible dust related to the work.

3.48 SYSTEMS COMMISSIONING (OCT 2021)

A. The Lessor shall incorporate commissioning requirements to verify that the installation and performance of energy consuming systems meet the Government's project requirements. These systems include, at a minimum, heating, ventilating, air conditioning and refrigeration (HVAC&R) systems and associated controls, lighting controls, and domestic hot water systems. The commissioning shall cover work associated with TIs or alterations. In instances involving minimal improvements, recommissioning is required to ensure that the systems are operating properly. In the event the Government exercises a renewal option, recommissioning is required within 60 days after the exercising of the option.

B. The Lessor shall submit a written commissioning plan prior to completion of DIDs. In instances involving minimal improvements not requiring DIDs, the plan is due within 60 days prior to Space acceptance. The plan shall include:

1. A schedule of systems commissioning (revised as needed during all construction phases of the project, with such revisions provided to the LCO immediately); and

2. A description of how commissioning requirements will be met and confirmed.

3.49 LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)

A. Lessor shall provide a minimum of **2** loading dock(s) for the exclusive use of the Government. The dock configuration shall be **24' high and consist of two (2) bay area docks, measuring 38' x 24' with door dimensions of 38' x 23' and a loading dock lift gate with dimensions of 8' x 4'.**

B. Lessor shall equip each dock with two molded rubber bumpers (at least 6 inches by 12 inches by 14 inches) and heavy-duty bump blocks (the dock must be fully protected with edge guards and dock bumpers). Lessor shall equip each dock with exterior dock seals to prevent the exchange of air from indoors to outdoors and vice versa when the trailer docked for loading or unloading. The entire loading dock bay shall be enclosed unless

otherwise specified by Lessee. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.

C. Dock-high doors shall be a minimum of 8' wide by 10' high and shall be approximately 48" above finished exterior grade unless otherwise specified in the Agency Special Requirements. Doors shall be insulated (R8 or better) with 2" angled, metal track and manual push-up. Door shall be spring loaded to assist opening and to safe return to the closed position. Weather-tight seals shall be provided around all 4 sides of the doors.

D. Drive-in doors shall be a minimum of 12' wide by 16' high unless otherwise specified in the Agency Special Requirements. The slope of the ramp shall not exceed 8.3% or by local code, whichever is more stringent. Doors shall be insulated (R8 or better) with 2" angled, metal track with chain hoist for opening and closing. Weather-tight seals shall be provided around all 4 sides of the doors.

E. Lessor shall equip each dock with **hydraulic dock levelers.** If exterior to the building, the entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Any open loading docks must be covered at least 1,200 mm (4 feet) beyond the edge of the loading dock platform over the loading berth. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.

F. Lessor shall provide sufficient ventilation to remove carbon monoxide even when doors and windows are shut. Ventilation air intakes must be at least 25 feet away from loading docks, garage entries, and similar carbon monoxide contamination points. Docks shall be separated by at least 50 feet in any direction from utility rooms, utility mains, and service entrances, including electrical, telephone/data, fire detection/alarm systems, fire suppression water mains, cooling and heating mains, etc. All regular and emergency fuel storage locations shall be located away from loading docks.

G. All dock wells shall be level throughout. Each dock shall have an **electronic roll-up, coiling type industrial steel warehouse & dock** door with lock. The loading dock area shall be nearly flat with a 1:50 slope for drainage. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). When a steeper slope is required in the apron area, the headroom must increase with a gradient allowance to permit trucks to traverse the grade change. If the approach to the loading dock is ramped, the design must permit easy snow removal.

H. Lessor shall equip each loading dock with adjustable lights capable of illuminating the truck or van interior. Each dock shall have either a trailer lock or wheel chocks chained to the platforms. Where specified by Government on Exhibit **A** (Floor Plans), the Lessor shall provide a ramp from the loading dock down to the vehicle parking area to facilitate deliveries from small trucks and vans. This ramp must have a maximum 8.3% slope. Public and loading dock access must not be from the same point of access (at least one personnel door shall be provided in addition to overhead doors).

I. All docks shall provide shelter to people and materials in inclement weather. Operating controls for individual dock doors, dock levelers and lights shall be located on the interior wall adjacent to each dock door.

J. Service dock access may be from an alley, from a below grade ramp, or from a site circulation drive. Lessor shall provide sufficient space for an **tractor trailer** to maneuver and service the facility, and also to screen the service drive as much as possible. At a minimum, Lessor shall provide a truck turning radius of **53'** sized for **tractor trailer** trucks for all loading docks. The service drive must always be separated from access to the parking area. One-way design for service traffic is preferred in order to avoid the need for large turning areas. The service area of the facility must not interfere with public access roadways.

K. Lessor shall provide at least one off-street berth for loading and unloading. Loading berths must be located adjacent to the loading dock areas. Unless otherwise specified by local zoning regulations, a single berth must be a minimum of 4,600 mm (15 feet) wide and sized for the longest vehicle servicing the building as determined by Lessee. Additional loading berths do not need to be wider than 3,600 mm (12 feet) if they are contiguous with another loading berth. Lessor shall provide an apron space in front of the loading berth for vehicle maneuvering equal to the length of the berth plus 600 mm (2 feet). The apron must be relatively flat and have positive drainage with a minimum slope of 2%. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). If programming forces a steeper slope in the apron area, the headroom should increase with a gradient allowance to allow trucks to traverse the grade change.

L. Loading dock areas must be separated and visually screened (wherever practical) from the main public building entrance(s). Lessor shall provide an internal staging area adjacent to the loading dock. The staging area must not interfere with emergency egress from the building. Loading docks must have a direct route to freight elevators (if any) and be sized to accommodate the transport of supplies, equipment replacement parts, and building goods. If provided for, a dock manager's room must have visual control of the entire dock area as well as the building entrance and exit. Service circulation must be separated from public areas such as lobbies, corridors, and elevators. Loading dock stairs must be on the driver's left when backing into the dock. The grade of the apron must slope away from the loading dock and shall not exceed an 8.3% slope.

M. Trash rooms must be located adjacent to loading docks or service entrances. Trash rooms must be sized to accommodate the trash handling equipment required and provide storage for trash and recycling generated during a three day occupancy of the building. Space must be allowed for sorting and recycling of paper, bottles and cans, metals, and other materials. Facilities that use trash containers that are picked up by vendors must have at least one loading berth for the trash container.

3.50 EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)

Emergency power backup is required for all alarm systems, CCTV monitoring devices, fire alarm systems, entry control devices, lighting, etc., and special equipment, as identified elsewhere within this Lease. Costs for emergency power to critical systems that are security requirements should be allocated to the BSAC cost component.

3.51 MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)

Roof access shall meet the applicable egress requirements in the National Fire Protection Association (NFPA) 101, Life Safety Code or IBC (current as of the Award Date of this Lease).

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

3.52 ~~DUE DILIGENCE AND NATIONAL ENVIRONMENTAL POLICY ACT REQUIREMENTS – LEASE (SEP 2014)~~ INTENTIONALLY DELETED

3.53 ~~NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS – LEASE (SEP 2014)~~ INTENTIONALLY DELETED

SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES

4.01 ~~SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2020)~~ INTENTIONALLY DELETED

4.02 CONSTRUCTION DOCUMENTS (SEP 2012)

The Lessor's CDs shall include all mechanical, electrical, plumbing, fire protection, life safety, lighting, structural, security, and architectural improvements scheduled for inclusion into the Space. CDs shall be annotated with all applicable specifications. CDs shall also clearly identify TIs already in place and the work to be done by the Lessor or others. Notwithstanding the Government's review of the CDs, the Lessor is solely responsible and liable for their technical accuracy and compliance with all applicable Lease requirements.

4.03 ~~TENANT IMPROVEMENTS PRICE PROPOSAL (OCT 2020)~~ INTENTIONALLY DELETED

4.04 ~~BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2015~~) INTENTIONALLY DELETED

4.05 ~~GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2021)~~ INTENTIONALLY DELETED

4.06 ~~CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (OCT 2020)~~ INTENTIONALLY DELETED

4.07 ~~PROGRESS REPORTS (OCT 2020)~~ INTENTIONALLY DELETED

4.08 ~~ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)~~ INTENTIONALLY DELETED

4.09 ~~CONSTRUCTION INSPECTIONS (SEP 2015)~~ INTENTIONALLY DELETED

4.10 ~~LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (OCT 2021)~~ INTENTIONALLY DELETED

4.11 ~~AS-BUILT DRAWINGS (OCT 2021)~~ INTENTIONALLY DELETED

4.12 ~~LIQUIDATED DAMAGES (JUN 2012)~~ INTENTIONALLY DELETED

4.13 ~~SEISMIC RETROFIT (SEP 2013)~~ INTENTIONALLY DELETED

4.14 GOVERNMENT PROJECT MANAGEMENT SYSTEM (OCT 2021)

The Government may direct the Lessor to use the Government's designated project management system for post-award and post-occupancy activities. This includes, but is not limited to, design submittals (DIDs, CD, as-builts), schedule submissions, pricing proposals, reuse plans, commissioning plans, and product data sheets.

SECTION 5 TENANT IMPROVEMENT COMPONENTS

5.01 ~~TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)~~ INTENTIONALLY DELETED

5.02 ~~FINISH SELECTIONS (SEP 2015)~~ INTENTIONALLY DELETED

5.03 WINDOW COVERINGS (WAREHOUSE) (JUN 2012)

A. Window Blinds. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the TIs. The blinds may be aluminum or plastic vertical blinds, horizontal blinds with aluminum slats of one-inch width or less, solar fabric roller shades, or an equivalent product pre-approved by the Government. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Government.

5.04 DOORS: SUITE ENTRY (OCT 2019)

A. Suite entry doors shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Government. Hollow core wood doors are not acceptable. They shall be operable by a single effort; and shall meet the requirement of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint finish that does not result in indoor air quality levels above 0.016 parts per million (ppm) of formaldehyde.

B. For leases 10,000 RSF or greater, the paint finish must meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT. and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False.

5.05 DOORS: INTERIOR (OCT 2019)

A. Doors within the Space shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 80" high. Doors shall be flush, solid core, wood with a natural wood veneer face or an equivalent door pre-approved by the LCO. Hollow core wood doors are not acceptable. They shall be operable with a single effort, and shall meet the requirements of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint and which does not result in indoor air quality levels above 0.016 parts per million (ppm) of formaldehyde.

B. For leases 10,000 RSF or greater, the paint finish must meet applicable, statutory environmentally preferable criteria related to biobased and recovered material content as outlined in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1338/paint/0?addon=False.

5.06 DOORS: HARDWARE (SEP 2013)

Doors shall have door handles or door pulls with heavyweight hinges. The Lessor is encouraged to avoid the use of chrome-plated hardware. All doors shall have corresponding doorstops (wall- or floor-mounted) and silencers. All door entrances leading into the Space from public corridors and exterior doors shall have automatic door closers. Doors designated by the Government shall be equipped with 5-pin, tumbler cylinder locks and strike plates. All locks shall be master keyed. Furnish at least two master keys for each lock to the Government. Any exterior entrance shall have a high security lock, with appropriate key control procedures, as determined by Government specifications. Hinge pins and hasps shall be secured against unauthorized removal by using spot welds or pinned mounting bolts. The exterior side of the door shall have a lock guard or astragal to prevent tampering of the latch hardware. Doors used for egress only shall not have any operable exterior hardware. All security-locking arrangements on doors used for egress shall comply with requirements of NFPA 101or the International Building Code current as of the Lease Award Date.

5.07 DOORS: IDENTIFICATION (JUN 2012)

Door identification shall be installed in approved locations adjacent to office entrances as part of the TIs. The form of door identification shall be approved by the Government.

5.08 PARTITIONS: SUBDIVIDING (OCT 2020)

A. Office subdividing partitions shall comply with applicable building codes and local requirements and ordinances and shall be provided as part of the TIs. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a minimum sound transmission class (STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the DIDs. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84).

B. HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.

C. If installed in accordance with the “Automatic Fire Sprinkler System” and “Fire Alarm System” paragraphs, sprinklers and fire alarm notification appliances shall be repositioned as appropriate after installation of partitions to maintain the level of fire protection and life safety.

D. Partitioning requirements may be satisfied with existing partitions if they meet the Government’s standards and layout requirements.

E. For leases 10,000 RSF or greater where the Government is a sole tenant of the Building , the Lessor is encouraged to use materials for newly installed gypsum board meeting applicable environmentally preferable criteria that are recommended in the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and HTTPS://SFTOOL.GOV/GREENPROCUREMENT/GREEN-PRODUCTS/3/BUILDING-FINISHES/1735/WALLBOARDGYPSUM-BOARDDRYWALL/0?ADDON=FALSE.

5.09 CEILINGS—TI (WAREHOUSE) (OCT 2019)

Government designated office and related areas shall contain a complete acoustical ceiling system (such a ceiling system include grid and lay-in tiles or other Building standard ceiling system as approved by the LCO).
A. Ceilings in office and related areas shall be at a minimum 9 feet and 0 inches and no more than 12 feet and 0 inches measured from floor to the lowest obstruction. Areas with raised flooring shall maintain these ceiling-height limitations above the finished raised flooring. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the Space, with no obvious damage to tiles or grid.

B. Prior to closing the ceiling, Lessor shall coordinate with the Government for the installation of any items above the ceiling.

C. Should the ceiling be installed in the Space prior to construction of the TI, then Lessor shall be responsible for all costs for the disassembly, storage during construction, and subsequent re-assembly of ceiling components which may be required to complete the TI. Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the construction of the TI.

D. Ceilings shall be a flat plane in each room and shall be suspended and finished as follows unless an alternate equivalent is pre-approved by the LCO:

1. Restrooms. Plastered or spackled and taped gypsum board.

2. Offices and conference rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the LCO. For leases 10,000 RSF or greater, newly installed tiles or panels shall meet applicable, statutory environmentally preferable criteria as outlined under the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/3/building-finishes/1732/acoustical-ceiling-tiles/0?addon=False

3. Corridors and eating/galley areas. Plastered or spackled and taped gypsum board or mineral acoustical tile.

5.10 WALL FINISHES (OCT 2019)

If the Government chooses to install a wall covering, the following specifications shall apply:

A. Commercial grade, weighing not less than 13 ounces per square yard.

B. For leases 10,000 RSF or greater, wall covering shall be vinyl-free, chlorine-free, plasticizer-free with recycled or bio-based content.. If the Government chooses to install a high-performance paint coating, it shall comply with the VOC limits of the Green Seal Standard GS-11.

5.11 ~~PAINTING—TI (OCT 2019)~~ INTENTIONALLY DELETED

5.12 ~~FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2019)~~ INTENTIONALLY DELETED

5.13 ~~HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED

5.14 ~~ELECTRICAL: DISTRIBUTION—TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED

5.15 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)

Telecommunications floor or wall outlets shall be provided as part of the TIs. At a minimum, each outlet shall house one 4-pair wire jack for voice and one 4-pair wire jack for data. The Lessor shall ensure that all outlets and associated wiring, copper, coaxial cable, optical fiber, or other transmission medium used to transmit telecommunications (voice, data, video, Internet, or other emerging technologies) service to the workstation shall be safely concealed under raised floors, in floor ducts, walls, columns, or molding. All outlets/junction boxes shall be provided with rings and pull strings to facilitate the installation of cable. Some transmission medium may require special conduit, inner duct, or shielding as specified by the Government.

5.16 ~~TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)~~ INTENTIONALLY DELETED

5.17 ~~DATA DISTRIBUTION (OCT 2020)~~ INTENTIONALLY DELETED

5.18 ~~ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (OCT 2020)~~ INTENTIONALLY DELETED

5.19 ~~LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED

5.20 ~~LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)~~ INTENTIONALLY DELETED

5.21 ~~AUTOMATIC FIRE SPRINKLER SYSTEM – TI (OCT 2016)~~ INTENTIONALLY DELETED

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM

6.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)

A. The Government's normal hours of operations are established as **8:00** AM to **4:00** PM, Monday through Friday, with the exception of Federal holidays. Services, maintenance, and utilities shall be provided during these hours. The Government shall have access to the Premises and its Appurtenant Areas at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, restrooms, lights, and electric power.

B. The Lessor and the Lessor's representatives, employees and contractors shall demonstrate a cooperative, positive, welcoming, respectful, professional and business-l ke demeanor and shall present a neat, clean, job-appropriate (professional) appearance.

6.02 UTILITIES SEPARATE FROM RENTAL/BUILDING OPERATING PLAN (OCT 2020)

A. If any utilities are excluded from the rental consideration, the Lessor shall obtain a statement from a registered professional engineer stating that all HVAC, plumbing, and other energy intensive Building systems can operate under the control conditions stated in the Lease. The statement shall also identify all Building systems which do not conform to the system performance values, including the "recommended" or "suggested" values of ANSI/ASHRAE Standard 90.1, Energy Standard for New Buildings Except Low-Rise Residential Buildings, according to the version that corresponds with how the Building systems were designed to perform, or state or local codes.

B. The Lessor shall provide and install as part of shell rent, separate meters for utilities. Sub meters are not acceptable. The Lessor shall furnish in writing to the Government, prior to occupancy by the Government, a record of the meter numbers and verification that the meters measure Government usage only. Proration is not permissible. In addition, an automatic control system shall be provided to assure compliance with heating and air conditioning requirements.

C. The Building operating plan shall be in effect as of the Lease Term Commencement Date and shall include a schedule of startup and shutdown times for operation of each Building system, such as lighting, HVAC, and plumbing.

6.03 ~~UTILITY CONSUMPTION REPORTING (OCT 2016)~~ INTENTIONALLY DELETED

6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2020)

A. In all office areas, temperatures shall conform to local commercial equivalent temperature levels and operating practices in order to maximize tenant satisfaction. These temperatures shall be maintained throughout the leased Premises and service areas, regardless of outside temperatures, during the hours of operation specified in the Lease. The Lessor shall perform any necessary systems start-up required to meet the commercially equivalent temperature levels prior to the first hour of each day's operation. At all times, humidity shall be maintained below 60% relative humidity.

B. In all office areas, during non-working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not be provided except as necessary to return Space temperatures to a suitable level for the beginning of working hours. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative.

C. In all office areas, thermal comfort. During all working hours, Lessor shall comply with ANSI/ASHRAE Standard 55, Thermal Environmental Conditions for Human Occupancy that corresponds with how the Building's HVAC system was designed to perform. At a minimum, the Lessor must meet ASHRAE Standard 55-2004.

D. Warehouse or garage areas require heating and ventilation only. Cooling of this Space is not required. Temperature of warehouse or garage areas shall be maintained at a minimum of 50° Fahrenheit.

E. The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the Lease and shall make a reasonable attempt to schedule major construction outside of office hours.

F. Normal HVAC systems' maintenance shall not disrupt tenant operations.

G. **128** ABOA SF of the Premises shall receive cooling at all times (24 hrs a day, 365 days a year) for purposes of cooling the designated server room. The temperature of this room shall be maintained at **70** degrees F, with humidity control not to exceed 60% relative humidity, regardless of outside temperature or seasonal changes.

H. In addition to the server room requirements stated above, the following areas shall receive HVAC at all times:

1. **3,391** ABOA SF of the Premises shall receive cooling at all times (24 hrs a day, 365 days a year) for purposes of cooling the designated curator storage rooms. The temperature of this room shall be maintained between 68-72 degrees F, with humidity control between 45%-50% relative humidity, regardless of outside temperature or seasonal changes.

I. The 24 hour, 365 days a year HVAC service(s) stated above shall be provided by the Lessor as part of the operating rent established under the Lease.

6.05 ~~OVERTIME HVAC USAGE (OCT 2020)~~ INTENTIONALLY DELETED

6.06 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)

The Government will be responsible for janitorial service for the Government Premises.

6.07 ~~SELECTION OF CLEANING PRODUCTS (OCT 2021)~~ INTENTIONALLY DELETED

6.08 ~~SELECTION OF PAPER PRODUCTS (OCT 2021)~~ INTENTIONALLY DELETED

6.09 SNOW REMOVAL (WAREHOUSE) (OCT 2020)

Lessor shall provide snow removal services for the Government on all days for which this Lease has designated normal hours. Lessor shall clear parking lots if the accumulation of snow exceeds two inches. Lessor shall clear sidewalks, wa kways, loading docks, dock ramps, and entrances before accumulation exceeds 1.5 inches. The snow removal shall take place no later than 5:00 AM, without exception. Should accumulation continue throughout the day, the Lessor shall provide such additional snow removal services to prevent accumulation greater than the maximums specified in this paragraph. In addition to snow removal, the Lessor shall keep sidewalks, wa kways, loading docks, dock ramps, and entrances free of ice during the normal hours. The Lessor shall remove excess buildup of sand and/or ice melt to minimize slipping hazards. If the Building entrance(s) has a northern exposure, then Lessor shall take additional measures (e.g., more frequent snow removal or application of ice-melting agents, warning signs, etc.) to protect the safety of pedestrians.

6.10 MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)

A. The Lessor is respons ble for the total maintenance, repair and replacement of the leased Premises, the Building, and the Property. Such maintenance, repairs and replacements include the site and private access roads, and all necessary repairs and replacements to the loading docks, ramps, levelers and all other associated equipment and features. All equipment and systems shall be maintained, repaired, and replaced to provide reliable, energy efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance respons bility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with current applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the Government's designated representative.

B. At the Lessor's expense, the Government reserves the right to require documentation of proper operations or testing inspection, testing, and maintenance of fire protection systems, such as fire alarm, fire sprinkler, standpipes, fire pump, emergency lighting, illuminated exit signs, emergency generator, prior to occupancy to ensure proper operation. These tests shall be witnessed by the Government's designated representative.

6.11 MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016)

A. Paint, wall coverings. Lessor shall maintain all wall coverings and high performance paint coatings in "l ke new" condition for the life of the Lease. All painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if the paint is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this Lease. In addition to the foregoing requirement,

1. Lessor shall repaint common areas at least every three years.

2. Lessor shall perform cyclical repainting of the Space every **5** years of occupancy. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.

3. If the warehouse portion of the Space was painted originally, Lessor shall perform cyclical repainting of the warehouse portion at the same cycle as the office and related space. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture per manufacturer's warranty, shall be at the Lessor's expense.

B. Carpet and flooring.

1. Except when damaged by the Government, the Lessor shall repair or replace flooring at any time during the Lease term when:

   a. Backing or underlayment is exposed;
   b. There are noticeable variations in surface color or texture;
   c. It has curls, upturned edges, or other noticeable variations in texture;
   d. Tiles are loose; or,
   e. Tears or tripping hazards are present.

2. Notwithstanding the foregoing, as part of the rental consideration, the Lessor shall replace all carpet and base coving in the Space every **10** years, with a product which meets the requirements in the "Floor Coverings and Perimeters" paragraph in this Lease.

3. Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture per manufacturer's warranty, if necessary. Work shall be performed after the normal hours established elsewhere in this Lease.

4. INTENTIONALLY DELETED

6.12 ASBESTOS ABATEMENT (OCT 2021)

If asbestos abatement work is to be performed in the Space after occupancy, the Lessor shall provide relocation and submit to the Government documentation that the abatement was done in accordance with OSHA, EPA, DOT, state, and local regulations and that final clearance for re-occupancy was achieved.

6.13 ONSITE LESSOR MANAGEMENT (APR 2011)

The Lessor shall provide an onsite Building superintendent or a locally designated representative available to promptly respond to deficiencies, and immediately address all emergency situations.

6.14 IDENTITY VERIFICATION OF PERSONNEL (OCT 2021)

A. The Government reserves the right to verify identities of personnel with routine and/or unaccompanied access to the Government's Space, including both pre and post occupancy periods. The Lessor shall comply with the GSA personal identity verification requirements, identified in the CIO P 2181.1 GSA HSPD-12 Personal Identity Verification and Credentialing Handbook. The Lessor can find the CIO policy and additional information at *HTTP://WWW.GSA.GOV/HSPD12*. This policy requires the Government to conduct background investigations and make HSPD-12 compliant suitability determinations for all persons with routine or unaccompanied access to Government leased Space. By definition, this includes at a minimum each employee of the Lessor, as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased Space for a period greater than 6 months. The Government may also require this information for the Lessor's employees, contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's Space.

B. Application Process: The background investigation will be done using the Government's prescribed process. The Lessor must provide information on each of their contractor/personnel meeting the above criteria to the Government, whereupon each identified contractor/personnel will be notified with instructions for completing the identity verification application within a given time frame. The application process will include completing supplemental information forms that must be inputted into the identity verification system in order for the application to be considered complete. Additionally, the Lessor must ensure prompt completion of the fingerprint process for their contractor/personnel. Email notifications will be sent with instructions on the steps to be taken to schedule an appointment for fingerprinting at an approved regional location along with instructions on how to complete the background investigation application.

C. The Lessor must ensure the Lease Contracting Officer (or the Lease Contracting Officer's designated representative) has all of the requested documentation timely to ensure the completion of the investigation.

D. Based on the information furnished, the Government will conduct background investigations. The Lease Contracting Officer will advise the Lessor in writing if a person fails the investigation, and, effective immediately, that person will no longer be allowed to work or be assigned to work in the Government's Space.

E. Throughout the life of the Lease, the Lessor shall provide the same data for any new employees, contractors, or subcontractors who will be assigned to the Government's Space in accordance with the above criteria. In the event the Lessor's contractor or subcontractor is subsequently replaced, the new contractor or subcontractor is not required to have persons re-apply who were cleared through this process while associated with the former contractor or subcontractor in accordance with GSA policy. The Lessor shall require each cleared person to re-apply and obtain a new clearance in accordance with GSA policy.

F. The Lessor is accountable for not allowing contractors to start work without the successful completion of the appropriate background investigation as required by GSA policy.

G. Access Card Retrieval/Return: Upon an Entry on Duty notification, the Government will issue a Personal Identity Verification (PIV) credential that is sometimes referred to as a GSA Access card. Lessors are responsible for all PIV credential issued to their contractors/personnel pursuant to this Lease. Lessors are specifically responsible for ensuring that all GSA PIV access cards are returned to the Lease Contracting Officer or their designee whenever their employees or a contractor no longer require access to the Space (such as When no longer needed for contract performance, upon completion of the Contractor employee's employment, and upon contract completion or termination). Additionally, the Lessor must notify the Lease Contracting Officer or their designee whenever a GSA PIV Access card is lost or stolen in which event the Lessor may be responsible for reimbursing the Government for replacement credentials at the current cost per PIV HSPD12 credential. Unreturned PIV Access cards will be considered as lost or stolen cards.

H. The Government reserves the right to conduct additional background checks on Lessor personnel and contractors with routine access to Government leased Space throughout the term of the Lease to determine who may have access to the Premises.

I. The Lease Contracting Officer may delay final payment under a contract if the Contractor fails to comply with these requirements.

J. The Lessor shall insert this paragraph in all subcontracts when the subcontractor is required to have physical access to a federally controlled facility or access to a federal information system.

6.15 SCHEDULE OF PERIODIC SERVICES (OCT 2020)

Upon acceptance of the Space, the Lessor shall provide the LCO with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly.

6.16 LANDSCAPING (OCT 2019)

A. For leases 10,000 RSF or greater where the Government is the sole occupant of the building, the Lessor shall use landscaping products that meet applicable statutory environmentally preferable criteria related to recycled content as outlined under the Green Procurement Compilation at HTTPS://SFTOOL.GOV/GREENPROCUREMENT and https://sftool.gov/greenprocurement/green-products/6/landscaping-products/0.

B. Landscape management practices shall prevent pollution by:
1. Employing practices which avoid or minimize the need for herbicides, fertilizers and pesticides; and

2. Composting/recycling all yard waste.

C. INTENTIONALLY DELETED

6.17 LANDSCAPE MAINTENANCE (APR 2011)

Landscape maintenance shall be performed during the growing season at not less than a weekly cycle and shall consist of watering, weeding, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an as-needed basis. In addition, dead, dying, or damaged plants shall be replaced.

6.18 RECYCLING—WAREHOUSE (OCT 2021)

A. Where state or local law, code, or ordinance requires recycling programs for the Premises, Lessor shall comply with such state and/or local law, code, or ordinance.

B. When implementing any recycling program, the Lessor shall provide an easily accessible, appropriately sized area (2 SF per 1,000 SF of Building gross floor area) that serves the Space for the collection and storage of materials for recycling. Telecom rooms are not acceptable as recycling space. During the Lease term, the Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the Building and in the Space.

C. For Leases 10,000 rentable SF or greater, with a Lease term greater than six months, the Lessor shall establish a recycling program for (at a minimum) paper, corrugated cardboard, glass, plastics, and metals where local markets for recovered materials exist and submit a Building recycling service plan with floor plans annotating recycling area(s) as part of DIDs, if applicable, to be reflected on the CD submission.

6.19 ~~RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)~~ INTENTIONALLY DELETED

6.20 SAFEGUARDING AND DISSEMINATION OF CONTROLLED UNCLASSIFIED INFORMATION (CUI) BUILDING INFORMATION (FEB 2020)

This clause applies to all recipients of CUI building information (which falls within the CUI Physical Security category), including offerors, bidders, awardees, contractors, subcontractors, lessors, suppliers and manufacturers.

Marking CUI. Contractors must submit any contractor-generated documents that contain building information to GSA for review and identification of any CUI building information that may be included. In addition, any documents GSA identifies as containing CUI building information must be marked in accordance with the Order and the Marking Controlled Unclassified Information Handbook (the current version may be found at https://www.archives.gov/files/cui/20161206-cui-marking-handbook-v1-1.pdf) before the original or any copies are disseminated to any other parties. If CUI content is identified, the CO may direct the contractor, as specified elsewhere in this contract, to imprint or affix CUI document markings (CUI) to the original documents and all copies, before any dissemination, or authorized GSA employees may mark the documents.

1. Authorized recipients.
   a. Building information designated as CUI must be protected with access strictly controlled and limited to those individuals having a Lawful Government Purpose to access such information, as defined in 32 C.F.R. § 2002.4(bb). Those with such a Lawful Government Purpose may include Federal, state and local government entities, and non-governmental entities engaged in the conduct of business on behalf of or with GSA. Non-governmental entities may include architects, engineers, consultants, contractors, subcontractors, suppliers, utilities, and others submitting an offer or bid to GSA, or performing work under a GSA contract or subcontract. Recipient contractors must be registered as "active" in the System for Award Management (SAM) database at www.sam.gov, and have a Lawful Government Purpose to access such information. If a subcontractor is not registered in the SAM database and has a Lawful Government Purpose to possess CUI building information in furtherance of the contract, the subcontractor must provide to the contractor its DUNS number or its tax ID number and a copy of its business license. The contractor must keep this information related to the subcontractor for the duration of the contract and subcontract.
   b. All GSA personnel and contractors must be provided CUI building information when needed for the performance of official Federal, state, and local government functions, such as for code compliance reviews and the issuance of building permits. Public safety entities such as fire and utility departments may have a Lawful Government Purpose to access CUI building information on a case-by-case basis. This clause must not prevent or encumber the necessary dissemination of CUI building information to public safety entities.

2. Dissemination of CUI building information:
   a. By electronic transmission. Electronic transmission of CUI information outside of the GSA network must use session encryption (or alternatively, file encryption) consistent with National Institute of Standards and Technology (NIST) SP 800-171. Encryption must be through an approved NIST algorithm with a valid certification, such as Advanced Encryption Standard or Triple Data Encryption Standard, in accordance with Federal Information Processing Standards Publication 140-2, Security Requirements for Cryptographic Modules, as required by GSA policy.
   b. By nonelectronic form or on portable electronic data storage devices. Portable electronic data storage devices include CDs,

DVDs, and USB drives. Nonelectronic forms of CUI building information include paper documents, photographs, and film, among other formats.

i. By mail. Contractors must only use methods of shipping that provide services for monitoring receipt such as track and confirm, proof of delivery, signature confirmation, or return receipt.

ii. In person. Contractors must provide CUI building information only to authorized recipients with a Lawful Government Purpose to access such information. Further information on authorized recipients is found in section 1 of this clause.

3. Record keeping. Contractors must maintain a list of all entities to which CUI is disseminated, in accordance with sections 2 and 3 of this clause. This list must include, at a minimum:
   a. The name of the state, Federal, or local government entity, utility, or firm to which CUI has been disseminated;
   b. The name of the individual at the entity or firm who is respons ble for protecting the CUI building information, with access strictly controlled and limited to those individuals having a Lawful Government Purpose to access such information;
   c. Contact information for the named individual; and
   d. A description of the CUI building information provided.

   Once "as built" drawings are submitted, the contractor must collect all lists maintained in accordance with this clause, including those maintained by any subcontractors and suppliers, and submit them to the CO. For Federal buildings, final payment may be withheld until the lists are received.

4. Safeguarding CUI documents. CUI building information (both electronic and paper formats) must be stored within controlled environments that prevent unauthorized access. GSA contractors and subcontractors must not take CUI building information outside of GSA or their own facilities or network, except as necessary for the performance of that contract. Access to the information must be limited to those with a Lawful Government Purpose for access.

5. Destroying CUI building information. When no longer needed, CUI building information must either be returned to the CO or destroyed in accordance with guidelines in NIST Special Publication 800-88, Guidelines for Media Sanitization.

6. Notice of disposal. The contractor must notify the CO that all CUI building information has been returned or destroyed by the contractor and its subcontractors or suppliers in accordance with paragraphs 4 and 5 of this clause, with the exception of the contractor's record copy. This notice must be submitted to the CO at the completion of the contract to receive final payment. For leases, this notice must be submitted to the CO at the completion of the lease term.

7. CUI security incidents. All improper disclosures or receipt of CUI building information must be immediately reported to the CO and the GSA Incident Response Team Center at gsa-ir@gsa.gov. If the contract provides for progress payments, the CO may withhold approval of progress payments until the contractor provides a corrective action plan explaining how the contractor will prevent future improper disclosures of CUI building information. Progress payments may also be withheld for failure to comply with any provision in this clause until the contractor provides a corrective action plan explaining how the contractor will rectify any noncompliance and comply with the clause in the future.

8. Subcontracts. The contractor and subcontractors must insert the substance of this clause in all subcontracts.

6.21 INDOOR AIR QUALITY (OCT 2019)

A. The Lessor shall control airborne contaminants at the source and/or operate the Space in such a manner that indoor air quality action limits identified in the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8), OSHA regulatory limits, and generally accepted consensus standards are not exceeded. .

B. The Lessor shall avoid the use of products containing toxic, hazardous, carcinogenic, flammable, or corrosive ingredients as determined from the product label or manufacturer's safety data sheet. The Lessor shall use available odor-free or low odor products when applying paints, glues, lubricants, and similar wet products. When such equivalent products are not available, lessor shall use the alternate products outside normal working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying chemicals or products with noticeable odors in occupied Spaces and shall adequately ventilate those Spaces during and after application.

C. The Lessor shall serve as first responder to any occupant complaints about indoor air quality (IAQ). The Lessor shall promptly investigate such complaints and implement the necessary controls to address each complaint. Investigations shall include testing as needed, to ascertain the source and severity of the complaint.

D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in Space that it occupies, as well as in space serving the Space (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by:

1. Making available information on Building operations and Lessor activities;
2. Providing access to Space for assessment and testing, if required; and
3. Implementing corrective measures required by the LCO. The Lessor shall take corrective action to correct any tests or measurements that do not meet GSA policy action limits in the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8), OSHA regulatory limits, and generally accepted consensus standards.

E. The Lessor shall provide to the Government safety data sheets (SDS) upon request for the following products prior to their use during the term of the Lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the

right to review such products used by the Lessor within the Space, common building areas, ventilation systems and zones serving the Space, and the area above suspended ceilings and engineering space in the same ventilation zone as the Space.

F. The Lessor shall use high efficiency (HEPA) filtration vacuums for cleaning and minimum MERV 10 rated ventilation system filtration whenever feasible.

G. The Lessor is encouraged to comply with best practices outlined in Appendix D- Indoor Air Quality in GSA Leased Facilities (Best Practices) within the PBS Desk Guide for Indoor Air Quality Management (Companion to GSA Order PBS 1000.8).

6.22 RADON IN AIR (OCT 2016)

If Space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased Space for 2 days to 3 days using charcoal canisters. The Lessor is responsible to provide Space in which radon levels in air are below the GSA action levels of 4 picoCuries per liter (pCi/L) for childcare and 25 pCi/L for all other space. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors shall be completed. For further information on radon, go to: HTTPS://WWW.EPA.GOV/RADON.

6.22 ~~RADON IN WATER (JUN 2012)~~ INTENTIONALLY DELETED

6.23 HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)

A. The leased Space shall be free of hazardous materials, hazardous substances, and hazardous wastes, as defined by and according to applicable Federal, state, and local environmental regulations. Should there be reason to suspect otherwise, the Government reserves the right, at Lessor's expense, to require documentation or testing to confirm that the Space is free of all hazardous materials.

B. Lessor shall, to the extent of its knowledge, notify Government of the introduction of any hazardous materials onto the Property by Lessor or others, including but not limited to, co-tenants occupying Space in the Building.

C. All hazardous materials stored in the Space must be kept and maintained according to applicable Federal, State, and local environmental regulations. The Government will notify Lessor of any hazardous materials it will store in the Space.

6.24 MOLD (OCT 2021)

A. Actionable mold is either visible mold or airborne mold of types and concentrations in excess of that found in the local outdoor air or non-problematic control areas elsewhere in the same building, whichever is lower. The Lessor shall safely remediate all actionable mold in accordance with sub-paragraph C below.

B. The Lessor shall provide Space to the Government that is free from ongoing water leaks or moisture infiltration. The Space and ventilation zones serving the Space shall also be free of actionable mold.

C. Within 48 hours following a flood, plumbing leak or heavy rain whereby the Government Space or air zones serving the Space may have become moisture damaged, the Lessor shall repair any leakage sources and remediate the moisture damage. Whenever moisture damage or infiltration persists such that: mold is visible, mold odors are present, or occupants register complaints about mold, the Lessor shall employ a board-certified industrial hygienist to inspect and evaluate the Space and air zones serving the Space for visible and/or actionable mold presence; inspection shall take place as soon as poss ble but no later than 15 calendar days following identification of a potential mold issue as descr bed above. Notwithstanding the above, when a board-certified industrial hygienist is not available to perform this inspection, the Lessor may, upon written request and the Government's approval, employ an environmental consultant experienced in mold assessment. The Lessor shall promptly furnish the mold report to the Government. After all leaks have been identified and corrected, the Lessor shall safely remediate all visible moldy and/or water damaged materials identified by the consultant using a qualified remediation contractor following the methods identified in "Mold Remediation in Schools and Commercial Buildings" (EPA 402-K-01-001, September 2008 or ANSI/IICRC S520-2015: Standard for Professional Mold Remediation) and all applicable state laws pertaining to mold remediation practices. Remediation shall also remove actionable mold levels. Remediation shall be completed within a time frame acceptable to the Lease Contracting Officer which shall be no later than 90 calendar days following confirmation of the presence of actionable mold.

D. The presence of actionable mold in the Premises may be treated as a Casualty, as determined by the Government, in accordance with the Fire and Other Casualty clause contained in the General Clauses of this Lease. In addition to the provisions of the Fire and Other Casualty clause of this Lease, should a portion of the Premises be determined by the Government to be un-tenantable due to an act of negligence by the Lessor or his agents, the Lessor shall provide reasonably acceptable alternative Space at the Lessor's expense, including the cost of moving, and any required alterations.

6.25 OCCUPANT EMERGENCY PLANS (OCT 2020)

The Lessor is required to cooperate, participate and comply with the development and implementation of the Government's Occupant Emergency Plan (OEP) and a supplemental Shelter-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising its OEP and SIP. The Plan, among other things, will include evacuation procedures and an annual emergency evacuation drill, emergency shutdown of air intake procedures, and emergency notification procedures for the Lessor's Building engineer or manager, Building security, local emergency personnel, and Government agency personnel.

6.26 ~~FLAG DISPLAY (OCT 2016)~~ INTENTIONALLY DELETED

6.27 PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)

Lessor shall provide, inspect, and maintain portable fire extinguishers in accordance with NFPA No. 10.

6.28 TRASH DUMPSTER SERVICE (WAREHOUSE) – GOVERNMENT PROVIDED (OCT 2016)

The Government will provide trash dumpster service for the Space. Lessor must provide an area conveniently located to the Government's loading area for the trash dumpsters at no additional charge to the Government.

6.29 ACCESS TO BUILDING INFORMATION (MAY 2014)

Building Information—including mechanical, electrical, vertical transport, fire protection and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, preferably by the development of an access list and controlled copy numbering. The LCO may direct that the names and locations of Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the Building directory.

SECTION 7 ADDITIONAL TERMS AND CONDITIONS

7.01 SECURITY REQUIREMENTS (OCT 2016)

The Lessor agrees to the requirements of Facility Security Level **III** attached to this Lease.

7.02 MODIFIED LEASE PARAGRAPHS (OCT 2016)

The following paragraphs have been modified in this Lease:

1.10
2.09
4.13
6.04

7.03 ADDENDUM TO GSA FORM 3517B, GENERAL CLAUSES, NO FEDERALLY ELECTED OFFICIALS TO BENEFIT (OCT 2018)

The following clause is added to GSA Form 3517B, General Clauses:

No Federally Elected Officials to Benefit

A. No person holding a Federally-elected office may directly or indirectly, regardless of whether such person took office before or after execution of the Lease, participate in or benefit from the Lease or any part thereof.

B. The foregoing prohibition shall not apply if the Lease is entered into with a publicly-held corporation or publicly-held entity for the general benefit of such corporation or entity.

C. Any violation of this clause shall render the Lease void, and the Government shall have no obligation to the Lessor in consequence thereof following the date the Lease is deemed void.

D. In the event the Lease is voided pursuant to this clause, the Lessor shall be and remain liable to the Government for any and all costs associated with relocating and housing Government occupants from the leased premises to replacement premises. Such costs shall include, but not be limited to:

1. moving and other physical relocation costs,
2. furniture, fixtures and equipment costs related to occupancy of replacement premises,
3. replication of tenant build-out costs at replacement premises,
4. excess rental costs at replacement premises for the remainder of the firm term of the terminated Lease, and
5. all other direct and consequential damages and costs associated with the Government relocating occupants from the leased premises to replacement premises, whether Federally-owned or leased.

E. Nothing in this clause shall be deemed or interpreted to waive, modify, alter or limit any provision of existing law, including 41 U.S.C. § 6306 and 18 U.S.C. §§ 431-433.

F. Lessor's obligation to be and remain liable for the costs and damages specified in this clause shall survive any voiding of the Lease pursuant to this clause or any provision of existing law.

7.04 PROVISIONAL ACCEPTANCE (FEB 2021)

A. At a time of exceptional circumstance, i.e., pandemic, the Government may accept the Space on a provisional basis until such time that a re-inspection on-site can occur. In this instance and upon request from the LCO, the Lessor shall provide such documentation (e.g., picture(s), video(s) and/or a representative on-site for a live-stream or 'virtual' wa kthrough) to confirm substantial completion. In such an instance the Government may withhold a percentage of lump sum Tenant Improvement payment as a reserve to ensure that all deficiencies and/or punch list item(s) will be addressed by the Lessor within the time frame established or until the Government can determine the space has been delivered in accordance with the Lease requirements, Design Intent Drawings and Construction Drawings.

B. At such time as a physical on-site inspection is deemed possible by the Government, the Government reserves the right to physically inspect the Space with an on-site representative to conduct a space measurement and to document any deficiencies and/or punch-list item(s) for the Lessor's correction.

C. Upon re-inspection and Government acceptance of any deficiencies and/or punch list item(s) documented per above, or in the instance of no such documented items, this provisional acceptance will be rendered non-provisional and fully accepted by the Government via subsequent Lease Amendment.

7.05 AS-EXISTING CONDITION (MAY 2022)

The premises under this Lease have been previously occupied by the Government under GSA Lease No. GS-11P-LDC12956. Accordingly, the leased premises were offered to and accepted by the Government in their “As-Existing” condition, except that the Lessor shall remain responsible for any fire-life safety deficiencies or code violations. Lessor represents that such items that were offered “As-Existing” are in good repair and tenantable condition. The intent of this qualification is to recognize that the Government may find such items or conditions to be at least minimally acceptable with regard to the Government's continued occupancy of the space. Nonetheless, such items or conditions are to be in "good repair and tenantable condition" at the time of the lease commencement or by any other specified date(s). Further, the lessor is to maintain (or replace, if necessary) such items or conditions so that they remain in "good repair and tenantable condition" throughout the term of this lease. Lessor is not relieved from requirements contained in the lease for base building maintenance, future alterations, repairs, replacements, construction and/or improvements. If replacement is or becomes necessary, such replacement must be no less than equal in quality and follow all applicable current local building codes.

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Exhibit A
Floor Plan

(b) (7)(F)

Lessor CS

Government La

DocuSign Envelope ID: B[redacted]48-5C4D-4060-9041-7066704B0DB0

(b) (7)(F)

GTM ARCHITECTS
7735 OLD GEORGETOWN ROAD
SUITE 700
BETHESDA, MD 20814
(240)333-2000
(240)333-2001 FAX

3035 V STREET N.E.
WASHINGTON, D.C. 20018

FINISH PLANS - 1ST FLOOR & MEZZANINE

US SUPREME COURT OFF-SITE STORAGE FACILITY

REVISIONS:
5-15-13 WALK-THRU COMMENTS

SEAL:

COPYRIGHT 2010, GTM ARCHITECTS, INC.

DRAWN BY: CP
CHECKED BY: JJ
SCALE: AS NOTED
DATE: 05-15-13
PROJECT NO. 13.0042
DRAWING NO. A1.1

Lessor CS Government

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Exhibit B
Parking Plan

(b) (7)(F)

Lessor (b) (5), (b) (7)(F) Government LA

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Exhibit C
Site Plan

(b) (7)(F)

Lessor _____ Government _____

(b) (7)(F)

(5)Small Loading Dock Landing: 33" x 11"

a. Flooring type: _____concrete _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall_____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____concrete_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation)_____1_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy sealed concrete floor**

(6) Small Loading Dock Main Delivery area: 47' x26' Ceiling Height: 11'

a. Flooring type: _____concrete _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete_____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____concrete_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation)_____1_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **2 bay area 8' x 8'**

(b) (7)(F)

(8) Mail Screening Rm: 28' x 24'

a. Flooring type: _____concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(9) Investigations Vestibule: 9' x 9'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling _____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(10) Investigations Room: 24' x 12'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(11) Mail Staging Vestibule:

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(12) Mail Staging Room 1: 18' x 12'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(13) Investigations Room: 24' x 12'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(14) Shower Room: 11' x 8' Two Stalls

a. Flooring type: _____Tiled_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____1_____

f. Wall Type: (gyp board or other?)_____Drywall _____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(15 & 16) Locker Rooms: 8' X 8'

a. Flooring type: _____ tiled_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling _____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____1_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Locker equipment provided by agency**

(17) Housekeeping Room: 12' x 7'

a. Flooring type: _____ Tile_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____1_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(18) Mail Supervisor's Office: 12' x 10'

a. Flooring type: _____ Tile_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _3_____

e. Quantity data outlets (per office or workstation) _____2_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(19) Mail Staff Office: 22' x 12'

a. Flooring type: _____ Tile_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____4_____

f. Wall Type: (gyp board or other?)_____Drywall_____.

g. Sound ransmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____

h. Additional Needs:

(20) Wash-Down Room: 18' X 12'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Epoxy Paint for the floors**

(21) Curator's Storage: 49' x 43'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _8_____

e. Quantity data outlets (per office or workstation) _____4_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: Controlled Temperatur Room at 68 degrees and Room Humidity between 45 and 50%. System need to run 24hrs a day 365 days a year.

(22) Curator's Storage (Controlled Temperature Area) : 44' x 29'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: Controlled Temperature Room at 68 degrees and Room Humidity between 45 and 50%. System need to run 24hrs a day 365 days a year. Roof Top Heating & Air Conditioning Unit with Dehumiification cycle.

Lessor CS Government La

(23) Mail Sorting Room: 31' x 19'

a. Flooring type: _____Tiled_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _7_____

e. Quantity data outlets (per office or workstation) _____4_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: Equipment provided by agency standard PC's used.

(24) Loading Dock Large: 38' x 24' Ceiling Height: 24'

a. Flooring type: _____concrete _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete_____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____concrete_____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation)_____1_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: 2 Bay area docks

Door Dimensions: 38' (W) 23' Ceiling

Depth and Width of area truck need to park at dock: 38' (D) x 24' (W)

Loading Dock Lift Gate: 8' (L) X 4' (H)

(25) Stationary Store: 73' x 47'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(26) Carpenter Shop: 73' x 47'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _20_____

e. Quantity data outlets (per office or workstation) _____8_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: Dust Collection System

Here is a list of the large machinery and the amperages that they use:

CNC Machine – 125 amps @ 208v

2 Table Saws – 15 @ 208v amps each

Bandsaw – 10 amps @ 230v

Double Miter Saw – 20 amps @ 208v

Sliding Table Saw – 20 Amps @ 208v

2 Belt Sanders – 20 Amps @ 208v

Dovetail Machine – 20 Amps @208v

Spindle Sander -20Amps @ 208v

Tilting Shaper – 40 Amps @ 230v

Tenoning Shaper – 30 Amps @ 230v

Kaeser Air Compressor – 34 Amps @ 208v

Chicago Air Compressor – 15 Amps @ 208v

Dust Collector -48 Amps @208v

Jointer – 15 Amps @ 208v

Edgebander – 50 Amps @ 230v

Planer – 35 Amps @ 230v

Widebelt Sander – 80 Amps @ 230v

Lacquer recycler – 20 Amps @208v

Finishing Booth - 60 Amps @ 208v

Paint Mixer – 20 Amps @ 208v

Drill Press – 20 Amps @ 208v

Lessor CS

Government La

(27) Frame Shop: 23' x 22'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _8_____

e. Quantity data outlets (per office or workstation) _____4_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(28) Finishing/Paint Shop/Office: 49' X 23'

a. Flooring type: _____concrete _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall_____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop ceiling_____

d. Quantity duplex electrical outlets , (per office or workstation) _8_____

e. Quantity data outlets (per office or workstation)_____2_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(29) Generator Room-(Back-Up) 28' x 24'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling _____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____1_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(30) Marshal's Storage Area: 53' x 27'

a. Flooring type: _____sealed concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(31) Warehouse Manager Office: 19' x 17'

a. Flooring type: _____Carpet_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(32) Warehouse Asst. Manager Office: 14' x 12'

a. Flooring type: _____carpet_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(33) Conference Room: 15' x 14'

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(34) Back Room Storage: 19' x15'

a. Flooring type: _____ concrete_____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____concrete _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drop Ceiling _____

d. Quantity duplex electrical outlets , (per office or workstation) _2_____

e. Quantity data outlets (per office or workstation) _____1_____

f. Wall Type: (gyp board or other?)_____concrete_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(35) Police Data Room: 13' x 9'

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(36) Telecomm Data Room: 14' x 9'

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _4_____

e. Quantity data outlets (per office or workstation) _____3_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

(37) Employee Lounge: 27' x 14'

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _5_____

e. Quantity data outlets (per office or workstation) 2_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: Sink, cabinets. Appliances furnished by agency

(38) Property & supply Employee Workstations: 26' x 24'

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Paint _____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _8_____

e. Quantity data outlets (per office or workstation) _____4_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs: **Space to Accommodate 3 work cubicles for employees**

(39) MEZZANNE: Two (2) Restrooms

a. Flooring type: _____Tiled _____

b. Wall finish type (Paint, wall covering, etc.) If each office area is different please note which offices will receive what type of wall finish):_____Drywall_____,

c. Ceiling type , (drywall, drop ceiling, etc.)_____Drywall_____

d. Quantity duplex electrical outlets , (per office or workstation) _1_____

e. Quantity data outlets (per office or workstation)_____0_____

f. Wall Type: (gyp board or other?)_____Drywall_____

g. Sound Transmission Coefficient (STC) sound proofing Requirement (if other than standard): _____Standard_____-

h. Additional Needs:

SECURITY REQUIREMENTS - (b) (7)(F) [redacted]

THESE PARAGRAPHS CONTAIN ADDITIONAL SECURITY REQUIREMENTS THAT MAY BE INSTALLED IN THE LEASED SPACE, AND UNLESS INDICATED OTHERWISE, ARE TO BE PRICED AS PART OF THE BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC). BECAUSE EACH BUILDING IS UNIQUE, THE FINAL LIST OF SECURITY COUNTERMEASURES WILL BE DETERMINED DURING THE DESIGN PHASE AND IDENTIFIED IN THE DESIGN INTENT DRAWINGS AND CONSTRUCTION DOCUMENTS. AFTER COMPLETING THE CONSTRUCTION DOCUMENTS, THE LESSOR SHALL SUBMIT A LIST OF THE ITEMIZED COSTS. SUCH COSTS SHALL BE SUBJECT TO NEGOTIATION.

NOTE THAT ITEMS IDENTIFIED AS "SHELL *" REPRESENT A LESSOR'S OBLIGATIONS OR THE GOVERNMENT'S RIGHTS AND ARE NOT NECESSARILY ITEMS TO BE CONSTRUCTED.

DEFINITIONS: Definitions are the same as those used in the Lease unless re-defined in these Security Requirements.

CRITICAL AREAS AND SYSTEMS- The areas that house systems that if damaged and/or compromised could have significant adverse consequences for the facility, operation of the facility, or mission of the agency or its occupants and visitors. These areas may also be referred to as "limited access areas," "restricted areas," or "exclusionary zones." Critical areas do not necessarily have to be within Government-controlled Space (e.g., generators, air handlers, electrical feeds, utilities, telecom closets or potable water supply that may be located outside Government-controlled Space).

DESIGN-BASIS THREAT – The Design-Basis Threat (DBT) is the profile and estimate of the threats to a Government facility across a range of specific undesirable events, and serves as the basis for determining appropriate security standards. The Lessor's technical consultant(s) shall work in conjunction with the Government, to apply the DBT to the post-award risk assessment. The risk assessment identifies recommended countermeasures and security design features that achieve the minimum baseline level of protection for a particular facility. The baseline level of protection may be further customized to address facility-specific conditions. The Lessor is responsible for providing countermeasure provisions outlined in this FSL document, as well as for additional items identified during the post-award risk assessment. Any additional countermeasures identified during this assessment shall be priced as BSAC.

(b) (7)(F) [redacted]

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

[redacted]

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

(b) (7)(F)

[redacted]

(b) (7)(F)

[redacted]

GENERAL CLAUSES
(Acquisition of Leasehold Interests in Real Property)

CATEGORY	CLAUSE NO.	48 CFR REF.	CLAUSE TITLE
GENERAL	1		SUBLETTING AND ASSIGNMENT
	2	552.270-11	SUCCESSORS BOUND
	3	552.270-23	SUBORDINATION, NON-DISTURBANCE AND ATTORNMENT
	4	552.270-24	STATEMENT OF LEASE
	5	552.270-25	SUBSTITUTION OF TENANT AGENCY
	6	552.270-26	NO WAIVER
	7		INTEGRATED AGREEMENT
	8	552.270-28	MUTUALITY OF OBLIGATION
PERFORMANCE	9		DELIVERY AND CONDITION
	10		DEFAULT BY LESSOR
	11	552.270-19	PROGRESSIVE OCCUPANCY
	12		MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT
	13		FIRE AND CASUALTY DAMAGE
	14		COMPLIANCE WITH APPLICABLE LAW
	15	552.270-12	ALTERATIONS
	16		ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY
PAYMENT	17	52.204-13	SYSTEM FOR AWARD MANAGEMENT MAINTENANCE
	18	552.270-31	PROMPT PAYMENT
	19	52.232-23	ASSIGNMENT OF CLAIMS
	20		PAYMENT
	21	52.232-33	PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT
STANDARDS OF CONDUCT	22	52.203-13	CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT
	23	552.270-32	COVENANT AGAINST CONTINGENT FEES
	24	52-203-7	ANTI-KICKBACK PROCEDURES
	25	52-223-6	DRUG-FREE WORKPLACE
	26	52.203-14	DISPLAY OF HOTLINE POSTER(S)
ADJUSTMENTS	27	552.270-30	PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY
	28	52.215-10	PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA
	29	552.270-13	PROPOSALS FOR ADJUSTMENT
	30		CHANGES
AUDITS	31	552.215-70	EXAMINATION OF RECORDS BY GSA
	32	52.215-2	AUDIT AND RECORDS—NEGOTIATION
DISPUTES	33	52.233-1	DISPUTES

LABOR STANDARDS	34	52.222-26	EQUAL OPPORTUNITY
	35	52.222-21	PROHIBITION OF SEGREGATED FACILITIES
	36	52.219-28	POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION
	37	52.222-35	EQUAL OPPORTUNITY FOR VETERANS
	38	52.222-36	EQUAL OPPORTUNITY FOR WORKERS WITH DISABILITIES
	39	52.222-37	EMPLOYMENT REPORTS ON VETERANS
SUBCONTRACTING	40	52.209-6	PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT
	41	52.215-12	SUBCONTRACTOR CERTIFIED COST OR PRICING DATA
	42	52.219-8	UTILIZATION OF SMALL BUSINESS CONCERNS
	43	52.219-9	SMALL BUSINESS SUBCONTRACTING PLAN
	44	52.219-16	LIQUIDATED DAMAGES—SUBCONTRACTING PLAN
	45	52.204-10	REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS
OTHER	46	52.204-25	PROHIBITION ON CONTRACTING FOR CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT
	47		INTENTIONALLY DELETED
	48	52.204-19	INCORPORATION BY REFERENCE OF REPRESENTATIONS AND CERTIFICATIONS

The information collection requirements contained in this solicitation/contract that are not required by regulation have been approved by the Office of Management and Budget (OMB) pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

GENERAL CLAUSES
(Acquisition of Leasehold Interests in Real Property)

1. SUBLETTING AND ASSIGNMENT (JAN 2011)

The Government may sublet any part of the premises but shall not be relieved from any obligations under this lease by reason of any such subletting. The Government may at any time assign this lease, and be relieved from all obligations to Lessor under this lease excepting only unpaid rent and other liabilities, if any, that have accrued to the date of said assignment. Any subletting or assignment shall be subject to prior written consent of Lessor, which shall not be unreasonably withheld.

2. 552.270-11 SUCCESSORS BOUND (SEP 1999)

This lease shall bind, and inure to the benefit of, the parties and their respective heirs, executors, administrators, successors, and assigns.

3. 552.270-23 SUBORDINATION, NON-DISTURBANCE AND ATTORNMENT (SEP 1999)

(a) Lessor warrants that it holds such title to or other interest in the premises and other property as is necessary to the Government's access to the premises and full use and enjoyment thereof in accordance with the provisions of this lease. Government agrees, in consideration of the warranties and conditions set forth in this clause, that this lease is subject and subordinate to any and all recorded mortgages, deeds of trust and other liens now or hereafter existing or imposed upon the premises, and to any renewal, modification or extension thereof. It is the intention of the parties that this provision shall be self-operative and that no further instrument shall be required to effect the present or subsequent subordination of this lease. Government agrees, however, within twenty (20) business days next following the Contracting Officer's receipt of a written demand, to execute such instruments as Lessor may reasonably request to evidence further the subordination of this lease to any existing or future mortgage, deed of trust or other security interest pertaining to the premises, and to any water, sewer or access easement necessary or desirable to serve the premises or adjoining property owned in whole or in part by Lessor if such easement does not interfere with the full enjoyment of any right granted the Government under this lease.

(b) No such subordination, to either existing or future mortgages, deeds of trust or other lien or security instrument shall operate to affect adversely any right of the Government under this lease so long as the Government is not in default under this lease. Lessor will include in any future mortgage, deed of trust or other security instrument to which this lease becomes subordinate, or in a separate non-disturbance agreement, a provision to the foregoing effect. Lessor warrants that the holders of all notes or other obligations secured by existing mortgages, deeds of trust or other security instruments have consented to the provisions of this clause, and agrees to provide true copies of all such consents to the Contracting Officer promptly upon demand.

(c) In the event of any sale of the premises or any portion thereof by foreclosure of the lien of any such mortgage, deed of trust or other security instrument, or the giving of a deed in lieu of foreclosure, the Government will be deemed to have attorned to any purchaser, purchasers, transferee or transferees of the premises or any portion thereof and its or their successors and assigns, and any such purchasers and transferees will be deemed to have assumed all obligations of the Lessor under this lease, so as to establish direct privity of estate and contract between Government and such purchasers or transferees, with the same force, effect and relative priority in time and right as if the lease had initially been entered into between such purchasers or transferees and the Government; provided, further, that the Contracting Officer and such purchasers or transferees shall, with reasonable promptness following any such sale or deed delivery in lieu of foreclosure, execute all such revisions to this lease, or other writings, as shall be necessary to document the foregoing relationship.

(d) None of the foregoing provisions may be deemed or construed to imply a waiver of the Government's rights as a sovereign.

4. 552.270-24 STATEMENT OF LEASE (SEP 1999)

(a) The Contracting Officer will, within thirty (30) days next following the Contracting Officer's receipt of a joint written request from Lessor and a prospective lender or purchaser of the building, execute and deliver to Lessor a letter stating that the same is issued subject to the conditions stated in this clause and, if such is the case, that (1) the lease is in full force and effect; (2) the date to which the rent and other charges have been paid in advance, if any; and (3) whether any notice of default has been issued.

(b) Letters issued pursuant to this clause are subject to the following conditions:

(1) That they are based solely upon a reasonably diligent review of the Contracting Officer's lease file as of the date of issuance;

(2) That the Government shall not be held liable because of any defect in or condition of the premises or building;

(3) That the Contracting Officer does not warrant or represent that the premises or building comply with applicable Federal, State and local law; and

(4) That the Lessor, and each prospective lender and purchaser are deemed to have constructive notice of such facts as would be ascertainable by reasonable pre-purchase and pre-commitment inspection of the Premises and Building and by inquiry to appropriate Federal, State and local Government officials.

5. 552.270-25 SUBSTITUTION OF TENANT AGENCY (SEP 1999)

The Government may, at any time and from time to time, substitute any Government agency or agencies for the Government agency or agencies, if any, named in the lease.

6. 552.270-26 NO WAIVER (SEP 1999)

No failure by either party to insist upon the strict performance of any provision of this lease or to exercise any right or remedy consequent upon a breach thereof, and no acceptance of full or partial rent or other performance by either party during the continuance of any such breach shall constitute a waiver of any such breach of such provision.

7. INTEGRATED AGREEMENT (JUN 2012)

This Lease, upon execution, contains the entire agreement of the parties and no prior written or oral agreement, express or implied, shall be admissible to contradict the provisions of the Lease. Except as expressly attached to and made a part of the Lease, neither the Request for Lease Proposals nor any pre-award communications by either party shall be incorporated in the Lease.

8. 552.270-28 MUTUALITY OF OBLIGATION (SEP 1999)

The obligations and covenants of the Lessor, and the Government's obligation to pay rent and other Government obligations and covenants, arising under or related to this Lease, are interdependent. The Government may, upon issuance of and delivery to Lessor of a final decision asserting a claim against Lessor, set off such claim, in whole or in part, as against any payment or payments then or thereafter due the Lessor under this lease. No setoff pursuant to this clause shall constitute a breach by the Government of this lease.

9. DELIVERY AND CONDITION (JAN 2011)

(a) Unless the Government elects to have the space occupied in increments, the space must be delivered ready for occupancy as a complete unit.

(b) The Government may elect to accept the Space notwithstanding the Lessor's failure to deliver the Space substantially complete; if the Government so elects, it may reduce the rent payments.

10. DEFAULT BY LESSOR (APR 2012)

(a) The following conditions shall constitute default by the Lessor, and shall give rise to the following rights and remedies for the Government:

(1) Prior to Acceptance of the Premises. Failure by the Lessor to diligently perform all obligations required for Acceptance of the Space within the times specified, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may terminate the Lease on account of the Lessor's default.

(2) After Acceptance of the Premises. Failure by the Lessor to perform any service, to provide any item, or satisfy any requirement of this Lease, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may perform the service, provide the item, or obtain satisfaction of the requirement by its own employees or contractors. If the Government elects to take such action, the Government may deduct from rental payments its costs incurred in connection with taking the action. Alternatively, the Government may reduce the rent by an amount reasonably calculated to approximate the cost or value of the service not performed, item not provided, or requirement not satisfied, such reduction effective as of the date of the commencement of the default condition.

(3) Grounds for Termination. The Government may terminate the Lease if:

(i) The Lessor's default persists notwithstanding provision of notice and reasonable opportunity to cure by the Government, or

(ii) The Lessor fails to take such actions as are necessary to prevent the recurrence of default conditions,

and such conditions (i) or (ii) substantially impair the safe and healthful occupancy of the Premises, or render the Space unusable for its intended purposes.

(4) Excuse. Failure by the Lessor to timely deliver the Space or perform any service, provide any item, or satisfy any requirement of this Lease shall not be excused if its failure in performance arises from:

(i) Circumstances within the Lessor's control;

(ii) Circumstances about which the Lessor had actual or constructive knowledge prior to the Lease Award Date that could reasonably be expected to affect the Lessor's capability to perform, regardless of the Government's knowledge of such matters;

(iii) The condition of the Property;

(iv) The acts or omissions of the Lessor, its employees, agents or contractors; or

(v) The Lessor's inability to obtain sufficient financial resources to perform its obligations.

(5) The rights and remedies specified in this clause are in addition to any and all remedies to which the Government may be entitled as a matter of law.

11. 552.270-19 PROGRESSIVE OCCUPANCY (SEP 1999)

The Government shall have the right to elect to occupy the space in partial increments prior to the substantial completion of the entire leased premises, and the Lessor agrees to schedule its work so as to deliver the space incrementally as elected by the Government. The Government shall pay rent commencing with the first business day following substantial completion of the entire leased premise unless the Government has elected to occupy the leased premises incrementally. In case of incremental occupancy, the Government shall pay rent pro rata upon the first business day following substantial

completion of each incremental unit. Rental payments shall become due on the first workday of the month following the month in which an increment of space is substantially complete, except that should an increment of space be substantially completed after the fifteenth day of the month, the payment due date will be the first workday of the second month following the month in which it was substantially complete. The commencement date of the firm lease term will be a composite determined from all rent commencement dates.

12. MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT (APR 2015)

The Lessor shall maintain the Property, including the building, building systems, and all equipment, fixtures, and appurtenances furnished by the Lessor under this Lease, in good repair and tenantable condition so that they are suitable in appearance and capable of supplying such heat, air conditioning, light, ventilation, safety systems, access and other things to the premises, without reasonably preventable or recurring disruption, as is required for the Government's access to, occupancy, possession, use and enjoyment of the premises as provided in this lease. For the purpose of so maintaining the premises, the Lessor may at reasonable times enter the premises with the approval of the authorized Government representative in charge. Upon request of the Lease Contracting Officer (LCO), the Lessor shall provide written documentation that building systems have been properly maintained, tested, and are operational within manufacturer's warranted operating standards. The Lessor shall maintain the Premises in a safe and healthful condition according to applicable OSHA standards and all other requirements of this Lease, including standards governing indoor air quality, existence of mold and other biological hazards, presence of hazardous materials, etc. The Government shall have the right, at any time after the Lease Award Date and during the term of the Lease, to inspect all areas of the Property to which access is necessary for the purpose of determining the Lessor's compliance with this clause.

13. FIRE AND CASUALTY DAMAGE (JUN 2016)

If the building in which the Premises are located is totally destroyed or damaged by fire or other casualty, this Lease shall immediately terminate. If the building in which the Premises are located are only partially destroyed or damaged, so as to render the Premises untenantable, or not usable for their intended purpose, the Lessor shall have the option to elect to repair and restore the Premises or terminate the Lease. The Lessor shall be permitted a reasonable amount of time, not to exceed **270 days** from the event of destruction or damage, to repair or restore the Premises, provided that the Lessor submits to the Government a reasonable schedule for repair of the Premises within **60 days** of the event of destruction or damage. If the Lessor fails to timely submit a reasonable schedule for completing the work, the Government may elect to terminate the Lease effective as of the date of the event of destruction or damage. If the Lessor elects to repair or restore the Premises, but fails to repair or restore the Premises within **270 days** from the event of destruction or damage, or fails to diligently pursue such repairs or restoration so as to render timely completion commercially impracticable, the Government may terminate the Lease effective as of the date of the destruction or damage. During the time that the Premises are unoccupied, rent shall be abated. Termination of the Lease by either party under this clause shall not give rise to liability for either party.

Nothing in this lease shall be construed as relieving Lessor from liability for damage to, or destruction of, property of the United States of America caused by the willful or negligent act or omission of Lessor.

14. COMPLIANCE WITH APPLICABLE LAW (JAN 2011)

Lessor shall comply with all Federal, state and local laws applicable to its ownership and leasing of the Property, including, without limitation, laws applicable to the construction, ownership, alteration or operation of all buildings, structures, and facilities located thereon, and obtain all necessary permits, licenses and similar items at its own expense. The Government will comply with all Federal, State and local laws applicable to and enforceable against it as a tenant under this lease, provided that nothing in this Lease shall be construed as a waiver of the sovereign immunity of the Government. This Lease shall be governed by Federal law.

15. 552.270-12 ALTERATIONS (SEP 1999)

The Government shall have the right during the existence of this lease to make alterations, attach fixtures, and erect structures or signs in or upon the premises hereby leased, which fixtures, additions or structures so placed in, on, upon, or attached to the said premises shall be and remain the property of the Government and may be removed or otherwise disposed of by the Government. If the lease contemplates that the Government is the sole occupant of the building, for

purposes of this clause, the leased premises include the land on which the building is sited and the building itself. Otherwise, the Government shall have the right to tie into or make any physical connection with any structure located on the property as is reasonably necessary for appropriate utilization of the leased space.

16. ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (APR 2015)

(a) Ten (10) working days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of building shell and TIs conforming to this Lease and the approved DIDs is substantially complete, and a Certificate of Occupancy has been issued as set forth below.

(b) The Space shall be considered substantially complete only if the Space may be used for its intended purpose and completion of remaining work will not unreasonably interfere with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punchlist generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.

(c) The Lessor shall provide a valid Certificate of Occupancy, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue Certificates of Occupancy or if the Certificate of Occupancy is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates that the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease to ensure an acceptable level of safety is provided. Under such circumstances, the Government shall only accept the Space without a Certificate of Occupancy if a licensed fire protection engineer determines that the offered space is compliant with all applicable local codes and ordinances and fire protection and life safety-related requirements of this Lease.

17. 52.204-13 SYSTEM FOR AWARD MANAGEMENT MAINTENANCE (OCT 2018)

This clause is incorporated by reference.

18. 552.270-31 PROMPT PAYMENT (JUN 2011)

The Government will make payments under the terms and conditions specified in this clause. Payment shall be considered as being made on the day a check is dated or an electronic funds transfer is made. All days referred to in this clause are calendar days, unless otherwise specified.

(a) *Payment due date—*

(1) *Rental payments.* Rent shall be paid monthly in arrears and will be due on the first workday of each month, and only as provided for by the lease.

(i) When the date for commencement of rent falls on the 15th day of the month or earlier, the initial monthly rental payment under this contract shall become due on the first workday of the month following the month in which the commencement of the rent is effective.

(ii) When the date for commencement of rent falls after the 15th day of the month, the initial monthly rental payment under this contract shall become due on the first workday of the second month following the month in which the commencement of the rent is effective.

(2) *Other payments.* The due date for making payments other than rent shall be the later of the following two events:

(i) The 30th day after the designated billing office has received a proper invoice from the Contractor.

(ii) The 30th day after Government acceptance of the work or service. However, if the designated billing office fails to annotate the invoice with the actual date of receipt, the invoice payment due date shall be deemed to be the 30th day after the Contractor's invoice is dated, provided a proper invoice is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(b) *Invoice and inspection requirements for payments other than rent.*

(1) The Contractor shall prepare and submit an invoice to the designated billing office after completion of the work. A proper invoice shall include the following items:

(i) Name and address of the Contractor.

(ii) Invoice date.

(iii) Lease number.

(iv) Government's order number or other authorization.

(v) Description, price, and quantity of work or services delivered.

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the remittance address in the lease or the order).

(vii) Name (where practicable), title, phone number, and mailing address of person to be notified in the event of a defective invoice.

(2) The Government will inspect and determine the acceptability of the work performed or services delivered within seven days after the receipt of a proper invoice or notification of completion of the work or services unless a different period is specified at the time the order is placed. If actual acceptance occurs later, for the purpose of determining the payment due date and calculation of interest, acceptance will be deemed to occur on the last day of the seven day inspection period. If the work or service is rejected for failure to conform to the technical requirements of the contract, the seven days will be counted beginning with receipt of a new invoice or notification. In either case, the Contractor is not entitled to any payment or interest unless actual acceptance by the Government occurs.

(c) *Interest Penalty.*

(1) An interest penalty shall be paid automatically by the Government, without request from the Contractor, if payment is not made by the due date.

(2) The interest penalty shall be at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) that is in effect on the day after the due date. This rate is referred to as the ''Renegotiation Board Interest Rate,'' and it is published in the **Federal Register** semiannually on or about January 1 and July 1. The interest penalty shall accrue daily on the payment amount approved by the Government and be compounded in 30-day increments inclusive from the first day after the due date through the payment date.

(3) Interest penalties will not continue to accrue after the filing of a claim for such penalties under the clause at 52.233–1, Disputes, or for more than one year. Interest penalties of less than $1.00 need not be paid.

(4) Interest penalties are not required on payment delays due to disagreement between the Government and Contractor over the payment amount or other issues involving contract compliance or on amounts temporarily withheld or retained in accordance with the terms of the contract. Claims involving disputes, and any interest that may be payable, will be resolved in accordance with the clause at 52.233-1, Disputes.

(d) *Overpayments.* If the Lessor becomes aware of a duplicate payment or that the Government has otherwise overpaid on a payment, the Contractor shall—

(1) Return the overpayment amount to the payment office cited in the contract along with a description of the overpayment including the—

(i) Circumstances of the overpayment (*e.g.,* duplicate payment, erroneous payment, liquidation errors, date(s) of overpayment);

(ii) Affected lease number; (iii) Affected lease line item or sub-line item, if applicable; and

(iii) Lessor point of contact.

(2) Provide a copy of the remittance and supporting documentation to the Contracting Officer.

19. 52.232-23 ASSIGNMENT OF CLAIMS (MAY 2014)

(Applicable to leases over the micro-purchase threshold.)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 6305 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

20. PAYMENT (MAY 2011)

(a) When space is offered and accepted, the amount of American National Standards Institute/Building Owners and Managers Association Office Area (ABOA) square footage delivered will be confirmed by:

(1) The Government's measurement of plans submitted by the successful Offeror as approved by the Government, and an inspection of the space to verify that the delivered space is in conformance with such plans or

(2) A mutual on-site measurement of the space, if the Contracting Officer determines that it is necessary.

(b) Payment will not be made for space which is in excess of the amount of ABOA square footage stated in the lease.

(c) If it is determined that the amount of ABOA square footage actually delivered is less than the amount agreed to in the lease, the lease will be modified to reflect the amount of ABOA space delivered and the annual rental will be adjusted as follows:

ABOA square feet not delivered multiplied by one plus the common area factor (CAF), multiplied by the rate per rentable square foot (RSF). That is: (1+CAF) x Rate per RSF = Reduction in Annual Rent

21. 52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT (OCT 2018)

This clause is incorporated by reference.

22. 52.203-13 Contractor Code of Business Ethics and Conduct (JUN 2020)

(Applicable to leases over $5.5 million total contract value and performance period is 120 days or more.)

This clause is incorporated by reference.

23. 552.270-32 COVENANT AGAINST CONTINGENT FEES (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover the full amount of the contingent fee.

(b) *Bona fide agency,* as used in this clause, means an established commercial or selling agency (including licensed real estate agents or brokers), maintained by a Contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

(1) Bona fide employee, as used in this clause, means a person, employed by a Contractor and subject to the Contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

(2) Contingent fee, as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

(3) Improper influence, as used in this clause, means any influence that induces or tends to induce a *Government* employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

24. 52.203-7 ANTI-KICKBACK PROCEDURES (JUN 2020)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

This clause is incorporated by reference.

25. 52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(Applicable to leases over the Simplified Lease Acquisition Threshold, as well as to leases of any value awarded to an individual.)

This clause is incorporated by reference.

26. 52.203-14 DISPLAY OF HOTLINE POSTER(S) (JUN 2020)

(Applicable to leases over $5.5 Million total contract value and performance period is 120 days or more.)

(a) *Definition.*

United States, as used in this clause, means the 50 States, the District of Columbia, and outlying areas.

(b) *Display of fraud hotline poster(s).* Except as provided in paragraph (c)—

(1) During contract performance in the United States, the Contractor shall prominently display in common work areas within business segments performing work under this contract and at contract work sites-

(i) Any agency fraud hotline poster or Department of Homeland Security (DHS) fraud hotline poster identified in paragraph (b)(3) of this clause; and

(ii) Any DHS fraud hotline poster subsequently identified by the Contracting Officer.

(2) Additionally, if the Contractor maintains a company website as a method of providing information to employees, the Contractor shall display an electronic version of the poster(s) at the website.

(3) Any required posters may be obtained as follows:

Poster(s)	***Obtain from***
_____	_____
_____	_____

(*Contracting Officer shall insert—*

(i) Appropriate agency name(s) and/or title of applicable Department of Homeland Security fraud hotline poster); and

(ii) The website(s) or other contact information for obtaining the poster(s).)

(c) If the Contractor has implemented a business ethics and conduct awareness program, including a reporting mechanism, such as a hotline poster, then the Contractor need not display any agency fraud hotline posters as required in paragraph (b) of this clause, other than any required DHS posters.

(d) *Subcontracts.* The Contractor shall include the substance of this clause, including this paragraph (d), in all subcontracts that exceed the threshold specified in Federal Acquisition Regulation 3.1004(b)(1) on the date of subcontract award, except when the subcontract—

(1) Is for the acquisition of a commercial item; or

(2) Is performed entirely outside the United States.

27. 552.270-30 PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

(a) If the head of the contracting activity (HCA) or his or her designee determines that there was a violation of subsection 27(a) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in the Federal Acquisition Regulation, the Government, at its election, may—

(1) Reduce the monthly rental under this lease by five percent of the amount of the rental for each month of the remaining term of the lease, including any option periods, and recover five percent of the rental already paid;

(2) Reduce payments for alterations not included in monthly rental payments by five percent of the amount of the alterations agreement; or

(3) Reduce the payments for violations by a Lessor's subcontractor by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was placed.

(b) Prior to making a determination as set forth above, the HCA or designee shall provide to the Lessor a written notice of the action being considered and the basis thereof. The Lessor shall have a period determined by the agency head or designee, but not less than 30 calendar days after receipt of such notice, to submit in person, in writing, or through a representative, information and argument in opposition to the proposed reduction. The agency head or designee may, upon good cause shown, determine to deduct less than the above amounts from payments.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this lease.

28. 52.215-10 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA (AUG 2011)

(Applicable when cost or pricing data are required for work or services over $750,000.)
This clause is incorporated by reference.

29. 552.270-13 PROPOSALS FOR ADJUSTMENT (OCT 2016)

This clause is incorporated by reference.

30. CHANGES (MAR 2013)

(a) The LCO may at any time, by written order, direct changes to the Tenant Improvements within the Space, Building Security Requirements, or the services required under the Lease.

(b) If any such change causes an increase or decrease in Lessor's costs or time required for performance of its obligations under this Lease, whether or not changed by the order, the Lessor shall be entitled to an amendment to the Lease providing for one or more of the following:

(1) An adjustment of the delivery date;

(2) An equitable adjustment in the rental rate;

(3) A lump sum equitable adjustment; or

(4) A change to the operating cost base, if applicable.

(c) The Lessor shall assert its right to an amendment under this clause within 30 days from the date of receipt of the change order and shall submit a proposal for adjustment. Failure to agree to any adjustment shall be a dispute under the Disputes clause. However, the pendency of an adjustment or existence of a dispute shall not excuse the Lessor from proceeding with the change as directed.

(d) Absent a written change order from the LCO, or from a Government official to whom the LCO has explicitly and in writing delegated the authority to direct changes, the Government shall not be liable to Lessor under this clause.

31. 552.215-70 EXAMINATION OF RECORDS BY GSA (JUN 2016)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)
This clause is incorporated by reference.

32. 52.215-2 AUDIT AND RECORDS—NEGOTIATION (JUN 2020)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)
This clause is incorporated by reference.

33. 52.233-1 DISPUTES (MAY 2014)

This clause is incorporated by reference.

34. 52.222-26 EQUAL OPPORTUNITY (SEP 2016)

This clause is incorporated by reference.

35. 52.222-21 PROHIBITION OF SEGREGATED FACILITIES (APR 2015)

This clause is incorporated by reference.

36. 52.219-28 POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION (SEP 2021)

(Applicable to leases exceeding the micro-purchase threshold.)
This clause is incorporated by reference.

37. 52.222-35 EQUAL OPPORTUNITY FOR VETERANS (JUN 2020)

(Applicable to leases $150,000 or more, total contract value.)

(a) *Definitions*. As used in this clause-

"Active duty wartime or campaign badge veteran," "Armed Forces service medal veteran," "disabled veteran," "protected veteran," "qualified disabled veteran," and "recently separated veteran" have the meanings given at Federal Acquisition Regulation (FAR) 22.1301.

(b) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-300.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified protected veterans, and requires affirmative action by the Contractor to employ and advance in employment qualified protected veterans.

(c) Subcontracts. The Contractor shall insert the terms of this clause in subcontracts valued at or above the threshold specified in FAR 22.1303(a) on the date of subcontract award, unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

38. 52.222-36 EQUAL OPPORTUNITY FOR WORKERS WITH DISABILITIES (JUN 2020)

(Applicable to leases over $15,000 total contract value.)

(a) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-741.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified individuals on the basis of disability, and requires affirmative action by the Contractor to employ and advance in employment qualified individuals with disabilities.

(b) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of the threshold specified in Federal Acquisition Regulation (FAR) 22.1408(a) on the date of subcontract award, unless exempted by rules, regulations, or orders of the Secretary, so that such provisions will be binding upon each subcontractor or vendor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs of the U.S. Department of Labor, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

39. 52.222-37 EMPLOYMENT REPORTS ON VETERANS (JUN 2020)

(Applicable to leases $150,000 or more, total contract value.)
This clause is incorporated by reference.

40. 52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JUN 2020)

(Applicable to leases over $35,000 total contract value.)

This clause is incorporated by reference.

41. 52.215-12 SUBCONTRACTOR CERTIFIED COST OR PRICING DATA (JUN 2020)

(Applicable if over $750,000 total contract value.)

This clause is incorporated by reference.

42. 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2018)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)
This clause is incorporated by reference.

43. 52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (SEP 2021) ALTERNATE III (JUN 2020)

(Applicable to leases over $750,000 total contract value.)
This clause is incorporated by reference.

44. 52.219-16 LIQUIDATED DAMAGES—SUBCONTRACTING PLAN (SEP 2021)

(Applicable to leases over $750,000 total contract value.)
This clause is incorporated by reference.

45. 52.204-10 REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS (JUN 2020)

(Applicable if over $30,000 total contract value.)
This clause is incorporated by reference.

46. 52.204-25 PROHIBITION ON CONTRACTING FOR CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT (AUG 2020)

(a) *Definitions.* As used in this clause—

Backhaul means intermediate links between the core network, or backbone network, and the small subnetworks at the edge of the network (*e.g.*, connecting cell phones/towers to the core telephone network). Backhaul can be wireless (e.g., microwave) or wired (*e.g.*, fiber optic, coaxial cable, Ethernet).

Covered foreign country means The People's Republic of China.

Covered telecommunications equipment or services means–

(1) Telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities);

(2) For the purpose of public safety, security of Government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities);

(3) Telecommunications or video surveillance services provided by such entities or using such equipment; or

(4) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country.

Critical technology means–

(1) Defense articles or defense services included on the United States Munitions List set forth in the International Traffic in Arms Regulations under subchapter M of chapter I of title 22, Code of Federal Regulations;

(2) Items included on the Commerce Control List set forth in Supplement No. 1 to part 774 of the Export Administration Regulations under subchapter C of chapter VII of title 15, Code of Federal Regulations, and controlled-

(i) Pursuant to multilateral regimes, including for reasons relating to national security, chemical and biological weapons proliferation, nuclear nonproliferation, or missile technology; or

(ii) For reasons relating to regional stability or surreptitious listening;

(3) Specially designed and prepared nuclear equipment, parts and components, materials, software, and technology covered by part 810 of title 10, Code of Federal Regulations (relating to assistance to foreign atomic energy activities);

(4) Nuclear facilities, equipment, and material covered by part 110 of title 10, Code of Federal Regulations (relating to export and import of nuclear equipment and material);

(5) Select agents and toxins covered by part 331 of title 7, Code of Federal Regulations, part 121 of title 9 of such Code, or part 73 of title 42 of such Code; or

(6) Emerging and foundational technologies controlled pursuant to section 1758 of the Export Control Reform Act of 2018 (50 U.S.C. 4817).

Interconnection arrangements means arrangements governing the physical connection of two or more networks to allow the use of another's network to hand off traffic where it is ultimately delivered (*e.g.*, connection of a customer of telephone provider A to a customer of telephone company B) or sharing data and other information resources.

Reasonable inquiry means an inquiry designed to uncover any information in the entity's possession about the identity of the producer or provider of covered telecommunications equipment or services used by the entity that excludes the need to include an internal or third-party audit.

Roaming means cellular communications services (*e.g.*, voice, video, data) received from a visited network when unable to connect to the facilities of the home network either because signal coverage is too weak or because traffic is too high.

Substantial or essential component means any component necessary for the proper function or performance of a piece of equipment, system, or service.

(b) *Prohibition*. (1) Section 889(a)(1)(A) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2019, from procuring or obtaining, or extending or renewing a contract to procure or obtain, any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. The Contractor is prohibited from providing to the Government any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless an exception at paragraph (c) of this clause applies or the covered telecommunication equipment or services are covered by a waiver described in FAR 4.2104.

(2) Section 889(a)(1)(B) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2020, from entering into a contract, or extending or renewing a contract, with an entity that uses any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless an exception at paragraph (c) of this clause applies or the covered telecommunication equipment or services are covered by a waiver described in FAR 4.2104. This prohibition applies to the use of covered telecommunications equipment or services, regardless of whether that use is in performance of work under a Federal contract.

(c) *Exceptions.* This clause does not prohibit contractors from providing—

(1) A service that connects to the facilities of a third-party, such as backhaul, roaming, or interconnection arrangements; or

(2) Telecommunications equipment that cannot route or redirect user data traffic or permit visibility into any user data or packets that such equipment transmits or otherwise handles.

(d) Reporting requirement. (1) In the event the Contractor identifies covered telecommunications equipment or services used as a substantial or essential component of any system, or as critical technology as part of any system, during contract performance, or the Contractor is notified of such by a subcontractor at any tier or by any other source, the Contractor shall report the information in paragraph (d)(2) of this clause to the Contracting Officer, unless elsewhere in this contract are established procedures for reporting the information; in the case of the Department of Defense, the Contractor shall report to the website at https://dibnet.dod.mil. For indefinite delivery contracts, the Contractor shall report to the Contracting Officer for the indefinite delivery contract and the Contracting Officer(s) for any affected order or, in the case of the Department of Defense, identify both the indefinite delivery contract and any affected orders in the report provided at https://dibnet.dod.mil.

(2) The Contractor shall report the following information pursuant to paragraph (d)(1) of this clause

(i) Within one business day from the date of such identification or notification: the contract number; the order number(s), if applicable; supplier name; supplier unique entity identifier (if known); supplier Commercial and Government Entity (CAGE) code (if known); brand; model number (original equipment manufacturer number, manufacturer part number, or wholesaler number); item description; and any readily available information about mitigation actions undertaken or recommended.

(ii) Within 10 business days of submitting the information in paragraph (d)(2)(i) of this clause: any further available information about mitigation actions undertaken or recommended. In addition, the Contractor shall describe the efforts it undertook to prevent use or submission of covered telecommunications equipment or services, and any additional efforts that will be incorporated to prevent future use or submission of covered telecommunications equipment or services.

(e) *Subcontracts.* The Contractor shall insert the substance of this clause, including this paragraph (e) and excluding paragraph (b)(2), in all subcontracts and other contractual instruments, including subcontracts for the acquisition of commercial items.

47. *INTENTIONALLY DELETED*

48. 52.204-19 INCORPORATION BY REFERENCE OF REPRESENTATIONS AND CERTIFICATIONS (DEC 2014)

This clause is incorporated by reference.

[*TERRENO V STREET, LLC*]
INDIVIDUAL SMALL BUSINESS SUBCONTRACTING PLAN

I. IDENTIFICATION DATA:

Address: 3035 V Street, NE, Washington, DC 20018

Date Prepared: 2/15/2022
Description of Lease: Warehouse Lease, 27,100 RSF
Request for Lease Proposal Number: 8DC2652
Lease Number: NA

II. LEASE PERIODS AND ESTIMATED LEASE DOLLAR VALUE

Firm Term: Ten (10) Years
Non-Firm Term: _____
Option: _One Five (5) Year Option_

Total Estimated Lease Value - $9,270,910.00
Firm Term (b) (4)
Non-Firm Term: $ _____
Option Period : (b) (4)

Place of Performance: 3035 V Street, NE, Washington, DC 20018

DUNS Number: (b) (4)

III. GOALS:

Terreno V Street, LLC provides the following separate dollar and percentage goals, which are a percentage of the total subcontracting dollars for each business category:

Firm Term (expressed in dollars and percentages of the total dollars planned to be subcontracted) **Years 1 - 10**		
PLANNED SUBCONTRACTING TO:	**DOLLARS**	**PERCENT**
1. Total Dollars to be Subcontracted ***(2 + 3 = 1) large and all small businesses must equal total amount to be subcontracted (both $ and %)***	(b) (4)	
2. Large Businesses (Other than Small)		
3. All Small Businesses (including ANCs & Indian tribes)		

4. Veteran-Owned Small Businesses (VOSB)[1]	(b) (4)	
5. Service-Disabled Veteran-Owned Small Businesses (SDVOSB)		
6. HUBZone Small Business (HUBZone)		
7. Small Disadvantaged Businesses (SDB) (including ANCs & Indian tribes)		
8. Women-Owned Small Businesses (WOSB)		

If applicable:

Non-Firm Term (expressed in dollars and percentages of total dollars planned to be subcontracted) **Years X – X**		
PLANNED SUBCONTRACTING TO:	**DOLLARS**	**PERCENT**
1. Total Dollars to be Subcontracted ***(2 + 3 = 1) large and all small businesses must equal total amount to be subcontracted (both $ and %)***	(b) (4)	
2. Large Businesses (Other than Small)		
3. All Small Businesses (including ANCs & Indian tribes)		
4. Veteran-Owned Small Businesses (VOSB)		
5. Service-Disabled Veteran-Owned Small Businesses (SDVOSB)		
6. HUBZone Small Business (HUBZone)		
7. Small Disadvantaged Businesses (SDB) (including ANCs & Indian tribes)		
8. Women-Owned Small Businesses (WOSB)		

If applicable (for each option):

Option (expressed in dollars and percentages of total dollars planned to be subcontracted)		
PLANNED SUBCONTRACTING TO:	**DOLLARS**	**PERCENT**
1. Total Dollars to be Subcontracted ***(2 + 3 = 1) large and all small businesses must equal total amount to be subcontracted (both $ and %)***	(b) (4)	
2. Large Businesses (Other than Small)		
3. All Small Businesses (including ANCs & Indian tribes)		
4. Veteran-Owned Small Businesses (VOSB)		
5. Service-Disabled Veteran-Owned Small Businesses (SDVOSB)		
6. HUBZone Small Business (HUBZone)		
7. Small Disadvantaged Businesses (SDB) (including ANCs & Indian tribes)		
8. Women-Owned Small Businesses (WOSB)		

[1] Items 4 through 8 stand on their own. They do not equate to the small business total. Refer to "How to do the math" tips in the instructions.

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Total (Firm term + Non-firm Term + Option(s)):

TOTAL LEASE GOALS (expressed in dollars and percentages of total dollars planned to be subcontracted)		
PLANNED SUBCONTRACTING TO:	**DOLLARS**	**PERCENT**
1. Total Dollars to be Subcontracted ***(2 + 3 = 1) large and all small businesses must equal total amount to be subcontracted (both $ and %)***	(b) (4)	
2. Large Businesses (Other than Small)		
3. All Small Businesses (including ANCs & Indian tribes)		
4. Veteran-Owned Small Businesses (VOSB)		
5. Service-Disabled Veteran-Owned Small Businesses (SDVOSB)		
6. HUBZone Small Business (HUBZone)		
7. Small Disadvantaged Businesses (SDB) (including ANCs & Indian tribes)		
8. Women-Owned Small Businesses (WOSB)		

IV. PRINCIPAL TYPES OF SUPPLIES AND SERVICES TO BE SUBCONTRACTED:

The principal types of supplies and/or services that Terreno V Street, LLC anticipates to be subcontracted and the identification of the type of business concern planned are as follows.

Business Category or Size

Construction

Supplies/Services	Large	Small	VOSB	SDVOSB	HUBZone	SDB	WOSB
Painting NAICS 238230		X	X	X		X	X
Electrical NAICS 238210	X	X					
Carpentry NAICS 238350		X	X	X		X	
Flooring NAICS 238330	X	X			X	X	X
Mechanical NAICS 238220	X	X	X		X		

Business Category or Size
Recurring Services

Supplies/Services	Large	Small	VOSB	SDVOSB	HUBZone	SDB	WOSB
Snow Removal NAICS 561790		X	X	X		X	
HVAC Repairs NAICS 238220	X	X	X				
Landscaping/Parking Lot Maintenance NAICS 561730		X		X	X		X
Alarm Monitoring NAICS 561621	X	X	X				X
Handicapped Lift Maintenance NAICS 238990	X	X				X	

Business Category or Size
Other Subcontracted Supplies and/or Services

Supplies/Services	Large	Small	VOSB	SDVOSB	HUBZone	SDB	WOSB
NA							

V. DESCRIPTION OF METHOD USED TO DEVELOP SUBCONTRACTING GOALS:

Terreno V Street, LLC used the following method to develop the subcontracting goals:

Based on management of the entire warehouse complex on V Street owner by Terreno, Terreno and its management company have substantial market information and relationships with local businesses serving the warehouses it owns. From prior dealings, Terreno is able to identify subcontracting opportunities to be competed among the available contractors. SDVOSB's and Hubzone companies received the smallest goal allocations because there are not a significant pool of available contractors in these categories available in the trade and services to be procured under the applicable lease.

VI. DESCRIPTION OF METHOD USED TO IDENTIFY POTENTIAL SOURCES:

Terreno V Street, LLC identifies potential subcontractors using the following source lists and organizations:
Potential sources for solicitation purposes are maintained by our management company in a list identifying sources and classification of the business types available. Additionally, we can access the System for Award Management (SAM), veterans service organizations, the National Minority Purchasing Council Vendor Information Service, the Research and Information Division of the Minority Business Development Agency in the Department of Commerce, or small, HUBZone, small disadvantaged, and women-owned small business trade associations in the DC area.

VII. INCLUSION OF INDIRECT COSTS IN ESTABLISHING GOALS:

Indirect costs _____HAVE BEEN (or) __X___HAVE NOT BEEN included in the dollar and percentage subcontracting goals stated above.

If indirect costs HAVE been included[2], the method used to determine the proportionate share of indirect costs to be incurred with small business concerns was as follows:

_____

_____

_____

VIII. PROGRAM ADMINISTRATOR:

Name: Loraine Johnson
Title/Position: Senior Property Manager
Address: 7600 Tysons One Place, Suite 600
City/State/Zip Code: McLean, VA 22102
Telephone number: 301-577-1874
Email Address (b) (6) [redacted] @transwestern.com

Alternate POC with contact information: (b) (6) [redacted]

Duties: FAR clause 52.219-9(e) requires the contractor to perform the following functions in order to effectively implement this plan to the extent, consistent with efficient contract performance:

[2] Including indirect costs may be beneficial to avoid "0" dollar goals. If indirect costs are included in the goals, these costs must be included in the Standard Form 294 report submitted after award.

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

1. Assist SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns by arranging solicitations, time for the preparation of bids, quantities, specifications, and delivery schedules so as to facilitate the participation by such concerns. Where the Contractor's lists of potential SB, VOSB, SDVOSB, HUBZone, SDB and WOSB subcontractors are excessively long, reasonable effort shall be made to give all such small business concerns an opportunity to compete over a period of time.

2. Provide adequate and timely consideration of the potentialities of SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns in all "make-or-buy" decisions.

3. Counsel and discuss subcontracting opportunities with representatives of SB, VOSB, SDVOSB, HUBZone, SDB and WOSB firms.

4. Confirm that a subcontractor representing itself as a HUBZone small business concern is identified as a certified HUBZone small business concern by accessing the System For Award Management (SAM) database or by contacting SBA.

5. Provide notice to subcontractors concerning penalties and remedies for misrepresentations of business status as SB, VOSB, SDVOSB, HUBZone, SDB and WOSB for the purpose of obtaining a subcontract that is to be included as part or all of a goal contained in the Contractor's subcontracting plan.

6. For all competitive subcontracts over the simplified acquisition threshold, as defined in FAR 2.101 on the date of subcontract award, in which a small business concern received a small business preference, upon determination of the successful subcontract offeror, prior to award of the subcontract the Contractor must inform each unsuccessful small business subcontract offeror in writing of the name and location of the apparent successful offeror and if the successful subcontract offeror is a SB, VOSB, SDVOSB, HUBZone, SDB or WOSB.

7. Assign each subcontract the NAICS code and corresponding size standard that best describes the principal purpose of the subcontract.

Other ways the Plan Administrator can ensure the company meets the goals of the plan **demonstrating "good faith effort"**:

____Develop and promote company/division policy statements that demonstrate the company's/division's support for awarding contracts and subcontracts to SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns.
__X__Develop and maintain bidders' lists of SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns from all possible sources.
____Ensure periodic rotation of potential subcontractors on bidders' lists.
____Ensure that SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns are included on the bidders' list for every subcontract solicitation for products and services they are capable of providing.

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

__X__Ensure that subcontract procurement “packages” are designed to permit the maximum possible participation of SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns
____Review subcontract solicitations to remove statements, clauses, etc., which might tend to restrict or prohibit SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns.
____Ensure that the subcontract bid proposal review board documents its reasons for not selecting any low bids submitted by SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns.
____Oversee the establishment and maintenance of contract and subcontract award records.
____Attend or arrange for the attendance of company counselors at Business Opportunity Workshops, Minority Business Enterprise Seminars, Trade Fairs, etc.
__X__Directly or indirectly counsel SB, VOSB, SDVOSB, HUBZone, SDB and WOSB concerns on subcontracting opportunities and how to prepare bids to the company.
____Conduct or arrange training for purchasing personnel regarding the intent and impact of Section 8(d) of the Small Business Act on purchasing procedures.
____Develop and maintain an incentive program for buyers that support the subcontracting program.
____Monitor the company’s performance and make any adjustments necessary to achieve the subcontract plan goals.
__X__Prepare and submit timely reports as outlined in Section VII.
____Coordinate the company’s activities during compliance reviews by Federal agencies.
____Promote opportunities for small businesses on the company website

IX. EQUITABLE OPPORTUNITY:

Terreno V Street, LLC will make every effort to ensure that all small business concerns have an equitable opportunity to compete for subcontracts. These efforts may include one or more of the following activities:

A. Outreach efforts to obtain sources by:
_X__ Contacting minority and small business trade associations
_X__ Contacting business development organizations
___ Requesting sources from the Dynamic Small Business Search (Link to Dynamic Small Business Search)
___ Attending small and minority business trade fairs and procurement conferences

B. Internal efforts to guide and encourage purchasing personnel:
___ Presenting workshops, seminars and training programs
_X__ Establishing, maintaining and using small, hubzone small, small disadvantaged, women-owned small, veteran-owned small, and service-disabled veteran-owned small business source lists, guides, and other data for soliciting subcontracts

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

___ Monitoring activities to evaluate compliance with the subcontracting plan

C. Other Additional efforts:
_____ None _____
_____
_____
_____

X. ASSURANCES OF CLAUSE INCLUSION AND FLOW DOWN:

Terreo V Street, LLC agrees to include the FAR Clause 52.219-8, "Utilization of Small Business Concerns" in all subcontracts that offer further subcontracting opportunities, and will require all subcontractors (*except small business concerns*) that receive subcontracts in excess of $750,000 ($1,500,000 for construction) to adopt a plan that complies with the requirements of the clause at 52.219-9, Small Business Subcontracting Plan.

XI. ASSIGNMENT OF SIZE STANDARDS TO SUBCONTRACTS

Terreno V Street, LLC agrees to assign North American Industry Classification System (NAICS) codes to subcontracts and further agrees to to provide the socio-economic status of the successful subcontractor in the notification to the unsuccessful offerors for the subcontracts in accordance with FAR 52.219-9.

XII. REPORTING AND COOPERATION:

Terreno V Street, LLC agrees to:

(10)(i) Cooperate in any studies or surveys as may be required;

(ii) Submit periodic reports so that the Government can determine the extent of compliance by the offeror with the subcontracting plan;

(iii) Submit the SF 294 (Individual Subcontract Report)** to the LCO, and the Summary Subcontract Report (SSR) ** using the Electronic Subcontracting Reporting System (eSRS) (*http://www.esrs.gov*), following the instructions in the eSRS;

(iv) Ensure that its subcontractors with subcontracting plans agree to submit the SF 294 to the LCO and/or the SSR** using the eSRS;

(v) Provide its prime contract number and its DUNS number and the e-mail address of the Government or Contractor official responsible for acknowledging or rejecting the reports, to all first-tier subcontractors with subcontracting plans so they can enter this information into the eSRS when submitting their reports; and

(vi) Require each subcontractor with a subcontracting plan provide the prime contract number and its own DUNS number, and the e-mail address of the Government or Contractor official responsible for acknowledging or rejecting the reports, to its subcontractors with subcontracting plans.

Reports are to be submitted within 30 days after the close of each calendar period as indicated in the following chart:

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Calendar Period	Report Due	Date Due[3]	Submit Report to:
10/01--03/31	SF294*	04/30	LCO
04/01--09/30	SF294*	10/30	LCO
10/01--09/30	SSR**	10/30	eSRS

SF 294s are submitted until further notice in lieu of the ISRs.
****File the SSRs in the government-wide eSRS system as required by FAR clause 52.219-9(l).***

XIII. RECORDKEEPING:

Terreno V Street, LLC will maintain records concerning procedures that have been adopted to comply with the requirements and goals in the plan, including establishing source lists; and a description of efforts to locate SB (including ANCs and Indian tribes), VOSB, SDVOSB, HUBZone, SDB (including ANCs and Indian tribes), and WOSB concerns and award subcontracts to them. The records shall include at least the following (on a plant-wide or company-wide basis, unless otherwise indicated):

1. Source lists (*e.g.,* SAM), guides, and other data that identify *SB* (including ANCs and Indian tribes), VOSB, SDVOSB, HUBZone, SDB (including ANCs and Indian tribes), and WOSB concerns.

2. Organizations contacted in an attempt to locate sources that are *SB* (including ANCs and Indian tribes), VOSB, SDVOSB, HUBZone, SDB (including ANCs and Indian tribes), and WOSB concerns.

3. Records on each subcontract solicitation resulting in an award of more than the simplified acquisition threshold as defined in FAR 2.101 as of the date of the subcontract award, indicating:
   (A) Whether small business concerns were solicited and, if not, why not;
   (B) Whether veteran-owned small business concerns were solicited and, if not, why not;
   (C) Whether service-disabled veteran-owned small business concerns were solicited and, if not, why not;
   (D) Whether HUBZone small business concerns were solicited and, if not, why not;
   (E) Whether small disadvantaged business concerns were solicited and, if not, why not;
   (F) Whether women-owned small business concerns were solicited and, if not, why not; and

[3] The dates listed are considered “no later than”. Thus, the ISRs must be submitted to the LCO no later than these dates, April 30 and October 30, respectively, and the SSR must be entered into the eSRS system no later than October 30 each year.

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

(G) If applicable, the reason award was not made to a small business concern.

4. Records of any outreach efforts to contact
   (A) Trade associations;
   (B) Business development organizations;
   (C) Conferences and trade fairs to locate small, HUBZone small, small disadvantaged, and women-owned small business sources; and
   (D) Veterans service organizations

5. Records of internal guidance and encouragement provided to buyers through
   (A) Workshops, seminars, training, etc.; and,
   (B) Monitoring performance to evaluate compliance with the program's requirements.

6. On a contract-by-contract basis, records to support award data submitted by the offeror to the Government, including the name, address, and business size of each subcontractor. ***Contractors having commercial plans need not comply with this requirement.***

7. Other records to support your compliance with the subcontracting plan: (*Please describe below.*)

_____ None _____
_____
_____
_____

XIV. ADDITIONAL ASSURANCES:

1. Terreno V Street, LLC will make a good faith effort to acquire articles, equipment, supplies, services, or materials, or obtain the performance of construction work from the small business concerns that it used in preparing the bid or proposal, in the same or greater scope, amount, and quality used in preparing and submitting the bid or proposal.

2. Terreno V Street, LLC will provide the Lease Contracting Officer with a written explanation if the lessor fails to acquire articles, equipment, supplies, services or materials or obtain the performance of construction work as described in (d)(12) of FAR clause 52.219-9. This written explanation must be submitted to the Lease Contracting Officer within 30 days of contract completion.

3. Terreno V Street, LLC will not prohibit a subcontractor from discussing with the Lease Contracting Officer any material matter pertaining to the payment to or utilization of a subcontractor.

4. Terreno V Street, LLC assures that the offeror will pay its small business subcontractors on time and in accordance with the terms and conditions of the

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

subcontract, and notify the contracting officer if Terreno V Street, LLC pays a reduced or an untimely payment to a small business subcontractor (see FAR clause 52.242-5).

XV. COMMITMENT TO MAKE A GOOD FAITH EFFORT[4] *(Also refer to 13 CFR 125.3(d), Determination of Good Faith Effort)*

In order to demonstrate your compliance with a good faith effort to achieve the small business subcontracting goals, outline the steps below that your company plans to take.

Terreno V Street, LLC will take the following steps to demonstrate compliance with a good faith effort in achieving small business subcontracting goals:

We will make periodic internal audits of all actions taken by our property manager to insure continued good faith efforts to meet the goals and practices identified in this Plan.

The above requirements will be negotiated with the Lease Contracting Officer prior to approval. The Lease Contracting Officer must ensure per FAR 19.705-5(a)(5) that an acceptable plan is incorporated into and made a material part of the contract.

XVI. STATUTORY REQUIREMENTS (FAR 19.702 and FAR clause 52.219-9(c))

The undersigned recognizes the statutory requirements for a subcontracting plan. The subcontracting plan will be negotiated with the Contracting Officer in the time specified. The plan must be approved prior to contract award, option exercise, or renewal. The Contracting Officer must ensure per FAR 19.705-5(a)(5) that an acceptable plan is incorporated into and made a material part of the contract. Failure to submit and negotiate the subcontracting plan shall make the Offeror ineligible for award of a contract.

As stated in 15 U.S.C. 637(d)(8) as implemented under FAR 52.219-16, *Liquidated damages,* any contractor or subcontractor failing to comply in good faith with the requirements an approved subcontracting plan required by the clause of the contract "Utilization of Small Business Concerns" shall be a **material breach of the contract and may be considered in any past performance evaluation of the Contractor**. Further, 15 U.S.C. 637(d)(4)(F) directs that a contractor's **failure to make a good faith effort** to comply with the requirements of the subcontracting plan shall result in the imposition of liquidated damages.

SIGNATURE REQUIRED:

SUBMITTED by:

Signature: (b) (6) _____

Typed Name: Hayes Graham _____

[4] Defined in SBA regulations 13 CFR 125.3(d)(3)

Company Title: Associate

Date Signed: 3/24/2022

Government Lease Contracting Officer APPROVAL[5]:

Signature: DocuSigned by: (b) (6) [redacted] ACC7E9E39C154E7...

Printed Name: Lynn Abram

Agency: Supreme Court of the United States

Date Signed: 6/30/2022

[5] Contracting officer may indicate their approval by signing the plan, although not required. Approval is indicated when the negotiated subcontracting plan becomes a material part of the lease usually as an Exhibit upon award as required by FAR 19.705-5(a)(5) and FAR clause 52.219-9(c)(1).

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Exhibit H
RLP Amendment

AMENDMENT NUMBER ONE
TO
REQUEST FOR LEASE PROPOSALS NUMBER **8DC2652**
February 9, 2022

The following changes are hereby incorporated into the documents of RLP Number 8DC2652.

1. **Exhibit E – GSA Form 3517 B (General Clauses) of the RLP shall be replaced with the attached updated Exhibit.**

All other terms, conditions and requirements of the solicitation shall remain unchanged.

I hereby acknowledge receipt of Amendment Number One to **RLP 8DC2652** and accept all terms and conditions.

Lance Schwarz
Offeror's name printed/typed

(b) (6) [redacted]

Offeror's signed concurrence

3-28-22
Date

Lessor CS

Government [redacted] LA

DocuSign Envelope ID: BE4FE248-5C4D-4060-9041-7066704B0DB0

Exhibit I

Listing of Terreno V Street, LLC Tax Parcels

United States Supreme Court - Tax Break Out					
Square	**Lot**	**Address**	**BLDG SF**		**Amount**
4365	32	3030 V STREET, NE	108,500	$	199,692.81
4367	1	3130-3180 V STREET, NE	100,036	$	225,406.70
4367	2	3100 V STREET, NE	22,864	$	51,519.65
4371	1	3300 V STREET, NE	110,436	$	219,088.39
4371	2	3350-3390 V STREET, NE	64,198	$	127,358.18
4373	1	3015-3055 V STREET, NE	92,200	$	149,874.16
4373	2	3125-3165 V STREET, NE	92,025	$	150,223.99
4373	5	3325-3355 V STREET, NE	86,219	$	147,827.69
PAR-0173	93	3525 V STREET, NE	30,663	$	65,951.68
PAR-0173	95	3515 V STREET, NE	21,235	$	74,339.21
PAR-0173	96	3521 V STREET, NE	21,235	$	74,632.07
PAR-0173	90	3535 V STREET, NE	68,975	$	154,082.91
PAR-0173	123	3535 V STREET, NE	2,825	$	6,311.91
4365	28	NE	0	$	4,399.23
4365	29	NE	0	$	9,631.05
4365	804	V STREET , NE	0	$	10,052.46
4365	805	2310 31ST STREET, NE	0	$	47,214.26
4365	806	2320 31ST STREET, NE	0	$	44,801.46
4367	801	33RD STREET, NE	0	$	12,099.78
4371	805	RAILROAD TRACKS - REAR OF 3300-3390	0	$	18,060.41
4373	802	V STREET, NE	0	$	21,757.23
4373	803	V STREET, NE	0	$	9,665.54
4373	806	V STREET, NE	0	$	4,383.72
4373	807	V STREET, NE	0	$	23,660.01
PAR-0173	124	NY AVE, NE	0	$	51,343.71
Tax Year 2022	10/1/2021 - 9/30/2022		821,410	$	1,903,378.16

Pro Rata Share:	27,100
GSA (U.S. Supreme Court)	821,410
Pro Rata Share	3.30%

Lessor CS _____ Government LA _____