Review Date: 4/29/03 Checked By: B. Cotton

Checked Date: 5/2/03

Job #: 2603.025.203.RADSN Computed By: A. Rassas

Compute date: <u>4/28/03</u>

Page #:1 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

SDMS Document ID

1.0 PURPOSE/OBJECTIVE

Project: <u>Libby Asbestos Project</u>
Facility: The Second Hand Store

Client: Volpe

The purpose of this cost estimate is to provide costs for the removal of vermiculite containing insulation (VCI) and associated asbestos-containing material (ACM), demolition and reconstruction of The Second Hand Store in Libby, Montana. The costs include the work for removal of ACM and VCI, including containment, storage, transportation and disposal of generated contaminated materials, decontamination facility, demolition of the building, restoration of the site, reconstruction of the store site breakdown, and replacement of the store inventory.

The Second Hand Store is a 2-story, wood frame retail store, consisting of a first floor, approximately 80 ft by 65 ft (5,200 SF0, and an unfinished attic with exposed flooring. The store contains inventory throughout the first floor ad attic. The approximate area of VCI in the building is 1,480 SF. This includes a portion of the attic floor and 3 interior walls. The VCI has also leaked into the first floor of the store through cracks in building materials. In addition, the soil surrounding the building and underneath the crawl space is believed to be contaminated with asbestos-contaminated material.

2.0 PROCEDURE

The work for this project was split into 12 line items, each detailed in a cost worksheet, labeled CW3-1 through CW3-12. The work items were broken down as follows:

•	CW3-1	ACM Personal Protective Equipment (PPE)
•	CW3-2	Decontamination Facility
•	CW3-3	Containment System and Set-up
•	CW3-4	VCI Bulk Removal
•	CW3-5	Asbestos-Contaminated Soil Removal
•	CW3-6	Transportation and Disposal
•	CW3-7	Demolition PPE
•	CW3-8	Building Demolition
•	CW3-9	Site Restoration
•	CW3-10	Building Reconstruction
•	CW3-11	Site Breakdown
•	CW3-12	Replacement of Inventory

The cost worksheets were then summarized in a Cost Summary, CS-4. Cost worksheets and summary are attached.

3.0 DATA/REFERENCES

Information for the details of The Second Hand Store building, including size and type of building, were obtained from the Supplemental Interior Inspection Checklist (SIIC) and field visits. A copy of The Second Hand Store SIIC is attached for reference.

Costs for each item in the cost estimate were obtained from one or more of the following sources: published MEANS and ECHOS cost books, local vendor quotes, and previous work performed by CDM Federal.

Several cost adjustments were made based on the following factors:

Checked Date: 5/2/03

Review Date: 4/29/03 Checked By: B. Cotton Job #: 2603.025.203.RADSN Computed By: A. Rassas Compute date: 4/28/03 Page #:2 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

Client: Volpe

Project: Libby Asbestos Project

Facility: The Second Hand Store

<u>H&S Productivity (labor and equipment only)</u> – Some field work will be performed in Level C PPE. A productivity factor (HPF) of 0.55 is applied to labor and equipment unit costs derived directly from published sources. No factor is applied when health and safety impacts have been considered in the estimation of task durations.

Escalation to Base Year – When costs are taken from earlier dated cost sources, adjustments are made to reflect the current cost in 2003. 2001 cost sources are escalated by 3% to 2003 costs (EF=1.03). 2000 cost sources are escalated by 4% to 2003 costs (EF=1.04). 1998 cost sources are escalated by 9% to 2003 costs (EF=1.09). 1996 cost sources are escalated by 17% to 2003 costs (EF=1.17).

Area Cost Factor - An AF of 1.13 is used for Montana, except an AF of 1.00 (national unmodified average) is used for local vendor quotes.

<u>Subcontractor Overhead and Profit</u> - It is assumed that Subcontractor O&P is either included in the PC O&P or has been factored into vendor quotes or previous work.

Prime Contractor Overhead and Profit - It is assumed that home office OH is 5%, and field office OH is 10%. Profit of 8% is used for the Prime Contractor.

Many of these factors were obtained from "A Guide to Developing and Documenting Cost Estimates During the Feasibility Study", EPA 2000 and the Engineering News-Record website relating to building cost indexes (http://end.construction.com/featureds/conEco/costIndexes/default.asp).

4.0 <u>ASSUMPTIONS/ LIMITATIONS</u>

The following assumptions were made for the basis of this cost estimate:

- The following durations will be used for each of the listed tasks:
 - Building Containment and Set-up 2 days
 - Removal of VCI bulk material 5 days
 - ACM soil removal, backfill and compaction Iday
 - Building demolition 7 days
 - Site Breakdown 4 days

Therefore, the total duration for this project will be 19 days. It is assumed that the building reconstruction will take place at a later date.

- A crew of one labor foreman, 3 laborers, 3 equipment operators and 1 vacuum truck driver will be on site for the duration of the remediation work. A site manager will also be on site part time.
- Personal Protective Equipment (PPE) for the duration of the removal of VCI and ACM material will
 include respirators, disposable coveralls, gloves, foot covering, and protective eye wear.
- Decontamination area will be provided for the decontamination of employees, materials, and their equipment.
- Area warning signs and warning tapes will be provided at the regulated boundaries and entrances to
 regulated areas. Disposal warning labels will be attached to each asbestos disposal container removed
 from the abatement area.
- The entire building will serve as the containment area. All openings will be sealed and negative air pressure provided (air lock, 60-mil polyethylene over all windows, doors, wall openings, electrical outlets, etc, use duct tape to provide airtight seal). HEPA-filter vacuum cleaner and a HEPA-filter ventilation system will be provided in the work area.

Reviewed By: G. McKenzie
Review Date: 4/29/03
Checked By: B. Cotton

Computed By: A. Rassas
Compute date: 4/28/03

Page #:3 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

VCI will be removed from the 20' by 40' attic floor and 3 interior walls. Soil contaminated with ACM will also be removed along the perimeter of the building and beneath the crawl space.

Checked Date: 5/2/03

- Removal of the VCI will include removing the interior wall and vacuuming material directly into
 vacuum boxes, each holding 25 CY. The VCI in the attic floor is exposed; therefore, no finished floor
 will have to be removed prior to vacuuming. The vacuum boxes will be transported to an asbestos
 landfill for proper disposal.
- Vacuum boxes are currently mobilized on site for the Libby Asbestos Project. It is assumed that these boxes will be used for this property as well.
- The assumed dimensions of the contaminated soil material are 10 feet wide by 6 inches deep along the north, east and west perimeters of the building and 6" deep underneath the crawl space (approximate SF of building). This material will be loosened, vacuumed into the vacuum boxes, and disposed of at the asbestos landfill. The area will then be backfilled and compacted with clean soil.
- Once VCI bulk material is removed from the walls and the soil has been remediated, the building will be demolished. The wood structure as well as the concrete foundation will be demolished and disposed.
- The site will be graded and prepared for future building reconstruction.

These assumptions are based on the process currently being performed at other locations at the Libby Asbestos Project for removal of VCI and ACM. This cost estimate is an approximation and is based on approximated building dimensions, remediation durations and reconstruction costs.

5.0 <u>CALCULATION</u>

Client: Volpe

Project: Libby Asbestos Project

Facility: The Second Hand Store

This section contains the calculations and assumptions for each line item in the cost estimate.

5.1 ACM Personal Protective Equipment (CW3-1)

It is assumed that the workers in containment area (3 laborers, 3 equipment operators, 1 vacuum truck driver) will need 2 sets of Level C PPE per day for the duration of the VCI bulk removal and asbestos contaminated soil removal.

PPE needed = 7 people x 2 sets x 6 days = 84 each

In addition, the workers plus the foreman and site manager will need 2-way radios = 9 radios

5.2 Portable Decontamination Facility (CW3-2)

This line item includes set-up and removal fee for a portable decontamination facility for decontamination of employees, materials and equipment for the duration of the project. It is assumed an outside contractor will set-up and remove the facility. Decontamination material is to be disposed of with all other contaminated material.

5.3 Building Containment and Set-up (CW3-3)

Containment and set-up on site is assumed to take 2 days. Labor for this line item includes the following:

Laborer hours = 2 days x 8 hours/day x 3 laborers = 48 hours

Equipment operator hours = $2 \text{ days } \times 8 \text{ hours/day } \times 3 \text{ equip. operators} = 48 \text{ hours}$

Foreman hours = $2 \text{ days } \times 8 \text{ hours/day } \times 1 \text{ foreman} = 16 \text{ hours}$

Checked Date: 5/2/03

Review Date: 4/29/03 Checked By: B. Cotton Job #: 2603.025,203.RADSN Computed By: A. Rassas Compute date: 4/28/03

Page #:4 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

Site manager hours = 2 days x 4 hours/day x 1 foreman = 8 hours

The entire building area will be used as containment. Doors, windows, vents, etc. will be sealed off using polyethylene sheeting. It is assumed that the store has approximately 3 doors and 15 windows that will need to be sealed.

Quantity of polyethylene needed=

Client: Volpe

Project: Libby Asbestos Project

Facility: The Second Hand Store

	Width, ft	Height, ft	Area, SF
3 doors	2	7	42
15 windows	4	4	240
Total			282
Add 10 % safety factor (to account to	for vents, etc)		310

Based on similar work for the Libby Asbestos Project, it is assumed that 10 negative air units will be needed in order to provide adequate pressure for containment.

5.4 VCI Bulk Removal (CW3-4)

The 3 laborers, 3 equipment operators, 1 foreman, and 1 vacuum truck and driver will be on-site for the duration of the VCI bulk removal, 5 days. The site manager will be on site part time.

Laborer hours for VCI removal = $5 \text{ days } \times 8 \text{ hours/day } \times 4 \text{ laborers} = 160 \text{ hours}$

Foreman hours for VCI removal = $5 \text{ days } \times 8 \text{ hours/day } \times 1 \text{ foreman} = 40 \text{ hours}$

Vacuum Truck and driver time = 5 days * 8 hours/day = 40 hours (cost includes time for driver and truck)

Site manager hours for VCI removal = 5 days x 4 hours/day x 1 foreman = 20 hours

5.5 Asbestos-Contaminated Soil Removal (CW3-5)

Asbestos-containing soil has been visually seen in the soil along the exterior perimeter of the building and in the crawl space. The assumed dimensions for soil removal are approximately 10' wide by 6" deep along the north, west and east perimeter of the building. The south side is paved and will be vacuumed for surficial material. It is known that the basement crawl space has flooded in the past and serves as a drainage area for the railroad track and the city of Libby. Therefore, the entire area of the crawl space is assumed to be contaminated 6" deep.

N, E, and W perimeter of building = 80 + 75 + 84 = 239 LF

Volume of soil removed:

Along perimeter of building

Perimeter, ft	Width, ft	Depth, ft	Volume, CF	Volume, CY
239	10	0.5	1560	58

Review Date: 4/29/03 Checked By: B. Cotton

Checked Date: 5/2/03

Job #: 2603.025.203.RADSN Computed By: A. Rassas Compute date: 4/28/03 Page #:5 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

Underneath crawl space

Client: Volce

Project: Libby Asbestos Project

Facility: The Second Hand Store

Area, SF	Depth, ft		1
5,180	0.5	2590	96
		Total:	140

The soil will be loosened and then vacuumed into the vacuum boxes, similar to the VCI removal. Once the soil is removed, the area will be backfilled and compacted with clean soil.

Total labor hours for soil removal, backfill and compaction will include the 3 laborers, 3 equipment operators and 1 foreman for 1 day (site manger for ½ day). The vacuum truck and truck driver will also be needed for 1 day.

5.6 Transportation and Disposal (CW3-6)

This line item includes the transportation and disposal costs for each vacuum box to the asbestos landfill. The number of vacuum boxes is calculated by first calculating the volume of material being transported to the landfill, including VCI material, ACM soil, miscellaneous ACM material and decontamination material. It is assumed that the VCI is approximately '2' thick.

Asbestos landfill disposal volumes

	Thickness, ft.	Area, SF	Volume, SF	Volume, CY
VCI material	0.5	1,628	814	30
Asbestos-contaminated soil				140
Total				170
Add 15% expansion				196
Add 10% for misc.:				215

It is assumed that the vacuum boxes that are already mobilized on site for other properties at the Libby Asbestos Project will be used. Therefore, there will be no cost for the vacuum boxes themselves. The number of vacuum boxes will need to be calculated for disposal. Current disposal rates are \$200 per vacuum box.

The quantity of boxes will be based on the total volume of asbestos contaminated material. Each vacuum box can hold 25 CY of material.

Vacuum boxes for disposal = 215 CY / 25CY = 9 boxes

5.7 Demolition PPE (CW3-7)

It is assumed that the workers during demolition (3 laborers, 3 equipment operators, 1 labor foreman) will need 2 sets of Level D PPE per day for the duration of the demolition activities. This PPE includes disposable tyvek coveralls and ear plugs.

PPE needed = 7 people x 2 sets x 7 days = 98 each

In addition, the laborers plus the foreman and site manager will need 2-way radios = 8 radios

Review Date: <u>4/29/03</u> Checked By: <u>B. Cotton</u>

Checked Date: 5/2/03

Job #: 2603.025,203.RADSN Computed By: A. Rassas

Computed By: A. Rassas
Compute date: 4/28/03
Page #:6 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

5.8 Building Demolition (CW3-8)

Project: Libby Asbestos Project

Facility: The Second Hand Store

Client: Volpe

Building demolition costs were based on a cost per cubic foot of the entire building. Based on the dimensions from the SIIC, the following square foot area of the building was calculated and then multiplied by 16' (2 story building, each story is 8' high):

Square footage-first floor

	Width, ft	Length, ft	Area, SF
Storage	18	20	360
	14	. 8	112
	14	į 8	112
*	14	12	168
Stairs to attic area	14	12	168
Fire wood storage	10	10	100
Open Area	36	20	720
	25.5	30	765
Bathroom	10	10	100
Approx. desk area			
and entrance	30	20	600
Additions	35	5	175
	40	5	200
	40	10	400
	80	15	1200
			5,180

Total building volume = 5,180 SF * 16' tall = 82,880 CF

The foundation is also being demolished, which is the same square area as calculated above.

Concrete foundation demolition = 5,180 SF

Labor time will include 3 laborers, 3 equipment operators and 1 foreman full-time for 7 days, and 1 site manager for half-time (3.5 days).

The volume of demolished material is calculated based on the following assumptions:

- Interior walls and exterior walls are wood, approximately 1/2" thick each
- All walls are 16' high (2 stories x 8' high)
- Studs inside the walls are 2" by 4"'s, spaced every 2 feet
- Ceiling is approximately 2" thick
- Concrete foundation will is 4" thick, mesh reinforced.

First, the volume of a stud in a 16' high wall is calculated.

Stud volume = 1/6 ft x 1/3 ft x 16 ft high = 0.88 CF

Next, interior wall perimeters are calculated:

Review Date: 4/29/03 Checked By: B. Cotton Checked Date: 5/2/03 Job #: 2603.025.203.RADSN Computed By: A. Rassas Compute date: 4/28/03 Page #:7 of 8

Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

Client: Volpe

Project: Libby Asbestos Project

Facility: The Second Hand Store

	Width, ft	Length, ft Per	<u>rimeter, ft.</u>
Storage	18	20	76
	14	8	44
	14	12	52
	14	12	52
Stairs to attic area	14	12	52
Fire wood storage	10	10	40
Open Area	36	20	112
	25.5	30	111
Bathroom	10	10	40
Approx. desk area			
and entrance	30	1 20	100
Additions	35	5	80
	40	, 5	90
	40	10	100
	80	15	190
		. :	1,139

The number of wall studs is calculated based on the assumption that the number of studs is located in approximately half of the entire interior wall perimeter. This assumption accounts for the adjacent interior walls between adjoining rooms.

Stud volume is calculated by multiplying the number of studs times the volume of each stud:

The walls and ceiling volumes were calculated based on the assumptions listed above.

Interior wall volume =
$$1.139 LF \times 16^{\circ}$$
 high x 0.042 ft wide = 765 CF

Exterior wall perimeter =
$$35 + 5 + 18 + 15 + 80 + 75 + 84 = 312$$
 LF

Exterior wall volume =
$$312 LF \times 16^{\circ}$$
 high $\times 0.042$ ft wide = $210 CF$

Ceiling volume =
$$5,180 \text{ SF x } 2/12 \text{ ft} = 863 \text{ CF}$$

Finally, volume of studs, walls and ceiling were added together.

Review Date: <u>4/29/03</u> Checked By: B. Cotton

Computed By: A. Rassas Compute date: 4/28/03 Checked Date: 5/2/03 Page #:8 of 8

Job #: 2603.025.203.RADSN

Facility: The Second Hand Store Detail: ACM Removal, Demolition and Reconstruction Cost Estimate

Add 50% for expansion = 116 CY Add 10% for misc. demo material = 128 CY The concrete foundation is also being demolished. Using assumptions listed above,

> Concrete demolition volume = 5,180 SF x 4/12 ft thick = 863 CFAdd 15% expansion and 10% safety factor = 1092 CF

=40 CY

5.9 Site Restoration (CW3-9)

Client: Volpe

Project: Libby Asbestos Project

This line item includes the cost for labor for 1 day to provide final grading of the site.

Labor time will include 3 laborers, 3 equipment operators and 1 foreman full-time for 4 days, and 1 site manager for half-time (2 days).

Final grading of the property will be performed once demolition activities are completed. It is assumed that the total grading area will be twice the size of the building dimensions.

Area of Final Grading = 5.180 SF x 2 x 1SY/9 SF = 1.151 SY

5.10 Building Reconstruction (CW3-10)

An approximate unit cost of a retail store, based on total square footage, is used to quantify the cost for a newly constructed store. 5,180 SF is used as the total square footage, as calculated above. This unit cost includes the cost for total construction cost, including labor.

5.11 Site Breakdown (CW3-11)

This line item includes the cost for 4 laborers and 1 foreman for 2.5 days to clean and break-down site and equipment. Also included is the cost for the site manager for half-time (1.25 days).

5.12 Replace Inventory

An raw allowance of \$5000 is provided for the replacement of the store inventory.

6.0 CONCLUSIONS

The cost worksheet summary, CS-4, lists each of the above line items and associated costs, for a total capital cost of \$391,924. This cost includes decontamination, PPE, containment system, VCI bulk removal, asbestoscontaminated soil removal, transportation and disposal of contaminated material, building demolition, site breakdown and building reconstruction. Again, this cost estimate is an approximation based on approximate dimensions, remediation durations and approximate reconstruction costs.