Treadwell Rollo

7035


Sampling Plan Summary Former Paint Shop Varnish Plant Mare Island Naval Shipyard Vallejo, California

- Obtain permits, notify tenants
- Excavate an L-shaped area (30 feet by 8 feet plus 8 feet by 7 feet) on the northeast side of the
 Former Paint Shop Varnish Plant (FPSVP) to a depth of 7 feet below ground surface (bgs).
 Target volume of soil to excavate is approximately 77 cubic yards. Dewatering will be performed
 as needed. Excavated soil will be stockpiled and sampled for appropriate off-site disposal.
- Collect 8 soil verification samples; 4 from base and 4 from sidewalls of excavation, and collect an
 additional 3 QA/QC samples. Analyze samples for lead and Total Petroleum Hydrocarbons (TPH)
 as gasoline, diesel and motor oil (diesel and motor oil with silica-gel cleanup). If verification
 samples indicate that remediation goals (see below) have not been met, additional excavation,
 stockpiling and sampling will be performed at LMI's direction.
- Once verification sample results indicate that remediation goals have been met, backfill the excavation with clean backfill material and restored to pre-existing condition.
- Prepare Implementation Report for approval by DTSC.

Cleanup Levels for Planned Commercial/Industrial Uses


Cicaria Ecvos for Figurea Commercial, Industrial 0505			
Constituent	Depth	Average Cleanup Levels (mg/kg)	Maximum Cleanup Levels (mg/kg)
Lead	All	- 750	1,000
TPH-gasoline	0-10 feet bgs	1,168 ¹	500
TPH- diesel	0-10 feet bgs	1,168 ¹	1,000
TPH-motor oil	0-10 feet bgs	1,168 ¹	1,168

¹ = sum of all TPH concentrations




Excavation and Sampling Plan Summary Building 144 – Former Oil/Water Separator Mare Island Naval Shipyard Vallejo, California

- Obtain permits, notify tenants
- Excavate an area (30 feet by 30 feet, less 20 feet by 20 feet western corner section) in the
 central part of Building 144 to a depth of 7 feet below ground surface. Target volume of soil to
 excavate is approximately 182 cubic yards. Excavated soil will be stockpiled and sampled for offsite disposal.
- Collect 12 verification samples; 4 from base and 8 from sidewalls of excavation, plus 4 QA/QC samples. Analyze samples for lead. If verification samples indicate that the remediation goal for lead (750 mg/kg) has not been met, additional excavation, stockpiling and sampling will be performed at LMI's direction.
- Once verification sample results indicate that remediation goals have been met, backfill the excavation with clean backfill material and restored to pre-existing condition.
- Prepare an Implementation Report for approval by DTSC.




Sampling Plan Summary Building 854 PCB Site UL#01 Mare Island Naval Shipyard Vallejo, California

- Prepare Sampling and Analysis Plan for approval by USEPA and DTSC
- Obtain permits
- Lay out SAP-developed ~2-foot by ~4-foot grid of 19 sample locations.
- Remove localized areas of wood flooring to obtain samples at B854DR0111, B854DR112 and B854DR0113.
- At each location collect one concrete and one soil sample: 30-gram concrete sample will be
 collected using a drill and collecting powder generated; 40-gram soil sample will be collected
 from immediately beneath the floor by drive sampler or by trowel. Both samples at B854DR0100
 on concrete shelf will be concrete. Samples will be analyzed for PCBs, with a laboratory reporting
 limit of 0.025 mg/kg. The remediation goal for PCB's is 0.74 mg/kg. Samples will be collected in
 the vicinity of the 3 historical samples, as shown on Figure 1.
- Prepare a Site Characterization Report for approval by USEPA and DTSC.
- Prepare a Scope of Work defining the recommended next phase of activities, based on the results
 of characterization sampling.




Excavation and Sampling Plan Summary Building 1302 PCB Site UL#01 Mare Island Naval Shipyard Vallejo, California

- Obtain permits
- Excavate an L-shaped area 35 feet by 9 feet (Excavation A) and 9 feet by 7 feet (Excavation B)
 west of Building 1302 to a depth of 3 feet below the ground surface. Target volume of soil to
 excavate is approximately 42 cubic yards. Excavated soil will be stockpiled and sampled for offsite disposal.
- Collect 20 verification samples and an additional 6 QA/QC samples; 11 samples from the base and 9 samples from the sidewalls of the excavation. Analyze for PCBs with a laboratory reporting limit of 0.025 mg/kg. If verification samples indicate that the remediation goal for PCBs (less than or equal to 0.74 mg/kg) has not been met, additional excavation, stockpiling and sampling will be performed at LMI's direction.
- Once verification sample results indicate that remediation goals have been met, the excavation will be backfilled with clean backfill material and restored to pre-existing condition.
- Prepare a Remedial Action Summary Report for approval by USEPA and DTSC.
- Prepare a Closure Request for approval by USEPA and DTSC.



Sampling Plan Summary Building 1304 PCB Site UL#01 Mare Island Naval Shipyard Vallejo, California

- Prepare Sampling and Analysis Plan for approval by USEPA and DTSC.
- Obtain permits.
- Lay out 3-foot by 6.5-foot grid of 20 sample locations in the concrete/asphalt surface east of Building 1304.
- At each location collect one concrete/asphalt sample and one soil sample: 30-gram
 concrete/asphalt sample will be collected using a drill and collecting powder generated; 40-gram
 soil sample will be collected from immediately beneath the pavement by drive sampler or by
 trowel. Samples will be analyzed for PCBs, with a laboratory reporting limit of 0.025 mg/kg. The
 remediation goal for PCB's is 0.74 mg/kg.
- Prepare a Site Characterization Report for approval by USEPA and DTSC.
- Prepare a Scope of Work defining the recommended next phase of activities, based on the results
 of characterization sampling.



Sampling Plan Summary Building 1304 PCB Site UL#02 Mare Island Naval Shipyard Vallejo, California


- Obtain permits.
- Lay out 4 sample locations as shown on Figure 1.
- At each location collect one concrete and one soil sample: 30-gram concrete sample will be
 collected using a drill and collecting powder generated; 40-gram soil sample will be collected
 from immediately beneath the floor by drive sampler or by trowel. Samples will be analyzed for
 PCBs, with a laboratory reporting limit of 0.025 mg/kg. The remediation goal for PCB's is 0.74
 mg/kg.
- Prepare a Scope of Work defining the recommended next phase of activities, based on the results of characterization sampling.

BUILDING WAYS 1

EXPLANATION

Approximate location of proposed sample location by Treadwell & Rollo, Inc.

5054-0056 · Approximate location of previous sample collection with PCB concentration. One sample will be collected from this location



BUILDING WAYS 2



INVESTIGATION AREA C3 MARE ISLAND Vallejo, California


PROPOSED SAMPLING LOCATIONS BUILDING 1304 PCB SITE UL#02


Date 04/01/09 Project No. 4752.03 Figure 1

Treadwell&Rollo

Sampling Plan Summary Building 1342 PCB Site UL#01 Mare Island Naval Shipyard Vallejo, California

- Prepare Sampling and Analysis Plan for approval by USEPA and DTSC
- Obtain permits
- Lay out SAP-developed ~7.5-foot by ~9-foot grid of 20 sample locations.
- At each location collect one concrete and one soil sample: 30-gram concrete sample will be
 collected using a drill and collecting powder generated; 40-gram soil sample will be collected
 from immediately beneath the concrete by drive sampler or by trowel. Samples will be analyzed
 for PCBs, with a laboratory reporting limit of 0.025 mg/kg. The remediation goal for PCB's is
 0.74 mg/kg. Samples will be collected in the vicinity of the historical sample with the highest
 concentration, as shown on Figure 1.
- Prepare a Site Characterization Report for approval by USEPA and DTSC.
- Prepare a Scope of Work defining the recommended next phase of activities, based on the results of characterization sampling.





EXPLANATION

7195-0564 • Approximate location of previous sample collection with PCB concentration collection with PCB concentration

> Proposed primary sample location by Treadwell & Rollo, Inc. 102 💿

> 101 S Proposed primary and QA/QC sample location by Treadwell & Rollo, Inc.

100 Abbreviated sample ID. Table 1 provides Full

ug/100cm² Micrograms per square centimeter

mg/kg Milligrams per kilogram


INVESTIGATION AREA C3 MARE ISLAND Vallejo, California


PROPOSED SAMPLE LOCATIONS **BUILDING B1342 UL#01**


Date 03/31/09 Project No. 4752.03 Figure 1

Treadwell & Rollo

Approximate scale







BAO\B121 PCB_SAP_090508.DOC