

DOLAN & WOLTERS

EXCAVATING

18 Wilstow Drive - 11 Flanders Road
Budd Lake, N. J. 07828

238349



Combe Fill South
Parker Road
Chester, N.J.

Dear Sir;

Attached is a copy of the estimate requested for the replacement of the damaged lift station at Combe Fill South. We respectfully submit this estimate and trust it will meet all qualifications and standards.

Very truly yours,

Frank Dolan, pres.
Dolan Wolters Excavating, Inc.

FD/rd

DOLAN & WOLTERS
EXCAVATING

18 Wilstow Drive - 11 Flanders Road
Budd Lake, N. J. 07828

Combe Fill South
Parker Road
Chester, N.J.

UNIT	QTY.	DESCRIPTION	COST	INSTALLATION COST	TOTALS
pump	1	Marlow - Model 312 HEL - ID	\$2,176.00 plus 5%	\$2,000.00	\$4,176.00
Tank	1	10,000 Gal. Lqd.	\$5,000.00	\$1,200.00	\$6,200.00
Tank	1	3,500 Gal. Lqd.	\$1,800.00	\$ 750.00	\$2,550.00
Dist. Box	1	Four 6" lines in one 3" & one 4" out	\$1,000.00	\$1250.00	\$2,250.00
Pipe	1,000'	6" Orangeburg or 6" P.V.C.	\$2,000.00	\$5,000.00	\$7,000.00
Pump House	1	Above ground 8' X 10' sq. X 7' high	\$2,000.00	\$1,500.00	\$3,500.00
Electric Hook up	1	Breaker Box Controls - Wireing	\$3,150.00	\$1,200.00	\$4,350.00
Pipeing		Pipeing for pump check valves - valves by pass - 3" siphon etc.	\$5,000.00	\$3,700.00	\$8,700.00
Excavating		Dig out and remove old lift station * Excavate for new tanks - pump house, under ground pipeing 1,000' of Orangeburg to grade, new dist. box, pour concrete footings for pump pedestal & 10,000 gal. tank footing for pump house, All related grading - hauling & backfilling. Remove Approx. of 2,500 cu. yd. of Spoil			\$38,726.00 \$29,924.00
Concrete	30 cu.yd.		\$40.00 per yd.	\$100.00 per yd.	\$3,000.00
					\$71,650.00