BOEING FIELD -- RUNWAY 13L-31R UPGRADING

VERY PRELIMINARY PROJECT COST ESTIMATE

	Construction	Quantity	Unit Price	Cost	
1 LS	Mobilization	1	\$100,000	\$100,000	
2 LS	Construction Survey	1	\$40,000	\$40,000	
3 LS	FOD Control	1	\$100,000	\$100,000	
4 LS	Erosion Control	1	\$25,000	\$25,000	
5 SY	Asphalt Pavement Grinding	60,000	\$1.25	\$75,000	
6 CY	Off-Site Disposal of Pavement Grindings	1,500	\$10	\$15,000	
7 SY	Asphalt Pavement Removal	1,000	\$12	\$12,000	
8 LF	6" Perf. PVC Pipe	4,000	\$12	\$48,000	
9 SY	Filter Fabric	5,000	\$2	\$10,000	
10 CY	Porous Backfill	1,000	\$25	\$25,000	
11 Ea	MH / CB Adjustments	20	\$500	\$10,000	
12 LF	4 Way, 2" Encased PVC Conduit	1,000	\$20	\$20,000	
13 LF	2" PVC Conduit w/ Trenching/Backfill	10,000	\$6	\$60,000	
14 LF	Electrical Cable	10,000	\$3	\$30,000	
15 Ea	REILs	4	\$7,500	\$30,000	
16 Ea	D-T-G Signs	5	\$3,000	\$15,000	
17 Ea	Electrical Regulator	1	\$8,000	\$8,000	
18 LS	Misc. Electrical Adjustments	1	\$25,000	\$25,000	
19 Tn	Bituminous Tack Coat (CSS-1)	25	\$300	\$7,500	
20 Tn	Bituminous Surface Course (3" ave.)	10,000	\$40	\$400,000	
21 SY	Pavement Grooving	33,000	\$2	\$66,000	
22 SF	Runway and Taxiway Painting (2)	70,000	\$0.40	\$28,000	
			Total	\$1,149,500	
		30% Contingencies		\$344,850	
			8.2% Tax	\$94,259	
		Construction Total Engineering (15%)			\$1,588,609
					\$238,291
		1	Project Total		\$1,826,900

Prelim\$\$.xls

REID MIDDLETON

ReidMiddleton

728 134th Street SW, Suite 200 Everett, WA 204 (425) 741-3800

Fax: (425) 741-3900

Fax Transmittal

Date:

6/01/00

pages including cover:

2

To:

John Current

Fax #: 206-296-0190

Organization:

King County International Airport

Phone #:

206-205-8357

From:

Randy Hall

File No.

Project:

King County International Airport (Boeing Field)

Runway 13L-31R Rehabilitation

Subject:

Preliminary Project Cost Estimate

John,

For your files

Please phone (425) 741-3800 if you do NOT receive all pages.

06/01/00 THU 11:15 ITX/RX NO 83441

CIP ROUTING S.

Project Name: _	Runway 13L-31R Rehab				
Project Number	:001294				
1.0 Design					
1.1	Proposal/RFP				
1.2	Consultant Agreement				
	1.2.1 Bonds/Insurance				
	1.2.2 Amendments				
1.2	1.2.3 Contract Documents				
1.3 1.4	Invoices/Progress Payments Incoming Correspondence				
1.5	Outgoing Correspondence				
1.6	Record of Conversations (Phone/E-Mail)				
1.7	Technical Reports				
1.8	Drawings				
2.0 Construction					
2.1	Dramant/DED				
2.1	Proposal/RFP Contract				
	2.2.1 Change Orders				
	2.2.2 Contract Documents/Drawings				
	2.2.3 Bonds/Insurance Certificates				
	2.2.4 Permits/Licenses				
2.3	Invoices/Progress Payment				
2.4	Incoming Correspondence				
2.5	Outgoing Correspondence				
2.6	Record of Conversations (Phone/Email) Quality Control/Technical Reports				
2.7 2.8	Schedules				
2.8	Record Documents (As-Built)				
2.9.A	O&M Manuals				
2.9.B	Photos				
2.9.C	Certified Payrolls/State Prevailing Wage				
	Name:				
2.9.D	Field Notes				
2.9.E	Submittal No.				
3.0 Outside A	gencies				
3.1	Incoming Correspondence				
3.2	Outgoing Correspondence				
3.3	Record of Conversations (Phone/Email)				
3.4	Internal Correspondence Quality Control Reports				
3.6	Technical Reports				
3.7	External Funding Reports				
4.0 County Force Design					
4.1	Proposal/RFP/Scope of Work				
4.2	Work Authorization/Blanket Agreement				
4.3	Internal Correspondence				
4.5	Record of Conversations (Phone/Email) Technical Reports				
5.0 County Force Administration					
5.1	Internal Correspondence				
5.2	Record of Conversations (Phone/Email)				
5.3	Project Closeout				
5.4	Field Notes (Misc)				
	- W 1 12				
Requested By &	Requested By & Date				
Filed By & Date					

TP ROUTING SLIP PLANNING

Project Name:				
Project Number:				
6.0 Planning				
6.1	Project Scoping and Goals			
6.2	Project Budget			
6.3	Consultant Services			
6.4	Proposal/RFP			
6.5	Studies/Plans			
	6.5.1 Feasibility			
	6.5.2 Pre-Design			
	6.5.3 30 Percent Design			
6.6	Coordination			
	6.6.1 Department			
	6.6.2 Agencies/Jurisdictions			
	6.6.3 Community			
6.7	Correspondence			
6.8	•			
6.9	Plans			