



EPA WORK ASSIGNMENT FORM (WAF) FOR RAC									
1. WORK ASSIGNMENT (WA) INFORMATION									
Project Name: North Bron	son Industrial Area, Bronson, M	MI Contractor: Roy	F. Weston,	Inc.	WA No.: <u>03</u>	81-ROBE-051C			
Activity: Remedial Design	Oversight EPA Cor	ntract No. <u>68-W7-0026</u>		_ Revision	No.: Initial	_			
Date: May 18, 1999 Contractor Control No. Modification No.:  (Contracting Officer Use Only)									
2. DESCRIPTION OF A	CTION			_					
X New WA (need WP for the WA) . Attach SOW including schedule . Designate WAM	WA Amendment (need revised WP and/or cost estimate) Change in LOE or scope by task Add additional tasks or funds for increased activity	— Partial WP App  — WP Disapprova  — Final WP Approva  — Amendment to F  WP Approval  . Approve change ir  scope, or budget  . Approve addition	l val inal	Technical Dir Memorandum Details on scope schedule Minor shift with (no change in \$// Change WAM X Set or revise limit (EL)	, budget, or in SOW LOE)	Incremental Funding . Fund approved WP  WA Closeout Notification . Notify contractor to initiate WA closeout task . Revise EL after final invoice Other			
3. BUDGET INFORMATION									
Completion WA X	Term WA	Approved '	Work Plan B	ork Plan Budget		ure Limits Not to Be Exceeded			
Total Funding Received (\$)  Previous Total0  This Action0  New Total0		LOE (5 Term WAs Only		(\$)*	LOE Term WAs on	(\$)* 			
Funding Category: Site Characterization Activity Code: BE S/SID: 051C		* Includes fees			100				
4. WA COMPLETION DA	ATE Current: April	30, 2,000	Revis	ed:					
This action authorizes approval.		mence Task 1 - Pr	oject Plan	ining not to exc		orth Bronson, Michigan . nditure limit without CO			
Contractor Signatures:  Site Manager/Firm  Date			EPA Signatures:  Work Assignment Manager, Rosita Clarke-Moreno  Date						
Program Manager/Firm		Date	Project Officer, Pat Vogtman  Phone Number (312) 886-7251  Project Officer, Pat Vogtman  Date						
Approved As Approved With Not Submitted Changes Approved Signature of Contracting Officer, Ebon R. Greybourne Date									
WAM Copy	РО Сору		CO Copy			<i>,</i>			

# STATEMENT OF WORK FOR REMEDIAL DESIGN OVERSIGHT North Bronson Industrial Area, Bronson, Michigan

May 18, 1999

#### Introduction

#### Site Description

The North Bronson Industrial Area Superfund site (the site) is a two hundred-acre parcel located in the city of Bronson, Branch County, Michigan. The site occupies the northern (industrial) area of the city of Bronson, it is bounded to the east by Lincoln Street as projected northward to County Drain #30 (CD #30), to the north by CD #30, to the west by Burr Oak Road as projected north by CD#30, and to the south by Fillmore and Union Streets. The predominant features of the site are two sets of seepage lagoons located in the northeast and northwest sections of the site, and CD#30.

Contamination detected at the site is the result of industrial activity and waste handling practices in the North Bronson area since the early 1900's. Initially, several industries discharged plating and other industrial wastes directly into CD#30. To reduce the amount of contaminants entering the drain, the city of Bronson constructed seepage lagoons to retain the waste generated by industry. An industrial sewer system was also constructed and used to convey waste from the facilities to the lagoons.

In June 1984, the U.S. EPA ranked the site for inclusion on the National Priorities List (NPL) and in June 1986, the site was made final on the NPL. The Remedial Investigation and Feasibility Study was funded by U.S. EPA and performed by Michigan Department of Environmental Quality (MDEQ) (formerly Michigan Department of Natural Resources). Remedial Investigations started in mid-1987 and were completed in September 1993 for Operable Unit I, and the Feasibility Study was completed in May 1995. In July 1997 the MDEQ completed a FS Addendum. This addendum updates the cleanup goals to reflect amendments to Michigan law in June 1995, presents an additional groundwater remediation alternative for the site, and identifies the industrial sewer as a potential source of contamination at the site requiring further study. This Industrial sewer and any media impacted by the sewer are identified as Operable Unit II.

#### **Purpose**

The purpose of this work assignment is to obtain contractor support for the oversight of the remedial design (RD) at the North Bronson Industrial Area Superfund site. Implementation of the RD shall be performed by the Potentially Responsible Parties (PRPs).

### Description of the RD

The work to be implemented by the Respondents shall include, but is not limited to, the following components:

- a. Fencing in the western lagoon area and the treament wetland to control risks to human health and the environment associated with exposure to contaminants;
- b. Excavation of eastern lagoon sludge and soil and filling the excavated area with clean soil;
- c. Dredging of sediment from CD #30.
- d. Consolidating contaminated waste from the eastern lagoon and CD #30 into the western lagoons;
- e. Covering the western lagoons to control risks to human health and the environment associated with exposure to contaminants;

May 18, 1999

- f. Installing a French Drain between the western lagoons and CD #30 to capture contaminated groundwater;
- g. Pumping contaminated water from the French Drain;
- h. Constructing a treatment wetland to treat contaminated water collected by the Franch Drain. The goal for groundwater extraction and treatment is to reduce the concentration of contaminants to comply with state and federal surface water discharge criteria;
- i. Discharging treated water from the treatment wetland to CD #30;
- i. Monitoring groundwater and surface water quality to assess the effectiveness of the remedy;
- k. Marking the western lagoon area and the treatment wetland with permanent site markers;
- 1. Placing enforceable restrictions on future land and groundwater use;
- m. Predesign, additional and supplemental investigations/studies; and
- n. Correction of work deficiencies;

It is envisioned that a modification will be made to the Record of Decison to include a contingency for the remedy which will allow for an alternative method of groundwater treatment if the selected remedy does not meet the selected clean-up standards. However, this modification does not fundamentally alter the overall approach intended by the remedy, and would be typical of the type of changes that occur during the remedial design process.

#### Objectives of Oversight

The primary objective of PRP oversight is to ensure that the remedies specified in the RD and used in the remedial action (RA) protect public health and the environment during the life of the project and are implemented in compliance with the terms of the Settlement Agreement. Oversight meets its objectives by observing and documenting that the PRP has complied with all applicable laws, regulations, and requirements, and has met all performance standards specified in the Settlement Agreement.

## General Requirements

The contractor shall conduct the RD Oversight in accor .e with this SOW and to ensure consistency with the ROD issued on June 19, 1998, the Settlement Agreement (CD or AOC), the *Remedial Design and Remedial Action Handbook (DRAFT)* (USEPA Office of Solid Waste and Emergency Response Directive, August 1993) and all other guidance used by USEPA in conducting an RDRA. See references listed in Attachment 2.

A summary of the major deliverables and the schedule for submittal is attached. See Attachment 1.

The contractor shall furnish all necessary and appropriate personnel, materials, and services needed, or incidental to, performing and completing the RD oversight. This especially includes personnel familiar with the design and construction of wetlands for treatment; phytoremediation; sediment and soil excavation and consolidation, cap construction, and groundwater remediation.

A list of primary guidance and reference material is attached. See Attachment 2. In all cases, the contractor shall use the most recently issued guidance.

2

The contractor shall maintain oversight files as specified in the contract and by the Work Assignment Manager or Remedial Project Manager (WAM/RPM). The WAM/RPM may periodically audit the site files and record-

WAM/RPM during the project planning phase to develop a conceptual understanding of the site and the RD scope and requirements. It is anticipated that 2 contractor personnel will attend the site visit.

- Evaluate Existing Information and PRP Plans. The contractor shall obtain, copy, review, and comment on, as appropriate, available information pertaining to the site from USEPA and PRP Plans. The contractor shall not provide formal comments on documents which have already gone through the sign-off stage, such as ROD, RI, FS, etc., and shall not provide formal comments on the CD. The contractor shall obtain the necessary information from the RPM. The contractor shall evaluate or review the existing data and documents, including:
  - Record of Decision (review only)
  - RI, Feasibility Study and FS Addendum (review only)
  - Technical Memorandum OU II (review only)
  - Condent Decree and SOW (review only)

#### 1.1.4 RD Oversight Work Plan

1.1.4.1 Develop RD Oversight Work Plan. The contractor shall prepare and submit a RD Oversight Work Plan within 30 calendar days after receipt of the work assignment (WA). The contractor shall be information from the USEPA-approved PRP Work Plan, appropriate USEPA guidance, and technical direction provided by the USEPA WAM/RPM as the basis for preparing the RD Oversight Work Plan. RD oversight work must be coordinated and properly sequenced with USEPA and PRP RD activities. The contractor shall submit one copy of the work plan to the Contracting Officer (CO), Project Officer (PO) and Work Assignment Manager (WAM).

Develop Narrative. The RD Oversight Work Plan shall include a comprehensive description of project tasks, the procedures to accomplish them, project documentation, and project schedule. The contractor shall use their quality assurance/quality control (QA/QC) systems and procedures to assure that the work plan and other deliverables are of professional quality requiring only minor revisions. Specifically, the Work Plan shall include the following:

- ♦ Identification of RD project elements and the associated oversight tasking including review of PRP planning, design, and activity reporting documentation; field sampling and analysis activities, and treatmolity study activities. Output of this task will be a detailed work breakdown structure of the RD oversight project.
- The contractor's technical approach to each task to be performed, including a detailed description of each task; the assumptions used; any information to be produced during and at the conclusion of each task; and a description of the work products that will be submitted to USEPA. Information shall be presented in a sequence consistent with SOW.
- ♦ A schedule with specific dates for completion of each required activity and submission of each deliverable required by the SOW. This schedule shall also include information regarding timing, initiation, and completion of all critical path milestones for each activity and deliverable and the expected review time for USEPA.
- A list of key contractor personnel providing support on the work assignment.

- 1.1.4.2 Prepare Revised Oversight Work Plan (if necessary)
  - 1.1.4.2.1 Attend Fact Finding/Negotiation Meeting. The contractor shall attend a Work Plan fact finding/negotiation meeting at the Region 5 office.

    USEPA and the Oversight Contractor will discuss and agree upon the final technical approach and costs required to accomplish the tasks outlined in the SOW.
  - 1.1.4.2.2 Prepare & Submit Revised Oversight Work Plan. The contractor shall prepare and submit a revised work plan incorporating the agreements made in the fact finding/negotiation meeting.
- 1.1.5 Review PRP Plans. The contractor shall review and provide comments on the following PRP planning documents
  - 1.1.5.1 PRP Health and Safety Plan. The contractor shall review the PRP's <u>Draft</u> Health & Safety Plan.
  - 1.1.5.2 PRP Sampling and Analysis Plan. The contractor shall review the PRP's draft and final Sampling and Analysis Plan. The contractor's review shall include the PRP's Quality Assurance Project Plan and Field Sampling Plans as outlined below.
    - 1.1.5.2.1 PRP Quality Assurance Project Plan (QAPP)
    - 1.1.5.2.2 PRP Field Sampling Plan (FSP)
- 1.2 Preparation of Site-Specific Plans
  - 1.2.1 Develop Health and Safety Plan (HASP). The contractor shall prepare a site-specific HASP that specifies employee training, protective equipment, medical surveillance requirements, standard operating procedures, and a contingency plan in accordance with 29 CFR 1910.120 1(1) and (1)(2). Whenever possible, the contractor shall use the HASP developed by the PRP's.
  - 1.2.2 Develop Sampling and Analysis Plan (SAP). N/A
  - 1.2.3 Develop Quality Assurance Project Plan (QAPP). N/A
- 1.3 Project Management

The contractor shall perform general work assignment management including management and tracking of costs, preparation of Monthly Progress Reports, attendance at project meetings, and preparation and submittal of invoices. It is anticipated that the period of performance for this project is from June, 1999 through April, 2001.

If the contractor finds that the RD differs significantly from the ROD, the construction or implementation is not consistent with the design, requirements delineated within the Settlement Agreement (CD or AOC) are not being met, or that there are compliance issues with applicable or relevant and appropriate requirements (ARARs) at any point in the process, the contractor shall notify the WAM/RPM immediately to describe the issue.

1.3.1 Monthly Project Management and Reporting. The contractor shall provide general work assignment management and coordination to implement the work assignment SOW. The contractor shall prepare monthly progress reports in accordance with the requirements under the

- Technical requirements of the ROD, Unilateral Administrative Order (UAO), Administrative Order of Consent (AOC), CD, and compliance with ARARs
- Standard professional engineering practices
- Applicable statutes, USEPA policies, directives and regulations
- Spot checking design calculations to assess accuracy and quality of design activities
- Examination of planning and construction schedules for meeting project completion goals
- 7.1 Review PRP PreDesign Documents. The contractor shall review the PRP-prepared predesign, design, and remedial action (where applicable) project documentation to ensure professional quality, technical accuracy, compliance with the PRP RD Work Plan, the ROD and Unilateral Administrative Order, CERCLA, and all ARARs. Specific documents to be required include
  - 7.1.1 Interim Results Deliverables [e.g., Treatability Study Work Results]. The contractor shall review and provide comments on any PRP interim design deliverables.
    - Review of draft and final Pre-Design Studies Report
  - 7.1.2 Other Non-Specific PRP Design Deliverables. The contractor shall budget 200 LOE for this effort.
- 7.2 Review PRP Remedial Design Documents
  - 7.2.1 Review Preliminary Design. The contractor's review and comments of the PRP Work Plan,
    - PRP Pre-Design Work Plan, and the Preliminary Design. The Preliminary Design shall include a review of the Project Delivery Strategy and Scheduling, Preliminary Construction Schedule, Specifications Outline, Preliminary Drawings Basis of Design Report/Design Analysis, Preliminary Cost Estimate, and PRP Description of Variances with the ROD.

The contractor shall participate in a preliminary design review briefing. This meeting will take place in the USEPA regional office and last approximately half of a day. It is anticipated that approximately 2 contractor personnel will be in attendance.

The contractor shall review and provide comments on the PRP revised preliminary design (if applicable).

The contractor shall participate it a revised preliminary design review briefing via a conference call. This conference call will last approximately 1-2 hours. It is anticipated that approximately 1-2 contractor personnel will be in attendance.

7.2.2 Review Intermediate Design Documents. The contractor's review and comment of the Intermediate Design shall include a review of the Construction Schedule, Preliminary Specifications, Intermediate Drawings, Basis of Design Report/Design Analysis, Revised Cost Estimate, and PRP Description of Variances with the ROD.

The contractor shall participate in an intermediate design review briefing. This meeting will take place in the USEPA regional office and last approximately 1 day. It is anticipated that approximately 2 - 3 contractor personnel will be in attendance.

The contractor shall review the PRP conse to design review comments, and submit comments

- on the PRP's response.
- 7.2.3 Review Prefinal/Final Design. The contractor's review and comment of the Prefinal Design shall include a review of the Prefinal Design Specifications, Prefinal Drawings, Basis of Design Report/Design Analysis, Revised Cost Estimate.
  - The contractor shall participate in a prefinal design review conference call. The conference call will last approximately 2-3 hours. It is anticipated that approximately 1 2 contractor personnel will be in attendance at each meeting.
- 7.2.4 Review Final Design. The contractor shall review and comment of the Final Design. This shall include a review of the Final Design Specifications, Final Drawings, Basis of Design Report/Design Analysis, Final Cost Estimate.
- 7.2.5 The contractor shall review any PRP subcontract award document(s) available for review. This review may include reviews of the biddability (offerability) and constructability reviews and a revised project delivery strategy. The contractor shall assume 20 LOE for this effort.
- 7.2.6 The contractor shall review other PRP non-specific RD documents available for review. The contractor shall assume 150 LOE for this effort.
- 7.3 Review PRP Remedial Action Documents. N/A

#### Task 8 Remedial Action Oversight N/A

#### Task 9 Technical Meeting Support

This task includes work efforts related to attendance at and documentation of meetings with USEPA, PRPs, the PRP contractor, and the State Agency. The contractor shall attend various meetings throughout the performance of the work assignment. These meetings are in addition to the meetings specifically included within other tasks in this SOW. Meetings may be scheduled to coincide with the following specific milestones during the RD; at the PRP RD work plan review, in between design submittal reviews, before initiating on-site field sampling and treatability studies during the design phase, or at completion of all sampling during design activities. For budgeting purposes the contractor shall assume 4 meetings. It is anticipated that these meeting would take place in Bronson, Michigan and last approximately half a day each. It is also anticipated that approximately 1 - 2 contractor personnel will be in attendance at each of these meetings.

#### Task 10 Work Assignment Closeout

The contractor shall perform the necessary activities to close outwork assignment in accordance with contract requirements.

- 10.1 Package and Return Documents to Government. The contractor shall package and return all documents to EPA.
- 10.2 Prepare Closeout Report. The contractor shall prepare a Work Assignment Closeout Report (WACR). The WACR shall include all LOE by p-level and costs in accordance with the WBS. The contractor shall provide an electronic copy of the most recent mailing list to the WAM concurrent with submittal of the WACR. The contractor shall budget for 80 LOE for this effort.

# Attachment 1 Summary of Major Submittals for the Remedial Design Oversight at North Bronson Industrial Area Site, Bronson, Michigan

TASK	DELIVERABLE	NO. OF COPIES	DUE DATE (in calendar days)
1.1.4.1	RD Oversight Work Plan	3	30 days after receipt of work assignment (WA)
1.1.4.2	Revised RD Oversight Work Plan (if necessary)	3	15 days after meeting/agreement of USEPA comments
1.1.5.1	Comments on PRP H&S Plan	2	21 days after receipt of document
1.1.5.2.1	Comments on PRP QAPP	2	21 days after receipt of document
1.1.5.2.2	Comments on PRP FSP	2	21 days after receipt of document
1.2.1	Health & Safety Plan	2	30 days after receipt of WA
1.3.1	Monthly Progress Reports	3	In accordance with the requirements of the contract
1.3.1	Ad hoc financial information requests	, 1	14 days after WAM request
3.2.3.1	Periodic Field Oversight Reports	2	10 days after each <u>2</u> week field oversight event.
3.2.3.2	Final Summary Field Oversight Report	2	21 days after the end of all field oversight activities
7.1.1	Comments on Interim Design Documents	2	30 days after receipt of PRP Pre- Design Documents
7.1.2	Other Non-Specific PRP Deliverables	2	30 days after receipt of PRP Deliverable
7.2.1	Comments on PRP Preliminary Design Documents	2	30 days after receipt of PRP Preliminary Design documents
7.2.1	Comments on PRP Revised Preliminary Design	2	15 days after receipt of PRP Response
7.2.2	Comments on PRP Intermediate Design Documents	2	30 days after receipt of PRP Intermediate Design Documents
7.2.2	Comments on PRP Response of Intermediate Design	2	15 days after receipt of PRP Response
7.2.3	Comments on PRP Prefinal Design Documents	2	30 days after receipt of PRP Prefinal Design Documents
7.2.4	Comments on PRP Final Design Documents	2	15 days after receipt of PRP Final Design Documents

May 18, 1999

TASK	DELIVERABLE	NO. OF COPIES	DUE DATE (in calendar days)
7.2.5	Comments on PRP Subcontract Award Documents	2	15 days after receipt of PRP Subcontract Award Documents
10.2	Work Assignment Closeout Report	3	As directed in Work Assignment Closeout Notification

May 18, 1999 10

# Attachment 2 Regulations and Guidance Documents

The following list, although not comprehensive, comprises many of the regulations and guidance documents that apply to the RD process:

- American National Standards Practices for Respiratory Protection. American National Standards Institute Z88.2-1980, March 11, 1981.
- 2. ARCS Construction Contract Modification Procedures September 89, OERR Directive 9355.5-01/FS.
- CERCLA Compliance with Other Laws Manual, Two Volumes, USEPA, Office of Emergency and Remedial Response. August 1988 (DRAFT), OSWER Directive No. 9234.1-01 and -02.
- 4. Community Relations in Superfund A Handbook, USEPA, Office of Emergency and Remedial Response, June 1988, OSWER Directive No. 9230.0-3B.
- 5. A Compendium of Superfund Field Operations Methods, Two Volumes, USEPA, Office of Emergency and Remedial Response, EPA/540/P-87/001a, August 1987, OSWER Directive No. 9355.0-14.
- Construction Quality Assurance for Hazardous Waste Land Disposal Facilities, USEPA, Office of Solid Waste and Emergency Response, October 1986, OSWER Directive No. 9472.003.
- 7. Contractor Requirements for the Control and Security of RCRA Confidential Business Information, March 1984.
- 8. Data Quality Objectives for Remedial Response Activities, USEPA, Office of Emergency and Remedial Response and Office of Waste Programs Enforcement, EPA/540/G-87/003, March 1987, OSWER Directive No. 9335.0-7B.
- 9. Engineering Support Branch Standard Operating Procedures and Quality Assurance Manual, USEPA Region IV, Environmental Services Division, April 1, 1986 (revised periodically).
- 10. EPA NEIC Policies and Procedures Manual, EPA-330/9-78-001-R, May 1978, revised November 1984.
- 11. Federal Acquisition Regulation, Washington, DC: U.S. Government Printing Office (revised periodically).
- 12. Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final, USEPA, Office of Emergency and Remedial Response, October 1988, OSWER Directive NO. 9355.3-01.
- 13. Guidance on EPA Oversight of Remedial Designs and Remedial Actions Performed by Potential Responsible Parties, USEPA Office of Emergency and Remedial Response, EPA/540/G-90/001, April 1990.
- 14. Guidance on Expediting Remedial Design and Remedial Actions, EPA/540/G-90/006, August 1990.
- 15. Guidance on Remedial Actions for Contaminated Ground Water at Superfund Sites, USEPA Office of Emergency and Remedial Response (DRAFT), OSWER Directive No. 9283.1-2.
- 16. Guide for Conducting Treatability Studies Under CERCLA, USEPA, Office of Emergency and Remedial Response, Prepublication version.
- 17. Guide to Management of Investigation-Derived Wastes, USEPA, Office of Solid Waste and Emergency Response, Publication 9345.3-03FS, January 1992.
- Guidelines and Specifications for Preparing Quality Assurance Project Plans, USEPA, Office of Research and Development, Cincinnati, OH, QAMS-004/80, Decemb. 29, 1980.
- 19. Health and Safety Requirements of Employees Employed in Field Activities, USEPA, Office of Emergency and Remedial Response, July 12, 1982, EPA Order No. 1440.2.
- 20. Interim Guidance on Compliance with Applicable of Releasest and Appropriate Requirements, USEPA, Office of Emergency and Remedial Response, July 9, 1987, OSW) Directive No. 9234.0-05.
- 21. Interim Guidelines and Specifications for Preparing Quality Assurance Project Plans, USEPA, Office of Emergency and Remedial Response, QAMS-005/80, December 1980.
- 22. Methods for Evaluating the Attainment of Cleanup Standards: Vol. 1, Soils and Solid Media, February 1989, EPA 23/02-89-042; vol. 2, Ground water (Jul 1992).
- National Oil and Hazardous Substances Pollution Contingency Plan; Final Rule, Federal Register 40 CFR Part 300, March 8, 1990.
- 24. NIOSH Manual of Analytical Methods, 2nd edition. Volumes I-VII for the 3rd edition, Volumes I and II, National Institute of Occupational Safety and Health.
- 25. Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities, National Institute of Occupational Safety and Health/Occupational Health and Safety Administration/United States Coast Guard/Environmental Protection Agency, October 1985.
- 26. \_\_\_\_\_ OSWER Directive No. 9355.7-02, May 23, 1991. [Guidance, p. 3-5]
- 27. OSWER Directive No. 9242.3-08, December 10, 1991. [Guidance, p. 2-2]
- 28. Permits and Permit Equivalency Processes for CERCLA On-Site Response Actions, February 19, 1992, OSWER Directive 9355.7-03.
- Procedure for Planning and Implementing Off-Site Response Actions, Federal Register, Volume 50, Number 214, November 1985, pages 45933-45937.
- 30. Procedures for Completion and Deletion of NPL Sites, USEPA, Office of Emergency and Remedial Response, April 1989, OSWER Directive No. 9320.2-3A.
- 31. Quality in the Constructed Project: A Guideline for Owners, Designers and Constructors, Volume 1, Preliminary Edition

May 18, 1999

- for Trial Use and Comment, American Society of Civil Engineers, May 1988.
- 32. Remedial Design and Remedial Action Handbook (Draft). USEPA, Office of Emergency and Remedial Response, August 1993, OSWER Directive No. 9355.5-22.
- 33. Scoping the Remedial Design (Fact Sheet), May 1993, OSWER Publ. 9355-5-21 FS.
- 34. Standard Operating Safety Guides, USEPA, Office of Emergency and Remedial Response, November 1984.
- 35. Standards for the Construction Industry, Code of Federal Regulations, Title 29, Part 1926, Occupational Health and Safety Administration.
- 36. Standards for General Industry, Code of Federal Regulations, Title 29, Part 1910, Occupational Health and Safety Administration.
- 37. Superfund Guidance on EPA Oversight of Remedial Designs and Remedial Actions Performed by Potentially Responsible Parties, April 1990, \_\_\_\_\_.
- 38. Superfund Remedial Design and Remedial Action Guidance, USEPA, Office of Emergency and Remedial Response, June 1986, OSWER Directive No. 9355.0-4A.
- 39. Superfund Response Action Contracts (Fact Sheet), May 1993, OSWER Publ. 9242.2-08FS.
- 40. TLVs-Threshold Limit Values and Biological Exposure Indices for 1987-88, American Conference of Governmental Industrial Hygienists.
- 41. Treatability Studies Under CERCLA, Final. USEPA, Office of Solid Waste and Emergency Response, EPA/540/R-92/071a, October 1992.
- 42. USEPA Contract Laboratory Program Statement of Work for Inorganic Analysis, USEPA, Office of Emergency and Remedial Response, July 1988.
- 43. USEPA Contract Laboratory Program Statement of Work for Organic Analysis, USEPA, Office of Emergency and Remedial Response, February 1988.
- 44. User's Guide to the EPA Contract Laboratory Progr JSEPA, Sample Management Office, August 1982.
- 45. Value Engineering (Fact Sheet), USEPA, Office of Solid Waste and Emergency Response, Publication 9355.5-03FS, May 1990.
- 46. Guide to Documenting Cost and Performance for Remediation Projects, Publication EPA-542-B-95-002, March 1995.
- 47. Presumptive Remedies: Policy and Procedures, U.S. EPA. Office of Solid Waste and Emergency Response, Directive 9355.0-47FS, EPA 540-F-93-047, PB 93-963345, September, 1993.
- 48. Presumptive Remedies for Soils, Sediments, and Sludges at Wood Treater Sites, U.S. EPA, Office of Solid Waste and Emergency Response, Directive 9200.5-162, EPA/540/R-95/128, PB 95-963410, November, 1995.
- 49. Presumptive Response Strategy and Ex-Situ Treatment Technologies for Contaminated Groundwater at CERCLA Sites, U.S. EPA, Office of Solid Waste and Emergency Response, Directive 9283.1-12, EPA 5401R/023, June, 1996.