



Site 6

Former Fire Training School Former Naval Station Treasure Island

BCT Meeting Update

September 16, 2015

Bryce Bartelma Navy BRAC RPM

Fire Fighter Training






Firefighter Training – Extinguishing fuel oil fire, Treasure Island Damage Control School, 1945

Site 6 Record of Decision



Soil Remedy

- Excavation and off-site disposal of soil in certain areas at depths up to 5.5 feet below ground surface
- Land Use Restrictions / Institutional Controls (ICs)



Site 6 Record of Decision (Continued)




Groundwater Remedy

- Groundwater Monitoring
 Subareas 1 and 2
- Land Use Restrictions / ICs


Soil Gas Remedy

- Confirmation sampling to confirm soil gas is below screening levels in Subarea 2
- Requirement that construction of enclosed structures at Subarea 1 include vapor mitigation measures or the completion of a vapor intrusion evaluation



Site 6 Pre-Design Soil Sampling – Subarea 1





<u>Purpose</u>

- Refine Northwestern Limits
- Deep Excavation Changed due to RI/FS Figure Location Errors

- Elevated Dioxins Detected in 3 Sample Locations out of 9
 - Dioxin RG is 12 ng/kg
- Excavation will Expand to the West


Site 6 Pre-Design Soil Sampling – Subarea 2



Purpose

- Refine Eastern and Southern Limits
- Vertical Delineation in Deeper Excavation Area

- Elevated Dioxins Detected in 4 Sample Locations out of 8
- Excavation Reduction near 06-SB49 and 06-SB50
- Expand Southeastern Limits
- Vertical Delineation



Site 6 Pre-Design Soil Sampling – Subarea 3




Purpose

Shallow soil samples in hopes of reducing excavation near structures

- No Elevated Dioxin Detections Slight Excavation Reduction
- Structure (Transformer) Removed During Radiological Screening






Site 6 Pre-Design Soil Gas Sampling – Subarea 2



Purpose

- Soil Gas Sampling for Naphthalene
- Historical Location 06-SG08
 - Detection of 34 J μg/m3
 - Screening Level is 31.9 μg/m3

- No Detections of Naphthalene
- Lab Sample Analysis Error in 06-SG22 and 06-SG25
 - To Be Resampled During Remedial Action Activities



Site 6 Schedule



CERCLA Process

Draft Remedial Design / Remedial Action Work Plan – November 2015

RI/FS 2012 PCSR UST 240 2013

Proposed Plan/Record of Decision 2014

Pre-Design Sampling 2015 Remedial Design 2015 Remedial Action 2016



Questions?



