

**COST ANALYSIS**  
**Partial Excavation vs Full Depth Excavation**  
**Vineland OU3 Phase IV**  
**1-12-10**

This estimate evaluates the cost savings associated with removing only the top 18" of contaminated peat in certain areas of the Phase IV Floodplain. Following are the excavation guidelines that would be followed using this approach:

- For areas within 50' of the original stream centerline where the arsenic concentration is > 20 ppm, , excavate all peat down to the top of sand elevation.
- For the areas outside of 50' from the original stream centerline where the arsenic concentration is >120 ppm, excavate all peat down to the top of sand elevation
- For areas outside of 50' of the original stream centerline where the peat is between 20 and 120 ppm, excavate only the top 18" of the floodplain, place 2 layers of coir mat, and backfill with 12" of clean sand and 6" of clean manufactured topsoil.

**Contaminated Peat Quantities:**

Using SES's sample map, the total Phase IV contaminated area is 21.2 acres. The area of Phase IV that could be considered for partial excavation is approximately 9.6 acres. The remaining 11.6 acres will require full excavation to the top of sand elevation because it meets one of the following criteria:

- a. The peat contains >120 ppm As
- b. The area is within 50' of the original stream centerline
- c. The area is within the Maurice River diversion footprint

Full Excavation Area: Assuming an average of 4' excavation depth for the above areas, the quantity requiring full excavation is given by 11.6 acres x 43,560 sf/acre x 4' thick / (27 cf/cy) = 75,000 tons. This area will not be considered in this cost estimate.

Partial Excavation Area: The quantity of contaminated peat in the area being considered for partial excavation is given by 9.6 acres x 43,560 sf/acre x 4' thick / (27 cf/cy) = 62,000 tons.

Considering the partial excavation (9.6 acre) area only, the amount of contaminated peat to be excavated if only the top 18" is removed is:

$$9.6 \text{ acre} \times 43,560 \times 1.5 = 23,200 \text{ tons.}$$



## **ESTIMATED COST FOR PARTIAL EXCAVATION OF THE 9.6 ACRE AREA:**

Following is the crew size for the partial excavation area, as determined during the excavation/backfill test area work:

- 2 laborers – unroll and place mat
- 1 laborer – standby and guide trucks
- 1 laborer – foreman
- 1 laborer (50% of time) – miscellaneous support
- 1 operator – place mat and excavate contaminated soil
- 1 operator – move excavation soils to stockpile
- 1 operator – dozer/fill
- 1 operator (15% of time) – loader – bring in soil and fill
- 1 teamster (50% of time) – deliver fill

Totals:

4.5 laborers

3.15 operators

0.50 teamsters

Calculate the excavation rate during construction of the test area:

Test Area is 120' x 85' x 2.5' deep / 27 = 944 tons

Duration of test area work was 15 days

Rate of excavation of contaminated soil was 944 tons/ 15 days = 63 tons per day – this includes the time necessary to excavate the contaminated peat, place the mat and then place the temporary sand work platform. Note, there are some inefficiencies in this rate due to removal and reconstruction of some areas which failed where the coir mat overlap was reduced.

SES's WVN cost proposal assumed an excavation rate of approximately 120 tons per day.

For this estimate, will use a rate of 100 tons per day. This is significantly higher than the rate observed during the test area work but since the work is expected to get more efficient as it progresses, this is considered a reasonable rate.

Duration of partial excav area work: 23,200 tons/(100 tons/day) = 232 work days

## **PEAT EXCAVATION**

## Cost Estimate Phase IV Partial Excavation

		<b>Phase IV Partial Excavation - Daily Labor Cost</b>						
<b>Labor</b>								
<b>Craft</b>	<b>Hours</b>	<b>Labor Rate - Direct</b>	<b>Labor Rate - Fringe</b>	<b>Total Labor</b>				
Operators Directs	31.5	\$ 49.52		\$1,559.88				
Op Fringe	31.5		\$21.08	\$664.02				
Operator Steward	0	\$ 50.52		\$0.00				
Op Stew Fringe	0		\$21.08	\$0.00				
Laborers Directs	45	\$ 32.85		\$1,478.25				
Lab Fringe	45		\$ 20.25	\$911.25				
Laborer Steward	0	\$ 33.85		\$0.00				
Lab Stew Fringe	0		\$ 20.25	\$0.00				
Laborer Foreman	10	\$ 33.85		\$338.50				
Laborer FM Fringe	10		\$ 20.25	\$202.50				
Teamster Directs	5	\$ 28.70		\$143.50				
Tmstr Fringe	5		\$ 16.49	\$82.45				
Tmstr Steward	0	\$ 29.70		\$0.00				
Tmstr Stew Fringe	0		\$ 16.49	\$0.00				
			Sum Directs	\$3,520.13				
			Burden 30.12%	\$1,060.26				
			Subtotal	\$4,580.39				
			Fringes	\$1,860.22				
			Subtotal	\$6,440.61				

## **Cost Estimate Phase IV Partial Excavation**

[illegible]

## LABOR:

From the "Partial Excavation Daily Labor Cost" spreadsheet, the labor cost per day for the work crew is \$8,797.45 per day. Following is the estimated labor cost for the entire area:

$$232 \text{ days} \times \$8,797.45 \text{ per day} = \$2,040,000$$

## EQUIPMENT:

Dozer 232 days x 10 hrs/day x \$27.85/hr =	\$ 64,612
Moxy 232 days x 5 hrs/day x \$34.46/hr =	\$ 39,974
PC300 232 days x 10 hrs/day x \$71.26/hr =	\$165,323
Swamp Excavator 232 days x 10 hrs/day x \$175/hr =	\$406,000
Loader 232 days x 10 hrs/day x \$50/hr =	<u>\$116,000</u>
	\$791,909

## MATERIALS:

### Fuel/Oil/Grease

Dozer	2,320 hrs x 3 gall/hr x \$3/gall =	\$20,880
Moxy	1,160 hrs x 5 gall/hr x \$3/gall =	\$17,400
PC300	2,320 hrs x 6 gall/hr x \$3/gall =	\$41,760
Loader	2,320 hrs x 7.5 gall/hr x \$3/gall =	\$52,200
Swamp Excav	2,320 hrs x 6 gall/hr x \$3/gall =	<u>\$41,760</u>
		\$174,000

### Coir Mat:

408,576 sf (partial excav area) \* 13/8 \* 2 layers = 1,327,872 sf of mat  
(accounts for 5' overlap for each roll)

$$1,327,872 \text{ sf} \times \$0.312/\text{sf} = \$415,000$$

### Sand Fill:

$$408,576 \text{ sf} \times 1 \text{ ft thick} / 27 \times 1.5 \text{ tons/cy} \times \$6.50/\text{ton} = \$147,541$$

## SAND EXCAVATION

Estimated cost to excavate and remove the top 2' of the 3' thick temporary sand platform layer (note, topsoiling labor is not considered here because the cost for topsoiling is the same regardless of whether the partial excavation or full excavation procedure is followed)

Total quantity of sand to be excavated:

$$408,576 \text{ sf} \times 2' / 27 = 30,300 \text{ cy}$$

Per Means, use 800 cy/day for a 1 cy/excavator  
 $30,300 \text{ cy} / (800 \text{ cy/day}) = 38 \text{ days}$

#### LABOR:

Assume an excavation crew of 1 operator, 1 teamster (hauling away fill), and ½ laborer – see spreadsheet – est cost is \$2,333/day for labor

#### EQUIPMENT:

Excavator:	380 hrs x \$71.26/hr =	\$27,078
Moxy:	380 hrs x \$34.46/hr =	<u>\$13,095</u>
		\$40,173

#### MATERIALS:

##### Fuel/Oil/Grease

Excavator:	380 hrs x 6 gall/hr x \$3/gall =	\$ 6,840
Moxy:	380 hrs x 5 gall/hr x \$3/gall =	<u>\$ 5,700</u>
		\$12,540

#### TRANSPORTATION AND DISPOSAL

23,200 tons x \$80/ton =	<u>\$1,856,000</u>
--------------------------	--------------------

ESTIMATED COST FOR PARTIAL EXCAV	\$5,477,163
----------------------------------	-------------

#### ESTIMATED COST FOR FULL EXCAVATION OF THE 9.6 ACRE AREA:

LABOR/EQUIPMENT(Combined, per SES cost rpt) are \$50.36/ton (actual Phase II costs per cost report – does NOT include cost of fill – need to revise to account for fill)

62,000 tons x \$50.36/ton = \$3,122,320

**MATERIALS:**

Sand Fill  
3.5 ft thick x 408,576 sf x \$6.50/ton / (27 cf/cy) = \$ 344,263

**Transportation and Disposal:**

62,000 tons x \$80/ton = \$4,960,000

ESTIMATED FOR FULL EXCAV \$8,426,583


**POSSIBLE COST SAVINGS:**

**\$8,426,583 - \$5,477,163 = \$2,949,420**

# Casting Scenarios for HQ Briefing

Table -  
Phase Remaining

Activity	Phase	Estimated Cost	Funding Source
Multistate SJ	Phase 2		
Rte SJ to MRP	Phase 3	$\frac{X}{Y}$	Stim Plan
MRP to Confluence area	Phase 4a		Stim
Confluence area	Phase 4b or 5		



Now  
Phase 4 pre-hm

Phase 4 full-scale

Phase 2 restoration will be only  
minor left

Letterhead  
memo  
Operation completion  
for Contam mater  
excavation  
and processing  
for on 1 completed  
Dec. 21, 2007

While this marks  
the removal of  
contaminated  
source material  
from the  
plant site  
restoration activities  
remain to be  
completed for the  
on 1 area once  
the operation of  
the soil washing  
plant is complete.



## Cost Estimate Phase IV Partial Excavation

		<b>Phase IV Partial Excavation - Remove Temp Work Platform - Daily Labor Cost</b>						
<b>Labor</b>								
<b>Craft</b>	<b>Hours</b>	<b>Labor Rate - Direct</b>	<b>Labor Rate - Fringe</b>	<b>Total Labor</b>				
Operators Directs	10	\$ 49.52		\$495.20				
Op Fringe	10		\$21.08	\$210.80				
Operator Steward	0	\$ 50.52		\$0.00				
Op Stew Fringe	0		\$21.08	\$0.00				
Laborers Directs	5	\$ 32.85		\$164.25				
Lab Fringe	5		\$ 20.25	\$101.25				
Laborer Steward	0	\$ 33.85		\$0.00				
Lab Stew Fringe	0		\$ 20.25	\$0.00				
Laborer Foreman	0	\$ 33.85		\$0.00				
Laborer FM Fringe	0		\$ 20.25	\$0.00				
Teamster Directs	10	\$ 28.70		\$287.00				
Tmstr Fringe	10		\$ 16.49	\$164.90				
Tmstr Steward	0	\$ 29.70		\$0.00				
Tmstr Stew Fringe	0		\$ 16.49	\$0.00				
			Sum Directs	\$946.45				
			Burden 30.12%	\$285.07				
			Subtotal	\$1,231.52				
			Fringes	\$476.95				
			Subtotal	\$1,708.47				