

9 8

0001

FIR GGP 9/29
Tam 9/29
AIR 10/4/89

Westinghouse Environmental
and Geotechnical Services, Inc.

4000 DeKalb Technology Parkway, NE
Suite 250
Atlanta, Georgia 30340
(404) 458-9309
FAX (404) 458-9438

file 36628

19-533(2)

September 19, 1989

Tennessee Department of Health
and Environment
Division of Superfund
701 Broadway
307 Customs House
Nashville, Tennessee 37219-5403

ATTENTION: Mr. David Randolph
District Chief

SUBJECT: Letter of Clarification
Westinghouse Project 4124-89-106
Document Control 89106-0007

Dear Mr. Randolph:

This letter is to clarify the responsibilities of Westinghouse regarding the preparation of work plans for the Superfund sites in your district. Westinghouse understands the current status of each project to be as follows:

Stauffer Chemicals, Maury County

Westinghouse is responsible for evaluating technical quality of work conducted by Roux Associates for a hydrogeologic investigation at the site. Tasks to be performed by Westinghouse will potentially include the review of data, field methodologies, interpretations, conclusions, and recommendations. No work plan is required. TDHE will notify Westinghouse of individual tasks with individual letters of authorization. *A cost estimate will be prepared for each task by Westinghouse and a ceiling and notice to proceed will be given over the phone by TDHE.

Sadd Nashville, Davidson County 19-533(2)

No work plan is required at this time. The PRP has agreed to clean up the site and conduct an investigation to evaluate the extent of groundwater contamination. Past investigations have indicated that groundwater contamination has occurred, evidenced by samples collected from monitoring wells on site. If the PRP defaults on the consent order, Westinghouse may be asked to

9106018

prepare a work plan and resume the responsibilities of the investigation.

Saad Silver Springs, Rutherford County

Westinghouse is responsible for preparing a work plan for a detection monitoring program at the site. The purpose of the detection monitoring program is to determine the presence or absence of groundwater contamination. This work involves installing one well nest upgradient and at least three well nests downgradient of the source of contamination. Water quality degradation in private wells surrounding the area has provided potential evidence of contaminant migration from the site. No monitoring wells currently exist on site. The PRP has not agreed to clean the site.

Wayne Co. Landfill

Westinghouse is potentially responsible for preparing a work plan for a detection monitoring program at the site. The USGS has installed monitoring wells and collected groundwater samples at the site. A report on these activities is currently being prepared by USGS and is expected to be completed by early October. Following the review of the USGS report, TDHE will decide if further investigations will be necessary at the site.

Following your response to this letter, Westinghouse will proceed to prepare the work plans and cost estimates for the individual projects.


If you have any questions or require clarification, please contact us.

Very truly yours,

**WESTINGHOUSE ENVIRONMENTAL AND
GEOTECHNICAL SERVICES, INC.**



Mary C. Parsons
Hydrogeologist



Robert E. Helton
Program Director

cc: Cynthia A. Tschaepe
9106018