#### Hazardous Waste System Leak Testing

# 3M Tape Manufacturing Division Plant St. Paul, Minnesota

June 23, 1999

3M Project Number 20–1525 Laboratory Request No. W2107

#### Prepared for:

Jeffrey W. Stock Environmental Technology and Safety Services/3M Building 2–3–09 935 Bush Avenue PO Box 33331 St. Paul, Minnesota 55133–3331

#### Prepared by:

Precision Environmental 8251 Main Street Northeast Minneapolis, Minnesota 55432 (612) 780–9787 FAX (612) 780–7157

Date Printed: June 24, 1999

# CERTIFICATION OF TEST REPORT

۱.	Certification of sampling procedures by the team leader of the	ification of sampling procedures by the team leader of the personnel conducting the sampling procedures:				
	"I certify that the data presented in this test report are, to the b and complete. All exceptions are listed and explained below."	ertify that the data presented in this test report are, to the best of my knowledge and belief, true, accurate, I complete. All exceptions are listed and explained below."				
	Signature: Ashly La- Date: 6/14/99	Printed Name: Title: Representing:	Ashley V. Larson Operations Manager Precision Environmental			
2.	Certification of test report by the senior staff person at the testing company who is responsible for compiling and checking the test report:					
	"I certify that this test report and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the test information submitted. Based on my inquiry of the person or persons who performed sampling and analysis relating to the performance test, the information submitted in this test report is, to the best of my knowledge and belief, true, accurate, and complete. All exceptions are listed and explained below.:					
	Signature: Ashly Lon- Date: 6/14/99	Printed Name: Title: Representing:	Ashley V. Larson Operations Manager Precision Environmental			

## Table of Contents

Section	Description	<u>Page</u>
1.00	Introduction	1
2.00	Summary of Results	1
2.10	Method 21 Results	1
3.00	Test Procedures	2
	List of Tables	
Table 1	Method 21 Results Summary	3

## List of Appendices

Appendix A Field Data Sheets

#### 1.00 Introduction

This report is a summary of air emission monitoring and analysis performed by Precision Environmental as requested by:

Jeffrey W. Stock Environmental Technology and Safety Services/3M Building 2-3-09 935 Bush Avenue PO Box 33331 St. Paul, Minnesota 55133-3331

Monitoring results and procedures described in this report were performed on June 23, 1999 in conjunction with the following project:

Hazardous Waste System Leak Testing 3M Tape Manufacturing Division Plant St. Paul, Minnesota 3M Project No. 20-1525 3M Laboratory Request No. W2107

This location will be referred to as the project site for the remainder of the report. The purpose of the project was to test the hazardous waste system for leaks in accordance with EPA Method 21 and 40 CFR Part 264 Subpart BB-Air Emission Standards for Equipment Leaks.

#### 2.00 Summary of Results

#### 2.10 Method 21 Results

The St. Paul Tape Plant Hazardous Waste System was tested for leaks on June 23, 1999. Testing was conducted in accordance with EPA Method 21 and 40 CFR Part 264 Subpart BB-Air Emission Standards for Equipment Leaks.

A summary of the monitoring is as follows:

- A catalytic oxidation detector (GAS TECH Trace-Techtor) was used to test for leaks of the hazardous waste system. All valves and open-ends were tested in accordance with Method 21. A summary of results is shown in Table 1. Field data sheets are enclosed in Appendix A.
- 2. Based on the test results, no leaks were detected at the tested locations of the hazardous waste system.

#### 3.00 Test Procedures

The St. Paul Tape Plant Hazardous Waste System was tested for leaks on June 23, 1999. Testing was conducted in accordance with EPA Method 21 and 40 CFR Part 264 Subpart BB-Air Emission Standards for Equipment Leaks. Sampling parameters were as follows:

<u>Parameter</u>

Monitoring Instrument:

Catalytic Oxidation Detector

Model:

Trace-Techtor Manufacturer:

GAS TECH

Reference Compound: Calibration Gas:

Not Applicable

Response Factor(s):

4,400 ppmv n- Hexane

Not Applicable

Calibration Precision:

0.6 %

Response Time:

4

15 Seconds

Sample Flow Rate:

2 LPM

A summary of results is shown in Table 1. Field data sheets are enclosed in Appendix A.

Table 1

Method 21 Results Summary

Hazardous Waste System Leak Testing

3M Tape Manufacturing Division Plant - St. Paul, Minnesota

Precision Environmental June 23, 1999

Compliance Limit: 500 ppmv

Location	I.D. No.	Description	Background, ppmv	Result, ppmv	Difference, ppmv	Da/E-4
Building 51	2	Ball Valve	16	20	Difference, ppiny	Pass/Fail
Building 51	4	Valve	16	20	4	Pass
Building 51	9	Valve	3	3	0	Pass
Building 51	8	Open-End (Plugged)	3	4	1	Pass
Building 51	10	Valve	4	4	0	Pass
Building 51	10	Open-End (Gauge)	4	4		Pass
Building 51	13	Check Valve	4	4	0	Pass
Building 51	18	Gate Valve	4	4		Pass
Building 51	20	Valve	4	4	0	Pass
Building 51	20	Open-End	4	5	0	Pass
Building 51	23	Open-End (Capped)	2	2	·	Pass
Building 51	28	Gate Valve	3	6	. 0	Pass
Building 51	28	Open-End (Plugged)	3	3	3	Pass
<b>g</b>		opon and (ridggod)	3	3	0	Pass
Building 22	30	Pump	2	2	0	Pass
Building 22	31	Open-End (Plugged)	2	2	o o	Pass
Building 22	31	Valve	2	3	1	Pass
Building 22	33	Ball Valve	2	2	0	Pass
Building 22	34	Ball Valve	2	1	-1	
Building 22	35	Air-Actuated Valve	2	2	-1	Pass
Building 22	38	Open-End (Plugged)	3	3	0	Pass
. 5		-per <b>-</b> na (* *129 <b>3</b> 55)	Ü	3	U	Pass
Tanker Area	40	Open-End (Cam-Lock)	5	5	. 0	Pass
Tanker Area	41	Open-End	5	5	0	Pass
Tanker Area	42	Open-Епd (Cam-Lock)	5	5	0	Pass

# PRECISION

	ENVIRONN	1ENIAL	METHOD 21 DATA SHEET Page		EET Page of	
	eld Monitoring and Testing Services		•			
	Client Name: 3M	ET45	Project Title:		Here have some a confidence	
	Address: 935 bush Aux		Project Num	Project Title: Haz. Wast System Leak Defection Project Number:		
	City, State Zip:	City, State Zip: St. Paulimy		Contact:	ieff Stock	
:	Span	4400	Hexane	= 4400	0=0	
	Bulling 51	Ambient Azr		1.00		
	Background	3 ppn	Background	Resultern	Connerts	
	Buckground #2	Ballvalve	16	20	Backgrand collect -3' from welve	
	#4	valve	16	20	Braceground collected us from valve	
	#9	value	3	3	Backgrand allot -41 For vale	
	#8	phydogaeid	3	4	Background collected = 4 from sample	
	#10	Valve	4	4	Background wikefed ~ 2' ave	
	#10	gaure	4	4	"	
	#13	checkvale	4	4	Ц	
	HLY 1	galvalre	14	t-(	Background collected -31	
*1	#20	value	4	Ч	Background collected ~ 31 away	
	#20	openend	ij	5	li	
	#23	openend openend	2	,2	Background collected - J'away	
	#28		3	6	Background wilected -3' away	
	#28	gatevalve openend	3	3	L <sub>1</sub>	
PWL	: 16					
	Build Ing 22	Buckground	2			
	Location	Description	Backasoust	front	Congret	
	#30 #21	pump	2	2	Backgrand collected = 41 away	
	. +31	ODEN en	2	2	΄ '(	
AVY	#3/	Valve hardy	2	3	Background collected ~ 31 away	
	#33	Ballvalve	2	2	Background collected - 3'a-as	
	#34	Ball valve	2	١	(1	
	735	value POV	7		V	
}	#38	6pch 22	3	3	Background collected - 3'away	
	<u> 740</u>	can lock	S	5	· · · · · · · · · · · · · · · · · · ·	
	# 41	openend	5	5		
.	# 47	canlock	5	5		
ŀ		•		• •	, see hop	
	·					
	Form Completed by: AVL Date Completed: 6/23/99 Present on Site: Au				Present on Site: Acc	
	8251 Main Street Northeast • Minneapolis, Minnesota 55432-1849 • (612) 780-9787 • FAX (612) 780-7157 REV-062399					

## Attachment 4

# **3M**Environmental Standard



ET&S Providing Global Leadership

# **Above Ground Tank Inspection**

**Applicability** 

This standard applies to all 3M U.S. and O.U.S. operations.

Introduction

The following preventive maintenance/inspection standard has been developed to minimize the potential for adverse environmental effects associated with the above ground storage of hazardous substances and petroleum products.

Standard

Above ground storage tanks containing hazardous substances or petroleum products shall be routinely inspected.

Inspection Routine

Inspect tanks daily and monthly or at other appropriate intervals. Include the date of inspection and the inspector's initials. Keep inspection logs on file for three years.

Suggested inspection procedures:

DAILY

Examine the visible and readily accessible portions of each tank system, including the tank, piping, pumps, secondary containment, etc., for evidence of active leaks. Signs of leakage may include liquid flowing, unusual paint blistering, an unexplained wet area or odor inside the secondary containment. Note and investigate unusual conditions.

**MONTHLY** 

Check overfill and spill protection equipment (high level alarms, gauges, shutoffs) for proper operation. Examine visible portions of tank foundations and piping supports for deterioration. Check secondary containment structures for erosion, cracking, or other conditions which may compromise their integrity. Note and investigate unusual conditions.

Comments

Tanks containing materials such as water or inert gas are not part of this program, but some level of routine inspection may be appropriate.

For Further Information

Contact Environmental Technology and Services, St. Paul, MN, 612-778-4335

R. P. Bringer, Staff Vice President Environmental Technology and Services

Reissued: 1 Nov 90 -- to include O.U.S.

# Attachment 5

.....

.

# Attachment 6