ARCO Alaska, Inc.

Post Office Box 360 Anchorage, Alaska 99510 Telephone 907 277 5637



August 16, 1983

AUG 26 RECT

Mr. Raymond C. Nye Environmental Protection Specialist U.S. EPA - Region X 1200 Sixth Avenue Seattle, WA 98101

SUBJECT: Turbine and Heater Units - Prudhoe Bay PSD

Permits

Dear Ray:

This letter is in response to your letter of April 5, 1983 requesting information on turbine and heater units in the Prudhoe Bay field eastern operating area under existing PSD permits. Your letter requested:

- 1) identification of installed and ordered units
- 2) source test dates for permitted units
- 3) unit capacity ordered matched to unit capacity permitted

The charts attached provide the requested information.

There are variations to the permits shown in the charts that we believe are within the scope of the applications. I have included a discussion of these variations to supplement your information request.

First, the Seawater Injection Plant East (SIPE) contains four 2500 HP turbines instead of the four 4000 HP turbines itemized in your permit list. This variation of horsepower is addressed within Table 3-2 of the Technical Note of Air Quality Impacts in Prudhoe Bay Oil Field, December 1980, Radian Corp. And, the proposed heaters to be installed are two 185 MMBtu/hr heaters included in the 750 MMBtu/hr heater capacity permitted at the SIPE.

Second, the Seawater Treatment Plant (STP) plans to operate six 120 MMBtu/hr heaters rather than the permitted heaters listed below. However, the proposed units should result in less emissions as shown.



Mr. Raymond C. Nye August 16, 1983 Page 2

Permitted Heaters	g/Sec NO <sub>X</sub>	Proposed Heaters	g/Sec NO <sub>x</sub>
3-100MM 2-60 MM	7.88 2.85	6-120MM	17.85
3-100MM	7.2		
TOTAL	18.93		17.85

Note: All calculations are based on heater emission factors included in the PSD Permit Application for the Prudhoe Bay Unit Waterflood, September 1979. Radian Corp.

There are also several turbines and heaters shown on the lists as permitted but not currently planned. The location and required capacity requirements of these sources is currently being reevaluated. As noted on the attached lists sealift and subsequent start-up of these units would occur no earlier than 1986.

Finally, please note Michael Johnston's letter (February 22, 1980), which discusses the resulting permit. He indicated that the permit will specify the turbine size and heat recovery combination that describes the worst case ambient impact scenario. This preliminary determination would indicate the worst case scenario would be permitted, but that the permit can be changed without public comment as long as the variation is within the scope of the application. We believe that all of the variations of the permitted sizes shown on the attached charts are within the scope of the existing permits.

If you have any questions about the discussion of permitted units or need additional information for the attached charts, please contact me (907) 263-4307 or W. Pat Metz (907) 263-4306.

Alan J. Schuyler Senior Engineer

Regulatory Compliance

AJS:tlh-0016 Attachment

cc: Steve Torok, EPA-Juneau - w/attachment Leonard Verrelli, ADEC-Juneau - w/attachment

#### PSD PERMITTED AIR SOURCES

### FLOW STATION 1 (FS-1)

PSD Permit	Quantity	Size	Sealift Year	Startup Date	Test Date
(II) X8009	1 (2)	5 MHP	1981	1984	1984
(II) X8009	1	5 MHP	1985	1986	1986
(II) X8009	<b>(2</b> ) (3)	36 MHP	1983	1984	1984
(II) X8009	1)	36 MHP	P	_	_
(IV) X8113	1 (1)	5 MHP	P	-	-
(IV) X8113	1 (1)	125 MM	P	-	
(IV) X8113	1 (1)	36 MHP	P	_	-

P = Currently permitted but will not be constructed before 1988 MM =  $1 \times 10^6$  Btu/hr. MHP = 1000 HP

# PSD PERMITTED AIR SOURCES

## INJECTION PLANT-EAST (IPE)

t Startup
1984 1984
1984 1984
1984 1984
1984 1984

 $MM = 1 \times 10^6 \text{ Btu/hr.}$  MHP = 1000 HP

WF = Waterflood S = Swap I

#### PSD PERMITTED AIR SOURCES

### SEAWATER TREATMENT PLANT (STP)

			Act	cual	Sealift	Startup	
PSD Permit	Quantity	Size	Quantity	Size	Year	Date	Test Date
(WF) X8101	3 (3)	110 MM	6	120 MM	1983	1984	1984
(WF) X8101	2 (2)	60 MM					
(S) X8101	3	100 MM					
(IV) X8113	8 (8)	4 MHP					

 $MM = 1x10^6 \text{ Btu/hr.}$  MHP = 1000 HP

WF = Waterflood S = Swap I

# PSD PERMITTED AIR SOURCE FLOW STATION 2 (FS-2)

PSD P	ermit	Quantity	S	ize	Seal	ift Year	Startup Date	Test Date
(II)	X8009	2	36	MHP	1	981	1982	1983
(II)	X8009	(1) (H)	36	MHP	1	983	1984	1984
(II) :	X8009	1	36	MHP		P	-	-,
(II) :	X8009	(1)	5	MHP	1	980	1982	1983
(II)	X8009	(1) (2)	5	MHP	1	982	1983	1983
(II)	X8009	1 (1)	100	MM		P	-	- 0
(IV)	X8113	2 (2)	5	MHP	1	985	1986	1986

P = Currently permitted but will not be constructed before 1988 MM =  $1 \times 10^6$  Btu/hr. MHP = 1000 HP

PSD PERMITTED AIR SOURCES

### FLOW STATION 3 (FS-3)

PSD Permit	Quantity	Size	Sealift Year	Startup _Date_	Test Date
(II) X8009	2	36 MHP	1982	1983	1983
(II) X8009	1 (4)	36 MHP	1983	1984	1984
(II) X8009	1	36 MHP	P	-	_
(II) X8009	(1)	5 MHP	1980	1983	1983
(II) X8009	1	5 MHP	1982	1983	1983
(IV) X8113	2 (2)	5 MHP	1984	1985	1985
(IV) X8113	1 (1)	125 MM	P	-	-

P = Currently permitted but will not be constructed before 1988 MM =  $1 \times 10^6$  Btu/hr. MHP = 1000 HP

#### PSD PERMITTED AIR SOURCE

### CENTRAL COMPRESSOR PLANT (CCP)

PSD Permit	Quantity	Size	Sealift Year	Startup Date	Test Date
(II) X8009	1 (1)	25 MHP	1981	1982	1982
(II) X8009	1 (1)	26 MM	P	-	-

P = Currently permitted but will not be constructed before 1988 MM =  $1 \times 10^6$  Btu/hr. MHP = 1000 HP