

August 18, 2000

Mr. Paul Peronard
US EPA
EPR-SA
999 18th St, Suite 500
Denver, CO 80202

Mr. Paul Peronard
US EPA
501 Mineral Avenue
Libby, Montana 59923


Re: **Addendum 3 to Approved Work Plan dated July 28, 2000**
Libby Asbestos Site (#8-BC), Libby, Lincoln County, Montana

Dear Mr. Peronard:

Please find attached, for your review and approval, Addendum No. 3, revising the work scope for the planer shop cleaning, in the above referenced work plan. URS is planning to begin the work described in Addendum No. 3 at 5:00 p.m. today so please call me with any comments or fax your approval to me by 2:00 p.m..

Thank you in advance for your immediate attention with this matter. Please call if you have any questions concerning this submittal.

Sincerely,



Jim Stout
Project Coordinator
Libby Asbestos Site

cc: Jon Constan, Montana Department of Environmental Quality (3 copies)
Ken Lund, Holme Roberts & Owen
Bob Mariam, WR Grace
David Cleary, WR Grace
Karen Brown, WR Grace
Matthew Cohn, US EPA

ADDENDUM NO. 3
Work Plan – Removal of Asbestos and Vermiculite
at the Export Plant, Libby Asbestos Site
18 August 2000

This addendum to the 28 July 2000 Work Plan for the removal of asbestos and vermiculite at the Libby Asbestos Site is issued to amend the sequence of cleaning activities for the Planer Shop, while maintaining the safety of the public and contractor personnel.

To finish the cleaning of the Planer Shop, URS and its subcontractor AcandS will do the following:

1. After 5:00 p.m. on August 18, 2000, URS and AcandS employees, in full PPE including respirators and Tyvek, will hand shovel and grub the Planer Shop foundation as needed for installation of a membrane to collect power wash overspray. The soil next to the Planer Shop foundation will be thoroughly wet to minimize dust prior to hand digging. Also, a source appearing to be vermiculite, leaking from the east wall of the Planer Shop, will be plugged and the loose material cleaned up prior to hand digging.
2. Building materials that have been decontaminated from inside the Planer Shop will be taken outside of the proposed exclusion zone to a staging area near the URS decontamination trailer and covered, if necessary.
3. Bagged asbestos impacted materials, including used PPE, will be removed from inside the Planer Shop and staged in the bed of a 12 cubic yard dump truck parked on the west side of the Planer Shop and covered with a tarp until approved for disposal at the mine.

To the extent that URS is able to continue work on the removal action each day without interruption, we anticipate that the September 4, 2000 deadline for completion of Planer Shop decontamination can be met.

Signature

Date

Printed Name of Signer