



ecology and environment, inc.

International Specialists in the Environment

Cloverleaf Building 3, 6405 Metcalf
Overland Park, Kansas 66202
Tel: (913) 432-9961. Fax: (913) 432-0670

May 15, 1998

Evan Kifer
Wellhead Protection Section
P.O. Box 250
Rolla, Missouri 65402

109316

Site:	Zykan Landfill
ID #:	100001574680
Break:	1.6
Other:	5-15-98



Dear Mr. Kifer,

Under the Superfund Technical Assessment and Response Team (START) contract with the U.S. Environmental Protection Agency (EPA), Ecology and Environment, Inc. (E & E), has been tasked to abandon 54 monitoring wells which were installed as part of a site investigation of the Zykan Landfill site in Wright City, Warren County, Missouri (see attached maps: Figures 1 and 2). This is a request for variance on the Missouri Well Construction regulation 10 CSR 23-4.080.

In 1971, Bob's Home Service (BHS), Inc., began operating as a refuse disposal area. The landfill was owned and operated by James Zykan under the title, "BHS Sanitary Landfill." Immediately to the north lies a hazardous waste landfill, BHS Industrial Waste Disposal Facility, which operated from 1977 until 1985 under an interim Resource Conservation and Recovery Act (RCRA) permit. Zykan was also the owner of the hazardous waste landfill. To avoid confusion between the two landfills, BHS Sanitary Landfill is referred to as the Zykan Landfill.

While in operation, several MDNR inspections of the Zykan Landfill revealed unsatisfactory operating practices, including locating fill areas in areas of natural drainage and lack of sufficient cover. In the Zykan Landfill, waste was disposed of in relatively shallow (8-10 feet) trenches. While in operation, the sanitary landfill was to accept municipal solid waste, bulky waste, brush and untreated wood waste. However, in 1972, Zykan expressed interest in accepting industrial chemicals as well. No permit to dispose of such wastes in the Zykan Landfill was granted. However, a letter from the Tretolite Division of Petrolite Corporation in St. Louis, Missouri to the Missouri Department of Health indicates that the sanitary landfill received 30 drums of industrial waste per month. Petrolite describes this waste as "paper

waste, woodscraps, polymers of condensed alanolamines (these should be biodegradable), other chemical wastes such as polyethylene oxide ethers not currently marketable" (Petrolite, 1974).

In 1986, Missouri Department of Natural Resources placed the former BHS Sanitary Landfill (Zykan Landfill) on the registry of Confirmed Abandoned or Uncontrolled Hazardous Waste Disposal Sites in Missouri. Entry was made under the name "Zykan Site" to avoid confusion between BHS Sanitary Landfill and BHS Industrial Waste Disposal Facility. The registry report stated that the industrial wastes accepted by the sanitary landfill was similar to that which was subsequently disposed of in the hazardous waste facility to the north. Waste categories included "toxic pesticides, organic hydrocarbons, inorganic heavy metals, paints, pigments, and trihalomethanes" (MDNR, 1986, MDNR, 1996).

The monitoring wells at the Zykan Site were installed over a period of about 10 years (1977-1987) due to a series of investigations that occurred over that time period. Several different monitoring well designs have been implemented at the site. However, the wells can be classified as belonging to one of five distinct series of monitoring wells (B, GM, GMW, K, and P series). Specific diagrams are attached for B, GM and GMW series wells (see Attachments 1, 2 and 3). The K series wells were bored with 6" hollow-stem augers. The annular space between the screened interval and the total depth was filled with sand. The remainder of the annular space above the sand was filled with a cement-bentonite grout (EPA, 1986). Exact construction details are unknown for the P series wells, but a report by the EPA (1986) states "... it is inferred construction procedures follow that of the initial P series wells (P-1 to P-16)." See Attachment 4 for the generalized well construction for the P series wells. It is unknown if a bentonite plug was used to seal off the space above the sand and it is assumed local (native) soil was used to fill the remainder of the annular space (EPA, 1986). Well construction information for all wells is summarized in Table 1.

An assessment conducted by E & E in March 1998 revealed that 54 of the wells located around the Zykan Landfill were in very poor condition. Several of the B series wells have severely cracked concrete pads. Though the assessed B series wells are equipped with locking steel stick-ups, two of the wells were lacking a well cap. The GM series wells lacked any well cap and no concrete pad was observed around any of the stick-ups. The steel stick-ups were unlocked at the time of the assessment. One GMW well was assessed. It was found to have a steel stick-up and a poured concrete pad, though the stick-up could not be properly locked. (NOTE: The other GMW wells, along with other wells at the site, are currently being used in a RCRA post-closure monitoring plan for the hazardous waste landfill to the north of this site and are not being considered for abandonment.) In the K and P series wells no concrete pads or protective

stick-ups were observed. This lack of protection apparently led to the destruction of some of these wells, as E & E was unable to locate some of the wells and others had broken PVC casings.

The wells are located in the vicinity of known hazardous waste disposal areas. Given this and the initial poor construction of the wells and the poor well maintenance, E & E has concluded that all of the assessed monitoring wells provide a threat to ground water, to varying degrees. Due to the evaluation given by E & E, EPA is requesting the abandonment of the described monitoring wells.

To carry out the abandonment an initial attempt will be made to pull all well casings. E & E is requesting a variance in the abandonment of the monitoring wells in the event that the casings cannot be pulled. The proposed variance for each well will include the following procedures, to be performed by a permitted well installation contractor:

- Soil will be excavated around the well to a depth of three feet below ground surface (BGS).
- The riser pipe will be cut off at three feet BGS.
- A high-solids bentonite slurry-grout, as described in 10 CSR 23-4.060 (11A), will be placed, using a tremie pipe, in the well from the bottom to the top.
- A one-foot thick concrete plug will then be placed on top of the well (from 3' to 2' BGS).
- From 2' BGS to the surface will be backfilled with native soil, compacted, and graded so that water runs away from the well location.

If you have further questions with regard to this request for variance, please contact Bob Overfelt, Patty Currier or myself at (913) 432-9961.

Sincerely,



Ron Ramold
Project Manager

ATTACHMENTS:

1. Maps
2. Table 1: Summary of Wells to be Abandoned
3. Well Construction Diagrams B Series Wells
4. Well Construction Diagrams GM Series Wells
5. Well Construction Diagram GMW Series Well
6. General Well Construction Diagram P Series Wells


REFERENCES

- Environmental Protection Agency (EPA), 1986, Update of the Hazardous Waste Ground-Water Task Force Evaluation of the B.H.S., Inc., Wright City, Missouri Facility, December 11, 1986.**
- Missouri Department of Natural Resources (MDNR), 1986, Confirmed Abandoned or Uncontrolled Hazardous Waste Disposal Sites in Missouri, Annual Report, January 1, 1986.**
- _____, 1996, Confirmed Abandoned or Uncontrolled Hazardous Waste Disposal Sites in Missouri and Hazardous Waste Remedial Fund Statement of Revenue, Expenditures, and Changes in Fund Balance, Fiscal Year 1995 Annual Report, January 1996.**
- Petrolite Corporation, Tretolite Division, 1974, E.J. Schnieders, Plant Manager, to Barney Bergman, Missouri Department of Health, Letter, April 18, 1974.**

ATTACHMENT 1

Maps

Figure 1: Site Location Map







Figure 2: Monitoring Well Location Map

ATTACHMENT 2

Table 1: Summary of Wells to be Abandoned

Table 1

**MONITORING WELL ASSESSMENT SUMMARY OF WELLS TO BE ABANDONED
ZYKAN LANDFILL SITE—WRIGHT CITY, MISSOURI
FEBRUARY 1998**

Monitoring Well	Water Level	Depth of Well		Depth to Top of Screen (reported ^a)	Surface Pad (Y/N)	Well Protector (Y/N)	Well Cap (Y/N)	Nominal Casing Diameter (inches) and Material	Borehole Diameter (inches)	Grout	Comments
		Reported ^a	Measured								
B Series											
B-15	38.96	58.89	58.40	48.89	Y	Y	Y	2" S _p	6"	Cement-bentonite grout	Cracked pad.
B-16	28.16	55.71	55.86	45.71	Y	Y	Y	2" S _p			Cracked pad.
B-17A	78.95	80.99	79.85	70.99	Y	Y	N	2" S _p			Cracked pad.
B-17C	25.56	50.44	50.90	40.44	Y	Y	Y	2" S _p			
B-18	19.72	45.86	45.85	35.86	Y	Y	Y	2" S _p			Cracked pad.
B-18A	18.86	30.89	25.20	25.89	Y	Y	Y	2" PVC			Cracked pad.
B-19A	16.21	36.22	35.80	31.22	Y	Y	Y	2" S _p			Cracked pad.
B-19B	17.96	24.72	20.10	14.72	Y	Y	Y	2" PVC			
B-20	23.04	55.86	55.85	45.86	Y	Y	Y	2" S _p			Cracked pad; no padlock.
B-22A	16.90	43.16	40.34	33.16	Y	Y	Y	2" S _p			Cracked pad.
B-23A	2.63	23.43	23.36	13.43	Y	Y	N	2" S _p			Cracked pad.
GM Series Wells											All GM wells constructed with 6" diameter steel well protectors.
GM-1	87.40	126	124.75	95.5	N	Y	N	4" PVC	?	Cement-bentonite grout	
GM-1R	26.01	60.3	57.58	37.3	N	Y	N	4" PVC			Electrical box attached.
GM-2	---	175.8	---	147.3	N	Y	N	4" PVC			Pump in well.
GM-3	dry	125.8	77.20	97.0	N	Y	N	4" PVC			
GM-4	46.10	105.0	83.50	75.7	N	Y	N	4" PVC			
GM Series Wells											
GMW-1R	38.63	104.25'	99.18	---	Y	Y	Y	2" S _p	6"	-	Broken well protector lid.
K Series Wells											
K-2 (ox)	36.20	58.9	55.03	56.9	N	N	N	1.5" PVC	? or = 6"	Cement-bentonite grout	
K-2 (80)	69.91	81.20	74.7	61.2	N	N	N	1.5" PVC			
K-3 (ox)	dry	76.35	78.1	66.35	N	N	Y	1.5" PVC			
K-3 (80)	47.21	79.9	76.45	59.9	N	N	Y	1.5" PVC			
K-3 (110)	---	120.8	---	90.8	N	N	Y	1.5" PVC			0.5" PVC within 1.5" PVC prevented depth measurements.
K-3 (br)	---	200.8	---	198.8				0.5" PVC			
K-4 (120)	---	130.2	---	120.2	N	N	Y	1.5" PVC			0.5" PVC within 1.5" PVC prevented depth measurements; reported depth data appears to be in error.
K-4 (br)	---	130.2	---	120.2				0.5" PVC			
K-4 (brr)	76.6	237.1	> 151	212.1	N	N	N	1.5" PVC			
K-5 (ox)	25.12	51.1	47.93	41.1	N	N	Y	1.5" PVC			
K-5 (80)	28.6	81.2	78.6	61.2	N	N	Y	1.5" PVC			
K-5 (sa)	---	106.7	---	96.7	N	N	Y	1.5" PVC			0.5" PVC within 1.5" PVC prevented depth measurements.
K-5 (br)	---	170.7	---	168.7				0.5" PVC			
K-6 (ox)	13.92	22.1	23.45	14.1	N	N	N	1.5" PVC			
K-6 (sl)	48.80	124.95	117.20	104.95	N	N	N	1.5" PVC			
K-6 (br)	47.50	180.9	> 151	175.9	N	N	N	1.5" PVC			
K-7 (ox)	dry	44.85	40.75	34.85	N	N	N	1.5" PVC			

Table 1—(Continued)

**MONITORING WELL ASSESSMENT SUMMARY OF WELLS TO BE ABANDONED
ZYKAN LANDFILL SITE—WRIGHT CITY, MISSOURI
FEBRUARY 1998**

Monitoring Well	Water Level	Depth of Well		Depth to Top of Screen (reported ^a)	Surface Pad (Y/N)	Well Protector (Y/N)	Well Cap (Y/N)	Nominal Casing Diameter (inches) and Material	Borehole Diameter (inches)	Grout	Comments
		Reported ^a	Measured								
K Series Wells											
K-7 (si)	91.95	7.7	104.95	-2.3	N	N	N	1.5" PVC	7 or = 6"	Cement-bentonite grout	Reported depth data appears to be in error.
K-7 (br)	65.98	195.1	> 151	190.1	N	N	N	1.5" PVC			
K-9 (80)	16.47	80.55	69.5	60.55	N	N	N	1.5" PVC			Silt at bottom of well.
K-9 (sa)	35.00	125.2	120.20	115.2	N	N	N	1.5" PVC			
K-9 (br)	24.80	164.2	> 151	159.2	N	N	N	1.5" PVC			
K-10 (80)	44.42	82.1	77.10	77.1	N	N	N	1.5" PVC			
K-10 (br)	50.91	80.3	81.55	60.3	N	N	N	1.5" PVC			
K-11 (ox)	9.38	49.9	43.25	39.9	N	N	N	1.5" PVC			0.5" PVC br insert missing from 1.5" PVC ox casing.
K-11 (br)		119.75		99.75	N	N	N	0.5" PVC			
K-11 (sa)	43.22	72.15	54.31	62.15	N	N	N	1.5" PVC			
K-12 (br)	107.55	216.35	> 151	214.35	N	N	N	1.5" PVC			
P Series											
P-18	17.62	53.6	53.3	13.6	N	N	N	4" PVC	?	Native soil (assumed)	
P-19	dry	33.5	54.05	-6.5	N	N	Y	4" PVC			Reported depth data appears to be in error.
P-20	15.76	52.7	51.52	12.7	N	N	Y	4" PVC			Large hole in side of casing stickup
P-21	47.75	53.65	54.73	13.65	N	N	Y	4" PVC			
P-22	53.40	52.8	53.40	12.8	N	N	Y	4" PVC			Well almost dry.
P-A	44.25	56.85	59.78	44.85	N	N	N	2" PVC	?	?	8" steel surface casing surrounding PVC stickup and protruding ~ 3" above surface.
P-B	52.5	80.3	80.2	68.3	N	N	Y				
P-C	57.63	84.0	85.25	72.0	N	N	Y				
P-D	25.61	55.0	50.18	43.0	N	N	Y				

KEY: E = Reported in EPA (1986).
J = Reported in Jacobs (1989).

Notes: For located wells, given reported depths incorporate height of stickup measured during site reconnaissance.

K series notation:

ox = Oxidized/unoxidized glacial till interface.
80 = 80 feet in depth.
sa = Completed in sand layer.
si = Completed in silty layer.
110 = 110 feet in depth.
br = Bit refusal.
brr = Bit refusal replacement.

ATTACHMENT 3

Well Construction Diagrams B Series Wells

GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: R. George/B. Bolin

Date: 11-9-85

Inspected by: D. Bury

Date: 11-9-85


Piez./Well# 15

Project No. W4C7729

Task No. 6

Method of Installation: _____

REMARKS: _____



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: Deka Date: 11/9-12/85

Inspected by: B. Billman Date: 11/9-12/85


Method of Installation: _____

REMARKS: _____

Piez./Well# 16

Project No. W4C7729

Task No. 6



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: Canonie

Date: 11/7-8/85

Inspected by: R. Johnson

Date: 11/7-8/85


Piez./Well# 17A

Project No. W4C7729

Task No. 6

Method of Installation: _____

REMARKS: _____



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: R. George

Date: 12-4-85

Inspected by: D. Bury

Date: 12-4-85


Piez./Well# B-17C

Project No. W4C7729

Task No. 6

Method of Installation: _____


REMARKS: _____



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.
LOCATION: Wright City, Missouri
Installed by: Deka **Date:** 11-18-85
Inspected by: B. Billman **Date:** 11-18-85
Method of Installation: _____
REMARKS: _____

Piez./Well# 18
Project No. W4C7729
Task No. 6



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: Deka Date: 11-1-9-85

Inspected by: B. Billman Date: 11-19-85


Method of Installation: _____

REMARKS: _____

Piez./Well# 18A

Project No. W4C7729

Task No. 6



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: R. George/B. Bolln

Date: 11-20-85

Inspected by: D. Bury

Date: 11-20-85


Method of Installation: _____

REMARKS: _____

Piez./Well# 19A

Project No. W4C7729

Task No. 6



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: R. George/B. Bolin

Date: 11-21-85

Inspected by: D. Bury

Date: 11-21-85


Piez./Well# 19B

Project No. W4C7729

Task No. 6


Method of Installation: _____

REMARKS: _____



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: <u>BHS, INC.</u>		Piez./Well# <u>20</u>
LOCATION: <u>Wright City, Missouri</u>		Project No. <u>W4C7729</u>
Installed by: <u>Deka</u>	Date: <u>11-5-85</u>	Task No. <u>6</u>
Inspected by: <u>B. Billman</u>	Date: <u>11-5-85</u>	
Method of Installation: _____		
REMARKS: _____		



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: Deka

Date: 12-5-85

Inspected by: K. Flory

Date: 12-5-85


Method of installation: _____

REMARKS: _____

Piez./Well# 22A

Project No. W4C7729

Task No. 6



GROUND WATER OBSERVATION WELL REPORT

PROJECT NAME: BHS, INC.

LOCATION: Wright City, Missouri

Installed by: Deka Date: 12-4-85

Inspected by: B. Billman Date: 12-4-85


Method of Installation: _____

REMARKS: _____

Piez./Well# 23A

Project No. W4C7729

Task No. 6




ATTACHMENT 4

Well Construction Diagrams GM Series Wells

MONITORING WELL GM1


N 684.2
E 1164.6
E 706.3



End of boring
Sampled: 10-13-82
Revised: 11-3-82
Installed: 11-3-82
Grouted: 11-6-82

MONITORING WELL GM2


N 2821.6
E 653.3
E 812.3



End of boring
Sampled: 10-11, 12-82
Revised: 11-3, 4-82
Installed: 11-4-82
Grouted: 11-8-82



MONITORING WELL GM3

N 2746.9
E 1727.4
E 772.8




E 675.0
E 667.8



Symptm 10-14-82
Received 11-4-82
'replied 11-5-82
Grated 11-9-82



NOTE: Installed through 6" dia
temporary steel casing
centering at floor position



El 6592, End of test boring
Sampled 8-2-94, Grouted 8-14-94

		D.E. Klockow & Associates Consulting Geotechnical Engineers 5921 Wagon Trail Road, Rt. 14, Columbia, Missouri 65202		314 443-6084 65202			Revision	Date
JOB No 8-008	BHS, Inc. Industrial Waste Management Facility Rt. 1, Box 116-F, Wright City, Missouri 63390 MONITORING WELL INSTALLATION DATA							
Date	8-10-64							

Soil Types

Soil Description



Clay

Clayey

Silt

Silty

Sand

Sandy

Gravel

Gravelly

Int. voids
Continuity

INTERBEDDED: Containing alternating layers of different soil types

INTERBEDDED: Containing alternating layers of different soil types

INTERBEDDED: Containing alternating layers of different soil types

LAMINATED: Containing thin and alternating layers of color or texture

MOTTLED: Containing appreciable random patches or streaks of varying color or texture

LAYER: Thickness greater than 3"

SEAM: Thickness ranges from 1/8" to 1/4"

STREAKED: Thickness less than 1/8"

Sampler Types

1. Thin-walled tube
2. Thin-walled

3. Thin-walled, 2 OD, 1 ID
ASTM D1586 (1974)

No recovery

Hydraulically pushed, 2 OD, 1 ID
Thin-walled sampler

Soil Properties

Symbol Property

M Shrinkage potential, percentage

DR Degree of saturation

NP Natural porosity

Q Unconfined compressive strength

W Plasticity index, liquid limit, plasticity chart

U Compression index, recompression index

Ve Coefficient of volume change, void ratio

Q Coefficient of consolidation, permeability

LEGEND FOR BORING LOGS

(Location 22+02.8
 :coordinates) P+25.0 K1 (SA/BR) (piezometer identification)

none type 50 to 100 %,
 50 %, with 5 to 12 %.

having alternating layers
 5

having appreciable, random
 tilts of varying color or

having thin and alternating
 layers.

3 observations random
 of varying color or

greater than 3".


ages from $\frac{1}{8}$ " to 3"

paper thin

1/4 tube
 -74

0 split-barrel
 -67 (B74)

pushed, 2" O.D., 1 3/4" I.D.
 sampler




DD - Date drilled
 DPI - Date piezometer installed

0 3 6 9 12
 Horizontal Scale: inches

Vertical Scale: Same as boring log

Stratification
 changes from
 boring logs
 M1
 S1
 S2
 M2
 S3
 M3
 S4
 M4
 S5
 M5
 S6
 M6
 S7
 M7
 S8
 M8
 S9
 M9
 S10
 M10
 S11
 M11
 S12
 M12
 S13
 M13
 S14
 M14
 S15
 M15
 S16
 M16
 S17
 M17
 S18
 M18
 S19
 M19
 S20
 M20
 S21
 M21
 S22
 M22
 S23
 M23
 S24
 M24
 S25
 M25
 S26
 M26
 S27
 M27
 S28
 M28
 S29
 M29
 S30
 M30
 S31
 M31
 S32
 M32
 S33
 M33
 S34
 M34
 S35
 M35
 S36
 M36
 S37
 M37
 S38
 M38
 S39
 M39
 S40
 M40
 S41
 M41
 S42
 M42
 S43
 M43
 S44
 M44
 S45
 M45
 S46
 M46
 S47
 M47
 S48
 M48
 S49
 M49
 S50
 M50
 S51
 M51
 S52
 M52
 S53
 M53
 S54
 M54
 S55
 M55
 S56
 M56
 S57
 M57
 S58
 M58
 S59
 M59
 S60
 M60
 S61
 M61
 S62
 M62
 S63
 M63
 S64
 M64
 S65
 M65
 S66
 M66
 S67
 M67
 S68
 M68
 S69
 M69
 S70
 M70
 S71
 M71
 S72
 M72
 S73
 M73
 S74
 M74
 S75
 M75
 S76
 M76
 S77
 M77
 S78
 M78
 S79
 M79
 S80
 M80
 S81
 M81
 S82
 M82
 S83
 M83
 S84
 M84
 S85
 M85
 S86
 M86
 S87
 M87
 S88
 M88
 S89
 M89
 S90
 M90
 S91
 M91
 S92
 M92
 S93
 M93
 S94
 M94
 S95
 M95
 S96
 M96
 S97
 M97
 S98
 M98
 S99
 M99
 S100
 M100
 S101
 M101
 S102
 M102
 S103
 M103
 S104
 M104
 S105
 M105
 S106
 M106
 S107
 M107
 S108
 M108
 S109
 M109
 S110
 M110
 S111
 M111
 S112
 M112
 S113
 M113
 S114
 M114
 S115
 M115
 S116
 M116
 S117
 M117
 S118
 M118
 S119
 M119
 S120
 M120
 S121
 M121
 S122
 M122
 S123
 M123
 S124
 M124
 S125
 M125
 S126
 M126
 S127
 M127
 S128
 M128
 S129
 M129
 S130
 M130
 S131
 M131
 S132
 M132
 S133
 M133
 S134
 M134
 S135
 M135
 S136
 M136
 S137
 M137
 S138
 M138
 S139
 M139
 S140
 M140
 S141
 M141
 S142
 M142
 S143
 M143
 S144
 M144
 S145
 M145
 S146
 M146
 S147
 M147
 S148
 M148
 S149
 M149
 S150
 M150
 S151
 M151
 S152
 M152
 S153
 M153
 S154
 M154
 S155
 M155
 S156
 M156
 S157
 M157
 S158
 M158
 S159
 M159
 S160
 M160
 S161
 M161
 S162
 M162
 S163
 M163
 S164
 M164
 S165
 M165
 S166
 M166
 S167
 M167
 S168
 M168
 S169
 M169
 S170
 M170
 S171
 M171
 S172
 M172
 S173
 M173
 S174
 M174
 S175
 M175
 S176
 M176
 S177
 M177
 S178
 M178
 S179
 M179
 S180
 M180
 S181
 M181
 S182
 M182
 S183
 M183
 S184
 M184
 S185
 M185
 S186
 M186
 S187
 M187
 S188
 M188
 S189
 M189
 S190
 M190
 S191
 M191
 S192
 M192
 S193
 M193
 S194
 M194
 S195
 M195
 S196
 M196
 S197
 M197
 S198
 M198
 S199
 M199
 S200
 M200
 S201
 M201
 S202
 M202
 S203
 M203
 S204
 M204
 S205
 M205
 S206
 M206
 S207
 M207
 S208
 M208
 S209
 M209
 S210
 M210
 S211
 M211
 S212
 M212
 S213
 M213
 S214
 M214
 S215
 M215
 S216
 M216
 S217
 M217
 S218
 M218
 S219
 M219
 S220
 M220
 S221
 M221
 S222
 M222
 S223
 M223
 S224
 M224
 S225
 M225
 S226
 M226
 S227
 M227
 S228
 M228
 S229
 M229
 S230
 M230
 S231
 M231
 S232
 M232
 S233
 M233
 S234
 M234
 S235
 M235
 S236
 M236
 S237
 M237
 S238
 M238
 S239
 M239
 S240
 M240
 S241
 M241
 S242
 M242
 S243
 M243
 S244
 M244
 S245
 M245
 S246
 M246
 S247
 M247
 S248
 M248
 S249
 M249
 S250
 M250
 S251
 M251
 S252
 M252
 S253
 M253
 S254
 M254
 S255
 M255
 S256
 M256
 S257
 M257
 S258
 M258
 S259
 M259
 S260
 M260
 S261
 M261
 S262
 M262
 S263
 M263
 S264
 M264
 S265
 M265
 S266
 M266
 S267
 M267
 S268
 M268
 S269
 M269
 S270
 M270
 S271
 M271
 S272
 M272
 S273
 M273
 S274
 M274
 S275
 M275
 S276
 M276
 S277
 M277
 S278
 M278
 S279
 M279
 S280
 M280
 S281
 M281
 S282
 M282
 S283
 M283
 S284
 M284
 S285
 M285
 S286
 M286
 S287
 M287
 S288
 M288
 S289
 M289
 S290
 M290
 S291
 M291
 S292
 M292
 S293
 M293
 S294
 M294
 S295
 M295
 S296
 M296
 S297
 M297
 S298
 M298
 S299
 M299
 S300
 M300
 S301
 M301
 S302
 M302
 S303
 M303
 S304
 M304
 S305
 M305
 S306
 M306
 S307
 M307
 S308
 M308
 S309
 M309
 S310
 M310
 S311
 M311
 S312
 M312
 S313
 M313
 S314
 M314
 S315
 M315
 S316
 M316
 S317
 M317
 S318
 M318
 S319
 M319
 S320
 M320
 S321
 M321
 S322
 M322
 S323
 M323
 S324
 M324
 S325
 M325
 S326
 M326
 S327
 M327
 S328
 M328
 S329
 M329
 S330
 M330
 S331
 M331
 S332
 M332
 S333
 M333
 S334
 M334
 S335
 M335
 S336
 M336
 S337
 M337
 S338
 M338
 S339
 M339
 S340
 M340
 S341
 M341
 S342
 M342
 S343
 M343
 S344
 M344
 S345
 M345
 S346
 M346
 S347
 M347
 S348
 M348
 S349
 M349
 S350
 M350
 S351
 M351
 S352
 M352
 S353
 M353
 S354
 M354
 S355
 M355
 S356
 M356
 S357
 M357
 S358
 M358
 S359
 M359
 S360
 M360
 S361
 M361
 S362
 M362
 S363
 M363
 S364
 M364
 S365
 M365
 S366
 M366
 S367
 M367
 S368
 M368
 S369
 M369
 S370
 M370
 S371
 M371
 S372
 M372
 S373
 M373
 S374
 M374
 S375
 M375
 S376
 M376
 S377
 M377
 S378
 M378
 S379
 M379
 S380
 M380
 S381
 M381
 S382
 M382
 S383
 M383
 S384
 M384
 S385
 M385
 S386
 M386
 S387
 M387
 S388
 M388
 S389
 M389
 S390
 M390
 S391
 M391
 S392
 M392
 S393
 M393
 S394
 M394
 S395
 M395
 S396
 M396
 S397
 M397
 S398
 M398
 S399
 M399
 S400
 M400
 S401
 M401
 S402
 M402
 S403
 M403
 S404
 M404
 S405
 M405
 S406
 M406
 S407
 M407
 S408
 M408
 S409
 M409
 S410
 M410
 S411
 M411
 S412
 M412
 S413
 M413
 S414
 M414
 S415
 M415
 S416
 M416
 S417
 M417
 S418
 M418
 S419
 M419
 S420
 M420
 S421
 M421
 S422
 M422
 S423
 M423
 S424
 M424
 S425
 M425
 S426
 M426
 S427
 M427
 S428
 M428
 S429
 M429
 S430
 M430
 S431
 M431
 S432
 M432
 S433
 M433
 S434
 M434
 S435
 M435
 S436
 M436
 S437
 M437
 S438
 M438
 S439
 M439
 S440
 M440
 S441
 M441
 S442
 M442
 S443
 M443
 S444
 M444
 S445
 M445
 S446
 M446
 S447
 M447
 S448
 M448
 S449
 M449
 S450
 M450
 S451
 M451
 S452
 M452
 S453
 M453
 S454
 M454
 S455
 M455
 S456
 M456
 S457
 M457
 S458
 M458
 S459
 M459
 S460
 M460
 S461
 M461
 S462
 M462
 S463
 M463
 S464
 M464
 S465
 M465
 S466
 M466
 S467
 M467
 S468
 M468
 S469
 M469
 S470
 M470
 S471
 M471
 S472
 M472
 S473
 M473
 S474
 M474
 S475
 M475
 S476
 M476
 S477
 M477
 S478
 M478
 S479
 M479
 S480
 M480
 S481
 M481
 S482
 M482
 S483
 M483
 S484
 M484
 S485
 M485
 S486
 M486
 S487
 M487
 S488
 M488
 S489
 M489
 S490
 M490
 S491
 M491
 S492
 M492
 S493
 M493
 S494
 M494
 S495
 M495
 S496
 M496
 S497
 M497
 S498
 M498
 S499
 M499
 S500
 M500
 S501
 M501
 S502
 M502
 S503
 M503
 S504
 M504
 S505
 M505
 S506
 M506
 S507
 M507
 S508
 M508
 S509
 M509
 S510
 M510
 S511
 M511
 S512
 M512
 S513
 M513
 S514
 M514
 S515
 M515
 S516
 M516
 S517
 M517
 S518
 M518
 S519
 M519
 S520
 M520
 S521
 M521
 S522
 M522
 S523
 M523
 S524
 M524
 S525
 M525
 S526
 M526
 S527
 M527
 S528
 M528
 S529
 M529
 S530
 M530
 S531
 M531
 S532
 M532
 S533
 M533
 S534
 M534
 S535
 M535
 S536
 M536
 S537
 M537
 S538
 M538
 S539
 M539
 S540
 M540
 S541
 M541
 S542
 M542
 S543
 M543
 S544
 M544
 S545
 M545
 S546
 M546
 S547
 M547
 S548
 M548
 S549
 M549
 S550
 M550
 S551
 M551
 S552
 M552
 S553
 M553
 S554
 M554
 S555
 M555
 S556
 M556
 S557
 M557
 S558
 M558
 S559
 M559
 S560
 M560
 S561
 M561
 S562
 M562
 S563
 M563
 S564
 M564
 S565
 M565
 S566
 M566
 S567
 M567
 S568
 M568
 S569
 M569
 S570
 M570
 S571
 M571
 S572
 M572
 S573
 M573
 S574
 M574
 S575
 M575
 S576
 M576
 S577
 M577
 S578
 M578
 S579
 M579
 S580
 M580
 S581
 M581
 S582
 M582
 S583
 M583
 S584
 M584
 S585
 M585
 S586
 M586
 S587
 M587
 S588
 M588
 S589
 M589
 S590
 M590
 S591
 M591
 S592
 M592
 S593
 M593
 S594
 M594
 S595
 M595
 S596
 M596
 S597
 M597
 S598
 M598
 S599
 M599
 S600
 M600
 S601
 M601
 S602
 M602
 S603
 M603
 S604
 M604
 S605
 M605
 S606
 M606
 S607
 M607
 S608
 M608
 S609
 M609
 S610
 M610
 S611
 M611
 S612
 M612
 S613
 M613
 S614
 M614
 S615
 M615
 S616
 M616
 S617
 M617
 S618
 M618
 S619
 M619
 S620
 M620
 S621
 M621
 S622
 M622
 S623
 M623
 S624
 M624
 S625
 M625
 S626
 M626
 S627
 M627
 S628
 M628
 S629
 M629
 S630
 M630
 S631
 M631
 S632
 M632
 S633
 M633
 S634
 M634
 S635
 M635
 S636
 M636
 S637
 M637
 S638
 M638
 S639
 M639
 S640
 M640
 S641
 M641
 S642
 M642
 S643
 M643
 S644
 M644
 S645
 M645
 S646
 M646
 S647
 M647
 S648
 M648
 S649
 M649
 S650
 M650
 S651
 M651
 S652
 M652
 S653
 M653
 S654
 M654
 S655
 M655
 S656
 M656
 S657
 M657
 S658
 M658
 S659
 M659
 S660
 M660
 S661
 M661
 S662
 M662
 S663
 M663
 S664
 M664
 S665
 M665
 S666
 M666
 S667
 M667
 S668
 M668
 S669
 M669
 S670
 M670
 S671
 M671
 S672
 M672
 S673
 M673
 S674
 M674
 S675
 M675
 S676
 M676
 S677
 M677
 S678
 M678
 S679
 M679
 S680
 M680
 S681
 M681
 S682
 M682
 S683
 M683
 S684
 M684
 S685
 M685
 S686
 M686
 S687
 M687
 S688
 M688
 S689
 M689
 S690
 M690
 S691
 M691
 S692
 M692
 S693
 M693
 S694
 M694
 S695
 M695
 S696
 M696
 S697
 M697
 S698
 M698
 S699
 M699
 S700
 M700
 S701
 M701
 S702
 M702
 S703
 M703
 S704
 M704
 S705
 M705
 S706
 M706
 S707
 M707
 S708
 M708
 S709
 M709
 S710
 M710
 S711
 M711
 S712
 M712
 S713
 M713
 S714
 M714
 S715
 M715
 S716
 M716
 S717

1. Shale
 2. VSL
 3. VSL
 4. 10
 5. 100
 6. 1000
 7. 10000
 8. 100000
 9. 1000000
 10. 10000000
 11. 100000000
 12. 1000000000
 13. 10000000000
 14. 100000000000
 15. 1000000000000
 16. 10000000000000
 17. 100000000000000
 18. 1000000000000000
 19. 10000000000000000
 20. 100000000000000000
 21. 1000000000000000000
 22. 10000000000000000000
 23. 100000000000000000000
 24. 1000000000000000000000
 25. 10000000000000000000000
 26. 100000000000000000000000
 27. 1000000000000000000000000
 28. 10000000000000000000000000
 29. 100000000000000000000000000
 30. 1000000000000000000000000000
 31. 10000000000000000000000000000
 32. 100000000000000000000000000000
 33. 1000000000000000000000000000000
 34. 10000000000000000000000000000000
 35. 100000000000000000000000000000000
 36. 1000000000000000000000000000000000
 37. 10000000000000000000000000000000000
 38. 100000000000000000000000000000000000
 39. 1000000000000000000000000000000000000
 40. 10000000000000000000000000000000000000
 41. 100000000000000000000000000000000000000
 42. 1000000000000000000000000000000000000000
 43. 100
 44. 1000
 45. 100
 46. 1000
 47. 100
 48. 1000
 49. 100
 50. 1000
 51. 100
 52. 1000
 53. 100
 54. 1000
 55. 100
 56. 1000
 57. 100
 58. 1000
 59. 100
 60. 1000
 61. 100
 62. 1000
 63. 100
 64. 1000
 65. 100
 66. 1000
 67. 100
 68. 1000
 69. 100
 70. 1000
 71. 100
 72. 1000
 73. 100
 74. 1000
 75. 100
 76. 1000
 77. 100
 78. 1000
 79. 100
 80. 1000
 81. 100
 82. 1000
 83. 100
 84. 1000
 85. 100
 86. 1000
 87. 100
 88. 1000
 89. 100
 90. 1000
 91. 100
 92. 1000
 93. 100
 94. 1000
 95. 100
 96. 1000
 97. 100
 98. 1000
 99. 100
 100. 1000



LEGEND FOR GEOLOGIC SECTIONS

D.E. Klockow & Associates Consulting Geotechnical Engineers 5921 Wagon Trail Road, Rt. 14, Columbia, Missouri	
Job No. 10-008	Date 4-20-88
BHS, Inc. Industrial Waste Management Facility Rt. 1, Box 116-F, Wright City, Missouri 63390 SYMBOLS & NOTATION USED FOR SUBSURFACE DATA	

ATTACHMENT 5

Well Construction Diagram GMW Series Well

GMW-1R

Ground Elevation : 787.08

Height of top of PVC riser pipe above ground surface. 788.83 -

Type of surface seal: Cement-sand concrete.

Depth of surface seal below ground surface. Min. 30"

I.D. of surface casing.

Type of surface casing: Steel 4"x4"

Depth of surface casing below ground. 39"

I.D. of riser pipe. 2"

Type of riser pipe, Upper: Schedule 40 PVC Lower: #316 stainless steel.

Depth, top of stainless steel: 60'

Diameter of borehole. 7"

Type of backfill: Cement with 10 bentonite.

Depth, top of seal. 77'

Type of seal: Bentonite pellets.

Depth, bottom of seal. 82'

Type of sand pack: Fine to medium sand.

Depth, top of sand pack. 82'

Depth, top of screened section. 90'

Type of screened section: #316 S.S.

Describe openings. 0.001"

I.D. of screened section. 2"

Depth, bottom of screened section. 100'

Depth, bottom of plugged blank section. 100' - 2 1/2"

Depth, bottom of sand column. 100' - 2 1/2"

Type of backfill below observation pipe. Bentonite pellets

Depth of hole bottom. 105'

611+ 1-16-A1

684.58

10'

687.1

687.1 / 100'

100' - 2 1/2"

100' - 2 1/2"

Bentonite pellets

105'

Industrial Waste Management Facility
Warren County, Missouri
GROUND WATER MONITOR WELL SCHEMATIC
Brucker & Associates Brentwood, Mo.
Consulting Engineers February 1988

ATTACHMENT 6

General Well Construction Diagram P Series Wells

REMOVABLE
PVC CAP

3" PVC SCHEDULE 40 PLASTIC PIPE

BENTONITE SEAL

SELECTED
GRADED SAND

10'

35'

25'

.025" WIDE SLOTS

8" DIA. HOLE

PVC CAP

PIEZOMETER

REITZ & JENS, INC.

CONSULTING ENGINEERS

111 SOUTH MERAMEC AVENUE

ST. LOUIS, MISSOURI 63105

FEBRUARY 1977

FIG. 2