

271 Wolfner Drive Saint Louis, Missouri 63026 314/349-8399 Fax 314/349-8384

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

July 1, 1994

Mr. Ruben McCullers Environmental Scientist U.S. EPA, Region VII WSTM/RCRA/RCOM 726 Minnesota Avenue Kansas City, Kansas 66101 JUL 05 1994

RCOM SECTION

Dear Mr. McCullers:

On behalf of The Knapheide Mfg. Co., Schreiber, Grana & Yonley, Inc. is pleased to submit this revised closure plan for the waste paint filters and over spray paper storage unit and the Brule incinerator unit at The Knapheide Mfg. Co.'s, West Quincy, Missouri facility.

The preparation of this plan was in accordance with the interim status closure requirements specified in 40 CFR 265, Subpart G and also addressed preliminary comments submitted by the Missouri Department of Natural Resources on March 15, 1994. Pursuant to the Mississippi River flooding experienced during the summer of 1993, flood waters inundated the facility such that the condition of the regulated units may have been altered. As such, additional sampling procedures are outlined for the purpose of assessing the condition of the Brule incinerator unit and for establishing background soil constituent concentrations. This revised plan includes provisions for collecting wipe samples from the Brule incinerator area in order that the unit and the associated concrete pad may be effectively characterized for disposal.

R00000634
RCRA Records Center

Center

was per BM 121 190

If you have any questions regarding any of the material presented, please contact Suzanne M. Riney, P.E. of my staff at (314) 349-8399. We appreciate your time and cooperation in this matter and look forward to a timely approval.

Sincerely,

Robert J. Schreiber, Jr., P.E.

President

RJS/sr/bkh

Enclosure

cc: Sandra L. Oberkfell; Rudnick & Wolfe

Steve Jakes; MDNR

Gary Korb; The Knapheide Mfg. Co.

knap07/closure.ltr

CLOSURE PLAN FOR WASTE PAINT FILTERS AND OVER SPRAY PAPER STORAGE UNIT AND THE BRULE INCINERATOR UNIT

Revised July 1, 1994

PREPARED FOR:

THE KNAPHEIDE MFG. CO. WEST QUINCY, MISSOURI

PREPARED BY:

SCHREIBER, GRANA & YONLEY, INC. ST. LOUIS, MISSOURI

SUBMITTED TO:

U.S. ENVIRONMENTAL PROTECTION AGENCY REGION VII KANSAS CITY, KANSAS

RECEIVED

JUL 05 1994

RCOM SECTION



TABLE OF CONTENTS

										1	A	GE
1.0	INTRO 1.1 1.2	DUCTION				 		 				1
2.0	WAST 2.1 2.2 2.3 2.4	E PAINT FILTERS AND OVE Maximum Inventory Closure Procedures Sampling & Analysis Plan Closure Criteria				 • •	• • •	 • •	• •	• •		5 5
3.0	BRUL 3.1 3.2 3.3	E INCINERATOR UNIT Closure Procedures Sampling & Analysis Plan Closure Criteria				 • •	• •	 • •	• •	• •		11 12
4.0	CLOS	URE SCHEDULE				 		 				14
5.0	CLOS	URE COST ESTIMATE			• • •	 		 			• •	14
		TAE	BLES									
TABL TABL TABL TABL	E 2 E 3	Sample Log-Waste Paint Filter Analytical Detection Limits . Sample Log-Brule Incineration Sample Log-Brule Incinerator	 ı Uni	 t .		 	• •	 • •	• •		• •	. 9 12
		FIGU	URE	S								
FIGUI FIGUI	RE 2	Vicinity Map Closure Units Location Diagra Sample Location Diagram	• • •	• • •	 	 • •	• •	 	• •	• •	• •	. 2
	NDIX NDIX				ts							

i

CLOSURE PLAN

FOR

WASTE PAINT FILTERS AND OVER SPRAY PAPER STORAGE UNIT AND THE

BRULE INCINERATOR UNIT

1.0 <u>INTRODUCTION</u>

1.1 Purpose


In June, 1993 a closure plan was prepared and submitted to address the "waste paint filter and over spray paper storage unit" and the "Brule incinerator unit". These units were referred to in the consolidated consent agreement and consent order between the U.S. Environmental Protection Agency (EPA) and The Knapheide Manufacturing Co. (Knapheide) (Docket Nos. V11-92-H-0008, V11-93-T-499-E); herein after referred to as "Consent Order".

Pursuant to this plan, Knapheide has elected to revise the closure plan in lieu of the Mississippi River flooding experienced during the summer of 1993. Flood waters inundated the facility such that the condition of the regulated units may be altered. As such, additional sampling procedures are outlined for the purpose of assessing the condition of the Brule incinerator unit and for establishing background soil constituent concentrations. Also included in this revised closure plan are preliminary comments generated by the Missouri Department of Natural Resources (MDNR) in March, 1993.

1.2 <u>Background</u>

Knapheide assembles custom truck body parts at its facility located in West Quincy, Missouri (Figure 1). The West Quincy facility operation includes the painting of assembled products.

The EPA, Region VII, alleged in a Resource Conservation and Recovery Act (RCRA) Compliance Complaint that waste paint filters and over spray paper generated by the painting operation are characteristically hazardous due to leachable chromium toxicity. The facility was cited in that complaint in part, for treatment of these hazardous wastes and storage of these hazardous wastes over 90 days without a permit. Pursuant to a Consent Order in settlement of said alleged violation, Knapheide must close the alleged waste paint filter and over spray paper storage unit in accordance with interim status rules as approved by the MDNR. In addition, the Consent Order requires that an inoperative Brule incinerator be similarly closed as a treatment unit for waste paint filters and over spray paper.



The wastestream referred to in the EPA complaint is waste paint filters and over spray paper (hereinafter referred to as used absorbent material) used to collect paint residues (see Appendix A for absorbent material analytical results). Used absorbent material was handled and stored at the subject closure area in sealed 55-gallon metal containers. Between 1980 and September 25, 1989, the used absorbent material was disposed of in the small on-site Brule incinerator. No other materials were disposed of in the incinerator. The ash generated by the incineration activities was collected and stored at the storage area.

The purpose of this Closure Plan is to comply with the Consent Order to provide a Closure Plan in accordance with 40 CFR 265 Subparts G and O for the subject closure area. This Closure Plan describes the steps necessary to completely close the interim status storage and treatment unit referenced in the Consent Order as being located at Knapheide's West Quincy facility. For purposes of this Closure Plan, the subject closure area will be divided into two (2) units:

- 1) Waste Paint Filters and Over Spray Paper Storage Unit; and
- 2) Brule Incinerator Unit


This Closure Plan will be amended if unexpected events occur during the implementation of the plan which would require a modification after it is approved by the EPA. Such an amendment will be submitted to the EPA within 30 days after the unexpected event has occurred per 40 CFR §265.112 (C)(2). As requested by the MDNR, Knapheide will notify the EPA and MDNR 45 days prior to the start of closure activities. MDNR and EPA will be notified 15 days prior to performing the sampling activities.

Knapheide will maintain at its facility the approved Closure Plan (including closure schedule) and will complete the closure within 180 days following the final plan approval by the EPA. Within 60 days of the completion of closure activities, a closure certification meeting the requirements of 40 CFR §265.115, will be provided to the EPA by registered mail.

2.0 WASTE PAINT FILTERS AND OVER SPRAY PAPER STORAGE UNIT

The area that comprises the former "waste paint filters and over spray paper storage unit" is not visually evident by current site conditions. The maximum extent of storage of used absorbent material containers extends from the incinerator southward along the eastern exterior wall of Building No. 6, approximately 66 feet south from the northeast corner of the building, and east to the fence line (see Figure 2).

Activities that were conducted at the waste paint filters and over spray paper storage unit consisted solely of the storage of used absorbent material and incinerator ash within sealed 55-gallon metal containers between 1980 and May 24, 1991. Storage activities involved moving full containers from satellite storage areas throughout the facility by forklift to the storage area for staging prior to incineration. Subsequently, ash from the incinerator operation was also contained and stored in the paint filter and over spray paper storage unit area prior to being shipped off-site.





APPROXIMATE
SCALE:
0' 25' 50'

CLOSURE UNITS LOCATION DIAGRAM

KNAPHEIDE MANUFACTURING COMPANY
WEST QUINCY, MISSOURI

FIGURE 2

DATE: 5-3-94

DWG.# KNAP06-2 SCHREIBER
GRANA
YONLEY
INCORPORATED
ENVIRONMENTAL ENGINEERS

Currently, the used absorbent material is stored in a less than 90 day storage area which is separate from the subject closure area. The facility retains Chief Supply of Haskell, Oklahoma to transport and dispose of the used absorbent material (EPA Designation No. D001, D007). Chief Supply blends the used absorbent material with other combustible fuels and redistributes it as an energy recovery fuel at an appropriate permitted treatment, storage or disposal facility.

2.1 Maximum Inventory

Based on information provided by facility personnel, the maximum inventory of containers ever stored in the waste paint filter and over spray paper storage unit was 958, 55-gallon metal containers. Of that amount, it is estimated that 888 containers held absorbent material while 70 containers held incinerator ash.

2.2 Closure Procedures

Currently, no containers of waste paint filters, over spray paper or incinerator ash are stored in the subject area. The last day of use for the waste paint filters and over spray paper storage unit was May 24, 1991. Hence, closing will consist only of sampling and analysis procedures to verify clean closure.

2.3 Sampling & Analysis Plan

In order to verify that contaminants have not been released to the ground surface from the storage and handling of absorbent material drums, a subsurface investigation will be conducted at the waste paint filters and over spray paper storage unit. The subsurface investigation will consist of collecting shallow (0-6") soil samples at the locations identified on Figure 3 and analyzing them for the constituents listed in the sample log (Table 1).

A stainless steel hand auger or trailer mounted drilling rig will be utilized to bore and collect samples. Discrete soil samples from the selected sampling locations will be collected from the base materials beneath the crushed rock layer at depths identified in Table 1. In the event deposited river sediments are encountered as a result of the flood of 1993, the soil collected will be from depths six inches below the deposited material. Two (2) background soil samples will also be collected from areas which do not exhibit obvious stains or other signs of possible surface contamination. Background soil constituent concentrations may be used as criteria for assessing the existence of soil contamination at the site.

Soil samples will be carefully removed from the sampling device using a stainless steel spoon and placed into an appropriate sampling jar. The samples will be collected by personnel in Level D protection utilizing clean latex or nitrile gloves. The personnel protection level will be upgraded if actual project conditions warrant a change.




TABLE 1 SAMPLE LOG WASTE PAINT FILTERS AND OVER SPRAY PAPER STORAGE UNIT

Sample ID No.	Matrix	Depth	Analysis*	Description
KNAP 01	Soil	0-6"	Total Metals	Surface Water Runoff Pathway Sample
KNAP 02	Soil	0-6"	Total Metals	Background Sample
KNAP 03	Soil	0-6"	Total Metals	Background Sample
KNAP 04	Soil	0-6"	Total Metals	Storage Unit Sample
KNAP 05	Soil	2'	Total Metals	Storage Unit Sample
KNAP 06	Soil	0-6"	Total Metals, VOA, BNA	Storage Unit Sample
KNAP 07	Soil	3-4"	TPH, VOA, BNA	Oily Layer Sample
KNAP 08	Soil	0-6"	Total Metals, VOA, BNA	Duplicate Soil Sample (KNAP 05)
KNAP 09	Water		VOA, BNA, TPH	Decontamination Blank

^{*}Total Metals = SW 846 EPA Approved Method



VOA - Volatile Organic Analysis - SW 846 Method 8240

BNA - Base Natural Acids - SW 846 Method 8270

TPH - Total Petroleum Hydrocarbons SW 846 Method 418.1

The sample bottles will be labeled identifying the sample location, sample collector, date of collection and analysis to be performed. The samples will then be transported to an independent laboratory whose quality assurance and quality control (QA/QC) procedures will be in accordance with EPA SW 846 methods. A chain-of-custody form will accompany the samples to the laboratory.

In addition to the laboratory QA/QC procedures, one (1) duplicate soil sample and one (1) decontamination blank will also be collected and submitted for analysis. The results of the duplicate soil and decontamination blank sample analyses will be used in comparison with the soil sample analyses results, to assess the potential presence of contamination as a result of field sampling procedures or laboratory analyses. All analytical results will be submitted to EPA and MDNR within 30 days after receipt of the sampling data.

Drill rig equipment and augers used in the investigation will be decontaminated prior to use on the site and prior to removal from the site. In addition, sampling equipment will be decontaminated between each sample location. This procedure will eliminate the possibility of contamination being introduced from an off-site source and the possibility of contamination encountered from the investigation does not leave the site. Decontamination will be performed using fresh water from a potable water supply in combination with Alconox soap. Distilled water will be used as a final rinse. Decontamination fluids will be collected and placed in appropriately-labelled 55-gallon DOT approved drums.

Excess soil cuttings which can not be replaced back to the respective soil boring will also be collected and placed in appropriately labelled 55 gallon DOT approved drums.

2.4 Closure Criteria

The waste paint filters and over spray paper storage unit will be considered to be clean closed if the soil sample analyses results indicate no detection of the parameters above the practical quantitation limits identified in Table 2 or if the total constituents of concern in the soil samples are equal to or less than the background soil sample concentrations or as referenced in Missouri soil literature or a risk based standard. The certification report submitted will include a report with photographs detailing all work completed to accomplish closure. A copy of the professional engineer's inspection report and results of sampling and laboratory analysis will also be submitted with the closure certification.

If analytical results indicate that contamination exists in the soil at the waste paint filters and over spray paper storage unit, Knapheide will submit a contingent Closure Plan for the unit within 60 days of EPA's notification to Knapheide that EPA has determined that additional closure activities are required. The contingent closure plan will address provisions outlined in 10 CSR 25-7.265(2)(I)6. and 10 CSR 25-7.265(2)(G)4.

TABLE 2
ANALYTICAL DETECTION LIMITS

	Practical Quantitation Limit					
Analytical Suite	Parameters	Method	Soil	Water	Wipe	
Metals	Arsenic Barium Cadmium Chromium Lead Mercury Selenium Silver	SW 846 7060 SW 846 6010 SW 846 7131 SW 846 7191 SW 846 7421 SW 846 7471 SW 846 7740 SW 846 7761	0.5 mg/kg 2.0 mg/kg 0.1 mg/kg 0.5 mg/kg 0.15 mg/kg 0.04 mg/kg 0.25 mg/kg 0.5 mg/kg	0.050 mg/L 0.005 mg/L 0.003 mg/L 0.005 mg/L 0.050 mg/L 0.0002 mg/L 0.100 mg/L 0.010 mg/L	0.050 μg/cm ² 0.005 μg/cm ² 0.003 μg/cm ² 0.005 μg/cm ² 0.050 μg/cm ² 0.0002 μg/cm ² 0.100 μg/cm ² 0.010 μg/cm ²	
Volatiles	Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acrolein Acrylonitrile Trichlorofluoromethane Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Vinyl Acetate Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (Total)	SW 846 8240	10 µg/kggggggggggggggggggggggggggggggggggg	10 μg/L 10 μg/L 10 μg/L 10 μg/L 100 μg/L 100 μg/L 100 μg/L 100 μg/S 100 μg/S 5 μg/S 5 μg/S 100 μg/S 5 μg/S	1,000 μg/cm ²	



TABLE 2 ANALYTICAL DETECTION LIMITS (continued)

			Practical Quantitation Limit		
Analytical Suite	Parameters	Method	Soil	Water	Wipe
Base Neutral Acids	Pyridine N-Nitrosodimethylamine Phenol bis(2-chloroethyl)Ether 2-Chlorophenol 1,3-Dichlorobenzene 1,4-Dichlorobenzene Benzyl Alcohol 1,2-Dichlorobenzene o-Cresol bis-(2-Chloro2propyl)Ether m & p-Cresol N-Nitroso-Di-n-propoylamine Hexachloroethane Nitrobenzene Isophorone 2-Nitrophenol 2,4-Dimethylphenol Benzoic Acid bis(2-Chloroethoxy)methane 2,4-Dichlorophenol 1,2,4-Trichlorobenzene Naphthalene 4-Chloro-3-methylphenol 2-Methylnaphthalene Hexachlorocyclopentadiene 2,4,6-Trichlorophenol 2-A,5-Trichlorophenol 2-Chloroanphthalene 2-Nitroaniline Dimethylphthalate Azobenzene Acenaphthylene 2,6-Dinitrotoluene 3-Nitroaniline Acenaphthene 2,4-Dinitrotoluene 3-Nitrophenol Dibenzofuran 2,4-Dinitrotoluene Diethylphthalate 4-Chlorophenol phenyl ether Fluorene 4-Nitrosodiphenylamine 4-Bromophenyl phenyl ether Fluorene 4-Nitrosodiphenylamine 4-Bromophenyl phenyl ether Hexachlorobenzene Pentachlorophenol N-Nitrosodiphenylamine 4-Bromophenyl phenyl ether Hexachlorobenzene Pentachlorophenol Phenanthrene Anthracene Carbazole Di-n-butylphthalate Fluoranthene Benzidine Pyrene Butylbenzylphthalate Fluoranthene Benzidine Pyrene Butylbenzylphthalate Benzo(a)anthracene Chyrsene bis-(2-Ethylhexyl)phthalate Di-n-octylphthalate Benzo(b)fluoranthene Benzo(c),hjperylene	SW 846 8270	330 µg/kgg 330 µg/kggg 330 µg/kggg 330 µg/kggg 330 µg/kggg 330 µg/kggg 330 µg/kggg 330 µg/kggggggggggggggggggggggggggggggggggg	10	10 μg/cm
Total Petroleum		SW 846 418.1	10 mg/kg	10 mg/L	10 mg/cm

SCHREIBER, GRANA & YONLEY, INC. =



3.0 BRULE INCINERATOR UNIT

Currently the inoperative Brule incinerator is located at the northeast edge of the waste paint filters and over spray paper storage unit area as shown in Figure 2. The Brule incinerator unit consists of a Brule incinerator located upon an approximately 15 x 15 foot square concrete pad. The areal definition of the Brule incinerator unit is taken as the extent of the incinerator's concrete foundation pad including an area approximately 65 feet to the northeast of the Brule incinerator unit, as well as the surface water runoff pathway which extends from the concrete foundation pad towards the east to the property line.

Between 1980 and the incinerator's last day of use, September 25, 1989, used absorbent material was burned in the Brule incinerator. Incineration activities consisted of placing used absorbent material, which had been transported from the waste paint filters and over spray paper storage unit, into the Brule incinerator and subsequently removing incinerator ash and placing it in sealed 55-gallon metal containers for storage at the waste paint filters and over spray paper storage unit. Ash generated by incineration activities from 1980 until September 25, 1989 was collected and stored at the storage unit, and was subsequently totally removed on May 24, 1991.

As noted above, from 1980 until September 25, 1989, containers of used absorbent material were incinerated on-site within a small Brule incinerator. According to the manufacturer, the Brule incinerator would achieve approximately 95 percent efficiency in reducing the volume of burned material. Based upon an annual generation (prior to 1989), and subsequent incineration of 12,000 waste paint filters, approximately five to ten 55-gallon containers of ash would be generated per year. The incinerator was operated under an air permit issued by MDNR under MDNR Waste Management Program Policy #202 (see Appendix B for design information and specifications of the Brule incinerator).

3.1 Closure Procedures

Proposed closure procedures for the unit as well as the concrete pad include dismantling the unit, collecting wipe samples of the incinerator, refractory brick, and of the concrete pad, and disposing of the incinerator and its associated concrete pad at an approved waste management facility. Based on results of the wipe sample laboratory analyses, it is anticipated that the incinerator unit and the concrete pad will meet the criteria for clean closure as presented in this section and will be considered a solid waste.

Wipe samples will be collected using standard methods which specify uniform sample areas, effective absorbent materials as well as moistening agents. For each analysis (Table 3), an appropriate solvent or distilled water will be applied to moisten a gauze pad or filter paper. This moistened absorbent will be used to thoroughly swab a 100 centimeter square area as measured by a sampling template. Clean templates will be used for each sample location. Following sample collection, the wipe samples will be stored in precleaned glass jars at 4°C.

TABLE 3 SAMPLE LOG FOR BRULE INCINERATOR UNIT

Sample ID No.	Matrix	Depth	Analysis	Description
BRULE 01	Wipe	Surface	Total Metal, VOA, BNA	Refractory Brick
BRULE 02	Wipe	Surface	Total Metals, VOA, BNA	Metal Stack
BRULE 03	Wipe	Surface	Total Metals, VOA, BNA	Concrete Pad

A total of three (3) wipe samples will be collected. Two will be from locations within the incinerator, the refractory brick and the metal surface of the stack, and one will be of the concrete pad surface. The Brule incinerator unit and the concrete pad will be disposed as special waste in a solid waste landfill if analytical results give indication that there are no constituents above the practical quantitation limits (Table 2) or that there are no concentrations above those normally found in refractory brick, portland cement or concrete. Existing guidance materials will be used for comparisons.

Upon confirmation of clean closure, the dismantled incinerator and its associated concrete pad will be loaded into roll-off boxes for transport to the designated solid waste facility. Remaining dust or ash if encountered, will be separately contained and disposed in a hazardous waste disposal facility. In the event the laboratory analyses results for the incinerator unit and concrete pad are above the practical quantitation limits (Table 2), or the guidance criteria for refractory brick, portland cement or concrete, the materials will be appropriately labeled, manifested and transported to a hazardous waste landfill.

3.2 <u>Sampling & Analysis Plan</u>

In order to verify that contaminants have not been released to the ground surface from the incineration of waste paint filters, over spray paper or incinerator ash, a subsurface investigation will be conducted at the Brule incinerator unit. This subsurface investigation will consist of collecting shallow (0-6") soil samples at the locations depicted on Figure 3 and analyzing them for the constituents listed in Table 4.

TABLE 4
SAMPLE LOG
FOR BRULE INCINERATOR UNIT AREA

Sample ID No.	Matrix	Depth	Analysis	Description			
KNAP 10	Soil	0-6"	Total Metals, VOA, BNA	Material transport pathway sample			
KNAP 11	Soil	0-6"	Total Metals	Surface water runoff pathway sample			
KNAP 12	Soil	0-6"	Total Metals	Sample underneath concrete pad			



A stainless steel hand auger or trailer mounted drilling rig will be utilized to collect soil samples. Discrete soil samples from the selected sampling locations will be collected from the base material beneath the crushed rock layer or immediately beneath the concrete pad. In the event deposited river sediments are encountered as a result of the flood of 1993, the soil collected will be from depths six inches below the deposited material. The background soil constituent concentrations (Table 1) will be used as criteria for assessing the existence of soil contamination at the site.

Soil samples will be carefully removed from the sampling device using a stainless steel spoon and placed into an appropriate sampling jar. The samples will be collected by personnel in Level D protection utilizing clean latex or nitrile gloves. The personnel protection level will be upgraded if actual project conditions warrant a change.

The sample bottles will be labeled identifying the sample location, sample collector, date of collection and analysis to be performed. The samples will then be transported to an independent laboratory whose QA/QC procedures will be in accordance with EPA SW 846 methods. A chain-of-custody form will accompany the samples to the laboratory. The QA/QC procedures outlined in Section 2.3 for assessing laboratory and field contamination of samples applies for the Brule incinerator unit areas as well.

All drill rig equipment and augers used in the investigation will be decontaminated prior to use on the site and prior to removal from the site. In addition, all sampling equipment will be decontaminated between each sample location. This procedure will eliminate the possibility of contamination being introduced from an off-site source and the possibility of contamination encountered from the investigation does not leave the site. Decontamination will be performed using fresh water from a potable water supply in combination with Alconox soap. Distilled water will be used as a final rinse. All decontamination fluids will be collected and placed in appropriately labeled 55-gallon DOT approved drums.

Excess soil cuttings which can not be replaced back to the respective soil boring will also be collected and placed in appropriately labeled 55-gallon DOT approved drums.

3.3 Closure Criteria

The Brule incinerator unit will be considered to be clean closed when the Brule incinerator is properly disposed and the soil sample analysis results indicate no detection of the parameters above the practical quantitation limits identified in Table 2 or if the total constituents of concern in the soil samples are equal to or less than the background soil sample concentrations or as referenced in Missouri soil literature or a risk based standard. The closure certification submitted to MDNR will include a report with photographs detailing all work completed to accomplish closure. A copy of the professional engineer's inspection report and results of sampling and laboratory analyses will also be submitted with the closure certification.



If analytical results indicate that contamination exists in the soil at the Brule incinerator unit, Knapheide will submit a contingent Closure Plan for the unit. The contingent closure plan will address provisions outlined in 10 CSR 25-7.265(2)(I)6. and 10 CSR 25-7.265(2)(G)4.

4.0 CLOSURE SCHEDULE

The expected time schedule for the closure activities are as follows:

Activity	Time for Activity	No. of Days from the Receipt of Approval of Plan
1. Mobilization	15 days	15 days
Incinerator Characterization Performance of Subsurface Investigation	5 days	20 days
3. Procure Sample Analytical Results	15 days	35 days
Incinerator Approval from Waste Disposal Facility	45 day	80 days
Dismantling and Disposal of Incinerator and Concrete Pad	10 days	90 days
6. Certification of Closure	30 days	130 days

Total estimated time for closure is approximately 130 days from the receipt of Closure Plan approval. If additional sampling is necessary, the time required for closure will be extended. If the closure activities will take longer than 180 days to complete, Knapheide will request an extension from the Regional Administrator 30 days prior to the 180 day period.

5.0 <u>CLOSURE COST ESTIMATE</u>

\$ 4,000.00
\$ 6,000.00
\$ 9,000.00
<u>\$ 6,000.00</u>

Total: \$25,000.00

APPENDIX A ABSORBENT MATERIAL ANALYTICAL RESULTS



March 12, 1991

Mr. Harold Huggins Knapheide Manufacturing Company 436 South Sixth Street, P.O. Box C-140 Quincy, Illinois 62301

RE: Analytical Results SCIE No. 91-1034

Dear Mr. Huggins:

SCI Environmental, Inc. (SCIE) is pleased to submit results of analytical testing performed on the samples submitted on February 18, 1991. The samples were analyzed for TCLP; EPA Method 1311 and ignitability. There were no analytical problems encountered with the analysis.

If you have any questions or need further clarification, please do not hesitate to call.

Thank you for selecting SCI Environmental for you analytical testing needs.

Respectfully submitted,

Elizabeth M. Color Elizabeth M. Cohoon Laboratory Manager

EMC/jr/031291-2.1tr

Enclosure



Sample	Sample	Ignitability
Number	Identity	(degrees F)
4310 .	Composite	> 200

Submitted By:

File:1034TCLP.dta

Laboratory Manager



DATA SUMMARY

Knapheide Manufacturing Company

436 South Sixth Street, P.O. Box C-140

Quincy, Illinois 62301

Project No.: 91-1034

Sample Matrix: Filters

Date Sampled: 2/14/91

Date Received: 2/18/91 Date Analyzed: 3/4/91 EPA Method No.: 1311

Sampled By: SCIE

Sample Location: Knapheide

TOXICITY CHARACTERISTIC LEACHATE PROCEDURE (TCLP)

SCIE Sample No.: 4310 Sample Identity: Paint Composite

		mercy. Paint composite
Contaminant	Results (ppm)*	Regulatory Level (ppm)*
Arsenic	ND(**) < 0.1	5.0
Barium	0.19	100.0
Benzene	ND < 0.1	0.5
Cadmium	ND < 0.1	1.0
Carbon tetrachloride	ND < 0.01	0.5
Chlorobenzene	ND < 0.1	100.0
Chloroform	ND < 0.1	6.0
Chromium	6.25	5.0
o-Cresol	ND < 10.0	200
m+p-Cresol	ND < 10.0	200
l,4-Dichlorobenzene	ND < 0.5	7.5
1,2-Dichloroethane	ND < 0.1	0.5
1,1-Dichloroethylene	ND < 0.1	0.7
2,4-Dinitrotoluene	ND < 0.1	0.13
Hexachlorobenzene	ND < 0.1	0.13
Hexachlorobutadiene	ND < 0.1	0.5
Hexachloroethane	ND < 0.1	. 3.0
Lead	ND < 0.1	5.0
Mercury .	ND < 0.001	0.2
Methyl ethyl ketone	9.4	200.0
Nitrobenzene	ND < 0.5	2.0
Pentachlorophenol	ND < 10.0	100.0
Pyridine	ND < 2.0	5.0
Selenium	ND < 0.1	1.0
Silver	ND < 0.05	5.0
Tetrachloroethylene	ND < 0.1	0.7
Trichlorehthylene	ND < 0.1	0.5
2,4,5-Trichlorophenol	ND < 10.0	400.0
2,4,6-Trichlorophenol	ND < 1.0	2.0
Vinyl Chloride	ND < 0.1	0.2

^{*} ppm = parts per million



^{**}ND = none detected above method detection limit

APPENDIX B BRULE INCINERATOR SPECIFICATIONS



- APPLICATION FOR PERMIT TO INSTALL OR MODIFY AN INCINERATOR

New Incinerator Modification of Ex	deting Incinerator	Date 12-6-	99	
1. Name of installation	2. Ad	dress .		3. Telephone
THE KNIPKEIDE MEG		5.6 57	-	(217)222-7/3/
4. Owner of Installation	<u> </u>	<u>, , , , , , , , , , , , , , , , , , , </u>		G. Telaphone
SAME		•		
	OR IDENTIFICATIO	N DESCRIPTION AND	SPECIFICATION	ONS
7. Nake B. Model		9. Serial Number		10. Type
BRULE =6 11. Rated capacity 12. Type w	4-75			Pretort: In tine othe
11. Rated capacity 12. Type w	esto	13. Waste heet content		14. Approximate firing rece
315 tothe "0"(F)	LTEKS)	8500	BTU/Ib	900 lb/ds
15. Reference	16. Pyrometric cons		•	ric test results
GFirebrick Costable Other		3 /		
18. ASME PTC 27 test results	19. Engineering plans		20. City bui	
on file structed	on (ite	Attached	No. AA	OLIAN data
·	DESIGN	INFORMATION		
21. Ovortire air	22. Undorfire sir		23. Excess of	ale
70 % 270 cu.fi./mla		17_cu. (t./min		
24. Primary chambar volume	25. Primary chambon	purner	26. Grate a	·
<u>52 w.n.</u>	300,000	BTU/hr.		6 sa.fr.
27. Secondary chamber volume	28. Secondary chame			cy chambar temporature
37:5 cu. 1t.	450,000	BTU/hr.	min / 5	OQ OF max OF
30. Tertincy chamber volume	31. Tertiory chamber			Chamber temperature
A. cu, ft,	N/A-	BTU/hr.	M/A min	ot war ot
	ck exit temperature	35. Stack lining	Unlinea	36. Cherging door . Poulloti
	OO OF OR	Fire 8rick	Castable	Double Guillotine Silvin
	ek exit volocity 39 ft/soc	39. Dampger barometric	gulilatine both	40. Grein looding (dry besis) A gr/SCF @ 12% CO
15 TD In. sq. ft.			~	
41. Installing company	42. Local representat			msking application (Signature)
KOENKER Plumbing. Address Telephone	403 Hamil	SKIRE 222-29		Telcphone
>duran tarabilities		i siapiione	7 - 7,10	•
_			 -	
General:				
			<i>~</i> –	0
Describe general matter o			PAINI	DOOLA FILLES
AND FLOOR PAPER				
Operation:				
	5 5 5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	d 2		- wask did wasks
Incinerator to operate: per year.	nours	per day,3_	- days pe	week, <u>yy</u> weeks

Application Instructions General

6.	Permit application reason: 7. Type of organization:
	New construction Alteration Change of location Change of ownership Change of ownership Change of ownership Change of ownership A Corporation Partnership Gov't Agency A Corporation Partnership A Corporatio
8.	Estimated cost of equipment or alteration:
	Air pollution control equipment \$ / 7,000 - \$ - 4,000
9.	For the new construction, alteration, transfer or ownership or location.
	What is the: Estimated starting date
10.	General nature of business:
	MANUPACTURE TRUCK EQUIPMENT
11.	
	Signature of responsible member of organization
12.	Typed or printed name of signer
13.	DIRECTOR OF GERSONNE!
	Official title of signer
14.	12-6-14
15.	(217) 222-7/3/
	Phone number .