

**N40192-15-D-9010**

**REQUIREMENTS CONTRACT FOR DEMOLITION OF BUILDING FACILITIES AND MISCELLANEOUS STRUCTURES AT ALL NAVY COMPLEX ACTIVITIES AND OTHER**

**WON 1362220, AJJY-14-4002, DEMOLISH 112 UNITS AT CAPEHART HOUSING (PHASE II) ANDERSEN AIR FORCE BASE, GUAM**

Date: 02 March 2017

Statement of Work (SOW) requires removal and disposal of Vinyl Asbestos Tiles including mastic only. Hazmat inspection and survey for the 112 units were performed by Globetec Group, Inc. (GGI). Hazmat test report shows positive results for Asbestos Containing Material (ACM) in grout cementitious material and other powdery material with paint in some of the Units; Lead Based Paint and Lead Containing Material (LBP/LCM) on ceramic tiles and concrete walls in some units. Note: The unforeseen HAZMAT will need to be abated prior to demolition.

ELIN		Quantity	Unit	Unit Price	Amount
E008	Removal, and Disposal of Vinyl Asbestos Tiles (VAT) Including Mastic	67617.62	SF	\$ (b) (4)	\$ (b) (4) -
E008	Removal, and Disposal of Asbestos in Grout Cementitious Material	472	SF	\$ (b) (4)	\$ (b) (4) -
E008	Removal, and Disposal of Asbestos in Powdery Material with Paint	2,612	SF	\$ (b) (4)	\$ (b) (4) -
	<b>Removal and Disposal of Asbestos Containing Materials</b>	<b>SUB TOTAL</b>			\$ (b) (4)
E011	Removal, and Disposal of Lead Containing Materials, Ceramic Tiles	900	SF	\$ (b) (4)	\$ (b) (4) -
E011	Removal, and Disposal of Lead Based Paint on Concrete Wall	288	SF	\$ (b) (4)	\$ (b) (4) -
	<b>Removal and Disposal of Lead Containing Materials</b>	<b>SUB TOTAL</b>			\$ (b) (4) -
	<b>Removal and Disposal of Asbestos and Lead Containing Materials (Unforeseen HAZMAT)</b>	<b>TOTAL COST</b>			\$ (b) (4) -