

Engineering Evaluation/Cost Analysis

Non Time Critical Removal Support Gulfco Marine Maintenance Superfund Site 906 Marlin Avenue Freeport, Brazoria County, Texas Contract No. EP-W-06-004 EPA Identification No. TXD055144539

Prepared for

U.S. Environmental Protection Agency Region 6

> 1445 Ross Avenue, Suite 1200 Dallas, Texas 75202

> > *Prepared by*

EA Engineering, Science, and Technology, Inc. 405 S. Highway 121 Building C, Suite 100 Lewisville, Texas 75067 (972) 315-3922

> December 2010 Revision: 00 EA Project No. 14342.67

CONTENTS

1.	EXECUTIVE SUMMARY	1
^	DITRODUCTION	,
2.	INTRODUCTION	
	2.1 PURPOSE OF REPORT	
	2.2 REPORT ORGANIZATION	
	2.3 SITE LOCATION AND DESCRIPTION	6
2	INVESTIGATIVE ACTIVITIES	(
3.	3.1 TERRESTRIAL ENVIRONMENT	
	3.1.1 North Area Surface Soil Sample Collection and Analysis	
	3.1.2 North Area Surface Soil Toxicity Testing	
	3.2 AQUATIC ENVIRONMENT	
	3.2.1 North Area Wetland Bulk Sediment Sample Collection and Analysis	
	3.2.2 North Area Wetland Bulk Sediment Toxicity Testing	
	3.2.2 North Area Wetland Surface Water Sample Collection and Analysis	
	3.2.4 North Area Wetland Surface Water Toxicity Testing	
	3.2.5 Intercoastal Waterway Bulk Sediment Sample Collection and Analysis	
	3.2.5 Intercoastal Waterway Bulk Sediment Toxicity Testing	
	3.3 CAP ASSESSMENT	
	3.3 CAP ASSESSIMENT	1 4
4	DATA ANALYSIS	13
٠.	4.1 CAP DATA	
	4.2 ECOLOGICAL DATA SUMMARY	
	.2 Ecobodicili Billingonini iki	
5.	RISK EVALUATION	14
6.	REMOVAL ACTION OBJECTIVES	
	6.1 IDENTIFICATION OF REMOVAL ACTION OBJECTIVES	
	6.1.1 Former Surface Impoundments	
	6.2 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS	15
_	VDENTYPICAL TRANSPORTED AND ANALYSIS OF DELICATION AND ADVISOR OF DELI	
7.	IDENTIFICATION AND ANALYSIS OF REMOVAL ACTION ALTERNATIVES	
	7.1 APPLICABLE REMOVAL ALTERNATIVES	
	7.1.1 Alternative # 1	
	7.1.2 Alternative # 2	
	7.1.3 Alternative # 3	
	7.1.4 Alternative # 4	
	7.1.5 Alternative # 5	
	7.2 ALTERNATIVE SCREENING	
	7.2.1 Effectiveness	
	7.2.2 Implementability	
	7.2.3 Cost	
	7.3 SEDIMENT SCREENING SUMMARY	
	7.4 GROUND WATER GENERAL RESPONSE ACTION SUMMARY	21

8.	COMPARATIVE ANALYSIS OF REMOVAL ALTERNATIVES	21
	8.1 COMPARATIVE ANALYSIS	22
	8.1.1 Effectiveness	22
	8.1.2 Implementability	
	8.1.3 Cost	

LIST OF APPENDICES

Appendix

A Baseline Ecological Risk Assessment – EA December 2010

LIST OF FIGURES

NUMBER

TITLE

INCLUDED IN APPENDIX A

LIST OF TABLES

NUMBER

TITLE

- 1 Summary of Cap Investigation Data
- 2 Removal Technology Screening
- 3 Alternative # 2 Cost Estimate
- 4 Alternative # 3 Cost Estimate
- 5 Alternative # 4 Cost Estimate
- 6 Alternative # 5 Cost Estimate

ACRONYMS AND ABBREVIATIONS

ARAR Applicable or Relevant and Appropriate Requirement

AST Above Ground Storage Tank

BCMCD Brazoria County Mosquito Control Department

BERA Baseline Ecological Risk Assessment

bgs below ground surface

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR Code of Federal Regulations

COPEC Constituent of Potential Ecological Concern

DQO Data Quality Objectives

EA Engineering, Science, and Technology, Inc.

EE/CA Engineering Evaluation/Cost Analysis EPA U.S. Environmental Protection Agency

GRA General Response Action

LC50 Lethal Concentration 50 Percent

NCP National Oil and Hazardous Substance Pollution Contingency Plan

NFA No Further Action

NTCRS Non Time Critical Removal Support

NPL National Priorities List
O&M Operation and Maintenance

OSWER Office of Solid Waste and Emergency Response

PAH Polynuclear Aromatic Hydrocarbons PBW Pastor, Behling & Wheeler, LLC

PSCR Preliminary Site Characterization Report

PRP Potentially Responsible Party RAO Remedial Action Objective

RCRA Resource Conservation and Recovery Act

SEM/AVS Acid Volatile Sulfides/Simultaneously Extracted Metals

Site Gulfco Marine Superfund Site

SLERA Screening Level Ecological Risk Assessment

SOP Standard Operating Procedure

SOW Statement of Work TBC To Be Considered

TCEQ Texas Commission on Environmental Quality

TOC Total Organic Carbon

TRRP Texas Risk Reduction Program

URS URS Corporation

USEPA United States Environmental Protection Agency

USFWS United States Fish and Wildlife Service

VOCs Volatile Organic Compounds

ENGINEERING EVALUATION / COST ANALYSIS Gulfco Marine Maintenance Superfund Site Non Time Critical Removal Support Freeport, Brazoria County, Texas

1. EXECUTIVE SUMMARY

This document presents an engineering evaluation and cost analysis (EE/CA) for select removal alternatives for the North Area of the Gulfco Marine Maintenance Superfund Site located in Freeport, Texas. EA performed the EE/CA for the U.S. Environmental Protection Agency (EPA) Region 6 as part of Task Order No. 0067-NSEE-06JZ under EPA Contract No. EP-W-06-004, in accordance with a Statement of Work (SOW) issued by EPA (October 2010).

The Site was operated by multiple companies as a barge cleaning and maintenance facility from 1971 to 1999. In May 2003, the EPA named the former Gulfco Marine Maintenance facility to the National Priorities List (NPL). The Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) Identification Number assigned to the Site is TXD055144539. This document focus on the selection of removal action alternatives associated with the former surface impoundments, the North Area surface soils, North Area Surface Water, and the Intercoastal Waterway sediments. While there are detections of hazardous constituents in ground water, response actions for ground water should be addressed separately.

Investigative Activities

Investigation of site terrestrial areas was limited to the upland regions in the North Area including the former surface impoundments and the area south of the former impoundment. Soils in these areas likely became contaminated with chemicals of potential concern (COPECs) due to surface runoff from the former surface impoundment area prior to capping. The final PRP screening level ecological risk assessment (SLERA) identified potential risk to lower-trophic receptors such as soil invertebrates in these upland areas. Media collected in support of the PRP baseline ecological risk assessment (BERA) included surface soils (0-6 inches below ground surface [bgs]), which represents the biologically active zone for soil-dwelling invertebrates. Toxicity tests were also conducted on surface soils to assess potential effects to these invertebrates

Investigation of site aquatic areas include the wetland areas of the North Area and the Intercoastal Waterway. Media (sediments and surface water) in these areas likely became contaminated with COPECs from direct discharge from barge cleaning operations, surface runoff, and flooding mechanisms. The final PRP SLERA identified potential risk to sediment and surface water dwelling invertebrates. Media collected in support of the PRP BERA included bulk sediments (0-6 inches bgs) and surface water from the North Area wetlands and bulk sediments (0-6 inches bgs) from the Intercoastal Waterway. Sediment pore water was also extracted from bulk sediments. Toxicity tests were conducted on wetland sediments and surface

water and Intercoastal Waterway sediments to assess potential effects to sediment and surface water dwelling invertebrates

These an alytical r esults for the supplemental PRP BERA soil, s ediment, and s urface water samples were assessed for overall risk through comparison to literature-based screening values and site-specific toxicity testing of representative receptors to site environmental media. Overall, the data collected in support of the PRP BERA met the data quality objectives (DQO) outlined in the *Final BERA Work Plan & SAP* (URS 2010b) and are ad equate for evaluation and r isk characterization in the PRP BERA.

The BERA in Appendix A focused on further addressing risk from surface soils and sediments in the North Area, sediments in the Intercoastal Waterway, and surface waters in the North Area wetlands. Potential risk was evaluated through additional data analysis.

Toxicity tests of North Area surface soils to soil invertebrates, represented by the marine polychaete, *N. arenaceodentata*, indicated a significant difference for growth at one sampling location. Toxicity tests of wetland sediments to sediment dwelling invertebrates, represented by the amphipod, *L. plumulosus*, indicated statistically significant differences in survival of *L. plumulosus* at four locations and significant differences in growth at two locations. No significant differences were observed for survival and growth of N. *arenaceodentata* for the North Area sediment or the Intracoastal Waterway sediment. Acute toxicity to the brine shrimp, *A. salina*, was indicated in one surface water sample from the North Area.

While the results of the site-specific toxicity test indicate the potential for adverse effects to benthic invertebrates, risk is likely overestimated due to the intermittent nature of surface water in the wetlands. Depending on rainfall and tide conditions, many of the areas selected for sediment toxicity analysis can often be completely dry. Significant populations of invertebrates would likely be limited to areas with perennial surface water. While individual effects may be present, it is unlikely that population level effects to growth and survival of invertebrates exist from COPECs in site surface soils, sediments and surface waters.

These findings are similar to those of the EA *Technical Memorandum Ecological and Habitat Health Assessment, Wetlands A, B, and C* (EA 2010) which indicated that observed human impacts to the Site wetland habitats are minor. The Site wetlands are not visually distinguishable from surrounding wetlands in terms of wetland species composition and approximate density, presence of invertebrates, and wildlife usage. These wetlands are providing valuable wetland marsh functions, such as wildlife habitat, food, flood storage, water quality enhancement, and ground water recharge. Any disturbance, such as excavation of sediments or other remedial activities, would require decades for sediments in this area to return to the salty sediment marsh type environment present today.

Additional refinement of the risk characterization for the wetlands sediments was warranted based on the results of site-specific toxicity test which indicate the potential for adverse effects at four of seven site samples that differ significantly from the reference samples.

Although the Appendix A BERA indicates that no further action is necessary based upon the ecological assessment, it may be beneficial from a risk management standpoint to remove some or all of the sediments from the potentially impacted areas.

Surface Impoundment Cap Inspection

Based upon the Technical Memorandum - Surface Impoundment Cap Evaluation for Erosion (EA 2010), the thickness of the cap is approximately 2.5 to 3.5 feet thick. TCEQ Guidelines indicate a thickness of four feet is needed for Class 1 wastes. Additionally, the cap has ruts in the western portion. The majority of the ruts are 3 inches in depth with one rut as much as 6 inches in depth. These ruts appear to be the result of vehicular traffic across the cap. The ruts do not appear to have penetrated the entire thickness of the cap at this time and thus have not compromised the integrity of the cap.

Removal Action Alternative Summary

The data presented in the Appendix A BERA along with the site inspections and data collected to evaluate the former surface impoundments cap indicates that further remedial action may or may not be warranted to mitigate potential exposures to human health and environment. An area of buried debris is also present immediately south of the capped surface impoundments. In addition to the ecological risk assessment, an evaluation of the existing surface impoundment cap was performed. To address the debris area and the existing surface impoundment cap, five removal alternatives were identified and evaluated. The five alternatives are:

- Alternative # 1 No Further Action (NFA)
- Alternative # 2 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas
- Alternative # 3 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and install a gravel drive on the western portion of the cap to facilitate vehicular traffic
- Alternative # 4 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and extend the cap to the south to cover the debris area.
- Alternative # 5 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and extend the cap to the south to cover the debris area, and install a gravel drive on the western portion of the cap to facilitate vehicular traffic

A brief description of each alternative is presented in Section 6.1. As the presence of the waste material under the cap will be unchanged, institutional controls (which are currently in place) will remain a part of the recommended alternative.

These five alternatives were evaluated based upon cost, effectiveness and implementability. In the comparative analysis of the five alternatives, Alternative # 5 is the most protective of the alternatives but also the most costly. Alternative # 4 is also protective but does not include the gravel drive designed to protect the cap from the effects of vehicular traffic. Alternatives # 2 and # 3 are less costly than Alternatives # 4 and # 5 but do not address potentially impacted sediments located south of the existing surface impoundment cap. Alternative # 1 will not be effective in addressing the RAOs. The EPA will make the final decision regarding which alternative to implement.

Page 5 of 24 December 2010

2. INTRODUCTION

This document presents the Engineering Evaluation/Cost Analysis (EE/CA) prepared by EA Engineering, Science, and Technology, Inc. (EA) for the Gulfco Marine Superfund Site (Site) located in Freeport, Brazoria County, Texas. EA performed the EE/CA for the U.S. Environmental Protection Agency (EPA) Region 6 as part of the Non Time Critical Removal Support (NTCRS) Task Order No. 0067-NSEE-06JZ under EPA Contract No. EP-W-06-004, in accordance with a Statement of Work (SOW) issued by EPA (October 2010).

The Site was operated by multiple companies as a barge cleaning and maintenance facility from 1971 to 1999. In May 2003, the EPA named the former Gulfco Marine Maintenance facility to the National Priorities List (NPL). The Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) Identification Number assigned to the Site is TXD055144539. The purpose of this Task Order was to conduct an engineering evaluation and cost analysis for the planned removal activities and to provide the data necessary to select a remedy that eliminates, reduces, or controls risks to human health and the environment.

The Draft Preliminary Site Characterization Report (PSCR) (URS Corporation (URS), November 2010), the Final Nature and Extent Data Report (Pastor, Behling & Wheeler, LLC (PBW), May 2009, the Final Screening Level Ecological Risk Assessment (SLERA) (PBW, May 2010), and the Baseline Ecological Risk Assessment (BERA) (Appendix A) provide the basis for this EE/CA.

2.1 PURPOSE OF REPORT

In this EE/CA, potential remedial alternatives are qualitatively developed and assessed against three evaluation criteria to evaluate the relative merits of each alternative and to help identify the preferred alternative. This document focuses on general response actions associated with the former surface impoundments, the North Area surface soils, North Area Surface Water, and the Intercoastal Waterway sediments. The South Area of the site is being remediated separately. While there are detections of hazardous constituents in ground water, response actions for ground water will be addressed separately. The data presented in the Appendix A BERA, along with the site inspections and data collected to evaluate the former surface impoundments cap, indicates that further remedial action may be warranted to mitigate potential exposures to human health and environment. As such, an EE/CA identifying remedial alternatives to address impacted on-site soils is appropriate. This EE/CA summarizes the removal action objectives, identification of potential removal alternatives, and a detailed evaluation of five alternatives for in-place soil.

The three criteria to be employed in evaluation of removal alternatives are:

- Effectiveness
- Implementability
- Cost

Page 6 of 24 December 2010

2.2 REPORT ORGANIZATION

In accordance with the SOW, the following information is included in this EE/CA. A discussion of investigative activities is presented in Section 2. Data analysis is presented in Section 3. Risk Evaluation is presented in Section 4. Removal Action Objectives are presented in Section 5. Identification and analysis of removal action alternatives is presented in Section 6 and Section 7 presents a comparative analysis of removal alternatives.

2.3 SITE LOCATION AND DESCRIPTION

The site is located in Freeport, Texas at 906 Marlin Avenue (also referred to as County Road 756) (Appendix A - Figure 1). The site consists of approximately 40 acres along the north bank of the Intercoastal Waterway between Oyster Creek (approximately one mile to the east) and the Texas Highway 332 Bridge (approximately one mile to the west). The site includes approximately 1,200 feet of shoreline on the Intercoastal Waterway, the third busiest shipping canal in the United States.

Marlin Avenue divides the site into two primary areas (Appendix A - Figure 2). For the purposes of descriptions in this report, Marlin Avenue is approximated to run due west to east. The property north of Marlin Avenue (the North Area) consists of undeveloped land and closed surface impoundments, while the property south of Marlin Avenue (the South Area) was developed for industrial uses with multiple structures, a dry dock, an above ground storage tank (AST) farm, and two barge slips connected to the Intercoastal Waterway.

Adjacent property to the north, west, and east of the North Area is undeveloped. Adjacent property to the east of the South Area is currently used for industrial purposes while to the west the property is currently vacant and previously served as a commercial marina. The Intercoastal Waterway bounds the site to the south. Residential areas are located south of Marlin Avenue, approximately 300 feet west of the site, and 1,000 feet east of the site.

Some of the North Area is upland created from dredge spoil, but most of this area is considered wetlands, as per the United States Fish and Wildlife Service (USFWS) Wetlands Inventory Map (USFWS, 2008). The most significant surface features in the North Area are two ponds (the Fresh Water Pond and the Small Pond) and the closed former surface impoundments (Appendix A - Figure 2). The former surface impoundments and the former parking area south of the impoundments and Marlin Avenue comprise the vast majority of the upland area within the North Area. An area of buried debris is also present immediately south of the capped surface impoundments.

Field observations during the Remedial Investigation indicate the North Area wetlands are irregularly flooded with nearly all of the wetland area inundated by surface water that can accumulate to a depth of one foot or more during extreme high tide conditions, storm surge events (such as hurricanes), and/or in conjunction with surface flooding of Oyster Creek northeast of the site. Due to very low topographic slope and low permeability surface sediments, the wetlands are also very poorly draining and can retain surface water after major rainfall events. Under normal tide conditions and during periods of normal or below normal rainfall,

Page 7 of 24 December 2010

standing water within the wetlands (outside of the two identified ponds discussed below) is typically limited to a small, irregularly shaped area immediately north of the Fresh Water Pond and similar areas south and southeast of the former surface impoundments. Depending on rainfall and tide conditions, these areas can often be completely dry. As such, given the absence of any appreciable area of perennial standing water, the wetlands are effectively hydrologically isolated from Oyster Creek, except during intermittent, and typically brief, flooding events.

Water in the Fresh Water Pond is approximately 4 to 4.5 feet deep and is relatively brackish (PBW, 2009). This pond appears to be a borrow pit created by the excavation of soil and sediment as suggested by the well-defined pond boundaries and relatively stable water levels. Water levels in the Fresh Water Pond are not influenced by periodic extreme tidal fluctuations as the pond dikes preclude tidal floodwaters in the wetlands from entering the pond, except for extreme storm surge events.

The small irregularly shaped area immediately north of the Fresh Water Pond is a salt panne, a shallow depression that retains seawater for short periods of time such that salt accumulates to high levels over multiple tidal cycles.

The Small Pond is a very shallow depression located in the eastern corner of the North Area. The Small Pond is not influenced by daily tidal fluctuations and behaves in a manner consistent with the surrounding wetland (*i.e.*, becomes dry during dry weather, but retains water in response to and following rainfall and extreme tidal events). The Small Pond is also indicative of a salt panne.

The South Area includes approximately 20 acres of upland that was created from dredged material from the Intercoastal Waterway. The two most significant surface features within the South Area are a former dry dock and the AST tank farm. The remainder of the South Area surface consists primarily of former concrete laydown areas, concrete slabs from former site building, gravel roadways and sparsely vegetated open areas with some localized areas of denser brush vegetation, particularly near the southeast corner of the South Area. As described in the *Final BERA Problem Formulation* (URS, May 2010), the terrestrial portions of the South Area do not contain complete exposure pathways relevant to this assessment and are not considered further in the BERA process.

Aerial spraying of the wetland areas north of Marlin Avenue, including the North Area, for mosquito control has historically been and continues to be performed by the Brazoria County Mosquito Control District and its predecessor agency, the Brazoria County Mosquito Control Department (both referred to hereafter as BCMCD). Aerial spraying for mosquito control has been performed from altitudes of 50 to 100 feet (Lake Jackson News, 1957). Recently, BCMCD has been using Dibrom©, and organophosphate insecticide, with a diesel fuel carrier through a fogging atomizer application (Facts, 2006, 2008a, 2008b), as well as other compounds such as ScourgeTM, Kontrol 30-30, and Fyfanon® (personal communication between Gary Miller [USEPA] and Fran Henderson [BCMCD]). Truck-based spraying has also been performed along Marlin Avenue. Both types of spraying were observed during the performance of site Remedial Investigation activities.

Page 8 of 24 December 2010

3. INVESTIGATIVE ACTIVITIES

Multiple phases of investigation have been completed as part of the remedial investigation. Most recently, sediment and surface water, and Intercoastal Waterway sediment samples were collected in support of the PRP BERA. The following section presents a summary of the data pertinent to the development of the EE/CA.

3.1 TERRESTRIAL ENVIRONMENT

Investigation of site terrestrial areas was limited to the upland regions in the North Area including the former surface impoundments and the area south of the former impoundment. Soils in these areas likely became contaminated with constituents of potential ecological concern (COPECs) due to surface runoff from the former surface impoundment area prior to capping. The final PRP Screening Level Ecological Risk Assessment (SLERA) identified potential risk to lower-trophic receptors such as soil invertebrates in these upland areas. Media collected in support of the PRP BERA included surface soils (0-6 inches below ground surface [bgs]), which represents the biologically active zone for soil-dwelling invertebrates. Toxicity tests were also conducted on surface soils to assess potential effects to these invertebrates. The analytical data for each sample are presented in Appendix A of the *Preliminary Site Characterization Report* (PSCR) (PBW, 2010) and are summarized in Appendix A - Table 1 of the BERA.

3.1.1 North Area Surface Soil Sample Collection and Analysis

A total of six (6) surface soil samples were collected (0-6 inches bgs) from the North Area. Five (5) samples (NAS01 to NAS05) were collected in the area south of the former surface impoundment area, and one sample (NAS06) was collected in the northwest corner of the former surface impoundment area (Appendix A - Figure 3a). An additional three (3) samples, NAS07, NAS08, and NAS09, were collected in the soil reference area approximately 2000 ft east of the site (Appendix A - Figure 3b).

All samples were analyzed for the following metals identified as COPECs in previous steps of the risk assessment process:

- Barium
- Chromium
- Copper, and
- Zinc

In addition, 3 of the 6 soil samples from the North Area (NAS02, NAS03, and NAS05) were analyzed for 4,4'-DDT and Aroclor-1254.

Page 9 of 24 December 2010

3.1.2 North Area Surface Soil Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted on the six surface soil samples collected from the North Area and the three reference samples to evaluate direct toxicity to soil-dwelling invertebrates. A 28-day earthworm (*Eisenia fetida*) chronic bioassay was originally proposed in the *Final BERA Work Plan and SAP* (URS, 2010b); however, elevated salinity in the surface soil samples made use of the earthworm problematic. When earthworms were introduced to the North Area soil samples there was an immediate avoidance reaction followed by acute mortality in all of the site and background samples. The elevated salinity levels are believed to be due to frequent inundation of estuarine during storm events. Also, much of the soil was originally dredge spoils from the Intercoastal Waterway, which was used as a fill material.

An alternative to the earthworm bioassays was developed following discussion and agreement by the USEPA. This alternative treated the soils samples as sediments by adding synthetic seawater and exposing the marine polychaetous annelid, *Neanthes arenaceodentata*, to a 21-day bioassay to assess growth and survival. Polychaetes are more taxonomically similar to and occupy a similar feeding guild to earthworms. The North Area soil toxicity testing was conducted from September 10 through October 1, 2010.

3.2 AQUATIC ENVIRONMENT

Investigation of site aquatic areas includes the wetland areas of the North Area and the Intercoastal Waterway. Media (sediments and surface water) in these areas likely became contaminated with COPECs from direct discharge from barge cleaning operations, surface runoff, and flooding mechanisms. The final PRP SLERA identified potential risk to sediment and surface water dwelling invertebrates. Media collected in support of the BERA included bulk sediments (0-6 inches bgs) and surface water from the North Area wetlands and bulk sediments (0-6 inches bgs) from the Intercoastal Waterway. Sediment pore water was also extracted from bulk sediments. Toxicity tests were conducted on wetland sediments and surface water and Intercoastal Waterway sediments to assess potential effects to sediment and surface water dwelling invertebrates. The analytical data for each sample are presented in Appendix A of the PSCR and are summarized in Appendix A - Table 2 to Table 6 of the BERA.

3.2.1 North Area Wetland Bulk Sediment Sample Collection and Analysis

A total of seven (7) bulk sediment samples were collected (0-6 bgs) from the North Area wetlands. Fives (5) samples (EWSED03 to EWSED07) were collected in the wetland areas south of the former surface impoundment area, and two samples (EWSED01 and EWSED02) were collected north of the Fresh Water Pond (Appendix A - Figure 4). An additional two (2) samples, EWSED08 and EWSED09, were collected in the sediment reference area north of the site and west of the former surface impoundments (Appendix A - Figure 4).

All samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

• Polycyclic Aromatic Hydrocarbons (PAHs): 2-methylnaphthalene, acenaphthene,

December 2010

acenaphthylene, anthracene, benzo(a)anthracene, benzo(a)pyrene, benzo(g,h,i)perylene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, phenanthrene, pyrene

- Pesticides: 4,4'-DDT, endrin aldehyde, endrin ketone, gamma-chlordane
- Metals: arsenic, copper, lead, nickel, zinc
- Acid Volatile Sulfides/Simultaneously Extracted Metals (AVS/SEM)
- Grain size analysis

In addition to the bulk sediment samples, pore water was extracted and analyzed for COPECs for all but one sediment sample (EWSED05). This sample was too dry to extract pore water.

3.2.2 North Area Wetland Bulk Sediment Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted on the seven site sediment samples collected from the North Area and the two reference samples to evaluate direct toxicity to sediment-dwelling invertebrates. Two 28-day chronic bioassays were conducted using the amphipod, *Leptocheirus plumulosus*, and the polychaete, *Neanthes arenaceodentata*. Both organisms were selected for toxicity testing because both are representative of common species found along the Texas gulf coast, are sensitive to site COPECs, and are tolerant to a wide range of sediment and salinity conditions. Study endpoints of growth, mortality, and reproduction were measured for the *Leptocheirus* bioassay, while only the growth endpoint (with mortality data used to assist in the calculations) was used for the *Neanthes* bioassay.

3.2.3 North Area Wetland Surface Water Sample Collection and Analysis

A total of three (3) surface water samples were collected from the North Area wetlands. One sample (EWSW01) was collected in the area north of the Fresh Water pond. One sample (EWSW03) was collected in the small, irregularly shaped waterbody south of the former surface impoundment, and one sample (EWSW04) was collected from the near the Small Pond (Appendix A - Figure 5). Surface water was not present at the reference location (EWSW02) and analysis and this location could not be performed.

All surface water samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

- Acrolein (EWSW01 only)
- Dissolved copper (EWSW01 and SWSW03)
- Dissolved silver (EWSW04 only)

3.2.4 North Area Wetland Surface Water Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted on the three site surface water samples collected from the North Area to evaluate direct toxicity to surface water-dwelling invertebrates. A 7-day chronic bioassay analysis that measured the survival and growth of the mysid shrimp, *Mysidopsis bahia*, was originally proposed in the *Final BERA Work Plan & SAP* (URS, 2010b);

Page 11 of 24 December 2010

however, elevated salinity in the surface water samples from the salt panne areas (40% salinity at EWSW01 and 39% at EWSW04) made use of this test organism problematic.

An alternative to the mysid shrimp bioassays was developed following discussion and agreement by the USEPA. This alternative used the brine shrimp (*Artemia salina*), which is better suited to high salinities. Furthermore, since *A. salina* is typically more sensitive to environmental contaminants than fish, toxicity data should be protective of the fish community. No standards have been established for toxicity testing conducted on brine shrimp and a standard operating procedure (SOP) was developed by the analytical lab by referencing SOPs available for determining toxicity to produced (oil field) waters. The test protocol was shortened from 7 days to 96-hours and measured acute mortality of the organisms as the test endpoint. The shortened test period would likely be more representative of the intermittent nature of the surface water being evaluated in the North Area wetlands.

Surface water toxicity tests were conducted three times between September 16 and October 3, 2010 due to several factors including an incorrect food source being used for the test organism and control failures.

3.2.5 Intercoastal Waterway Bulk Sediment Sample Collection and Analysis

A total of five (5) bulk sediment samples (EIWSED01 to EIWSED05) were collected (0-6 inches bgs) from the Intercoastal Waterway (Figure 6). An additional two (2) samples (EIWSED06 and EIWSED07) were collected in the sediment reference area for the Intercoastal Waterway (Appendix A - Figure 6).

All bulk sediment samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

- Polycyclic Aromatic Hydrocarbons (PAHs): acenaphthene, benzo(a)anthracene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, phenanthrene, pyrene
- Pesticides: 4,4'-DDT
- Volatile Organic Compounds (VOCs): hexachlorobenzene

In addition to bulk sediment analysis, pore water was extracted and analyzed for the above COPECs at all seven sample locations.

3.2.6 Intercoastal Waterway Bulk Sediment Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted on the five sediment samples collected from the Intercoastal Waterway and the two reference samples to evaluate direct toxicity to sediment-dwelling invertebrates. Two 28-day chronic bioassays were conducted using the amphipod, *Leptocheirus plumulosus*, and the polychaete, *Neanthes arenaceodentata*. Both organisms were selected for toxicity testing because both are representative of common species found along the Texas gulf coast, are sensitive to Site COPECs, and are tolerant to a wide range of sediment and salinity conditions. Study endpoints of growth, mortality, and reproduction were measured for

Page 12 of 24 December 2010

the *Leptocheirus* bioassay, while only the growth endpoint (with mortality data used to assist calculations) was used for the *Neanthes* bioassay.

3.3 CAP ASSESSMENT

In addition to the supplemental investigative activities detailed above, an evaluation of the cap installed above the former surface impoundments was also performed. The evaluation of the cap was necessary to evaluate the continued effectiveness of this remedy. The surface impoundments were closed under the Texas Water Commission's (Texas Commission on Environmental Quality (TCEQ) predecessor agency) direction in 1982 (PBW, 2010). There is currently no formal operations and maintenance (O&M) program in place. Visual inspections along with samples of surface impoundment cap have been performed by PBW (Nature and Extent Data Report, PBW, May 2009) and EA. The most recent inspection and data collection effort was performed in December 2010. Information regarding this data collection effort was reported in the Technical Memorandum – Surface Impoundment Cap Evaluation for Erosion (EA, December 2010). Soil data collected from the additional borings installed in December 2010 are pending.

The following presents a summary of the available information regarding the current status of the cap:

- The upper surface of the cap consists of crushed shells (approximately six inches in thickness)
- Cap vegetation consists of mostly grasses with some brush. The majority of the brush is located along the perimeter of the cap with isolated patches within the interior portions of the cap
- Access to the cap is not controlled
- The cap has been documented to be generally 2.5 to 3.5 feet thick (Nature and Extent Data Report, PBW, May 2009)
- Rutting is present along the western portion of the cap. These ruts are due to vehicular traffic. The ruts are generally no more than 3 inches in depth with one location found to be approximately 6 inches deep.

The ruts do not appear to have penetrated the entire thickness of the cap at this time and thus have not compromised the integrity of the cap.

December 2010

4. DATA ANALYSIS

The following section presents a d iscussion of the data used to support the EE/CA. The data used was collected by both EA (for the cap and borrow pit evaluation) and URS (for the PRP Baseline Ecological Risk Assessment (BERA). The BERA prepared as part of the NTCRS Task Order (EA 2010) is included as Appendix A, and includes data from toxicity studies that are not included any PRP reports to date. As previously stated, an assessment of ground water is not included in this document. The nature and extent of the contaminants of interest (COIs) was presented in the NEDR (PBW, May 2009). For the purpose of this document, information regarding the nature and extent of contamination deemed relevant for preparation of the EE/CA is summarized below.

4.1 CAP DATA

As previously stated, the Cap material has been evaluated on several occasions. A consolidated summary of this information is included on Table 1. It should be noted that data collected as part of the field activities in December 2010 is pending.

4.2 ECOLOGICAL DATA SUMMARY

The Appendix A BERA focused on further addressing risk from surface soils and sediments in the North Area, sediments in the Intercoastal Waterway, and surface waters in the North Area wetlands. Potential risk was evaluated through the additional data collection and analysis.

Toxicity tests of North Area surface soils to soil invertebrates, represented by the marine polychaete, *N. arenaceodentata*, indicated a significant difference for growth at one sampling location. Toxicity tests of wetland sediments to sediment dwelling invertebrates, represented by the amphipod, *L. plumulosus*, indicated statistically significant differences in survival of *L. plumulosus* at four locations and significant differences in growth at two locations. No significant differences were observed for survival and growth of N. *arenaceodentata* for the North Area sediment or the Intracoastal Waterway sediment. Acute toxicity to the brine shrimp, *A. salina*, was indicated in one surface water sample from the North Area.

While the results of the site-specific toxicity test indicate the potential for adverse effects to benthic invertebrates, risk is likely overestimated due to the intermittent nature of surface water in the wetlands. Depending on rainfall and tide conditions, many of the areas selected for sediment toxicity analysis can often be completely dry. Significant populations of invertebrates would likely be limited to areas with perennial surface water. While individual effects may be present, it is unlikely that population level effects to growth and survival of invertebrates exist from COPECs in site surface soils, sediments and surface waters.

These findings are similar to those of the EA *Technical Memorandum Ecological and Habitat Health Assessment, Wetlands A, B, and C* (EA 2010) which indicated that observed human impacts to the Site wetland habitats are minor. The Site wetlands are not visually distinguishable from surrounding wetlands in terms of wetland species composition and approximate density,

December 2010

presence of invertebrates, and wildlife usage. These wetlands are providing valuable wetland marsh functions, such as wildlife habitat, food, flood storage, water quality enhancement, and ground water recharge. Any disturbance, such as excavation of sediments or other remedial activities, would require decades for sediments in this area to return to the salty sediment marsh type environment present today.

5. RISK EVALUATION

The following section present a summary of the risk assessments performed for the site. Both human health and ecological receptors were considered. The PRP Final Baseline Human Health Risk Assessment (BHHRA) (PBW, 2010a) presented a detailed summary of the human health risks. Conclusions from the PRP Final BHHRA concluded there were not unacceptable cancer risks nor non-cancer hazard indices for any of the five current or future exposure scenarios except for future exposure to an indoor industrial worker if a building is constructed over impacted ground water. The ecological risk evaluation presented in the Appendix A BERAconcluded the saltwater marsh area is a sensitive marsh sediment habitat created by years of temporary inundation by saltwater. Any disturbance of surficial sediments would require decades for sediments in this area to return to the salty sediment marsh type environment present today. This fact along with the data presented in the Appendix A BERA suggests that response actions for the risk associated with direct contact to invertebrates in the soil, sediments, and surface water may not be warranted.

6. REMOVAL ACTION OBJECTIVES

According to the NCP (40 CFR §300.430[a][1][I]), the goal of the remedy selection process is "to select remedies that are protective of human health and the environment, that maintain protection over time, and that minimize untreated waste." Remedial action objectives (RAOs) are medium-specific (e.g., soil or ground water) goals that address the requirements for protecting the human health and the environment (USEPA, 1988). In addition, Site actions must comply with ARARs relating to each action taken.

6.1 IDENTIFICATION OF REMOVAL ACTION OBJECTIVES

As discussed in Section 4.0 above, existing site conditions indicate the need for some form of a removal action. The remedial action objectives (RAO) are typically developed for exposure pathways posing an unacceptable risk. As previously stated, ground water is not being addressed in this document. It should be noted that the PRP BERA is currently undergoing EPA review. So while removal actions may not be warranted to address complete ecological exposure pathways, RAOs for ecological receptors have been included to allow EPA flexibility in the decision-making process. RAOs were identified for the Former Surface Impoundments based on future human health exposure and North Area Soils/Sediment/ Surface Water.

Page 15 of 24 December 2010

6.1.1 Former Surface Impoundments

As evidenced by the data from the cap investigations and the requirements set forth in the TCEQ Technical Guideline No. 3 (TCEQ, June 2009), the cap material is of sufficient vertical hydraulic conductivity but does not meet the criteria set forth for thickness for either a Class 1 or Class 2 waste. Additionally, ground water is impacted in the vicinity of the Former Surface Impoundments. Based on this information, the RAO for this area are: (1) Upgrade the cap to minimize the potential for waste exposure; and (2) minimize potential for continued degradation of ground water. Related to the ecological receptors in the North Area, the RAOs are: (1) Reduce the mobility and toxicity of sediments; and (2) Minimize the potential for direct contact with impacted sediments.

6.2 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS

ARARs are federal and state environmental laws and regulations that specify clean-up levels or performance standards for CERCLA sites.

Section 121(d) of CERCLA, as amended by Superfund Amendments and Reauthorization Act, states that on-site remedial actions must attain ARARs. ARARs may include regulations, standards, criteria, or limitations promulgated under federal or state laws. An ARAR may be either "applicable" or "relevant and appropriate," but not both. The NCP in 40 CFR §300 defines ARARs (USEPA, 1994).

Three categories of ARARs exist: chemical-, location-, and action-specific requirements. Chemical-specific ARARs are health- or risk-based numerical values or methodologies that, when applied to site-specific conditions, result in the establishment of numerical clean-up values. These values establish the acceptable amount or concentration of a chemical that may be detected in or discharged to the ambient environment. Location-specific ARARs are restrictions on the concentrations of hazardous substances or on activities conducted at the Site that result from site characteristics or its immediate environment. For example, location of the Site or proposed remedial action in a flood plain, wetland, historic place, or sensitive ecosystem may trigger location-specific ARARs. Action-specific ARARs are technology- or activity-based requirements or limitations on actions taken. These requirements are triggered by the specific remedial activities selected. Action-specific ARARs do not in themselves determine the remedial alternative; rather, they indicate how an alternative must be conducted (EPA, 1994).

In addition to the legally binding requirements established as ARARs, many federal and state programs have developed criteria, advisories, guidelines, or proposed "To Be Considered" (TBC) standards. TBC material may provide useful information or recommend procedures if no ARAR addresses a particular situation or if existing ARARs do not provide protection. In such situations, TBC criteria or guidelines should be used to set remedial action levels. TBC criteria are not legally binding and do not have the status of ARARs.

Chemical-, location-, and action-specific ARARs for the remedial alternatives are listed below.

Federal Chemical-Specific ARARs

Page 16 of 24 December 2010

- Safe Drinking Water Act (40 United States Code [USC] Section 300)
 - 40 Code of Federal Regulations (CFR) 141 (National Primary Drinking Water Standards)—Establish health-based standards for public water systems (maximum contaminant levels or MCLs).
 - Public Law No. 99-339, 100 Statute 642, 1986 (Maximum Contaminant Level Goals) – Establish drinking water quality goals set at levels of known or anticipated adverse health effects, with an adequate margin of safety.
- Clean Water Act (33 USC Section 1251-1376)
 - o 40 CFR Part 131 (Water Quality Criteria) Sets criteria for ambient water quality on the basis of toxicity to aquatic organisms and human health.
 - 40 CFR Part 136 (EPA Guidelines Establishing Test Procedures for the Analysis of Pollutants) – Establish EPA regulations on test procedures for the analysis of pollutants
- Resource Conservation and Recovery Act (RCRA) (42 USC 6905, 6912, 6924, 6925)
 - o 40 CFR Part 261 (Identification and Listing of Hazardous Waste) Defines those solid wastes that are subject to regulation as hazardous waste under 40 CFR Parts 262-265 and Parts 124, 270, and 271.

Federal Chemical-Specific TBCs

• EPA OSWER Directive 9355.02 – MCLs for ground water contaminants

Federal Action-Specific ARARs

• 40 CFR 264.228 – Surface Impoundments – Provides criteria for closure and post-closure care

State of Texas Action-Specific ARARs

- Title 30 TAC Chapter 111 Requires that all reasonable precautions shall be taken to prevent particulate matter from becoming airborne, including use of water or chemicals for control of dust. Applicable during site excavation activities.
- Title 31 TAC Chapter 501 Subchapter B 501.23 Policies for development in critical areas.
- Texas Commission on Environmental Quality Industrial Solid Waste Management, Technical Guideline No. 3 Sets forth requirements for landfill cover design
- Title 30 TAC Chapter 335, Subchapter F Sets forth specific requirements for industrial hazardous waste landfills.
- Title 30 TAC Chapter 335, Subchapter T Sets forth specific requirements for commercial industrial nonhazardous waste landfills.
- Title 30 TAC Chapter 335, Subchapter O Land Disposal Restriction standards for the disposal of hazardous wastes.

Federal Chemical-Specific Potential ARARs

Page 17 of 24 December 2010

- Safe Drinking Water Act (40 United States Code [USC] Section 300)
 - 40 Code of Federal Regulations (CFR) 143 (National Secondary Drinking Water Standards)—Establish welfare-based standards for public water systems (secondary maximum contaminant levels).
- Clean Air Act (42 USC Section 7401-7642)
 - 40 CFR Part 50 (National Primary and Secondary Ambient Air Quality Standards)—Establish standards for ambient air to protect public health and welfare (including standards for particulate matter and lead).
- Resource Conservation and Recovery Act (RCRA) (42 USC 6905, 6912, 6924, 6925)
 - 40 CFR Part 264 (RCRA Ground Water Protection) Provides for ground water protection standards, general monitoring requirements, and technical requirements.
 - o 40 CFR Part 257.3-4 (RCRA Solid Waste Disposal Facility Requirements)-Provides for protection of ground water at solid waste disposal facilities

Federal Chemical- and Action-Specific Potential ARARs

- RCRA (42 USC 6905, 6912, 6924, 6925)
 - o 40 CFR Part 268 (Land Disposal Restrictions) Establish a timetable for restriction of burial of wastes and other hazardous materials.

Federal Action-Specific Potential ARARs

- RCRA (42 USC Sections 6901-6987)
 - o 40 CFR Part 257 (Criteria for Classification of Solid Waste Disposal Facilities and Practices) Establish criteria for use in determining which solid waste disposal facilities and practices pose a reasonable probability of adverse effects on health, and thereby constitute prohibited open dumps.
- Hazardous Materials Transportation Act (49 USC Sections 1801-1813)
 - 49 CFR Parts 107, 171-177 (Hazardous Materials Transportation Regulations) Regulate transportation of hazardous materials

Federal Location-Specific Potential ARARs

- Fish and Wildlife Coordination Act (16 USC Sections 661-666) Requires consultation when a federal department or agency proposes or authorizes any modification of any stream or other body of water and adequate provision for protection of fish and wildlife resources.
- Endangered Species Act of 1973 (16 USC 1531-1544) Provides for the conservation of ecosystems upon which threatened and endangered species of fish, wildlife and plants depend.

Page 18 of 24 December 2010

• Clean Water Act (33 USC Section 1251-1376) – Section 404 of the Clean Water Act established a program to regulate the discharge of dredged or fill material into waters of the United States.

State of Texas Chemical-Specific Potential ARARs

Title 30 TAC Chapter 307 – Establishes limits for constituents for the protection of surface water quality.

State of Texas TBCs

• Texas Risk Reduction Program (TRRP) Title 30 Chapter 350 – Establishes the TCEQ's minimum remediation standards for present and past uncontrolled constituent releases using risk evaluation to determine if corrective action is necessary.

Federal Potential TBCs

- EPA OSWER Directive 9347.3-06FS Guidance in establishing cleanup goals dealing with treatment levels for contaminated soil and sediment
- Final Guidance, Superfund Removal Guidance for Preparing Action Memoranda, September 2009
- Federal Ambient Water Quality Criteria Establish protection of aquatic organisms and human health from contaminated sediment.

7. IDENTIFICATION AND ANALYSIS OF REMOVAL ACTION ALTERNATIVES

7.1 APPLICABLE REMOVAL ALTERNATIVES

This section presents a list of removal alternatives potentially applicable to remediation of the impacted soils at the former surface impoundment area in Lot 56. In general, the alternatives fit into one or more category of general response actions (GRA). GRAs are generic, medium-specific, remedial actions that will satisfy the RAOs discussed earlier. GRAs may include no action, institutional controls, containment, removal, treatment, disposal, monitoring, or a combination thereof (EPA, 1988). The development of remedial alternatives begins with the identification of GRAs that can meet RAOs, which are then screened and developed into remedial alternatives to address all contaminated media at the Site. Alternatives for the remediation of soil will fall into GRAs No Further Action (NFA), institutional controls, containment, removal, and treatment. All alternatives deal with the former surface impoundment area shown on Figure 2 in Appendix A

The following five alternatives were considered.

Alternative # 1 No Further Action (NFA)

December 2010

Alternative # 2 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas (Containment).

- Alternative # 3 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and install a gravel drive on the western portion of the cap to facilitate vehicular traffic (Containment).
- Alternative # 4 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and extend the cap to the south to cover a debris area (Containment).
- Alternative # 5 Upgrade the existing cap such that a minimum of four feet of clay material covers the former surface impoundment areas and extend the cap to the south to cover a debris area and install a gravel drive on the western portion of the cap to facilitate vehicular traffic (Containment).

A brief description of each alternative is presented below. As the presence of the waste material under the cap will be unchanged, institutional controls will be required to remain a part of each of the recommended alternatives.

7.1.1 Alternative # 1

As required by the NCP (40 CFR § 300.430 [e] [6]), remedial alternatives must include the NFA alternative to be used as the baseline alternative against which the effectiveness of all other remedial alternatives are judged. The NFA alternative may not be effective in addressing the RAOs for the Site, but is retained per NCP requirement for future evaluation to provide a baseline for comparison against other technologies. At present there are institutional controls in the form of Restrictive Covenants on Lots 55, 56, and 57, executed in July of 2009. The covenants restrict the use of the property to commercial/industrial use and allow no human habitation. The covenant also restricts use of ground water for any purpose. The EPA and TCEQ must approve of any plans to construct a building on any of the Lots.

7.1.2 Alternative # 2

Implementation of the second alternative would include upgrading the existing cap such that a minimum clay thickness of four feet is achieved. According to the TCEQ – Industrial Solid Waste Management, Technical Guideline No. 3, the minimum recommended compacted soil thickness of a clay final cover is four feet along with a drainage and vegetative layer. To be protective, a minimum thickness of four feet is recommended. The upgrade to the surface impoundment cap would include removal of the oyster shells that lie on top of the cap, the addition of approximately 1.5 feet of additional clay material and install approximately 18 inches of topsoil. The surface of the cap would then be seeded to provide vegetative cover for the cap. An operations and maintenance program should also be implemented to maintain the cap.

Page 20 of 24 December 2010

7.1.3 Alternative # 3

Implementation of the third alternative would include upgrading the existing cap such that a minimum clay thickness of four feet is achieved. According to the TCEQ – Industrial Solid Waste Management, Technical Guideline No. 3, the minimum recommended compacted soil thickness of a clay final cover is four feet along with a drainage and vegetative layer. To be protective, a minimum thickness of four feet is recommended. The upgrade to the surface impoundment cap would include removal of the oyster shells that lie on top of the cap, the addition of approximately 1.5 feet of additional clay material and install approximately 18 inches of topsoil. The surface of the cap would then be seeded to provide vegetative cover for the cap. Additionally, a gravel drive (consisting of three to six inches of #57 stone) would be installed on the western portion of the cap to facilitate vehicular traffic. Additionally, and operations and maintenance program should be established for maintenance of the cap.

7.1.4 Alternative # 4

Implementation of the fourth alternative would include extension of the cap to the south to include the covering of a small debris area. The debris would remain onsite and would be contained beneath the extended surface impoundment cap. In addition, the existing cap would be upgraded such that a minimum clay thickness of four feet is achieved. The minimum recommended compacted soil thickness of a clay final cover is four feet along with a drainage and vegetative layer. To be protective, a minimum thickness of four feet is recommended. The upgrade to the surface impoundment cap would include removal of the oyster shells that lie on top of the cap, the addition of approximately 1.5 feet of additional clay material and install approximately 18 inches of topsoil. The surface of the cap would then be seeded to provide vegetative cover for the cap. An operations and maintenance program should be established for maintenance of the cap.

7.1.5 Alternative # 5

Implementation of the fifth alternative would include the covering of the debris are to the south of the existing cap. The debris would remain onsite and would be contained beneath the extended surface impoundment cap. In addition, the existing cap would be upgraded such that a minimum clay thickness of four feet is achieved. According to the TCEQ – Industrial Solid Waste Management, Technical Guideline No. 3, the minimum recommended compacted soil thickness of a clay final cover is four feet for Class 1 waste or three feet for Class 2 waste. To be protective, a minimum thickness of four feet is recommended. The upgrade to the surface impoundment cap would include removal of the oyster shells that lie on top of the cap, the addition of approximately 1.5 feet of additional clay material and install approximately 18 inches of topsoil. The surface of the cap would then be seeded to provide vegetative cover for the cap. Additionally, a gravel drive (consisting of three to six inches of #57 stone) would be installed on the western portion of the cap to facilitate vehicular traffic. The gravel drive would be installed after the minimum four feet of clay is installed and compacted.

7.2 ALTERNATIVE SCREENING

Page 21 of 24 December 2010

Three p reliminary s creening criteria (effectiveness, implementability, and cost) were used to screen remedial alternatives. Definitions for these screening criteria are presented below, and the results of soil technology screening are summarized on Table 2.

7.2.1 Effectiveness

This criterion is a measure of the ability of an option to: (1) reduce toxicity, mobility, or volume;

- (2) minimize residual risks; (3) afford long-term protection; (4) comply with ARARs;
- (5) minimize short-term impacts; and (6) achieve protectiveness in a limited duration. Alternatives that offer significantly less effectiveness than other proposed technologies may be eliminated from the alternative development process. Options that do not provide adequate protection of human health and the environment likewise are eliminated from further consideration.

7.2.2 Implementability

Implementability is a measure of the technical feasibility and availability of the option and the administrative feasibility of implementing it (e.g., obtaining permits for off-site activities, rights-of-way, or construction). Options that are technically or administratively infeasible or that would require equipment, specialists, or facilities that are not available within a reasonable period may be eliminated from further consideration.

7.2.3 Cost

Qualitative relative costs for implementing the remedy are considered. Alternatives that cost more to implement, but offer no benefit in effectiveness or implementability over other technologies, may be excluded from the alternative development process.

7.3 SEDIMENT SCREENING SUMMARY

The results of the soil technology screening are summarized in Table 2. Each of the five technologies discussed above have been retained for further evaluation. The soil remediation technologies retained are subjected to further analysis as individual components in removal alternatives (Section 7.0).

7.4 GROUND WATER GENERAL RESPONSE ACTION SUMMARY

While hazardous constituents have been detected in ground water in the vicinity of the surface impoundments, further response actions beyond the repair and or upgrades to the surface impoundment cap are beyond the scope of the non-time critical removal action.

8. COMPARATIVE ANALYSIS OF REMOVAL ALTERNATIVES

Page 22 of 24 December 2010

This section evaluates the remedial alternatives presented in Section 6 using the three criteria mentioned previously: 1) Effectiveness, 2) Implementability, and 3) Cost. The comparison criteria and evaluation process are discussed below and Table 2 presents the evaluation of the five remedial alternatives.

8.1 COMPARATIVE ANALYSIS

8.1.1 Effectiveness

Each alternative is evaluated in terms of risk that remains at the Site after the RAO has been met. The primary focus of this evaluation is the extent and effectiveness of controls used to manage the risk posed by treatment residuals or untreated wastes. The following factors will be considered in evaluating this criterion:

- Adequacy of remedial controls
- Reliability of remedial controls
- Magnitude of the residual risk

Alternative # 1

Since this alternative consists of no action, this alternative may not be effective at addressing the potential risk for release of contaminants at the surface impoundment cap nor at addressing the potential risks posed by sediments and surface water. This alternative is used as a reference for the remaining alternatives.

Alternative # 2

Alternative # 2 consists of upgrading the existing surface impoundment cap. This alternative will reduce the risks posed by the potential for a breach of the cap. This alternative will be more effective than Alternative # 1.

Alternative # 3

Alternative # 3 consists of upgrading the existing surface impoundment cap and installing a gravel drive to facilitate vehicular traffic. This alternative will reduce the risks posed by the potential for a breach of the cap. Additionally, this alternative will be protective of the cap by reducing the impacts of vehicular traffic. This alternative will be more effective than Alternative # 1 and Alternative # 2.

Alternative # 4

Alternative # 4 consists of performing an extension of the cap to include the debris area south of the cap and upgrading the existing surface impoundment cap. This alternative will reduce the risks posed by the potential for a breach of the cap. Compared with Alternative # 3, this alternative will be more effective due to the extending of the surface impoundment cap.

Page 23 of 24 December 2010

Alternative # 5

Alternative # 5 consists of performing an extension of the cap to include the debris area south of the cap and upgrading the existing surface impoundment cap. Also, a gravel drive will be installed to facilitate vehicular traffic. This alternative will reduce the risks posed by the potential for a breach of the cap. Additionally, this alternative will be protective of the cap by reducing the impacts of vehicular traffic. Compared with Alternative # 3, this alternative will be more effective due to the extending of the surface impoundment cap. Compared with Alternative # 4, this alternative will be protective of the cap by reducing the impacts of vehicular traffic.

8.1.2 Implementability

This criterion addresses the technical and administrative feasibility of implementing an alternative and the availability of various services and materials that may be required during its implementation. The following factors were considered:

- Ability to construct the technology
- Monitoring requirements
- Availability of equipment and specialists
- Ability to obtain approvals from regulatory agencies

For each of the five alternatives, standard earth-moving equipment such as bull dozer and excavator are necessary to implement the alternative. Locating a borrow source with sufficient clay material for the cap would be the most challenging task. Each alternative would be implementable.

8.1.3 Cost

The cost for each alternative is calculated from estimates of capital and operation and maintenance (O&M) costs. Capital costs consist of direct and indirect costs. Direct costs include the purchase of equipment, labor, and materials necessary to implement the alternative. Indirect costs include engineering, financial, and other services such as testing and monitoring. Annual O&M costs for each alternative include operating labor, maintenance materials and labor, auxiliary materials, and energy. For the alternatives described herein, the O&M costs would consist of costs for cap maintenance.

The cost estimate is normally expected to fall within the range of 50 percent above to 30 percent below the actual project cost (accuracy of + 50% and - 30%). Cost estimates for remediation alternatives are presented in Tables 3 to 6 and are summarized below.

Alternative	Capital Cost	O&M Cost	Total Cost
1	\$0	\$0	\$0

Page 24 of 24 December 2010

2	\$1,775,800-828,700	\$132,000-61,600	\$1,907,800-890,300
3	\$1,938,700-904,700	\$132,000-61,600	\$2,070,700-966,300
4	\$2,190,000-1,022,000	\$132,000-61,600	\$2,322,000-1,083,600
5	\$2,345,400-1,094,500	\$132,000-61,600	\$2,477,400-1,156,100

The evaluation of the five alternatives is summarized in Table 2. As previously stated, the EPA is currently reviewing the PRP BERA. So while the evaluations presented above include response actions related to protection of human health and the environment. The EPA will make the decision as to which alternative to implement.

REFERENCES

- Pastor, Behling & Wheeler, LLC (PBW), 2009. *Nature and Extent Data Report, Gulfco Marine Maintenance Site, Freeport, Texas.* May 3.
- Pastor, Behling & Wheeler, LLC (PBW), 2010a. Final Baseline Human Health Risk Assessment, Gulfco Marine Maintenance Site, Freeport, Texas. March 31.
- Pastor, Behling & Wheeler, LLC (PBW), 2010b. Final Screening Level Ecological Risk Assessment Report, Gulfco Marine Maintenance Site, Freeport, Texas. May 3.
- Pastor, Behling & Wheeler, LLC (PBW). 2010c. *Preliminary Site Characterization Report* (*PSCR*), *Gulfco Marine Maintenance Site*, *Freeport*, *Texas*. November 3.Lake Jackson News. 1957.
- EA Engineering Science and Technology, 2010. *Technical Memorandum Surface Impoundment Cap Evaluation for Erosion*, December
- Texas Commission on Environmental Quality (TCEQ) 2009. June 2009. Technical Guideline No. 3
- USEPA. 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA (Interim Final). OSWER Directive 9355.3-01. EPA/540/G-89-004. October.
- USEPA. 1994. "National Oil and Hazardous Substances Pollution Contingency Plan." Title 40 Code of Federal Regulations, Part 3 and 59 Federal Register 47384. 18 October.
- URS Corporation (URS), 2010a. Final Baseline Ecological Risk Assessment Problem Formulation Report, Gulfco Marine Maintenance Site, Freeport, Texas. September 2.
- URS Corporation (URS), 2010b. Final Baseline Ecological Risk Assessment Work Plan & Sampling and Analysis Plan, Gulfco Marine Maintenance Site, Freeport, Texas. September 2.

Tables

Table 1 Page 1 of 1 SUMMARY OF CAP INVESTIGATION DATA GULFCO MARINE MAINTENANCE SUPERFUND SITE

Boring Location	Cap Material Description	Observed Cap Thickness (feet)	Liquid Limit ⁽²⁾ (%)	Plastic Limit (2) (%)	Plasticity Index (2) (%)	Percent Passing # 200 Sieve (3) (%)	Moisture Content ⁽⁴⁾ (%)	Vertical Hydraulic Conductivity (5) (cm/sec)
PBW Investigation	2009							
ND1GT01	Sandy Lean Clay	2.9	48	16	32	70	20	3.5 x 10 ⁻⁸
ND2GT02	Lean Clay with Sand	>3.5	49	14	35	84	23	1.4 x 10 ⁻⁸
NE1GT03	Lean Clay with Sand	2.5	49	13	35	74	19	5.0 x 10 ⁻⁹
NE2GT04	Fat Clay	3.6	58	15	43	88	26	5.9 x 10 ⁻⁹
EA Investigation - De	ecember 2010							
		DATA CURR	ENTLY UN	DER REVIE	W			
TCEQ Technical Gui	ideline No. 3 Recommended Value	/Range			10-35	> 20		< 1.0 x 10 ⁻⁷

- 1) Crushed oyster shell surface observed above clay cap at all four boring locations PBW 2009.
- 2) ASTM Method D 4318
- 3) ASTM Method D 1140
- 4) ASTM Method D 2216
- 5) US Army Corp of Engineers, Engineering Manual Method 1110-2-1906

TABLE 2 Page 1 of 1

REMOVAL ALTERNATIVE SCREENING GULFCO MARINE MAINTENANCE SUPERFUND SITE

General Response Action	Alternative #	Components	Brief Description	Effectiveness	Implementability	Cost	Status
No Action	1	No Action	No action	Not effective in addressing RAOs	Implementable	Low	Retained
Containment	2	Upgrade Existing Surface Impoundment Cap.	Address the potential risk for breaching of the existing surface impoundment cap.		Implementable - cap maintenance will need to be performed for life of the cap.	Moderate	Retained
Containment	3	Upgrade Existing Surface Impoundment Cap and Install Gravel Drive to Facilitate Vehicular Traffic.	Address the potential risk for breaching of the existing surface impoundment cap and provides protection for the cap by minimizing the effects of vehicular traffic.	Would be effective in reducing risks associated with the existing surface impoundment cap and provides additional protection that will aid in maintenance costs.	Implementable - cap maintenance will need to be performed for life of the cap.	Moderate	Retained
Containment	4	Extend the Cap to Cover the Debris Area south of the former surface impoundment area. Also, upgrade existing surface impoundment cap.	Addresses the debris area south of the surface impoundment cap. Debris will be contained onsite. Upgrade of the cap will also be performed.	· ·	Implementable - cap maintenance will need to be performed for life of the cap.	Moderate	Retained
Containment	5	Extend the Cap to Cover the Debris Area south of the former surface impoundment area. Also, upgrade existing surface impoundment cap and Install Gravel Drive to Facilitate Vehicular Traffic.	Addresses the debris area south of the surface impoundment cap. Debris will be contained onsite. Upgrade of the cap will also be performed. Provide additional protection for the cap by minimizing the effects of vehicular traffic.	Would be effective in addressing the debris area. Also, would be effective in reducing risks associated with the existing surface impoundment cap and provides additional protection that will aid in maintenance costs.	Implementable - cap maintenance will need to be performed for life of the cap.	Moderate	Retained

Table 3 - COST ESTIMATE - ALTERNATIVE # 2 Sulfco Marine Maintenance Superfund Site Gulfco Marine Maintenance Description: Perform Upgrade to the Cap. Includes 5 years cap maintenance. Location: Freeport, Brazoria County, Texas Base Year: 2010 Date: Dec 27, 2010 Assumptions: Upgrades to the cap will include removing the approximately 6-inch layer of oyster shells on top of the cap, installing an additional 1.5- foot layer of clay material, placing topsoil and hydroseeding surface. UNIT COST DESCRIPTION QTY TOTAL CAPITAL COSTS Remedial Design Remedial Design 100,000 REMEDIAL DESIGN SUBTOTAL 100,000 SITE PREPARATION Site Prep Erosion Control Plan Development & Submittals LS 12,000 \$ 12,000 Professional estimate Site Survey/Utility Locate 1.500 4,500 RS Means 2005 Environmental Remediation Cost Data Erosion Control Implementation - Silt Fencing 2,000 7,000 LS Construct Decon Station for Trucks and Heavy Equipment 1 4.800 4.800 Professional estimate Equipment Delivery 300.00 Professional estimate each 1.500 Office/Equipment Trailer Miscellaneous Materials days 150.00 450 Professional estimate each 5,000 5,000 Professional estimate Wheel Loader davs 350 1.050 Hertz equipment rental Pickup Trucks (2) days <u>Labor</u> Site Superintendent OA Officer 30 hrs 110 3.300 Professional estimate Operator (2) 65 Technician 30 hrs 1,950 Professional estimate Site Safety and Health Officer 110 3 300 Professional estimate Per Diem 2,160 Professional estimate days 720 Site Prep Subtotal 55,290 Professional Services, Project Management, and Fees LS 3,200 3,200 Legal Fees for Institutional Controls and Deed Project management Pollution Liability Insurance of subtotal 2,765 3% of subtotal 1,659 Payment and performance bond 3% of subtotal 1.659 Construction/program managemen 5,529 Undefined scope and market allowance 15% of subtotal 8,294 Professional Services, Project Management, and Fees Subtotal 23,104 SITE PREPARATION SUBTOTAL 78,394 CAP UPGRADE AND FIELD OVERSIGHT Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles rolls s 80 \$ 400 Heavy Equipment Rental for Installation of Engineered Cover 325 6,500 days Hertz equipment rental Backhoe 20 days 200 4,000 Hertz equipment rental 200 250 Roller/Compacto 20 days 4.000 Hertz equipment rental 20 5,000 Dump Truck days Hertz equipment rental Pickup Trucks (2) 40 day 80 3,200 Hertz equipment rental Earthwork RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) Clay Layer (includes compaction) 7,800 CY 28 45 218,400 5,800 261,000 Top Soil CY Quality Control Testing (includes compaction testing) LS 78,000 78,000 RS Means Costworks 2010 1st quarter Erosion Control Blanket 8,000 RS Means 312513100100 4.000 12,000 Hydroseeding acres Professional estimate Subcontractor Labor Site superintendent QA Officer 200 hrs 110 22,000 Professional estimate 22,000 110 Operators (2) 400 hrs 75 30,000 Professional estimate 26,000 22,000 Technicians (2) 400 65 Professional estimat Site Safety and Health Officer 110 200 Professional estimate hrs Per Dien 20 days 840 16,800 **739,300** Professional estimate SUBTOTAL Professional Services, Project Management, and Fees 5% Project management of subtotal 36,965 of subtotal 22,179 22,179 Pollution Liability Insurance 3% 3% Payment and performance bond Construction/program management 10% of subtotal 73,930 Undefined scope and market allowance of subtotal Professional Services. Project Management, and Fees Subtotal 266,148 SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BACKFILL SUBTOTAL 1,005,448 CAPITAL COST TOTAL \$ 1,183,842

20.000

18,700 17,500

16,400 15,400

\$1,271,842

20.000

20,000

20,000

20.000

20,000

LS

LS

LS

Cap maintenance at 7% net present value Cap maintenance at 7% net present value Cap maintenance at 7% net present value

Cap maintenance at 7% net present value Cap maintenance at 7% net present value

ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3)

ANNUAL CAP MAINTENANCE (Year 4) ANNUAL CAP MAINTENANCE (Year 5)

TOTAL ESTIMATED COST

Table 4 - COST ESTIMATE - ALTERNATIVE # 3 Sulfco Marine Maintenance Superfund Site Gulfco Marine Maintenance Description: Perform Upgrade to the Cap and Install Roadway to Facilitate Vehicular Traffic. Includes 5 years cap maintenance. Location: Freeport, Brazoria County, Texas Base Year: 2010 Date: Dec 27, 2010 Assumptions: Upgrades to the cap will include removing the approximately 6-inch layer of oyster shells on top of the cap, installing an additional 1.5- foot layer of clay material, placing topsoil and hydroseeding surface. UNIT COST DESCRIPTION QTY TOTAL CAPITAL COSTS Remedial Design Remedial Design 100,000 \$ 100,000 REMEDIAL DESIGN SUBTOTAL 100,000 SITE PREPARATION Site Prep Erosion Control Plan Development & Submittals LS 12,000 \$ 12,000 Professional estimate Site Survey/Utility Locate 1.500 4,500 RS Means 2005 Environmental Remediation Cost Data Erosion Control Implementation - Silt Fencing 2,000 7,000 LS Construct Decon Station for Trucks and Heavy Equipment 1 4.800 4.800 Professional estimate Equipment Delivery 300.00 Professional estimate each 1.500 Office/Equipment Trailer Miscellaneous Materials days 150.00 450 Professional estimate each 5,000 5,000 Professional estimate davs Wheel Loader 350 1.050 Hertz equipment rental Pickup Trucks (2) days <u>Labor</u> Site Superintenden 3,300 OA Officer 30 hrs 110 3.300 Professional estimate Operator (2) Technician 30 hrs 65 1,950 Professional estimate Site Safety and Health Officer 110 3 300 Professional estimate Per Diem 2,160 Professional estimate days 720 Site Prep Subtotal 55,290 Professional Services, Project Management, and Fees LS 3,200 3,200 Legal Fees for Institutional Controls and Deed Project management Pollution Liability Insurance of subtotal 2,765 3% of subtotal 1,659 Payment and performance bond 3% of subtotal 1.659 Construction/program managemen 5,529 Undefined scope and market allowance 15% of subtotal 8,294 Professional Services, Project Management, and Fees Subtotal 23,104 SITE PREPARATION SUBTOTAL 78,394 CAP UPGRADE AND FIELD OVERSIGHT Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles rolls s 80 \$ 400 Heavy Equipment Rental for Installation of Engineered Cover 325 days 7,800 Hertz equipment rental Backhoe 20 days 200 4,000 Hertz equipment rental 200 250 Roller/Compacto 24 24 days 4 800 Hertz equipment rental 6,000 Hertz equipment rental Dump Truck days Pickup Trucks (2) 48 days 80 3.840 Hertz equipment rental Earthwork RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) Clay Layer (includes compaction) 7,800 CY 28 218,400 5,800 261,000 Top Soil CY Quality Control Testing (includes compaction testing) LS 78,000 78,000 RS Means Costworks 2010 1st quarter Erosion Control Blanket 2,000 SY 8,000 RS Means 312513100100 4.000 Hydroseeding acres 12,000 Professional estimate #57 Rock 1,800 2,400 CY 20 36,000 12,000 Professional estimate Geotextile Subcontractor Labor Site superintendent 240 hrs 110 26,400 Professional estimate 240 440 26,400 33,000 QA Officer 110 Professional estimate Professional estimate Operators (2) 75 hrs Technicians (2) 480 65 31 200 Professional estimate Site Safety and Health Officer 110 26,400 Professional estimate hrs 23,520 **819,160** Per Diem 28 davs 840 Professional estimate SUBTOTAL Professional Services, Project Management, and Fees 40,958 of subtotal Project management Pollution Liability Insurance 3% of subtotal 24,575 Payment and performance bond of subtotal 24,575 Construction/program management 10% of subtotal 81.916 Undefined scope and market allowance 15% of subtotal 122,874 Professional Services, Project Management, and Fees Subtotal 294,898 SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BACKFILL SUBTOTAL 1,114,058 CAPITAL COST TOTAL 1,292,452 ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3) Cap maintenance at 7% net present value Cap maintenance at 7% net present value Cap maintenance at 7% net present value 20.000 20,000 18,700 17,500 LS 20,000 LS 20,000 16,400 15,400 Cap maintenance at 7% net present value Cap maintenance at 7% net present value

\$1,380,452

LS

LS

20,000

20,000

ANNUAL CAP MAINTENANCE (Year 4)

ANNUAL CAP MAINTENANCE (Year 5)

TOTAL ESTIMATED COST

Culfoo Marino Maintonanco Suncefee d Sito	1:	able 5 - CO				
Site: Gulfoo Marine Maintenance Superfund Site Site: Gulfoo Marine Maintenance Location: Freeport, Brazoria County, Texas Base Year: 2010 Date: Dec 27, 2010		-	Includes Soils to underne	s 5 years cap be excavated eath the exten	maintenance. are estimated to be app ded surface impoundment	and EWSED07 by Extending the Surface Impoundment Cap to the South - Perform Upgrade to the Cap. proximately 5,000 cubic yards (~200 feet x 675 feet x 1 foot). These soils will be contained onsite ent cap. Upgrades to the cap will include removing the approximately 6-inch layer of oyster shells on top or
DESCRIPTION	QTY	UNIT		, installing ar FCOST	TOTAL	rer of clay material , placing topsoil and hydroseeding surface. NOTES
CAPITAL COSTS REMEDIAL DESIGN						
<u>Remedial Design</u> Remedial Design	1	LS	\$	150,000	150,000	Professional estimate
REMEDIAL DESIGN SUBTOTAL					150,000	
SITE PREPARATION Site Prep						
Erosion Control Plan Development & Submittals	1	LS	\$	12,000		Professional estimate
Site Survey/Utility Locate	4 2,400	acres	\$	1,500		RS Means 2005 Environmental Remediation Cost Data
Erosion Control Implementation - Silt Fencing Construct Decon Station for Trucks and Heavy Equipment	2,400	ft LS	\$ \$	3.50 4,800		Professional estimate Professional estimate
Equipment Delivery	5	each	s	300.00		Professional estimate
Office/Equipment Trailer	3	days	\$	150.00	450	Professional estimate
Miscellaneous Materials	1	each	\$	5,000		Professional estimate
Wheel Loader Pickup Trucks (2)	3 6	days days	\$ \$	350 80		Hertz equipment rental Professional estimate
	Ü	-my.s	-			
Labor Site Superintendent	30	J	\$	110	3,300	Professional actimate
Site Superintendent QA Officer	30 30	hrs hrs	\$	110		Professional estimate Professional estimate
Operator (2)	60	hrs	\$	75	4,500	Professional estimate
Technician	30	hrs	\$	65		Professional estimate
Site Safety and Health Officer Per Diem	30 3	hrs days	\$ \$	110 720		Professional estimate Professional estimate
		,	-	_		
Site Prep Subtotal					58,190	
Professional Services, Project Management, and Fees						
Legal Fees for Institutional Controls and Deed	1	LS	\$	3,200	3,200	
Project management	5%	of subtotal of subtotal			, ,	
Pollution Liability Insurance Payment and performance bond	3% 3%					
Pollution Liability Insurance Payment and performance bond Construction/program management	3% 3% 10%	of subtotal of subtotal			1,746	
Payment and performance bond Construction/program management Undefined scope and market allowance	3%	of subtotal		<u>.</u>	1,746 5,819 8,729	
Payment and performance bond Construction/program management	3% 10%	of subtotal of subtotal			1,746 5,819 8,729	
Payment and performance bond Construction/program management Undefined scope and market allowance	3% 10%	of subtotal of subtotal		: 	1,746 5,819 8,729	
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF	3% 10% 15%	of subtotal of subtotal		: 	5 1,746 5 5,819 6 8,729 6 24,148	
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL	3% 10% 15%	of subtotal of subtotal	\$: 	1,746 5,819 6,8,729 6,24,148 8,338	
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles	3% 10% 15%	of subtotal of subtotal of subtotal	s		1,746 5,819 8,729 24,148 8 82,338	
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer	3% 10% 15%	of subtotal of subtotal of subtotal	s	80 :	1,746 5,819 6,8,729 6,24,148 8,338	Hertz equipment rental
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe	3% 10% 15% CAP 5	of subtotal of subtotal of subtotal rolls	s s	80 : 325 : 200 :	1,746 5,819 8,729 24,148 82,338 400 6,9,100 6,5,600	Hertz equipment rental Hertz equipment rental
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe RollerCompactor	3% 10% 15% CAP 5 28 28 28	of subtotal of subtotal of subtotal rolls days days days	\$ \$ \$	80 : 325 : 200 : 200 :	1,746 5,819 5,8,729 6,24,148 82,338 400 5,9,100 5,600 5,5,600	Hertz equipment rental
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe	3% 10% 15% CAP 5	of subtotal of subtotal of subtotal rolls	s s	80 : 325 : 200 :	1.746 5.819 5.8,729 5.24,148 6.82,338 6.400 6.9,100 6.5,600 7,000 7,000	
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal STE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller(Compactor Dump Truck Pickup Trucks (2)	3% 10% 15% CAP 5 28 28 28 28 28	of subtotal of subtotal of subtotal rolls days days days days	\$ \$ \$ \$	80 : 325 : 200 : 200 : 250 : 250 : 325 : 3	1.746 5.819 5.8,729 5.24,148 6.82,338 6.400 6.9,100 6.5,600 7,000 7,000	Hertz equipment rental Hertz equipment rental
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck	3% 10% 15% CAP 5 28 28 28 28 28	of subtotal of subtotal of subtotal rolls days days days days	\$ \$ \$ \$	80 : 325 : 200 : 200 : 250 : 250 : 325 : 3	1,746 5,819 8,729 24,148 82,338 400 5,9100 5,600 5,600 5,600 4,480	Hertz equipment rental Hertz equipment rental Hertz equipment rental
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil	3% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000	of subtotal of subtotal of subtotal of subtotal rolls days days days days CY	\$ \$ \$ \$ \$	80 325 200 200 250 80 28 45	1,746 5,819 5,8,729 6,24,148 6,82,338 6,400 6,9,100 6,5,600 7,000 6,4,480 6,263,200 6,315,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres)
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing)	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days CY CY LS	\$ \$ \$ \$ \$	80 325 200 200 250 80 28 45 78,000	1,746 5,819 8,729 24,148 82,338 400 5,9,100 5,5,600 6,5,600 6,7,000 6,4,480 6,263,200 6,315,000 78,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil	3% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000	of subtotal of subtotal of subtotal of subtotal rolls days days days days CY	\$ \$ \$ \$ \$	80 325 200 200 250 80 28 45	1,746 5,819 5,8,729 6,24,148 6,9,100 6,5,600 7,000 6,4,480 6,263,200 6,315,000 7,8,000 6,7,000 6,8,000 6,8,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres)
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding	3% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days CY CY LS SY	\$ \$ \$ \$ \$ \$	80 325 200 200 250 80 28 45 78,000 4	1,746 5,819 5,8,729 6,24,148 6,9,100 6,5,600 7,000 6,4,480 6,263,200 6,315,000 7,8,000 6,7,000 6,8,000 6,8,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means Costworks 2010 1st quarter
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Exosion Control Blanket Hydroseeding Subcontractor Labor	3% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000 1 2,000 3	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	80 325 200 200 250 80 28 45 78,000 4,000	1,746 5,819 5,8,729 6,24,148 6,82,338 6,400 6,9,100 6,5,600 7,000 6,4,480 6,263,200 6,315,000 7,000 6,78,000 6,8000 6,8000 6,8000 6,8000 6,8000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding	3% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days CY CY LS SY	\$ \$ \$ \$ \$ \$	80 325 200 200 250 80 28 45 78,000 4	1,746 5,819 8,729 24,148 82,338 400 6,9,100 6,5,600 6,5,600 6,5,600 6,7,000 6,4,480 6,263,200 6,7,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means Costworks 2010 1st quarter
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF A Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2)	3% 10% 15% 10% 15% 10% 15% 10% 15% 10% 15% 10% 10% 10% 10% 10% 10% 10% 10% 10% 10	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days have cry cy is sy compared to the subtotal rolls of the subtotal rolls of	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 80 : 45 : 78,000 : 4 : 4,000 : 110 : 110 : 157 : 5	1.746 5.819 5.8,729 6.24,148 6.82,338 6.400 6.9,100 6.5,600 6.5,600 7,000 6.4,480 6.263,200 6.315,000 6.8,000 6.8,000 6.12,000 6.30,800 6.30,800 6.30,800 6.42,000 6.42,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate Professional estimate Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2)	3% 10% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 1 2,000 3 280 280 560 560 560 560	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days hare subtotal cry cry cry ls sy acres	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	80 : 325 : 200 : 200 : 250 : 80 : 80 : 4 : 4 : 4,000 : 110 : 110 : 75 : 65	1,746 5,819 8,729 24,148 82,338 400 5,9,100 5,5,600 5,5,600 6,5,600 6,7,000 6,4,480 6,263,200 6,7,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate Professional estimate Professional estimate Professional estimate Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF A Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2)	3% 10% 15% 10% 15% 10% 15% 10% 15% 10% 15% 10% 10% 10% 10% 10% 10% 10% 10% 10% 10	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days have cry cy is sy compared to the subtotal rolls for the subtotal rolls for subtota	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 80 : 45 : 78,000 : 4 : 4,000 : 110 : 110 : 157 : 5	1,746 5,819 8,729 8,729 24,148 82,338 400 9,100 5,5,600 5,5,600 7,000 4,480 263,200 315,000 78,000 8,000 12,000 30,800 42,000 30,800	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate Professional estimate Professional estimate Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Sail Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer	3% 10% 10% 15% CAP 5 28 28 28 28 56 9,400 7,000 3 280 280 560 560 280	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days have cy cy cy ls sy acres	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 45 45,000 4 4,000 110 75 65 110	1,746 5,819 8,729 24,148 82,338 400 5,9100 5,600 5,600 5,600 6,7,000 4,480 6,263,200 6,315,000 6,78,000 6,315,000 6,30,800	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees	3% 10% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 280 28	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days have subtotal control of the subtotal subtotal rolls and subtotal sub	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 45 : 78,000 : 4 : 4,000 : 110 : 110 : 75 : 65 : 110 : 840 :	1,746 5,819 8,729 8,729 24,148 82,338 400 9,100 5,5,600 5,5,600 6,7,000 4,480 6,263,200 6,315,000 7,000 6,30,800 6,300 6,300 6,300 6,300 6,300 6,300 6,300 6,300 6,300 6,300 6	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management	3% 10% 15% 10% 15% 10% 15% 10% 15% 10% 10% 10% 10% 10% 10% 10% 10% 10% 10	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78,000 4 4,000 110 110 75 65 110 840	1,746 5,819 8,729 24,148 82,338 400 5,9,100 5,5600 5,5600 7,000 6,4,480 6,315,000 6,315,000 6,30,800 6	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF A Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance	3% 10% 15% 10% 15% 10% 15% 10% 15% 10% 15% 10% 10% 10% 10% 10% 10% 10% 10% 10% 10	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 45 : 78,000 : 4 : 4,000 : 110 : 110 : 75 : 65 : 110 : 840 :	1,746 5,819 8,729 24,148 82,338 400 6,9,100 6,5,600 6,5,600 6,5,600 6,7,000 6,4,480 6,315,000 78,000 6,315,000 78,000 6,30,800 6,	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management	3% 10% 15% 28 28 28 28 56 9,400 7,000 1 2,000 280 560 560 280 28 3% 3% 3% 10%	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78,000 4 4,000 110 110 75 65 110 840	1,746 5,819 8,729 24,148 82,338 400 5,9100 5,5600 5,5600 5,5600 7,000 4,480 6,315,000 7,000 6,315,000 6,30,800	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance	3% 10% 10% 15% 28 28 28 28 28 56 28 28 28 28 28 28 36 36 38 3% 3%	of subtotal of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 80 : 45 : 78.000 : 4 : 4,000 : 110 : 110 : 75 : 65 : 110 : 840 :	1.746 5.819 8.8229 8.224,148 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000 8.270,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 280 28 5% 3% 3% 3% 10% 15%	rolls days days days days days days days da	s s s s s s s s s s s s s s s s s s s	80 : 325 : 200 : 200 : 250 : 80 : 80 : 45 : 78,000 : 4 : 4,000 : 110 : 110 : 75 : 65 : 110 : 840 :	1.746 5.819 8.8229 8.224,148 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.2338 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.263,200 8.270,000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BA	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 280 28 5% 3% 3% 3% 10% 15%	rolls days days days days days days days da	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78.000 110 110 75 65 110 840	1.746 5.819 8.729 8.729 8.729 8.729 8.729 8.729 8.729 8.729 8.729 8.720	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 12513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF A Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BA CAPITAL COST TOTAL	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 560 280 28 3% 3% 10% 15%	of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78,000 4 4,000 110 110 75 65 110 840	1,746 5,819 8,729 24,148 82,338 400 5,9,100 5,5600 5,5600 5,5600 7,000 4,480 6,263,200 315,000 78,000 6,30,800 12,000 6,30,800 12,000 6,30,800 6,30,800 6,30,800 6,30,800 6,30,800 78,000 12,000 6,42,000 6,30,800	Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF a Sail Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Te	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 280 28 5% 3% 3% 3% 10% 15%	of subtotal of subtotal of subtotal of subtotal of subtotal also days days days days days days days days	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 80 44 4,000 110 110 75 65 110 840 20.000	1.746 5.819 5.8,729 5.24,148 6.24,148 6.32,338 6.400 6.5,600 7.000 6.5,600 7.000 6.4,480 6.263,200 6.315,000 6.30,800 6.	Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate Cap maintenance at 7% net present value
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heave Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BA CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3)	3% 10% 15% CCAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 280 560 560 280 28 5% 3% 10% 15% CCKFILL SUB1	of subtotal of subtotal of subtotal of subtotal rolls days days days days days days days day	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78,000 4 4,000 110 110 75 65 110 840	1.746 5.819 8.829 6.24,148 6.82,338 6.9,100 6.5,600 6.5,600 6.5,600 6.7,000 6.4,480 6.263,200 6.7,000 6.8,000 6.8,000 6.30,800 6.	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF A Soil Staging Areas G-mil LDPE liners for top and bottom of stockpiles Heavy Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BA CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3) ANNUAL CAP MAINTENANCE (Year 4)	3% 10% 15% CAP 5 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 280 560 280 280 560 280 10% 15% **CKFILL SUB1 1 1 1 1 1	of subtotal of subtotal of subtotal of subtotal of subtotal always days days days days days days days d	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 28 45 78,000 4 4,000 110 110 840 20,000 20,000 20,000 20,000	1.746 5.819 8.729 8.729 6. 24,148 8. 82,338 8. 400 6. 9,100 6. 5,600 6. 5,600 7,000 6. 4,480 6. 315,000 6. 315,000 6. 315,000 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 30,800 6. 31,500 6. 30,800 6. 31,500	Hertz equipment rental Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means 212513100100 Professional estimate Professional estimate Professional estimate Professional estimate Professional estimate Professional estimate Professional estimate Professional estimate Cap maintenance at 7% net present value Cap maintenance at 7% represent value
Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SITE PREPARATION SUBTOTAL SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF Soil Staging Areas 6-mil LDPE liners for top and bottom of stockpiles Heave Equipment Rental for Installation of Engineered Cover Dozer Backhoe Roller/Compactor Dump Truck Pickup Trucks (2) Earthwork Clay Layer (includes compaction) Top Soil Quality Control Testing (includes compaction testing) Erosion Control Blanket Hydroseeding Subcontractor Labor Site superintendent QA Officer Operators (2) Technicians (2) Site Safety and Health Officer Per Diem SUBTOTAL Professional Services, Project Management, and Fees Project management Pollution Liability Insurance Payment and performance bond Construction/program management Undefined scope and market allowance Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND BA CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3)	3% 10% 15% CAP 5 28 28 28 28 28 28 56 9,400 7,000 1 2,000 3 280 560 560 280 28 5% 3% 3% 10% 15% CCKFILL SUB1 1 1 1	of subtotal of subtotal of subtotal of subtotal of subtotal of subtotal days days days days days days days days	s s s s s s s s s s s s s s s s s s s	80 325 200 200 250 80 325 45 78,000 4 4 4,000 110 110 75 65 110 840 20,000 20,0	1.746 5.819 8.729 8.729 6.24,148 82,338 82,338 82,338 82,338 8400 6.9,100 6.5,600 7,000 6.5,600 7,000 6.4,480 8.000 12,000 8.000 8.000 12,000 8.000	Hertz equipment rental Hertz equipment rental Hertz equipment rental RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres) RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres) RS Means Costworks 2010 1st quarter RS Means 312513100100 Professional estimate

	T	blo 6 CC	Ter	ECTIMA	TE - ALTERI	NATIVE # 5
Gulfco Marine Maintenance Superfund Site	1;	abie o - Co	JS1	ESTIMA	IL - ALIEK	VALIVE#5
Site: Gulfco Marine Maintenance Location: Freeport, Brazoria County, Texas Base Year: 2010		-	Install	Roadway to F	Pacilitate Vehicular Tra	and EWSED07 by Extending the Surface Impoundment Cap to the South - Perform Upgrade to the Cap and affic. Includes 5 years cap maintenance. oproximately 5,000 cubic yards (~ 200 feet x 675 feet x 1 foot). These soils will be contained onsite
Date: Dec 27, 2010		Assumptions:	under	neath the exten	ded surface impoundn	nent cap. Upgrades to the cap will include removing the approximately 6-inch layer of oyster shells on top of
DESCRIPTION	QTY	UNIT		p, installing ar IT COST	additional 1.5- foot la TOTAL	yer of clay material , placing topsoil and hydroseeding surface. NOTES
CAPITAL COSTS	QII	UNII	UN	ir cosi	TOTAL	NOTES
REMEDIAL DESIGN						
<u>Remedial Design</u> Remedial Design	1	LS	\$	150,000	\$ 150,000	Professional estimate
REMEDIAL DESIGN SUBTOTAL					\$ 150,000	
SITE PREPARATION						
Site Prep						
Erosion Control Plan Development & Submittals Site Survey/Utility Locate	1 4	LS acres	\$ \$	12,000 1,500		Professional estimate RS Means 2005 Environmental Remediation Cost Data
Erosion Control Implementation - Silt Fencing	2,400	ft	\$	3.50	\$ 8,400	Professional estimate
Construct Decon Station for Trucks and Heavy Equipment	1	LS	\$	4,800	4,800	Professional estimate
Equipment Delivery	5	each	\$	300.00		Professional estimate
Office/Equipment Trailer Miscellaneous Materials	3	days each	\$ \$	150.00 5,000		Professional estimate Professional estimate
Wheel Loader	3	days	\$	350		Hertz equipment rental
Pickup Trucks (2)	6	days	\$	80	\$ 480	Professional estimate
<u>Labor</u>	**	,		***	e 220-	
Site Superintendent QA Officer	30 30	hrs hrs	\$ \$	110 110		Professional estimate Professional estimate
Operator (2)	60	hrs	\$	75	\$ 4,500	Professional estimate
Technician	30 30	hrs	\$ \$	65 110		Professional estimate Professional estimate
Site Safety and Health Officer Per Diem	30	hrs days	\$	720		Professional estimate Professional estimate
Site Prep Subtotal				-	\$ 58,190	
-						
<u>Professional Services, Project Management, and Fees</u> Legal Fees for Institutional Controls and Deed	1	LS	s	3,200	\$ 3,200	
Project management	5%	of subtotal			\$ 2,910	
Pollution Liability Insurance Payment and performance bond	3% 3%	of subtotal of subtotal			\$ 1,746 \$ 1,746	
Construction/program management	10%	of subtotal			\$ 5,819	
Undefined scope and market allowance	15%	of subtotal		_		
Professional Services, Project Management, and Fees Subtotal					\$ 24,148	
SITE PREPARATION SUBTOTAL					\$ 82,338	
SOIL EXCAVATION, FIELD OVERSIGHT, EXTENSION OF	CAP					
<u>Soil Staging Areas</u> 6-mil LDPE liners for top and bottom of stockpiles	5	rolls	s	80	\$ 400	
Heavy Equipment Rental for Installation of Engineered Cover						
Dozer	32	days	\$	325		Hertz equipment rental
Backhoe Roller/Compactor	28 32	days days	\$ \$	200 200		Hertz equipment rental
Dump Truck	32	days	\$	250	\$ 8,000	Hertz equipment rental
Pickup Trucks (2)	60	days	\$	80	\$ 4,800	Hertz equipment rental
Earthwork Clay Layer (includes compaction)	9,400	CY	s	28	\$ 263,200	RS Means Costworks 2010 1st quarter (assumes 24-inch clay layer across three acres)
Top Soil	7,000	CY	\$	45		RS Means Costworks 2010 1st quarter (assumes 18-inch layer of top soil across three acres)
Quality Control Testing (includes compaction testing)	1	LS	\$	78,000		RS Means Costworks 2010 1st quarter
Erosion Control Blanket Hydroseeding	2,000	SY acres	s s	4,000		RS Means 312513100100 Professional estimate
#57 Rock	1,800	CY	\$	20	\$ 36,000	Professional estimate
Geotextile	2,400	SY	\$	5	\$ 12,000	Professional estimate
Subcontractor Labor						
Site superintendent QA Officer	320 320	hrs hrs	\$ \$	110 110		Professional estimate Professional estimate
Operators (2)	600	hrs	\$	75	\$ 45,000	Professional estimate
Technicians (2) Site Safety and Health Officer	640 320	hrs hrs	\$ \$	65 110	\$ 41,600 \$ 35,200	Professional estimate Professional estimate
Per Diem	320	nrs days	\$	840		Professional estimate Professional estimate
SUBTOTAL		*			\$ 978,880	
Professional Services, Project Management, and Fees					_	
Project management Pollution Liability Insurance	5% 3%	of subtotal of subtotal			\$ 48,944 \$ 29,366	
Payment and performance bond	3%	of subtotal			\$ 29,366	
Construction/program management Undefined scope and market allowance	10% 15%	of subtotal			\$ 97,888 \$ 146,832	
condenned scope and marker allowance	15%	of subtotal		-	\$ 146,832 \$ 352,397	
Professional Services, Project Management, and Fees Subtotal		OTAL			\$ 1,331,277	
	ACKFILL SUBT					
Professional Services, Project Management, and Fees Subtotal	ACKFILL SUBT			:	\$ 1,563,615	
Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND B CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1)	1	LS	\$	20.000	\$ 20,000	Cap maintenance at 7% net present value
Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND B CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2)		LS LS	\$	20.000	\$ 20,000 \$ 18,700	Cap maintenance at 7% net present value
Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND B CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3) ANNUAL CAP MAINTENANCE (Year 4)	1 1 1 1	LS LS LS LS	\$ \$ \$	20,000 20,000 20,000 20,000	\$ 20,000 \$ 18,700 \$ 17,500 \$ 16,400	Cap maintenance at 7% net present value Cap maintenance at 7% net present value Cap maintenance at 7% net present value
Professional Services, Project Management, and Fees Subtotal SOIL EXCAVATION, FIELD OVERSIGHT, TREATMENT AND B CAPITAL COST TOTAL ANNUAL CAP MAINTENANCE (Year 1) ANNUAL CAP MAINTENANCE (Year 2) ANNUAL CAP MAINTENANCE (Year 3)	1 1 1	LS LS LS	\$ \$	20.000 20,000 20,000	\$ 20,000 \$ 18,700 \$ 17,500 \$ 16,400	Cap maintenance at 7% net present value Cap maintenance at 7% net present value

Appendix A Baseline Ecological Risk Assessment EA – December 2010



Baseline Ecological Risk Assessment (BERA)

Non-Time Critical Removal Support Gulfco Marine Maintenance Superfund Site Freeport,Brazoria County, Texas Contract No. EP-W-06-004 Task Order: 0067-NSEE-06JZ

Prepared for

U.S. Environmental Protection Agency Region 6 1445 Ross Avenue Dallas, Texas 75202-2733

Prepared by

EA Engineering, Science, and Technology, Inc. 405 S. Highway 121 Building C, Suite 100 Lewisville, Texas 75067 (972) 315-3922

> December 2010 Revision: 00 EA Project Number 14342.67

TABLE OF CONTENTS

			Page
1.0	INTE	RODUCTION	3
	1.1	SITE BACKGROUND	3
	1.2	ECOLOGICAL RISK ASSESSMENT PROCESS	5
	1.3	SCOPE OF DOCUMENT AND REPORT ORGANIZATION	6
2.0	SITE	INVESTIGATIONS IN SUPPORT OF THE BERA	6
	2.1	TERRESTRIAL ENVIRONMENT	6
		2.1.1 North Area Surface Soil Sample Collection and Analysis	
		2.1.2 North Area Surface Soil Toxicity Testing	
	2.2	AQUATIC ENVIRONMENT	8
		2.2.1 North Area Wetland Bulk Sediment Sample Collection and Analysis2.2.2 North Area Wetland and Intercoastal Waterway Bulk Sediment Toxic Testing8	
		2.2.3 North Area Wetland Surface Water Sample Collection and Analysis.	
		2.2.4 North Area Wetland Surface Water Toxicity Testing	
		2.2.5 Intercoastal Waterway Bulk Sediment Sample Collection and Analys	
3.0	EFFI	ECTS ANALYSIS	10
	3.1	TERRESTRIAL ENVIRONMENT	10
		3.1.1 Comparison of North Area Surface Soil Concentrations to Literature-Based Ecological Screening Values (ESVs)	
		3.1.2 Results of the <i>N. arenaceodentata</i> Toxicity Tests	
	3.2	AQUATIC ENVIRONMENT – NORTH AREA WETLANDS	
		3.2.1 Comparison of Sediment and Pore Water Concentrations to Literature	e-
		Based ESVs	
		3.2.2 Results of the <i>N. arenaceodentata</i> Toxicity Tests	
		3.2.3 Results of the <i>L. plumulosus</i> Toxicity Tests3.2.4 Comparison of Wetland Surface Water Concentrations to Literature-I	
		ESVs 13	Daseu
		3.2.5 Results of the A. salina Toxicity Tests	13
	3.3	AQUATIC ENVIRONMENT – INTERCOASTAL WATERWAY	
		3.3.1 Comparison of Sediment Concentrations to Literature-Based ESVs	
		3.3.2 Results of the <i>N. arenaceodentata</i> Toxicity Tests	
		3.3.3 Results of the <i>L. plumulosus</i> Toxicity Tests	14
	3.4	SUMMARY	15
4.0	RISK	CHARACTERIZATION	15
	4.1	IDENTIFICATION OF POTENTIAL STRESSORS	
	4.2	DIRECT EXOPSURE OF SOIL INVERTEBRATES	

		4.2.1 Comparison of North Area Surface Soils to Literature-Based Benchmarks	316
		4.2.2 N. arenaceodentata Toxicity Testing and Identification Potential Stressor	s16
	4.3	DIRECT EXPOSURE OF BENTHIC INVERTEBRATES IN WETLANDS	
		SEDIMENTS1	7
		4.3.1 Comparison of North Area Sediments to Literature-Based benchmarks 1	7
		4.3.2 N. arenaceodentata and L. plumulosus Toxicity Testing and Identification	
		of Potential Stressors	7
	4.4	DIRECT EXPOSURE OF BENTHIC INVERTEBRATES IN	
		INTERCOASTAL WATERWAY SEDIMENTS1	8
		4.4.1 Comparison of North Area Sediments to Literature-Based benchmarks 1	8
		4.4.2 N. arenaceodentata and L. plumulosus Toxicity Testing and Identification	
		of Potential Stressors	8
	4.5	DIRECT EXPOSURE OF AQUATIC ORGANISMS IN NORTH AREA	
		SURFACE WATER1	
		4.5.1 Comparison of North Area Sediments to Literature-Based benchmarks 1	
		4.5.2 A. salina Toxicity Testing and Identification of Potential Stressors1	9
5.0	UNC	ERTAINTY1	9
6.0	CON	CLUSIONS2	20
7.0	REF	ERENCES2	22

LIST OF TABLES

Table

Table 1	Data Summary Table for North Area Surface Soils
Table 2	Data Summary Table for North Area Wetland Sediments
Table 3	Data Summary Table for North Area Wetland Sediment Pore Water
Table 4	Data Summary Table for North Area Wetland Surface Water
Table 5	Data Summary Table for Intercoastal Waterway Sediments
Table 6	Data Summary Table for Intercoastal Waterway Sediment Pore Water
Table 7	Summary of Toxicity Testing for Soil and Sediment

LIST OF FIGURES

Figure

Figure 1	Site Location Map
Figure 2	Site Map
Figure 3a	Sample Locations and Potential Stressors in North Area Soils
Figure 3b	Reference Area Soils
Figure 4	Sample Locations and Potential Stressors in Wetland Sediments
Figure 5	Sample Locations and Potential Stressors in Wetland Surface Water
Figure 6	Sample Locations and Potential Stressors in Intercoastal Waterway Sediments
Figure 4 Figure 5	Sample Locations and Potential Stressors in Wetland Sediments Sample Locations and Potential Stressors in Wetland Surface Water

LIST OF ACRONYMS AND ABBREVIATIONS

AST Above Ground Storage Tank

AVS/SEM Acid Volatile Sulfides/Simultaneously Extracted Metals

BCMCD Brazoria County Mosquito Control Department

BERA Baseline Ecological Risk Assessment

bgs below ground surface

Chromalloy Chromalloy American Corporation

COPEC Constituent of Potential Ecological Concern

DDT dichlorodiphenyltrichloroethane DESR Data Evaluation Summary Report DOW The DOW Chemical Company

DQO Data Quality Objective

EA Engineering, Science, and Technology, Inc. EC20 Effects concentration 20 percent reduction

EPA Environmental Protection Agency ESV Ecological Screening Value

Facts Brazoria County Facts FS Feasibility Study

ft feet

FWS Fish & Wildlife Service GRG Gulfco Restoration Group

LC50 Lethal Concentration 50 percent

LDL LDL Coastal Limited LP microgram per liter mg/kg milligram per kilogram mg/L milligram per liter

μmol/goc micromole per gram organic carbon

NPL National Priorities List

NTCRS Non Time Critical Removal Support

OC organic carbon

PAH Polycyclic Aromatic Hydrocarbon

PBW Pastor, Behling & Wheeler PCA Principal Components Analysis

PSCR Preliminary Site Characterization Report

RI Remedial Investigation SAP Sampling and Analysis Plan

SLERA Screening Level Ecological Risk Assessment SMDP Scientific Management Decision Point

SOP Standard Operating Procedure

TCEQ Texas Commission of Environmental Quality
TNRCC Texas Natural Resource Conservation Commission

TOC Total Organic Carbon

UAO Unilateral Administrative Order

URS URS Corporation

VOC Volatile Organic Compound

1.0 INTRODUCTION

The U.S. Environmental Protection Agency (EPA) named the former site of Gulfco Marine Maintenance, Inc. in Freeport, Brazoria County, Texas (the site) to the National Priorities List (NPL) in May 2003. The EPA issued a modified Unilateral Administrative Order (UAO), effective July 29, 2005, which was subsequently amended effective January 31, 2008. The UAO required a Remedial Investigation (RI) and Feasibility Study (FS) be conducted for the site. As part of the RI/FS, a *Screening Level Ecological Risk Assessment* (SLERA) was prepared (Pastor, Behling & Wheeler [PBW] 2010a) on behalf of LDL Coastal Limited LP (LDL), Chromalloy American Corporation (Chromalloy) and The Dow Chemical Company (Dow), collectively known as the Gulfco Restoration Group (GRG). The Scientific/Management Decision Point (SMDP) provided in the final SLERA concluded there was a potential for adverse ecological effects, and a more thorough assessment was warranted.

This document summarizes the site investigation activities and analysis that has been performed in accordance with the *Final BERA Work Plan & Sampling and Analysis Plan (SAP)* (URS 2010b) and presents the assessment of ecological risk in the form of a Baseline Ecological Risk Assessment (BERA) for the Gulfco Marine Maintenance Superfund Site located in Freeport, Texas.

This BERA has been prepared in accordance with EPA guidance (EPA 1997; EPA 1998; EPA 1999) and the Texas Natural Resource Conservation Commission (TNRCC) guidance (TNRCC 2001).

1.1 SITE BACKGROUND

The site is located in Freeport, Texas at 906 Marlin Avenue (also referred to as County Road 756) (Figure 1). The site consists of approximately 40 acres along the north bank of the Intercoastal Waterway between Oyster Creek (approximately one mile to the east) and the Texas Highway 332 bridge (approximately one mile to the west). The site includes approximately 1,200 feet (ft) of shoreline on the Intercoastal Waterway, the third busiest shipping canal in the United States.

Marlin Avenue divides the site into two primary areas (Figure 2). For the purpose of descriptions in this report, Marlin Avenue is approximated to run due west to east. The property north of Marlin Avenue (the North Area) consists of undeveloped land and closed surface impoundments, while the property south of Marlin Avenue (the South Area) was developed for industrial uses with multiple structures, a dry dock, an above ground storage tank (AST) farm, and two barge slips connected to the Intercoastal Waterway.

Adjacent property to the north, west, and east of the North Area is undeveloped. Adjacent property to the east of the South Area is currently used for industrial purposes while to the west the property is currently vacant and previously served as a commercial marina. The Intercoastal Waterway bounds the South area to the south. Residential areas are located south of Marlin Avenue, approximately 300 ft west of the site, and 1,000 ft east of the site.

Some of the North Area is upland created from dredge spoil, but most of this area is considered wetlands, as per the U.S. Fish and Wildlife Service (FWS) Wetlands Inventory Map (FWS 2008). The most significant surface features in the North Area are two ponds (the Fresh Water Pond and the Small Pond) and the closed former surface impoundments (Figure 2). The former surface impoundments and the former parking area south of the impoundments and Marlin Avenue comprise the vast majority of the upland area within the North Area.

Field observations during the PRP RI indicate the North Area wetlands are irregularly flooded with nearly all of the wetland area inundated by surface water that can accumulate to a depth of one ft or more during extreme high tide conditions, storm surge events (such as hurricanes), and/or in conjunction with surface flooding of Oyster Creek located northeast of the site. Due to very low topographic slope and low permeability surface sediments, the wetlands are also very poorly draining and can retain surface water after major rainfall events.

During site reconnaissance performed by EA on 15 December 2010 it was noted that the wetlands are part of the contiguous high marsh/salt pan area between the site and Oyster Creek. These wetland areas were inundated with water (surface to 4 cm below grade), and connecting ditches and the marsh pan held several centimeters of water (EA 2010b).

Under normal tide conditions and during periods of normal or below normal rainfall, standing water within the wetlands (outside of the two identified ponds discussed below) is typically more limited. Depending on rainfall and tide conditions, these areas can either be completely full of water or completely dry.

Water in the Fresh Water Pond is approximately 4 to 4.5 ft deep and is relatively brackish (PBW, 2009). This pond appears to be a borrow pit created by the excavation of soil and sediment as suggested by the well-defined pond boundaries and relatively stable water levels. Water levels in the Fresh Water Pond are not influenced by periodic extreme tidal fluctuations as the pond dikes preclude tidal floodwaters in the wetlands from entering the pond, except for during extreme storm surge events.

The small irregularly shaped area immediately north of the Fresh Water Pond (Figure 2) is a salt panne, a shallow depression that retains seawater for short periods of time such that salt accumulates to high levels over multiple tidal cycles.

The Small Pond is a very shallow depression located in the eastern corner of the North Area. The Small Pond is not influenced by daily tidal fluctuations and behaves in a manner consistent with the surrounding wetland (*i.e.*, becomes dry during dry weather, but retains water in response to and following rainfall and extreme tidal events). The Small Pond is also indicative of a salt panne.

The South Area includes approximately 20 acres of upland that was created from dredged material from the Intercoastal Waterway. The two most significant surface features within the South Area are a former dry dock and the AST tank farm. The remainder of the South Area surface consists primarily of former concrete laydown areas, concrete slabs from former site buildings, gravel roadways and sparsely vegetated open areas with some localized areas of

denser brush vegetation, particularly near the southeast corner of the South Area. As described in the *Final BERA Problem Formulation* (URS Corporation [URS] 2010a), the terrestrial portions of the South Area do not contain complete exposure pathways relevant to this assessment and are not considered further in the BERA process.

Aerial spraying of the wetland areas north of Marlin Avenue, including the North Area, for mosquito control has historically been and continues to be performed by the Brazoria County Mosquito Control District and its predecessor agency, the Brazoria County Mosquito Control Department (both referred to hereafter as BCMCD). Aerial spraying for mosquito control has been performed from altitudes of 50 to 100 ft (Lake Jackson News 1957). Recently, BCMCD has been using Dibrom©, and organophosphate insecticide, with a diesel fuel carrier through a fogging atomizer application (Brazoria County Facts 2006, 2008a, 2008b), as well as other compounds such as ScourgeTM, Kontrol 30-30, and Fyfanon® (personal communication between Gary Miller [EPA] and Fran Henderson [BCMCD 27 October 2010]). Truck-based spraying has also been performed along Marlin Avenue. Both types of spraying were observed during the performance of site RI activities by the PRP.

1.2 ECOLOGICAL RISK ASSESSMENT PROCESS

In the superfund program, ecological risk is evaluated in an eight-step process, as defined in the Ecological Risk Assessment Guidance for Superfund (EPA 1977):

- 1) Screening Level Problem Formulation
- 2) Screening Level Exposure Estimate and Risk Calculation
- 3) BERA Problem Formulation
- 4) Study Design and Data Quality Objective Process
- 5) Field Sampling Plan Verification
- 6) Site Investigation and Data Analysis
- 7) Risk Characterization
- 8) Risk Management

The first two steps of the process were completed in the final PRP SLERA for the site (PBW 2010a). At the conclusion of the SLERA, the potential for adverse risk to several ecological receptors was determined and a SMPD was made to continue in the risk assessment process.

The third step in the process (BERA Problem Formulation) was completed for the site by the PRP in the *Final Baseline Ecological Risk Assessment Problem Formulation* (URS 2010a). In the problem formulation step, the list of constituents of potential ecological concern (COPEC) is further refined, contaminant fate and transport is evaluated, assessment endpoints, and a conceptual site model are defined, and questions of risk are developed.

The fourth and fifth steps in the BERA process were completed by the PRP in the *Final Baseline Ecological Risk Assessment Work Plan & Sampling and Analysis Plan (SAP)* (URS 2010b). In these steps, a work and sampling plan is developed for collecting additional media in support of the BERA and the methods for evaluating the potential for risk at the site (*i.e.*, toxicity testing) are outlined. Data quality objectives (DQOs) are also defined in these steps.

The sixth and seventh steps in the BERA process are addressed in this document and include the execution of the work and sampling plan, the analysis of the data, and the estimation of ecological risks. If the results of the first seven steps indicate a potential for ecological risk, a risk management decision (Step 8) is developed concerning what future actions, if any, may be undertaken to manage risk.

1.3 SCOPE OF DOCUMENT AND REPORT ORGANIZATION

This document outlines the site investigation and analysis (Step 6) conducted in support of the BERA and the resulting risk characterization (Step 7) of the ecological risk process. Risks are estimated using both qualitative and quantitative methods (toxicity testing). The results of this BERA will support Step 8 (risk management) if needed. Possible decision outcomes from the BERA include:

- There is adequate information to conclude that no adverse ecological risk is present (i.e., risk is within acceptable limit and further evaluation is not needed)
- There is adequate information to conclude that adverse ecological risk is present and development of remedial alternatives is warranted (i.e., continue to Step 8)
- Available information is not adequate to estimate risk (i.e., data gaps are present)

Section 2 of this document provides a discussion of the site investigation activities that were completed in support of this BERA and outlined in the PRP's *Final Baseline Ecological Risk Assessment Work Plan & SAP* (URS 2010b). Section 3 summarizes the media concentrations and exposure point concentrations for site samples. Section 4 provides an analysis of the effects to ecological receptors. Section 5 provides the risk characterization. Section 6 provides a discussion of the uncertainties associated with the BERA, and Section 7 summarizes the conclusions of the BERA.

2.0 SITE INVESTIGATIONS IN SUPPORT OF THE BERA

This section describes the sampling procedures and analysis of North Area surface soil, wetland sediment and surface water, and Intercoastal Waterway sediment collected in support of the BERA. Sampling activities were conducted by the PRP between August 2010 and September 2010. The sample collection methods, analytical methods, and toxicity testing methods are described in the *Final BERA Work Plan & SAP* (URS 2010b) and summarized below. Overall, the data collected by the PRP in support of the BERA met the DQOs outlined in the *Final BERA Work Plan & SAP* (URS 2010b) and are adequate for evaluation and risk characterization in the BERA.

2.1 TERRESTRIAL ENVIRONMENT

Investigation of site terrestrial areas was limited to the upland regions in the North Area including the former surface impoundments and the area south of the former impoundment. Soils in these areas likely became contaminated with COPECs due to surface runoff from the

former surface impoundment area prior to capping. The final PRP SLERA identified potential risk to lower-trophic receptors such as soil invertebrates in these upland areas (PBW 2010a). Media collected in support of the PRP BERA included surface soils (0-6 inches below ground surface [bgs]), which represents the biologically active zone for soil-dwelling invertebrates. Toxicity tests were also conducted on surface soils to assess potential effects to these invertebrates. The analytical data for each sample are presented in Appendix A of the *Preliminary Site Characterization Report* (PSCR) (PBW 2010b) and summarized in Table 1.

2.1.1 North Area Surface Soil Sample Collection and Analysis

A total of six (6) surface soil samples were collected (0-6 inches bgs) from the North Area. Five (5) samples (NAS01 to NAS05) were collected in the area south of the former surface impoundment area, and one sample (NAS06) was collected in the northwest corner of the former surface impoundment area (Figure 3a). An additional three (3) samples were collected in the soil reference area approximately 2000 ft east of the site (Figure 3b). Analytical results are shown in Table 1.

All samples were analyzed for the following metals identified as COPECs in previous steps of the risk assessment process:

- Barium
- Chromium
- Copper, and
- Zinc

In addition, three of the six soil samples from the North Area (NAS02, NAS03, and NAS05) were analyzed for 4,4'- dichlorodiphenyltrichloroethane (DDT) and Aroclor-1254.

2.1.2 North Area Surface Soil Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted using the six surface soil samples collected from the North Area and the three reference samples to evaluate direct toxicity to soil-dwelling invertebrates. A 28-day earthworm (*Eisenia fetida*) chronic bioassay was originally proposed by the PRP in the *Final BERA Work Plan and SAP* (URS 2010b); however, elevated salinity in the surface soil samples made use of the earthworm problematic. When earthworms were introduced to the North Area soil samples there was an immediate avoidance reaction followed by acute mortality in all of the site and background samples. The elevated salinity levels are believed to be due to frequent inundation of estuarine during storm events. Also, much of the soil was originally dredge spoils from the Intercoastal Waterway, which was used as a fill material.

An alternative to the earthworm bioassays was developed following discussion and agreement by the EPA. This alternative treated the soils samples as sediments by adding synthetic seawater and exposing the marine polychaetous annelid, *Neanthes arenaceodentata*, to a 21-day bioassay to assess growth and survival. Polychaetes occupy a similar feeding guild to earthworms. The North Area soil toxicity testing was conducted from September 10 through October 1, 2010.

2.2 AQUATIC ENVIRONMENT

Investigation of site aquatic areas included the wetland areas of the North Area and the Intercoastal Waterway. Media (sediments and surface water) in these areas likely became contaminated with COPECs from direct discharge from barge cleaning operations (Intercoastal Waterway), surface runoff, and flooding mechanisms. The final PRP SLERA identified potential risk to sediment and surface water dwelling invertebrates (PBW 2010a). Media collected in support of the PRP BERA included bulk sediments (0-6 inches bgs) and surface water from the North Area wetlands and bulk sediments (0-6 inches bgs) from the Intercoastal Waterway. Sediment pore water was also extracted from bulk sediments. Toxicity tests were conducted using wetland sediments and surface water and Intercoastal Waterway sediments to assess potential effects to sediment and surface water dwelling invertebrates. The analytical data for each sample are presented in Appendix A of the Preliminary Site Characterization Report (PSCR) and summarized in Table 2 through Table 6.

2.2.1 North Area Wetland Bulk Sediment Sample Collection and Analysis

A total of seven (7) bulk sediment samples were collected by the PRP at depths of 0-6 inches bgs from the North Area wetlands. Five (5) samples (EWSED03 to EWSED07) were collected in the wetland areas south of the former surface impoundment area, and two samples (EWSED01 and EWSED02) were collected north of the Fresh Water Pond (Figure 4). An additional two (2) samples were collected in the sediment reference area north of the site and west of the former surface impoundments (Figure 4). Analytical results are shown in Table 2.

All samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

- Polycyclic Aromatic Hydrocarbons (PAHs): 2-methylnaphthalene, acenaphthene, acenaphthylene, anthracene, benzo(a)anthracene, benzo(a)pyrene, benzo(g,h,i)perylene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, phenanthrene, pyrene
- Pesticides: 4,4'-DDT, endrin aldehyde, endrin ketone, gamma-chlordane
- Metals: arsenic, copper, lead, nickel, zinc
- Acid Volatile Sulfides/Simultaneously Extracted Metals (AVS/SEM)
- Grain size analysis

In addition to the bulk sediment samples, pore water was extracted and analyzed for COPECs for all but one sediment sample (EWSED05)(Table 3). This sample was too dry to extract pore water.

2.2.2 North Area Wetland and Intercoastal Waterway Bulk Sediment Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted using the seven site sediment samples collected from the North Area and the two reference samples to evaluate direct toxicity to sediment-dwelling invertebrates. Bioassays were also conducted using the five sediment

samples collected from the Intercoastal Waterway and the two reference samples to evaluate direct toxicity to sediment-dwelling invertebrates. Two 28-day chronic bioassays were conducted using the amphipod, *Leptocheirus plumulosus*, and the polychaete, *N. arenaceodentata*. Both organisms were selected for toxicity testing because both are representative of common species found along the Texas gulf coast marshes, are sensitive to site COPECs, and are tolerant to a wide range of sediment and salinity conditions. Study endpoints of growth, mortality, and reproduction were measured for the *L. plumulosus* bioassay, while only the growth endpoint (with mortality data used to assist in the calculations) was used for the *N. arenaceodentata* bioassay.

2.2.3 North Area Wetland Surface Water Sample Collection and Analysis

A total of three (3) surface water samples were collected from the North Area wetlands. One sample (EWSW01) was collected in the area north of the Fresh Water pond. One sample (EWSW03) was collected in the small, irregularly shaped waterbody south of the former surface impoundment, and one sample (EWSW04) was collected from the near the Small Pond (Figure 5). Surface water was not present at the reference location (EWSW02) and analysis and this location could not be performed. Analytical results are shown in Table 4.

All surface water samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

- Acrolein (EWSW01 only)
- Dissolved copper (EWSW01 and SWSW03)
- Dissolved silver (EWSW04 only)

2.2.4 North Area Wetland Surface Water Toxicity Testing

Laboratory toxicity tests (bioassays) were conducted using the three site surface water samples collected from the North Area to evaluate direct toxicity to surface water-dwelling invertebrates. A 7-day chronic bioassay analysis that measured the survival and growth of the mysid shrimp, *Mysidopsis bahia*, was originally proposed in the *Final BERA Work Plan & SAP* (URS 2010b); however, elevated salinity in the surface water samples from the salt panne areas (40% salinity at EWSW01 and 39% at EWSW04) were outside the testing tolerances for this test organism.

An alternative to the mysid shrimp bioassays was developed following discussion and agreement by the EPA. This alternative used the brine shrimp (*Artemia salina*), which is better suited to testing at high salinities. No standards have been established for toxicity testing conducted on brine shrimp and a standard operating procedure (SOP) was developed by the analytical lab by referencing SOPs available for determining toxicity to produced (oil field) waters. The test protocol was shortened from 7 days to 96-hours and measured acute mortality of the organisms as the test endpoint. The shortened test period would likely be more representative of the intermittent nature of the surface water being evaluated in the North Area wetlands.

Surface water toxicity tests were conducted three times between September 16 and October 3, 2010.

2.2.5 Intercoastal Waterway Bulk Sediment Sample Collection and Analysis

A total of five (5) bulk sediment samples (EIWSED01 to EIWSED05) were collected (0-6 inches bgs) from the Intercoastal Waterway (Figure 6). An additional two (2) samples (EIWSED06 and EIWSED07) were collected in the sediment reference area for the Intercoastal Waterway (Figure 6). Analytical results are shown in Table 5.

All bulk sediment samples were analyzed for the following parameters identified as COPECs in previous steps of the risk assessment process:

- PAHs: acenaphthene, benzo(a)anthracene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, phenanthrene, pyrene
- Pesticides: 4,4'-DDT
- Volatile Organic Compounds (VOCs): hexachlorobenzene

In addition to bulk sediment analysis, pore water was extracted and analyzed for the above COPECs at all seven sample locations.

3.0 EFFECTS ANALYSIS

This section presents 's effects analysis of the data collected through supplemental sampling activities and toxicity testing of site media for the Gulfco site. This analysis evaluates the potential adverse impacts associated with COPCs and calculates effects concentration 20 percent reduction (EC20s), where relevant. The toxicity test reports are available in the *Final Preliminary Site Characterization Report (PSCR)* (PBW 2010b). The independent evaluation by the EA project team is included in the Data Evaluation Summary Report (DESR) (EA 2010a).

3.1 TERRESTRIAL ENVIRONMENT

3.1.1 Comparison of North Area Surface Soil Concentrations to Literature-Based Ecological Screening Values (ESVs)

Table 1 provides a summary of the 2010 surface soil analytical results generated from implementation of the BERA sampling plan. Table 1 also compares the Texas Commission of Environmental Quality (TCEQ) soil benchmarks to the 2010 North Area surface soil concentrations.

The 2010 surface soil data shows exceedances of soil benchmarks for barium, chromium, copper, and zinc. Barium (which ranges from 52.2 milligram per kilogram [mg/kg] to 502 mg/kg) exceeded the TCEQ soil benchmark of 300 mg/kg in one site location (NAS04) and one reference sample (NAS07). Chromium (which ranges from 7.86 mg/kg to 97.3 mg/kg) exceeded the TCEQ soil benchmark of 30 mg/kg in two site locations (NAS01 and NAS05). Copper (which ranges from 10.1 mg/kg to 221 mg/kg) exceeded the soil benchmark of 61 mg/kg at only one site location (NAS01). Zinc (which ranges from 62.3 mg/kg to 5770 mg/kg) exceeded the

TCEQ soil benchmark of 120 mg/kg at five of the six site locations (NAS01 to NAS05) and two of the reference samples (NAS07 and NAS08).

TCEQ soil benchmarks were not available for the organics (4,4'-DDT and Aroclor-1254).

3.1.2 Results of the *N. arenaceodentata* Toxicity Tests

The results of the *N. arenaceodentata* toxicity tests are presented in Table 7 and summarized below from the PSCR (PBW 2010b). The testing of *N. arenaceodentata* over a 21-day exposure period showed no statistically significant difference between the North Area surface soil samples and the reference samples to the survival and growth endpoints for *N. arenaceodentata*. Survival of the six site samples ranged from 76 percent to 96 percent and the survival of the three reference samples ranged from 60 percent to 92 percent. Growth data show a similar relationship between the site and reference samples. The complete report for the 21-day *N. arenaceodentata* is presented in the PSCR (PBW 2010b).

In the evaluation, reference soils in NAS08 and NAS09 were pooled since they showed similar toxicological responses; however, reference soils at NAS07 were compared independently to site samples due to a significant difference at this location for both assessment endpoints. No site samples exhibited reduced survival to *N. arenaceodentata* when compared to either NAS07 or the pooled references consisting of NAS08 and NAS09. For the growth endpoint, however, growth at NAS01 was 57 percent lower than growth in reference NAS07 which is a statistically significant difference. The analytical results for NAS01 and the reference soils are provided on Figures 3a and 3b. No other site samples exhibited reduced growth when compared to NAS07. The output files for the analysis are presented in the DESR (EA 2010a).

3.2 AQUATIC ENVIRONMENT – NORTH AREA WETLANDS

3.2.1 Comparison of Sediment and Pore Water Concentrations to Literature-Based ESVs

Table 2 summarizes the analytical results for the 2010 wetland sediment samples collected in support of the BERA. There were several exceedances of the sediment benchmarks for multiple individual PAHs (acenaphthene, acenaphthylene, benzo(a)pyrene, chrysene, dibenzo(a,h)anthracene, fluoranthene, phenanthrene, pyrene) and metals (lead, nickel, and zinc). Acenaphthene (which ranges from 0.0013 mg/kg to 0.075 mg/kg) exceeded the TCEQ sediment benchmark of 0.016 mg/kg in one site location (EWSED05). Acenaphthylene (which ranges from 0.0008 mg/kg to 0.057 mg/kg) exceeded the TCEQ sediment benchmark of 0.044 mg/kg in one site location (EWSED01). Benzo(a)pyrene (which ranges from 0.01 mg/kg to 0.79 mg/kg) exceeded the TCEQ sediment benchmark of 0.43 mg/kg in one site location (EWSED05). Chrysene (which ranges from 0.014 mg/kg to 0.77 mg/kg) exceeded the TCEQ sediment benchmark of 0.384 mg/kg in three site locations (EWSED01, EWSED02, and EWSED05). Dibenzo(a,h)anthracene (which ranges from 0.0026 mg/kg to 0.17 mg/kg) exceeded the TCEQ sediment benchmark of 0.0634 mg/kg in three site locations (EWSED01, EWSED02, and EWSED05). Fluoranthene (which ranges from 0.02 mg/kg to 1.3 mg/kg) exceeded the TCEQ sediment benchmark of 0.6 mg/kg in one site location (EWSED05). Phenanthrene (which ranges

from 0.013 mg/kg to 0.78 mg/kg) exceeded the TCEQ sediment benchmark of 0.24 mg/kg in one site location (EWSED05). Pyrene (which ranges from 0.021 mg/kg to 1.1 mg/kg) exceeded the TCEQ sediment benchmark of 0.665 mg/kg in one site location (EWSED05). Lead (which ranges from 12 mg/kg to 76.1 mg/kg) exceeded the TCEQ sediment benchmark of 46.7 mg/kg in two site locations (EWSED03 and EWSED05). Nickel (which ranges from 14.4 mg/kg to 22.5 mg/kg) exceeded the TCEQ sediment benchmark of 20.9 mg/kg in two site locations (EWSED03 and EWSED05). Zinc (which ranges from 70.1 mg/kg to 959 mg/kg) exceeded the TCEQ sediment benchmark of 150 mg/kg in four site locations (EWSED06).

Analytical results for additional parameters including grain size analysis and SEM/AVS are also presented in Table 2. The SEM/AVS ratios are all above 1.0, except EWSED08 (SEM/AVS ratio of 0.157). Sediment grain sizes are fairly consistent between locations, except for the relatively high fraction of gravel and low fraction of clay found at EWSED02 and EWSED03, which is the opposite of the typical sediment profile (i.e., low fraction of gravel and high fraction of clay).

Table 3 summarizes the analytical results for the 2010 sediment pore water samples. The only exceedances of surface water benchmarks from site sediment pore water samples were for endrin aldehyde, endrin ketone, copper, and zinc. Endrin aldehyde (which ranges from <0.00000046 milligrams per liter [mg/L] to 0.000015 mg/L) exceeded the TCEQ surface water benchmark of 0.000002 mg/L in three site locations (EWSED01 to EWSED03). Endrin ketone (which ranges from <0.00000066 mg/L to 0.000007 mg/L) exceeded the TCEQ surface water benchmark of 0.000002 mg/L in one site location (EWSED03). Copper (which ranges from <0.000342 mg/L to 0.00702 mg/L) exceeded the TCEQ surface water benchmark of 0.0036 mg/L in two site locations (EWSED03 and EWSED05). Zinc (which ranges from <0.00135 mg/L to 0.626 mg/L) exceeded the TCEQ surface water benchmark of 0.0842 mg/L in two site locations (EWSED04 and EWSED06).

The only exceedances of either sediment or surface water benchmark in the background samples were 4,4'-DDT in sediment and 4,4'-DDT, endrin aldehyde, and nickel in pore water.

3.2.2 Results of the *N. arenaceodentata* Toxicity Tests

The results of the *N. arenaceodentata* toxicity tests are presented in Table 7 and summarized below from the PSCR (PBW 2010b). For *N. arenaceodentata* and the survival endpoint there were no statistically significant differences between the seven site samples and the two reference samples. Survival rates ranged from 72 percent to 96 percent in site samples and 68 percent to 76 percent in the reference samples. For the primary growth endpoint, there were also no statistical differences between the seven site samples and the two reference samples (PBW 2010b).

In the evaluation, reference soils in NAS08 and NAS09 were pooled since they showed similar toxicological responses. No Site samples exhibited reduced survival or growth to *N. arenaceodentata* when compared to the pooled references consisting of NAS08 and NAS09. The output files for the analysis are presented in the DESR (EA 2010a).

3.2.3 Results of the *L. plumulosus* Toxicity Tests

For the amphipod *L. plumulosus*, there were no statistical differences between the seven site samples and the two reference samples for either the survival or growth endpoint. Survival rates ranged from 13 percent to 58 percent in site samples and between 19 percent and 33 percent in reference samples (Table 7). There were insufficient offspring available for statistical analysis of reproduction as an endpoint.

In the evaluation, reference soils in NAS08 and NAS09 were pooled since they showed similar toxicological responses. Four site samples exhibited significantly reduced survival when compared to the pooled reference data set. These were EWSED03, EWSED04, EWSED06, and EWSED07. The reduced survival rates were 62, 55, 75, and 43 percent, respectively. The analytical results for the four locations exhibiting reduced survival and the reference areas are provided on Figure 4.

Growth was also significantly lower in samples EWSED03 and EWSED06 when compared with the pooled reference data set. The magnitude of the reduced growth appears to be ecological significant with growth reduced by 63 percent and 80 percent respectively. The output files for the analysis are presented in the DESR (EA 2010a).

3.2.4 Comparison of Wetland Surface Water Concentrations to Literature-Based ESVs

Table 4 provides a summary of the 2010 wetland surface water samples collected in support of the BERA included the TCEQ surface water benchmarks. The only exceedance of a surface water benchmark was for dissolved copper at EWSW03. The background location (EWSW02) could not be sampled for surface water during the 2010 sampling event as this area was dry.

3.2.5 Results of the A. salina Toxicity Tests

The results of the *A. salina* toxicity tests are presented in Table 7 and summarized below from the PSCR (PBW 2010b). The surface water toxicity tests were conducted three times between September 16 and October 3, 2010. EWSW01 and EWSW04 showed no evidence of acute toxicity since survival in the undiluted samples were greater than or equal to 80 percent for all test durations where the corresponding control survival was greater than or equal to 90 percent. EWSW03 was found to be non-toxic in test runs 1 and 2 (survival in the undiluted sample was greater than or equal to 80 percent for all test durations where the corresponding control survival was greater than or equal to 90 percent. In test run 3, a concentration-related mortality response was observed for EWSW03. The corresponding medial lethal concentrations (LC50) are as follows:

- 24 hour = 30.7 percent
- 48 hour = 10.6 percent
- 72 hour = 6.2 percent

While the mortality response for EWSW03 in test run 3 is consistent with the detection of copper at a concentration above the TCEQ chronic surface water benchmark (0.00854 mg/L vs. 0.00360

mg/L), the magnitude of the exceedance is not consistent with the observed mortality in test run 3, and is not consistent with the absence of toxicity in the first two runs (PBW 2010b).

The evaluation included an independent review of the results for Run 3 for all samples, which exhibited an acceptable control survival for 72 hours. By relevant test method guidance (EPA 2002), the Probit Method is the preferred procedure for determining the LC50 if the data passes the chi-square test. The Probit Method was appropriate for the data from these tests, and was used in the analysis. The results were generally consistent with those presented in the PSCR (PBW 2010b):

- Samples EWSW01 and 4 did not exhibit acute toxicity (LC50 > 100 percent)
- Sample EWSW03 had an LC50 at 6 percent dilution.

The analytical results of at sample EWSW03 (the only place to indicate toxicity) are shown on Figure 5 and in Table 4.

3.3 AQUATIC ENVIRONMENT – INTERCOASTAL WATERWAY

3.3.1 Comparison of Sediment Concentrations to Literature-Based ESVs

Table 5 summarizes the analytical results for the 2010 Intercoastal Waterway sediment samples collected in support of the PRP BERA. Table 5 also compares the TCEQ marine sediment benchmarks to the 2010 bulk sediment results. The only exceedance of sediment benchmarks were in sample EIWSED02 and included 4,4'-DDT (0.0019 mg/kg), acenaphthene (0.023 mg/kg), and fluorene (0.02 mg/kg).

Table 6 summarizes the analytical results for the 2010 sediment pore water samples. There were no exceedances of the marine surface water benchmarks in sediment pore water.

3.3.2 Results of the *N. arenaceodentata* Toxicity Tests

Table 7 includes a summary of the Intercoastal Waterway sediment toxicity testing results as presented in the PSCR. For the survival endpoint, there were no statically significant differences between the five sediment samples collected from the site and the reference area. There were also no statistical differences between the five site samples and the reference samples regarding the growth endpoint. The complete report for the 28-day *N. arenaceodentata* is presented in the PSCR (PBW 2010b).

3.3.3 Results of the *L. plumulosus* Toxicity Tests

Table 7 includes a summary of the Intercoastal Waterway sediment toxicity testing results as presented in the PSCR. For the survival endpoint, there were no statically significant differences between the five sediment samples collected from the site and the reference area. There were also no statistical differences between the five site samples and the reference samples regarding the growth endpoint. The complete report for the 28-day *L. plumulosus* is presented in the PSCR (PBW 2010b).

3.4 SUMMARY

In the analysis of North Area surface soils, where reference samples were pooled for NAS08 and NAS09 and evaluated independently of reference sample NAS07, site sample NAS01 exhibited reduced growth of *N. arenaceodentata* when compared with reference sample NAS07.

When assessing survival and growth in the polychaete, *N. arenaceodentata*, and the amphipod, *L. plumulosus*, where reference samples were pooled, wetland sediments EWSED-03, EWSED-04, EWSED-06, and EWSED-07 exhibited significant reductions in survival of *L. plumulosus* when compared with survival in wetland sediment reference samples in the analysis. Site samples EWSED-03 and EWSED-06 also exhibited significantly reduced growth of *L. plumulosus* when compared with wetland sediment reference samples.

In the analysis, using pooled reference data to evaluate the results of the acute toxicity tests of three surface water samples to brine shrimp (*A. salina*), Samples EWSW-01 and EWSE-04 did not exhibit acute toxicity (LC50 > 100 percent), and Sample EWSW-03 had an LC50 between 5 and 6 percent dilution.

No significant toxicity to either *N. arenaceodentata* or *L. plumulosus* was observed in the Intracoastal Waterway sediment exposure area in the analysis using pooled reference data.

4.0 RISK CHARACTERIZATION

This section serves to analyze the data presented to this point in the BERA and provide an estimate of risk to the identified receptors in the North Area terrestrial environment and the aquatic environments located in the North Area and the Intercoastal Waterway. The risk characterization process will help address the ecological risk questions posed in the *Final BERA Work Plan & SAP (URS 2010b)*:

- 1) Does direct exposure to COPECs in surface soil adversely affect the abundance, diversity, productivity, and function of the soil invertebrate community?
- 2) Does direct exposure to COPECs in bulk sediments and pore water adversely affect the abundance, diversity, productivity, and function of benthic invertebrates?
- 3) Does direct exposure to COPECs in surface water adversely affect the abundance, diversity, productivity, and function of the fish community?

4.1 IDENTIFICATION OF POTENTIAL STRESSORS

One step in characterizing risk is the identification of potential stressors in each ecological area where toxicity is observed. Initial steps in this dose-response evaluation uses techniques that are occasionally referred to as "data mining" techniques intended to identify relationships between parameters. Procedures used included development of correlation matrices and Principal Components Analysis (PCA). Upon review of findings of these statistical procedures, the concentrations of a selected number of indicator chemicals that are significantly associated with

a 20 percent reduction in measurement endpoints (effects concentration 20 percent reduction, or EC20) were estimated. EC20s were estimated by the smoothed linear interpolation procedure recommended by relevant EPA test methods (see for example, EPA 2000, Section 16.2.5.7).

It is generally true that statistical associations are not conclusive regarding cause and effect. Because many of the chemicals are significantly correlated with other chemicals in the samples, the ability to conclude cause and effect from the statistical analyses is difficult. A subset of chemicals with the strongest statistical association with adverse effects was selected as indicator chemicals for estimation of EC20s. It is possible that these chemicals are not the cause of the adverse effect; adverse effects may actually be caused by one or more other chemicals that are correlated with the indicator chemicals. Nonetheless, the indicator chemicals selected have the strongest association with the adverse effects, and may be used to identify sediments that are likely to impair the identified ecological receptors.

Parameters evaluated included concentration of chemicals in bulk sediment, concentrations of organic chemicals normalized by the organic carbon content of the sediments/soils, concentrations of chemicals in pore water, ΣSEM/AVS, (ΣSEM-AVS)/Total Organic Carbon (TOC), organic carbon content (OC), and grain size (indicated by percent gravel, sand, silt, and clay).

The PCA procedure was implemented using SYSTAT 11 (SYSTAT Software, Inc. 2004). Two factors were sought. The first factor is a linear combination of the chemical concentrations that explains the largest portion of the variance in the concentration data. The second factor is orthogonal (not correlated) to the first and explains as much of the remaining variance in the data as possible. The results of this correlation analysis is provided in the DESR (EA 2010a).

4.2 DIRECT EXOPSURE OF SOIL INVERTEBRATES

The potential for adverse effects to the soil invertebrate community were evaluated primarily through comparison of COPEC concentrations in North Area surface soils to literature-based benchmarks and the 21-day bioassay results of *N. arenaceodentata*.

4.2.1 Comparison of North Area Surface Soils to Literature-Based Benchmarks

Only barium, chromium, copper, and zinc exceeded soil benchmarks. Exceedances of these benchmarks were limited to three site samples except zinc, which was present in five of six site samples. Only barium and zinc were present above screening levels in the reference area soils. While comparison to literature-based benchmarks can be a tool for assessing risk, this method has the highest uncertainty and lowest confidence because they are not site-specific toxicity values.

4.2.2 N. arenaceodentata Toxicity Testing and Identification Potential Stressors

The evaluation of toxicity testing results for this receptor indicates the potential for reduced growth of *N. arenaceodentata* at NAS01 ,which had the highest metals concentrations, when compared with reference sample NAS07. A limited number of potential stressors were quantified

in the North Area Soils exposure area. These were barium, chromium, copper, and zinc. Chromium, copper, and zinc were significantly correlated with each other (co-located), while barium was not associated with the other metals analyzed. As discussed in the DESR, chromium, copper, and zinc also appeared to be negatively associated with *N. arenaceodentata* growth, however the apparent relationships were not significant at the 0.10 level of significance, and are not investigated further here (EA 2010a).

4.3 DIRECT EXPOSURE OF BENTHIC INVERTEBRATES IN WETLANDS SEDIMENTS

4.3.1 Comparison of North Area Sediments to Literature-Based Benchmarks

Multiple PAHs and several metals exceeded sediment benchmarks. Exceedances of these benchmarks were limited in number for most COPECs (one to three samples at the most) and exceedances were typically within the same order of magnitude as the benchmark concentrations. The exception to this was zinc, which was present in four of the seven site samples. While comparison to literature-based benchmarks can be a tool for assessing risk, this method has the highest uncertainty and lowest confidence because they are not site-specific toxicity values.

4.3.2 N. arenaceodentata and L. plumulosus Toxicity Testing and Identification of Potential Stressors.

In the hypothesis analysis, where reference samples were pooled, wetland sediments EWSED-03, EWSED-04, EWSED-06, and EWSED-07 exhibited significant reductions in survival of *L. plumulosus* when compared with survival in wetland sediment reference samples. Site samples EWSED-03 and EWSED-06 also exhibited significantly reduced growth of *L. plumulosus* when compared with wetland sediment reference samples. No statistical difference was observed between wetland sediment samples and reference sediment samples when assessing survival and growth in the polychaete *N. arenaceodentata*.

Exploratory correlation and PCA revealed that, although PAH compounds were strongly correlated with each other (co-located) they were not closely associated with the toxic endpoints ($L.\ plumulosus$ survival and growth) (EA 2010a). To reduce the number of variables considered in the analysis, Total PAHs and Σ (PAHs/TOC) were determined, and individual PAH compounds were eliminated from the data set.

Correlation analysis showed that sediment grain size was not significantly associated with either of the toxic endpoints, while copper and zinc in bulk sediment, (Σ SEM-AVS)/TOC, and copper in pore water were significantly negatively associated (i.e. as one goes up the other goes down) with both toxic endpoints (EA 2010a). Nickel was significantly adversely associated with *L. plumulosus* survival. Significant association is indicated at the 0.05 level of significance. Nickel was not associated with *L. plumulosus* growth at the 0.05 level, but was adversely associated at the 0.10 level of significance. Arsenic was also adversely associated with the toxic endpoints at the 0.10 level of significance.

Pore water was not analyzed in all the samples that were analyzed for bulk sediment chemistry and AVS/SEM. Therefore the correlation analysis was performed separately (EA 2010a). Copper was the only pore water analyte that was significantly negatively associated with *L. plumulosus* survival and growth at the 0.05 level of significance; however zinc in pore water was negatively correlated with *L. plumulosus* growth at the 0.10 level of significance.

As a result of these analyses, the following analytes appear to be associated with the observed toxicity to *L. plumulosus* in wetland sediments:

- Copper (bulk sediment and pore water)
- Zinc (bulk sediment and pore water)
- (ΣSEM-AVS)/OC
- Arsenic (bulk sediment)
- Nickel (bulk sediment).

Correlation matrices for *L. plumulosus* endpoints versus bulk sediment chemistry and pore water chemistry are included in DESR (EA 2010a).

4.4 DIRECT EXPOSURE OF BENTHIC INVERTEBRATES IN INTERCOASTAL WATERWAY SEDIMENTS

4.4.1 Comparison of North Area Sediments to Literature-Based Benchmarks

Exceedances of the literature-based benchmarks were present only at location EIWSED02 in the Intercoastal Waterway. At this location, there were benchmark exceedances of 4,4'-DDT, acenaphthene, and fluorene. While comparison to literature-based benchmarks can be a tool for assessing risk, this method has the highest uncertainty and lowest confidence because they are not site-specific toxicity values.

4.4.2 N. arenaceodentata and L. plumulosus Toxicity Testing and Identification of Potential Stressors.

No significant toxicity to either *N. arenaceodentata* or *L. plumulosus* was observed in the Intracoastal Waterway sediment exposure area in either the analysis presented in the PSCR or the analysis using pooled reference data. Further analysis into the identification of potential stressors was, therefore, not performed for this ecological region.

4.5 DIRECT EXPOSURE OF AQUATIC ORGANISMS IN NORTH AREA SURFACE WATER

4.5.1 Comparison of North Area Sediments to Literature-Based benchmarks

The only exceedance of a surface water benchmark was for dissolved copper at EWSW03. Comparison to background levels was not available for surface water. While comparison to

literature-based benchmarks can be a tool for assessing risk, this method has the highest uncertainty and lowest confidence because they are not site-specific toxicity values.

4.5.2 A. salina Toxicity Testing and Identification of Potential Stressors.

The results of the acute toxicity tests of three surface water samples to brine shrimp (*A. salina*) were generally consistent between the original analysis presented in the PSCR and the analysis using pooled reference data: Samples EWSW01 and EWSW04 did not exhibit acute toxicity (LC50 > 100 percent), and Sample EWSW03 had an LC50 between 5 and 6 percent dilution.

Acute toxicity to *A. salina* was indicated in 1 of 3 samples (EWSW03). These samples were analyzed for copper, nickel, silver, and zinc to aid in the determination of potential stressors. The data set is too small for quantitative statistical evaluation; however concentrations of copper (8.54 microgram per liter [μ g/L]) and silver (0.049 μ g/L) are greater in the sample that exhibited acute toxicity to brine shrimp than in the other samples. If toxicity is attributable to copper, it appears that concentrations less than 3.4 μ g/L would not cause toxicity to *A. salina*.

5.0 UNCERTAINTY

Uncertainty exists in many areas of risk assessment. The nature of the uncertainties depends on the data available, the degree of knowledge of site conditions, and the assumption made throughout the risk assessment process. Site-specific uncertainties inherent in the BERA process are provided below:

- Toxicity to soil dwelling invertebrates was assessed using site toxicity data from *N. arenaceodentata*, a sediment dwelling marine polychaete, due to the high salinity of surface soils in the North Area. Site soils were submerged with synthetic seawater for the toxicity tests. The treatment of surface soils as sediments and the use of a marine invertebrate may over- or underestimate risk to soil-dwelling invertebrates present in the North Area terrestrial environment.
- Site media concentrations were compared to literature-based benchmarks, or ESVs, which are not site-specific. This may over or underestimate risk.
- Toxicity to surface water dwelling invertebrates was assessed using site toxicity test data for the brine shrimp, *A. salina*, for which no established SOP was available. Multiple runs of the surface water toxicity tests were required due to potential feeding issues of test organisms and repeated control failure. Surface water reference data was also not available due to dry conditions in the reference area for comparison to toxicity test results. These factors may over- or underestimate risk to surface water-dwelling invertebrates present in the North Area aquatic environment.
- The results of the toxicity studies are not always well correlated to the results of the analytical chemistry. For example, while reference samples were elevated in soil sample NAS07, the survival of *N. arenaceodentata* in that sample was high (92 percent). Contrastingly, reference concentrations of all metal COPECs were below the TCEQ soil

- benchmarks at sample location NAS09, yet this sample indicated the highest mortality (60 percent). Factors other than site COPECs may explain the observed toxicity. This could over- or underestimate risk.
- The use of synthetic seawater to treat the soils as sediments for the toxicity test could also over or underestimate risks.
- SEM/AVS ratios for wetland sediments are generally above 1.0, indicating that conditions do not highly favor the formation of metal sulfides making them less bioavailable. The ratio of "excess" SEM to the fraction organic carbon content in sediment is below 130 micromoles per gram organic carbon (μmol/goc) which is the concentration predicted to be non-toxic by the EPA (EPA, 2005) for six of the seven site samples. This may overestimate risk to metals from wetland sediments.
- The differences in how hypothesis testing were performed resulted different outcomes for wetland sediment and surface soils. This may over- or underestimate risk.

6.0 CONCLUSIONS

This BERA focused on further addressing risk from surface soils and sediments in the North Area, sediments in the Intercoastal Waterway, and surface waters in the North Area wetlands. Potential risk was evaluated through the additional data collection and analysis.

Toxicity tests of North Area surface soils to soil invertebrates, represented by the marine polychaete, *N. arenaceodentata*, indicated a significant difference for growth at one sampling location. Toxicity tests of wetland sediments to sediment dwelling invertebrates, represented by the amphipod, *L. plumulosus*, indicated statistically significant differences in survival of *L. plumulosus* at four locations and significant differences in growth at two locations. No significant differences were observed for survival and growth of N. *arenaceodentata* for the North Area sediment or the Intracoastal Waterway sediment. Acute toxicity to the brine shrimp, *A. salina*, was indicated in one surface water sample from the North Area.

While the results of the site-specific toxicity test indicate the potential for adverse effects to benthic invertebrates, risk is likely overestimated due to the intermittent nature of surface water in the wetlands. Depending on rainfall and tide conditions, many of the areas selected for sediment toxicity analysis can often be completely dry. Significant populations of invertebrates would likely be limited to areas with perennial surface water. While individual effects may be present, it is unlikely that population level effects to growth and survival of invertebrates exist from COPECs in site surface soils, sediments and surface waters.

These findings are similar to those of the EA *Technical Memorandum Ecological and Habitat Health Assessment, Wetlands A, B, and C* (EA 2010b) which indicated that observed human impacts to the Site wetland habitats are minor. The Site wetlands are not visually distinguishable from surrounding wetlands in terms of wetland species composition and approximate density, presence of invertebrates, and wildlife usage. These wetlands are providing valuable wetland marsh functions, such as wildlife habitat, food, flood storage, water quality enhancement, and

groundwater recharge. Any disturbance, such as excavation of sediments or other remedial activities, would require decades for sediments in this area to return to the salty sediment marsh type environment present today.

7.0 REFERENCES

- Brazoria County Facts. 2006. "Pilots Take to Skies to Eradiate Mosquitoes." June 16.
- Brazoria County Facts . 2008a. "County District Responds to Mosquito Outbreak." September 8.
- Brazoria County Facts . 2008b. "State Adds to Mosquito-Spraying Efforts." September 26.
- EA Engineering, Science, and Technology, Inc. (EA). 2010a. Data Evaluation Summary Report for the Baseline Ecological Risk Assessment, Gulfco Marine Maintenance Superfund Site, Freeport, Brazoria County, Texas. December 27.
- EA. 2010b. Technical Memorandum Ecological and Habitat Health Assessment, Wetlands A, B, and C, Gulfco Marine Maintenance Superfund Site, Freeport, Texas. December.
- U.S. Environmental Protection Agency (EPA). 1997. Ecological risk assessment guidance for Superfund: process for designing and conducting ecological risk assessments. Interim Final. EPA/540/R-97/006.
- EPA. 1998. Guidelines for Ecological Risk Assessment. Risk Assessment Forum. EPA/630/R-95/002F. April 1998
- EPA. 1999. Supplemental Guidance to RAGs: Region 4 Bulletins, Ecological Risk Assessment.

 Originally published November 1995. Website version last updated November 30, 2001.
- EPA. 2000. Methods for Measuring the Toxicity and Bioaccumulation of Sediment-associated Contaminants with Freshwater Invertebrates. Second Edition. EPA-600-R-99-064.
- EPA. 2002. Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms. Fifth Edition. EPA-821-R-02-012.
- EPA. 2005. Procedures for the Derivation of Equilibrium Partitioning Sediment Benchmarks (ESBs) for the Protection of Benthic Organisms: Metal Mixtures (Cadmium, Copper, Lead, Nickel, Silver, and Zinc. Office of Research and Development. EPA-600-R-02-011.
- U.S. Fish and Wildlife Service (FWS). 2008. *National Wetlands Inventory, Online Wetlands Mapper*. http://wetlandsfws.er.usgs.gov/wtlnds/launch.html. Accessed July 9, 2008.
- Lake Jackson News. 1957. "Spray Plane Swats Mosquito via Two Day Oil Spray Job." August 8.
- Pastor, Behling & Wheeler, LLC (PBW). 2009. *Nature and Extent Data Report, Gulfco Marine Maintenance Site, Freeport, Texas*. May 3.
- PBW. 2010a. Final Screening Level Ecological Risk Assessment Report, Gulfco Marine Maintenance Site, Freeport, Texas. May 3.

- PBW. 2010b. Preliminary Site Characterization Report (PSCR), Gulfco Marine Maintenance Site, Freeport, Texas. November 3.
- Personal communication between Gary Miller (EPA) and Fran Henderson (BCMCD), 27 October 2010.
- Texas Natural Resource Conservation Commission (TNRCC). 2001. *Guidance for Conducting Ecological Risk Assessments at Remediation Sites in Texas*, Toxicology and Risk Assessment Section. RG-263 (revised). December.
- URS Corporation (URS). 2010a. Final Baseline Ecological Risk Assessment Problem Formulation Report, Gulfco Marine Maintenance Site, Freeport, Texas. September 2.
- URS. 2010b. Final Baseline Ecological Risk Assessment Work Plan & Sampling and Analysis Plan, Gulfco Marine Maintenance Site, Freeport, Texas. September 2.



TABLE 1 1 of 1 DATA SUMMARY FOR NORTH AREA SOILS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Location	Comments	4,4'-DDT	Aroclor-1254	Barium	Chromium	Copper	Zinc
TCEQ Soil Benchmark			NA	NA	300	30	61	120
NAS01	North Area Soil				272	97.3	221	5770
NAS02	North Area Soil		0.0075 J	0.093 J	163	27.2	26.0	296 JH
NAS02DUP	North Area Soil		0.015 J	0.16 J	261	23.1	24.9	307 J
NAS03	North Area Soil		0.0078		190	15.4	22.9	307 J
NAS04	North Area Soil			0.01	502	7.86	10.8	321 J
NAS05	North Area Soil		0.008		198	30.9	27.4	309 J
NAS06	North Area Soil			-	52.2	13.4	10.8	62.3 J
NAS07	North Area Soil	Background location BSS-01			340	12.4	10.1	501
NAS08	North Area Soil	Background location BSS-02			182	13.6	12.6	182
NAS09	North Area Soil	Background location BSS-03			172	13.3	11.0	63.1

Values in mg/kg, dry weight
J = Estimated Concentration
H = Concentratin Biased High
mg/kg = milligrams per kilograms
-- Not Analyzed
Values in bold exceed screening

benchmark

TABLE 2 1 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Location	Date	2-Methylnaphthalene	Acenaphthene	Acenaphthylene	Anthracene
TCEQ Marine Sediment Benchmark			0.07	0.016	0.044	0.0853
EWSED01	Wetland	8/12/2010	0.0038 J	0.0046 J	0.057	0.043
EWSED02	Wetland	8/12/2010	0.002 J	0.0018 J	0.041	0.032
EWSED02DUP	Wetland	8/12/2010	0.0026 J	0.0013 J	0.03	0.024
EWSED03	Wetland	8/13/2010	0.0068	0.0043 J	0.0032 J	0.005
EWSED04	Wetland	8/13/2010	0.0037 J	0.0026 J	0.0069	0.006
EWSED05	Wetland	8/12/2010	0.02	0.075	0.018	0.078
EWSED06	Wetland	8/12/2010	0.0016 J	0.0013 J	0.0008 J	0.0011 J
EWSED07	Wetland	8/13/2010	0.0053	0.009	0.0091	0.027
EWSED08	Wetland	8/13/2010	0.001 J	< 0.00088	< 0.00069	0.001 J
EWSED09	Wetland	8/13/2010	0.00061 J	< 0.00076	< 0.00059	< 0.00058

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

TABLE 2 2 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Arsenic	SEM/AVS	Benzo(a)pyrene	Benzo(g,h,i)perylene	Copper	Indeno(1,2,3-cd)pyrene
TCEQ Marine Sediment Benchmark	8.2	NA	0.43	NA	34	NA
EWSED01	2.97	0.089	0.24	0.63	20.6	0.22
EWSED02	2.4	0.014	0.12	0.46	13.3	0.18
EWSED02DUP	2.51		0.097	0.35	14.6	0.16
EWSED03	5.36	0.002	0.028	0.058	25	0.034
EWSED04	4.35	0.039	0.04	0.076	20.3	0.064
EWSED05	3.06	0.002	0.79	0.68	28.9	0.79
EWSED06	3.23	0.084	0.01	0.019	28.1	0.019
EWSED07	5.94	0.005	0.087	0.1	30.7	0.1
EWSED08	2.92	6.4	0.014	0.017	15.8	0.019
EWSED09	2.58	0.062	0.0027 J	0.0032 J	11.7	0.0032 J

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

TABLE 2 3 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Lead	Nickel	4,4'-DDT	Endrin Aldehyde	Benzo(a)anthracene	Endrin ketone
TCEQ Marine Sediment Benchmark	46.7	20.9	0.00119	NA	0.261	NA
EWSED01	17.2	18.9	< 0.001 J	0.0007 J	< 0.066 J	< 0.000093
EWSED02	12	15.6	< 0.00017	< 0.00012	< 0.043 J	< 0.000093
EWSED02DUP	14.7	17.3	< 0.00017	< 0.001 J	< 0.00072 J	< 0.0011 J
EWSED03	48.4	21.7	0.0028	0.00027 J	0.024	< 0.00011 J
EWSED04	37.4	16.9	-		0.031	
EWSED05	76.1	14.4	< 0.019 J	0.0014 J	0.55	< 0.001 J
EWSED06	32.9	22.5	0.0012	< 0.00012	0.0069	< 0.000093
EWSED07	32.7	20.1			0.09	
EWSED08	19.8	16.3	0.0014	0.00052 J	0.011	< 0.00012
EWSED09	17.4	16.5	0.0016	< 0.00012	0.0024 J	< 0.000093

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

TABLE 2 4 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Chrysene	gamma-Chlordane	Dibenz(a,h)anthracene	Flourene	Flouranthene
TCEQ Marine Sediment Benchmark	0.384	0.00226	0.0634	0.019	0.6
EWSED01	0.39	< 0.00009	0.17	0.019	0.038
EWSED02	0.62	< 0.00009	0.11	0.013	0.023
EWSED02DUP	0.49	< 0.00009	0.094	0.011	0.019
EWSED03	0.064	< 0.00009	0.0074	0.0048	0.052
EWSED04	0.05	-	0.01	0.0032 J	0.076
EWSED05	0.77	< 0.00009	0.14	0.065	1.3
EWSED06	0.014	0.00025 J	0.0026 J	0.001 J	0.02
EWSED07	0.14		0.019	0.016	0.26
EWSED08	0.017	< 0.00012 J	0.003 J	0.00092 J	0.031
EWSED09	0.004	< 0.00023 J	< 0.0008	< 0.00061	0.0055

Notes: Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

TABLE 2 5 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Phenanthrene	Pyrene	Total Organic Carbon	Zinc	GRAVEL, MEDIUM,%	GRAVEL, FINE,%
TCEQ Marine Sediment Benchmark	0.24	0.665	NA	150	NA	NA
EWSED01	0.032	0.091	59400	115	2.52	3.49
EWSED02	0.016	0.14	24100	70.1	53.7	5.66
EWSED02DUP	0.014	0.11	30500	86.1		
EWSED03	0.049	0.069	18200	585	47.9	7.73
EWSED04	0.041	0.075	16700	417	0.57	2.19
EWSED05	0.78	1.1	18100	595	0.34	2.64
EWSED06	0.013	0.021	21500	959	18.7	0.87
EWSED07	0.15	0.19	23900	318		
EWSED08	0.015	0.027	46800	94.3	12.7	12.1
EWSED09	0.0024 J	0.0044 J	11200	88.3	1.97	2.31

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

TABLE 2 6 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	SAND, VERY COARSE,%	SAND, COURSE,%	SAND, MEDIUM,%	SAND, FINE,%	SAND, VERY FINE,%	SILT,%	CLAY,%
TCEQ Marine Sediment Benchmark	NA	NA	NA	NA	NA	NA	NA
EWSED01	5.58	2.82	1.8	2.12	2.42	61.6	21.2
EWSED02	2.91	1.77	1.15	2.29	1.64	13.7	10.8
EWSED02DUP							
EWSED03	4.83	3.01	1.75	1.93	0.93	29.2	1.7
EWSED04	2.88	3.18	2.98	7.02	4.59	81.4	0.6
EWSED05	2.83	4.49	4.93	8.91	6.96	38.7	27.5
EWSED06	0.67	0.41	0.27	2.06	1.24	21.6	61.7
EWSED07							
EWSED08	8.04	3.92	1.93	2.62	2.51	44.3	14.6
EWSED09	1.35	0.54	0.4	1.87	5.24	40.4	48.5

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

Values in **bold** exceed screening benchmark

TABLE 2 7 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Acid-volatile sulfide, μmol/gsed	Cadmium, SEM, μmol/gsed	Copper, SEM, µmol/gsed	Lead, SEM, μmol/gsed	Nickel, SEM, µmol/gsed	Zinc, SEM, µmol/gsed
TCEQ Marine Sediment Benchmark	NA	NA	NA	NA	NA	NA
EWSED01	0.018 J	< 0.0006	0.024	0.015	0.015	0.148
EWSED02	< 0.005	0.0007	0.03	0.029	0.03	0.259
EWSED02DUP						
EWSED03	< 0.004	0.0011	0.057	0.038	0.012	1.55
EWSED04	0.05	0.0012	0.16	0.088	0.016	1.02
EWSED05	< 0.004	< 0.0005	0.082	0.055	0.011	1.74
EWSED06	0.33	0.0019	0.092	0.04	0.019	3.79
EWSED07						
EWSED08	2.04	< 0.0008	0.016	0.021	0.028	0.255
EWSED09	0.004	< 0.0005	0.011	0.009	0.005	0.039

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

Values in **bold** exceed screening benchmark

TABLE 2 8 of 8 DATA SUMMARY FOR WETLAND SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	∑SEM, µmol/gsed	∑SEM/AVS	foc,goc/gsed	∑SEM-AVS, µmol/gsed	(∑SEM-AVS)/foc, μmol/goc
TCEQ Marine Sediment Benchmark	NA	NA	NA	NA	NA
EWSED01	0.2	11.3	0.0594	0.185	3.1
EWSED02	0.3	69.7	0.0273	0.344	12.6
EWSED02DUP			-		
EWSED03	1.7	415	0.0182	1.654	90.9
EWSED04	1.3	25.7	0.0167	1.235	74
EWSED05	1.9	472	0.0181	1.885	104.1
EWSED06	3.9	11.9	0.0215	3.613	168
EWSED07	0.7	184	0.0239	0.731	30.6
EWSED08	0.3	0.157	0.0468		
EWSED09	0.1	16.1	0.0112	0.061	5.4

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms AVS = Acid Volatile Sulfides

SEM = Simultaneously Extracted Metals

-- Not Analyzed

Values in **bold** exceed screening benchmark

TABLE 3 1 of 5 DATA SUMMARY TABLE FOR WETLAND SEDIMENT PORE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	2-Methylnaphthalene	4,4'-DDT	Acenaphthene	Acenaphthylene
TCEQ Marine Surface Water				
Benchmark	0.03	0.000001	0.0404	NA
EWSED01	0.000018 U	< 0.000012 J	< 0.0000052	0.000024
EWSED02	0.000026 U	< 0.0000047 J	< 0.0000044	< 0.0000034
EWSED03	0.000022 U	< 0.000016 J	< 0.0000047	< 0.0000036
EWSED04	0.000046		<0.0000085 J	0.000014 J
EWSED04DUP				-
EWSED06	0.000019 U	< 0.00000058	0.0000091 J	< 0.0000035
EWSED07	0.000013 U		< 0.000012	0.000032 Ј
EWSED08	0.0000083 U	0.000003 J	< 0.000005	< 0.0000039
EWSED09	0.000018 U	< 0.0000014 J	< 0.0000044	< 0.0000034

Values in mg/L

mg/L = milligrams/liter

< or U indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed Values in **bold** exceed screening

TABLE 3 2 of 5 DATA SUMMARY TABLE FOR WETLAND SEDIMENT PORE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Anthracene	Arsenic	Benzo(a)anthracene	Benzo(a)pyrene	Benzo(g,h,i)perylene
TCEQ Marine Surface Water					
Benchmark	0.00018	0.078	NA	NA	NA
EWSED01	0.000067	0.0037 J	< 0.0000031	< 0.0000051	0.000012 J
EWSED02	< 0.0000036	0.0041 J	< 0.0000026	< 0.0000043	0.000012 Ј
EWSED03	0.000013 J	0.0019 J	< 0.0000028	< 0.0000046	< 0.0000031
EWSED04	0.000047	0.00072 J	< 0.0000026	< 0.0000043	< 0.0000029
EWSED04DUP		0.00325	-	-	
EWSED06	< 0.0000037	0.00177 J	0.0000095 U	0.0000097 U	0.000023 U
EWSED07	0.000066	0.00063 J	< 0.0000067	< 0.000012	< 0.0000075
EWSED08	< 0.0000041	0.00576 J	< 0.000003	< 0.0000049	< 0.0000033
EWSED09	< 0.0000036	0.00171 J	< 0.0000026	< 0.0000043	< 0.0000029

Values in mg/L

mg/L = milligrams/liter

< or U indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed Values in **bold** exceed screening

TABLE 3 3 of 5 DATA SUMMARY TABLE FOR WETLAND SEDIMENT PORE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Chrysene	Copper	Dibenz(a,h)anthracene	Endrin Aldehyde
TCEQ Marine Surface Water				
Benchmark	NA	0.0036	NA	0.000002
EWSED01	< 0.000004	0.000922	< 0.000003	0.000013
EWSED02	0.000049	0.000342 U	0.0000034 J	0.0000067 J
EWSED03	< 0.0000036	0.00456	< 0.0000027	0.000015 J
EWSED04	< 0.0000034	0.00426	< 0.0000025	1
EWSED04DUP		0.00531 U		1
EWSED06	0.0000096 U	0.00702	0.000015 U	< 0.0000046
EWSED07	< 0.0000088	0.00303	< 0.0000065	1
EWSED08	< 0.0000039	0.00137	< 0.0000029	0.0000026 Ј
EWSED09	< 0.0000034	0.000761 U	< 0.0000025	<0.0000033 J

Values in mg/L

mg/L = milligrams/liter

< or U indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed Values in **bold** exceed screening

TABLE 3 4 of 5 DATA SUMMARY TABLE FOR WETLAND SEDIMENT PORE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Endrin ketone	Fluorene	Fluoranthene	gamma-Chlordane
TCEQ Marine Surface Water				
Benchmark	0.000002	0.05	0.00298	0.000004
EWSED01	< 0.00000078	0.000013 J	< 0.0000052	< 0.00000038
EWSED02	<0.000013 J	< 0.0000038	< 0.0000044	<0.0000013 J
EWSED03	0.000007 J	< 0.000004	< 0.0000047	<0.000016 J
EWSED04		0.0000047 J	< 0.0000044	
EWSED04DUP	1	-		
EWSED06	< 0.00000066	0.0000091 J	< 0.0000045	< 0.00000032
EWSED07	1	< 0.0000098	< 0.000012	
EWSED08	< 0.0000007	< 0.0000044	< 0.000005	0.0000033 J
EWSED09	< 0.0000011	< 0.0000038	< 0.0000044	<0.000016 J

Values in mg/L

mg/L = milligrams/liter

< or U indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed Values in **bold** exceed screening

TABLE 3 5 of 5 DATA SUMMARY TABLE FOR WETLAND SEDIMENT PORE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Indeno(1,2,3-cd)pyrene	Lead	Nickel	Phenanthrene	Pyrene	Zinc
TCEQ Marine Surface Water						
Benchmark	NA	0.0053	0.0131	0.0046	0.00024	0.0842
EWSED01	0.0000051 J	0.000115 U	0.00944	0.000012 J	< 0.0000042	0.0101
EWSED02	0.0000062 J	0.000113 U	0.00486	< 0.000005	< 0.0000035	0.00135 U
EWSED03	< 0.0000028	0.000425 U	0.00749 U	0.0000053 U	< 0.0000037	0.0413
EWSED04	< 0.0000026	0.00015 U	0.0114	< 0.000005	< 0.0000035	0.101
EWSED04DUP		0.000239 U				0.083
EWSED06	0.000014 U	0.000443 U	0.00915	0.0000068 J	< 0.0000036	0.626
EWSED07	< 0.0000067	0.000184	0.00917	< 0.000013	< 0.000009	0.0599
EWSED08	< 0.000003	0.00128 U	0.0142	< 0.0000057	< 0.000004	0.039
EWSED09	< 0.0000026	0.000236 U	0.00669	< 0.000005	< 0.0000035	0.00124 U

Values in mg/L

mg/L = milligrams/liter

< or U indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed Values in **bold** exceed screening

TABLE 4 1 of 1 DATA SUMMARY FOR WETLAND SURFACE WATER GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Acrolein	Copper	Nickel	Silver	Zinc
TCEQ Marine Surface Water					
Benchmark	0.005	0.0036	0.0131	0.00019	0.0842
EWSW01	< 0.00096	0.00338 J	0.00616	0.000020 J	0.029
EWSW01DUP	< 0.00096	0.00331	0.00601	0.000021 J	0.0279
EWSW03		0.00854	0.00474	0.000049	0.0242
EWSW04		0.00154	0.00396	0.000011 J	0.122

Notes: Values in mg/L

mg/L = milligrams/liter

< indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed

Values in **bold** exceed screening

TABLE 5 1 of 2 DATA SUMMARY FOR INTERCOASTAL WATERWAY SEDIMENTS GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Location	4,4'-DDT	Acenaphthene	Benzo(a)anthracene	Chrysene	Dibenz(a,h)anthracene
TCEQ Marine Sediment Benchmark		0.00119	0.016	0.43	0.384	0.0634
EIWSED01	IW	0.00023 J	0.0071	0.03	0.046	0.0046
EIWSED02	IW	0.0019	0.023	0.24	0.31	0.063
EIWSED03	IW	0.00032 J	0.0052	0.052	0.07	0.015
EIWSED03DUP	IW	0.00089 J	0.0022 J	0.048	0.067	0.014
EIWSED04	IW		0.0029 J	0.032	0.054	0.0087 Ј
EIWSED05	IW	0.00029 J	0.0046 J	0.042	0.059	0.01
EIWSED06	IW	< 0.00017	< 0.0014 JL	< 0.0017 JL	0.0019	< 0.0015 JL
EIWSED07	IW	< 0.00017	< 0.0014 JL	< 0.0017 JL	< 0.0015	< 0.0015 JL

Values in mg/kg, dry weight IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms

-- Not Analyzed

Values in **bold** exceed screening

TABLE 5
2 of 2

DATA SUMMARY FOR INTERCOASTAL WATERWAY SEDIMENTS
GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Fluoranthene	Fluorene	Hexachlorobenzene	Phenanthrene	Pyrene	Total Organic Carbon
TCEQ Marine Sediment Benchmark	0.6	0.019	NA	0.24	0.665	NA
EIWSED01	0.12	0.019		0.15	0.081	4130
EIWSED02	0.52	0.02		0.24	0.47	7200
EIWSED03	0.12	0.0067		0.071	0.1	6320
EIWSED03DUP	0.094	0.0032 J		0.043	0.11	6680
EIWSED04	0.074	0.0031 J	< 0.0012	0.028	0.073	5480
EIWSED05	0.1	0.0045 J		0.051	0.054	6820
EIWSED06	0.0019 JL	< 0.0011 JL	< 0.0012 JL	< 0.0014 JL	0.0025 JL	6060
EIWSED07	0.0018 JL	< 0.0011 JL	< 0.0012 JL	< 0.0014 JL	0.0018 JL	5090

Values in mg/kg, dry weight

IW = Intercoastal Waterway

J = Estimated Concentration

L = Concentratin Biased Low

< indicates samples was below indicated

detection limit.

mg/kg = milligrams per kilograms

-- Not Analyzed

Values in **bold** exceed screening

TABLE 6
1 of 2
DATA SUMMARY FOR INTERCOASTAL WATERWAY SEDIMENTS PORE WATER
GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	4,4'-DDT	Acenaphthene	Benzo(a)anthracene	Chrysene	Dibenz(a,h)anthracene
TCEQ Marine Surface Water Benchmark	0.000001	0.0404	NA	NA.	NA
EIWSED01	<0.0000035 J	0.000052	< 0.0000035	< 0.0000046	< 0.0000034
EIWSED02	<0.00000098 J	0.000037	< 0.0000028	< 0.0000037	< 0.0000027
EIWSED03	<0.0000013 J	0.000024	< 0.0000026	< 0.0000034	< 0.0000025
EIWSED04	<0.00000076 J	< 0.0000088	< 0.0000052	< 0.0000068	< 0.000005
EIWSED05	<0.0000013 J	0.000027	< 0.0000034	< 0.0000044	< 0.0000033
EIWSED05DUP	<0.0000016 J	0.000031	< 0.0000028	< 0.0000036	< 0.0000027
EIWSED06	<0.000001 J	< 0.0000088	< 0.0000052	< 0.0000068	< 0.000005
EIWSED07	< 0.00000058	< 0.000026	< 0.000018	< 0.000028	< 0.000017

Values in mg/l

mg/l = milligrams/liter

< indicates samples was below indicated detection limit.

J = Estimated Concentration

-- Not Analyzed

Values in **bold** exceed screening

TABLE 6
2 of 2

DATA SUMMARY FOR INTERCOASTAL WATERWAY SEDIMENTS PORE WATER
GULFCO MARINE MAINTENANCE SUPERFUND SITE

Sample ID	Fluoranthene	Fluorene	Hexachlorobenzene	Phenanthrene	Pyrene
TCEQ Marine Surface Water Benchmark	0.00298	0.05	NA	0.0046	0.00024
EIWSED01	< 0.0000059	0.000043	< 0.00000035	0.000031	< 0.0000047
EIWSED02	< 0.0000048	0.000029	< 0.00000031	0.000022 J	< 0.0000038
EIWSED03	< 0.0000044	0.00002 J	< 0.00000039	0.000012 J	< 0.0000035
EIWSED04	< 0.0000088	< 0.0000076	< 0.00000037	< 0.00001	< 0.000007
EIWSED05	< 0.0000057	0.000023 J	< 0.00000037	0.000015 J	< 0.0000045
EIWSED05DUP	< 0.0000047	0.000026	< 0.00000044	0.000015 J	< 0.0000037
EIWSED06	< 0.0000088	< 0.0000076	< 0.00000039	< 0.00001	< 0.000007
EIWSED07	< 0.00002	< 0.000027	< 0.000022	< 0.000022	< 0.000019

Values in mg/l

mg/l = milligrams/liter

< indicates samples was below

indicated detection limit.

J = Estimated Concentration

-- Not Analyzed

Values in **bold** exceed screening

TABLE 7
Page 1 of 1
SUMMARY OF TOXICITY TESTING FOR SOIL AND SEDIMENT
GULFCO MARINE MAINTENANCE SUPERFUND SITE

North Area Soils	21-day Neanthes arenaceodentata: Survival and Growth				
	Survival Growth - Biomass		Growth - Dry Wt.		
Sample ID	(%)	(mg)	(mg)**		
Lab Control for North Area Soils	100	2.058	2.058		
Site Locations:					
BERA SAmple ID: NAS01	76	0.6648	0.9817		
BERA Sample ID: NAS02	88	2.123	2.407		
BERA Sample ID: NAS03	96	2.603	2.704		
BERA Sample ID: NAS04	84	4.52	5.423		
BERA Sample ID: NAS05	76	1.998	2.695		
BERA Sample ID: NAS06	88	1.648	1.894		
North Area Reference Locations:					
BERA Sample ID: NAS07	92	1.533	1.679		
BERA Sample ID: NAS08	64	0.688	1.008		
BERA Sample ID: NAS09	60	0.5512	0.9815		

Wetlands Sediments	28-day Neanthes arenaceodentata: Mean Survival and Growth			28-day Leptocheirus plumulosus: Mean Survival, Growth and Reproduction			
	Survival	Growth - Biomass	Growth - Dry Wt.	Survival	Offspring	Growth - Biomass	Growth - Dry Wt.
Sample ID	(%)	(mg)	(mg)**	(%)	(Mean)	(mg)	(mg)**
Lab Control *	96	4.073	4.28	81.5	5.3	0.6773	0.8304
Site Locations:							
BERA Sample ID: EWSED01	96	3.073	3.234	35	0	0.2607	0.6566
BERA Sample ID: EWSED02	76	2.285	3.334	58	0.2	0.2313	0.4916
BERA Sample ID: EWSED03	84	2.004	2.421	20	0	0.2015	0.4202
BERA Sample ID: EWSED04	84	2.53	2.988	23.75	0	0.1518	0.529
BERA Sample ID: EWSED05	72	2.248	3.285	38	0	0.1614	0.4109
BERA Sample ID: EWSED06	80	1.78	2.36	13	0	0.05525	0.3764
BERA Sample ID: EWSED07	72	2.451	3.371	30	0.8	0.124	0.3924
Wetland Sediment Reference Locations:							
BERA Sample ID: EWSED08	66	1.586	2.741	33	0.6	0.2238	0.5988
BERA Sample ID: EWSED09	76	2.15	2.95	19	1.8	0.1162	0.5035

Intercoastal Sediments	28-day Neanthes arenaceodentata: Mean Survival and Growth			28-day Leptocheirus plumulosus: Mean Survival, Growth and Reproduction			
	Survival	Growth - Biomass	Growth - Dry Wt.	Survival	Offspring	Growth - Biomass	Growth - Dry Wt.
Sample ID	(%)	(mg)	(mg)**	(%)	(Mean)	(mg)	(mg)**
Lab Control*	96	4.073	4.28	81.5	5.3	0.6773	0.8304
Site Locations:							
BERA Sample ID: EIWSED01	92	4.412	4.857	41	0.6	0.2229	0.5559
BERA Sample ID: EIWSED02	80	4.984	6.614	64	1.8	0.3463	0.5576
BERA Sample ID: EIWSED03	92	4.993	5.491	39	1.2	0.237	0.5504
BERA Sample ID: EIWSED04	100	6.026	6.026	42	0.6	0.2092	0.4841
SERA Sample ID: EIWSED05	100	4.119	4.119	44	0.6	0.2463	0.5446
Intracoastal Sediment Reference Locations:							
BERA Sample ID: EIWSED06	100	4.784	4.784	42	1.2	0.19	0.4034
BERA Sample ID: EIWSED07	92	4.842	5.283	64	0	0.2475	0.3877

^{*} Average of Lab Control 1 and 2

^{* *} The primary growth endpoint Dry Wt is the dry weight of surviving organisms divided by the number of surviving organisms. Biomass (the dry weight of surviving organisms divided by initial number of organisms) is not routinely applied to sediment testing (EPA, 2000)















