

Attn: Mr. Luis Vega

EA Engineering, Science and Technology 405 Highway 121, Building C, Suite 100 Lewisville, TX 75067

Passive Soil Gas Survey – Analytical Report Date: December 10, 2012

Beacon Project No. 2594

Project Reference:	Circle Court Ground Water Plume Superfund site, Willow Park, TX
Samplers Installed:	November 8, 2012
Samplers Retrieved:	November 19, 2012
Samples Received:	November 20, 2012
Analyses Completed:	November 21, 2012
Laboratory Data Issued:	November 28, 2012

EPA Method 8260C (Modified)

All samples were successfully analyzed using thermal desorption-gas chromatography/mass spectrometry (TD-GC/MS) instrumentation to target a custom compound list following EPA Method 8260C. Laboratory results are reported in nanograms (ng) of specific compound per sample.

Laboratory QA/QC procedures included internal standards, surrogates, and blanks based on EPA Method 8260C. Analyses and reporting were in accordance with BEACON's Quality Assurance Project Plan.

Reporting limits

The reporting limit (RL) for each compound is equal to the limit of quantitation (LOQ), which is 10 nanograms (ng), and the limit of detection (LOD) is 5 ng. **Table 1** provides survey results in nanograms per sampler by sample-point number and compound name; measurements below the LOQ but above the LOD are flagged with a "J." The LOQs (<10 ng) represent a baseline above which results exceed laboratory-determined limits of precision and accuracy. Any field sample measurements above the upper calibration standard are estimated; however, these values are reported without qualifiers because all reported measurements are relative to each other and are appropriate to meet the survey objectives of locating source areas and vapor intrusion pathways and defining the lateral extent of contamination.

Calibration Verification

The continuing calibration verification (CCV) values for the calibration check compounds were all within $\pm 20\%$ of the true values as defined by the initial five-point calibration and met the requirements specified in Beacon Environmental's Quality Assurance Project Plan.

Method Blanks/Trip Blanks

Laboratory method blanks are run with each sample batch to identify contamination present in the laboratory. If contamination is detected on a method blank, measurements of identical compounds in that sample batch are flagged in the laboratory report. The laboratory method blanks analyzed in connection with the present samples revealed no contamination.

The trip blank is a sampler prepared, transported, and analyzed with other samples but intentionally not exposed. Any target compounds identified on the trip blanks are reported in the laboratory data. The analysis of the trip blank (labeled Trip-1 in **Table 1**) reported none of the targeted compounds.

BEACON ENVIRONMENTAL SERVICES, INC.

Passive Soil-Gas Survey Circle Court Ground Water Plume Superfund site Willow Park, TX

Passive Soil-Gas Survey Notes

When sample locations are covered with or near the edge of an artificial surface (e.g., asphalt or concrete), the concentrations of compounds in soil gas are often significantly higher than the concentrations would be if the surfacing were not present. Thus, a reading taken below or near an impermeable surface is much higher than it would be in the absence of such a cap. Therefore, the sample location conditions should be evaluated when comparing results between locations.

Survey findings are exclusive to this project and when the spatial relationships are compared with results of other BEACON Surveys it is necessary to incorporate survey and site information from both investigations (e.g., depth to sources, soil types, porosity, soil moisture, presence of impervious surfacing, sample collection times). BEACON recommends the guidelines stated in **Attachment 1** to establish a relationship between reported soil-gas measurements and actual subsurface contaminant concentrations, which will indicate those measurements representing significant subsurface contamination.

BEACON's passive soil-gas samplers are prepared with two sets of adsorbent cartridges for subsequent duplicate or confirmatory sample analysis. At EA's request, duplicate analysis was performed for seven (7) field samples. The duplicate samples were designated with a "DUP" following the sample number. When comparing quantitative results, a duplicate correspondence should be considered when the relative percent difference (RPD) between the two samples is less than or equal to 100%. For the purpose of calculating correspondences, all non-detections should be assigned, as a baseline value, the CRQL for the specific contaminant. Based on these assumptions, a 100% correlation was found between the duplicate samples and their base samples.

Project Details

Samplers were deployed on November 8, 2012, and were retrieved on November 19, 2012. **Attachment 2** describes the field procedures used. Individual deployment and retrieval times will be found in the Field Deployment Report (**Attachment 3**).

Sixty nine (69) field samples, seven field sample (7) duplicates, and one (1) trip blank were received by BEACON on November 20, 2012. Adsorbent cartridges from the passive samplers were thermally desorbed, then analyzed using gas chromatography/mass spectrometry (GC/MS) equipment, in accordance with EPA Method 8260C (Modified), as described in **Attachment 4**. BEACON's laboratory analyzed each sample for the targeted compounds; analyses were completed on November 21, 2012. Following a laboratory review, results were provided to EA on November 28, 2012. The Chain-of-Custody form, which was shipped with the samples for this survey, is supplied as **Attachment 5**.

Sample locations are shown on **Figure 1**. The following table lists frequency of detections based on the number of field samples analyzed, the reporting limit, and the maximum value for each mapped compound. The table also includes the transformation and interpolation method for the compound distribution maps provided.

Figure No.	2	3		
Compound	Cis-1,2-dichloroethene	Trichloroethene		
Frequency	3	11		
Reporting Limit (nanograms)	5	5		
Max Value (nanograms)	686	16,265		
Transformation Method	Log	Log		
Interpolation Method	Kriging	Kriging		

Attachments:

- -1- Applying Results From Passive Soil-Gas Surveys
- -2- Field Procedures
- -3- Field Deployment Report
- -4- Laboratory Procedures
- -5- Chain-of-Custody Form

ALL DATA MEET REQUIREMENTS AS SPECIFIED IN THE BEACON ENVIRONMENTAL SERVICES, INC. QUALITY ASSURANCE PROJECT PLAN AND THE RESULTS RELATE ONLY TO THE SAMPLES REPORTED. BEACON ENVIRONMENTAL SERVICES IS ACCREDITED TO ISO 17025:2005, AND THE WORK PERFORMED WAS IN ACCORDANCE WITH ISO 17025 REQUIREMENTS. THIS REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL, WITHOUT THE WRITTEN APPROVAL OF THE LABORATORY. RELEASE OF THE DATA CONTAINED IN THIS HARDCOPY DATA PACKAGE HAS BEEN AUTHORIZED BY THE LABORATORY DIRECTOR OR HIS SIGNEE, AS VERIFIED BY THE FOLLOWING SIGNATURES:

Steven C. Thornley Laboratory Director

Steven (Thornley

Patti J. Riggs V Quality Manager

Table 1

	Client Sample ID:	mb121120a	Trip-1	A1	A2	A3	A4
	Project Number:		2594	2594	2594	2594	2594
	Lab File ID:	A12112003	A12112005	A12112006	A12112007	A12112008	A12112009
	Received Date:		11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Time:	14:25	15:10	15:33	15:55	16:18	16:40
	Matrix:			Soil Gas	Soil Gas	Soil Gas	Soil Gas
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	A5	A6	A7	A8	B1	B2
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112010	A12112011	A12112012	A12112013	A12112014	A12112015
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Time:	17:03	17:26	17:48	18:10	18:33	18:56
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	11	<10
Trichloroethene		<10	<10	<10	11	470	<10

Table 1

	Client Sample ID:	В3	B4	B5	B6	В7	B8
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112016	A12112017	A12112018	A12112019	A12112020	A12112021
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Time:	19:19	19:42	20:05	20:28	20:51	21:14
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	C1	C2	C3	C4	C4.5	C5
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112022	A12112023	A12112024	A12112025	A12112026	A12112027
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Time:	21:36	21:59	22:21	22:44	23:06	23:29
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	C5.5	C6	C6.5	C7	C8	CD6.5
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112028	A12112029	A12112030	A12112031	A12112032	A12112033
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/20/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	23:52	0:14	0:36	0:59	1:22	1:45
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	D1	D2	D3.5	D4	D4 DUP	D4.5
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112034	A12112035	A12112036	A12112037	A12112038	A12112039
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	2:07	2:30	2:53	3:15	3:38	4:01
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	8 J	<10	<10	<10

Table 1

	Client Sample ID:	D5.5	D6	D6 DUP	D6.5	D7	D8
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112040	A12112041	A12112042	A12112043	A12112044	A12112045
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	4:23	4:46	5:08	5:30	5:53	6:16
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	DE3	DE3.5	DE3.5 DUP	DE4	DE4.5	DE4.5 DUP
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112046	A12112047	A12112048	A12112049	A12112050	A12112051
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	6:39	7:02	7:24	7:47	8:09	8:31
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	<10	<10	<10	<10	<10	<10
Trichloroethene		19	43	53	73	<10	<10

Table 1

	Client Sample ID:	DE5	DE5.5	DE6	E1	E2	E3
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112052	A12112053	A12112054	A12112055	A12112056	A12112057
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	8:54	9:16	9:38	10:01	10:23	10:46
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	33

Table 1

		F0.5	T. 4	77.5	П.	77.5	1.101.101
	Client Sample ID:	E3.5	E4	E5	E6	E7	mb121121a
	Project Number:	2594	2594	2594	2594	2594	
	Lab File ID:	A12112058	A12112059	A12112060	A12112061	A12112062	A12112103
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	11:08	11:31	11:53	12:15	12:38	14:10
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	686	19	<10	<10	<10	<10
Trichloroethene		16,265	683	<10	<10	<10	<10

Table 1

	Client Sample ID:	E8	F1	F2	F3	F4	F4 DUP
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112105	A12112106	A12112107	A12112108	A12112109	A12112110
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	14:55	15:17	15:40	16:03	16:25	16:48
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ene	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	67	<10	<10

Table 1

	Client Sample ID:	F5	F5 DUP	F6	F7	F8	G1
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112111	A12112112	A12112113	A12112114	A12112115	A12112116
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	17:11	17:33	17:56	18:18	18:41	19:03
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

	Client Sample ID:	G2	G3	G4	G4 DUP	G5	G6
	Project Number:	2594	2594	2594	2594	2594	2594
	Lab File ID:	A12112117	A12112118	A12112119	A12112120	A12112121	A12112122
	Received Date:	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012	11/20/2012
	Analysis Date:	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012	11/21/2012
	Analysis Time:	19:26	19:49	20:11	20:34	20:56	21:19
	Matrix:	Soil Gas					
	Units:	ng	ng	ng	ng	ng	ng
COMPOUNDS							
Vinyl Chloride		<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethe	ne	<10	<10	<10	<10	<10	<10
Trichloroethene		<10	<10	<10	<10	<10	<10

Table 1

Beacon Environmental Services, Inc. 323 Williams Street Bel Air, MD 21014 USA

	Client Sample ID:	G7
	Project Number:	2594
	Lab File ID:	A12112123
	Received Date:	11/20/2012
	Analysis Date:	11/21/2012
	Analysis Time:	21:42
	Matrix:	Soil Gas
	Units:	ng
COMPOUNDS		
Vinyl Chloride		<10
cis-1,2-Dichloroether	ne	<10
Trichloroethene		<10



2220680 2220700 2220720 2220740 2220760 2220780 2220800 2220820 2220840 2220860 2220880 2220900 2220920 2220940 2220960 2220980 2221000 2221020 2221040

LEGEND



Scale in Feet 40 80


PASSIVE SOIL-GAS SAMPLE LOCATION

Texas State Plane 1983 System: Zone: North Central Zone Datum: NAD 1983

Coordinate Units: Feet

Figure 1 Passive Soil-Gas Survey **Sample Locatoins**

Circle Court GW Plume Superfund Site Willow Park, TX



2220680 2220700 2220720 2220740 2220760 2220780 2220800 2220820 2220840 2220860 2220880 2220900 2220920 2220940 2220960 2220980 2221000 2221020 2221040



Beacon Project No. 2594, December 2012

LEGEND

1,000 NANOGRAMS/SAMPLER

PASSIVE SOIL-GAS SAMPLE LOCATION


Scale in Feet 40 80

Texas State Plane 1983 System: Zone: North Central Zone Datum: NAD 1983

Coordinate Units: Feet

Figure 2 Passive Soil-Gas Survey cis-1,2-Dichloroethene

Circle Court GW Plume Superfund Site Willow Park, TX



2220680 2220700 2220720 2220740 2220760 2220780 2220800 2220820 2220840 2220860 2220880 2220900 2220920 2220940 2220960 2220980 2221000 2221020 2221040



Beacon Project No. 2594, December 2012

LEGEND

1.000 NANOGRAMS/SAMPLER

PASSIVE SOIL-GAS SAMPLE LOCATION

Scale in Feet 40 80

Texas State Plane 1983 System: Zone: North Central Zone Datum: NAD 1983

Coordinate Units: Feet

Figure 3 Passive Soil-Gas Survey Trichloroethene

Circle Court GW Plume Superfund Site Willow Park, TX

Attachments

Attachment 1

APPLYING RESULTS FROM PASSIVE SOIL-GAS SURVEYS

The utility of soil-gas surveys is directly proportional to their accuracy in reflecting and representing changes in the subsurface concentrations of source compounds. Passive soil-gas survey results are the mass collected from the vapor-phase emanating from the source(s). The vapor-phase is merely a fractional trace of the source(s) and, as a matter of convenience, the units used in reporting detection values from passive soil-gas surveys are smaller than those employed for source-compound concentrations.

Passive soil gas data are reported in mass of compounds identified per sample location (e.g., nanograms (ng) or micrograms (μ g) per sampler). Results from a passive soil gas survey typically are then used to guide where follow-on intrusive samples should be collected to obtain corresponding concentrations of the contaminants in soil, soil gas, and/or groundwater, as well as eliminate those areas where intrusive samples are not required. It is not practical to report passive soil gas data as concentration because the sampler's uptake rates of the compounds are often greater than the replenishment rates of the compounds around the sampler, which results in low bias measurements, and the replenishment rates will be dependent on several factors that include, at a minimum, soil gas concentrations, soil porosity and permeability, and soil moisture level.

Whatever the relative concentrations of source and associated soil gas, best results are realized when the ratio of soil-gas measurements to actual subsurface concentrations remains as close to constant as the real world permits. It is the reliability and consistency of this ratio, not the particular units of mass (e.g., nanograms) that determine usefulness. Thus, BEACON emphasizes the necessity of conducting — at minimum — follow-on intrusive sampling in areas that show relatively high soil-gas measurements to obtain corresponding concentrations of soil and groundwater contaminants. These correspondent values furnish the basis for approximating a relationship. For extrapolating passive soil gas results to vapor intrusion evaluations, we recommend a minimum of three passive soil gas locations be converted to a shallow vapor well then sampled using an active soil gas method. Once a relationship is established, it can be used in conjunction with the remaining soil-gas measurements to estimate subsurface contaminant concentrations across the survey field. (See www.beacon-usa.com/passivesoilgas.html, Publication 1: Mass to Concentration Tie-In for PSG Surveys and Publication 4: Groundwater and PSG Correlation.) It is important to keep in mind, however, that specific conditions at individual sample points, including soil porosity and permeability, depth to contamination, and perched ground water, can have an impact on soil-gas measurements at those locations.

When passive soil-gas surveys are utilized as described above, the data provide information that can yield substantial savings in drilling costs and in time. They furnish, among other things, a checklist of compounds expected at each survey location and help to determine how and where drilling budgets can most effectively be spent. Passive soil-gas surveys can also be used as a remediation or general site monitoring tool that can be implemented on a quarterly, semi-annual or annual basis.

Attachment 2


FIELD PROCEDURES FOR PASSIVE SOIL-GAS SURVEYS

The following field procedures are routinely used during a BEACON Passive Soil-Gas Survey. Modifications can be and are incorporated from time to time in response to individual project requirements. In all instances, BEACON adheres to EPA-approved Quality Assurance and Quality Control practices.


- A. Field personnel carry a BESURE Sample Collection KitTM and support equipment to the site and deploy the passive samplers in a prearranged survey pattern. A passive sampler consists of a borosilicate glass vial containing hydrophobic adsorbent cartridges with a length of wire attached to the vial for retrieval. Although samplers require only one person for emplacement and retrieval, the specific number of field personnel required depends upon the scope and schedule of the project. Each Sampler emplacement generally takes less than two minutes.
- B. At each survey point a field technician clears vegetation as needed and, using a hammer drill with a 1"- to 1½"-diameter bit, creates a hole 12 to 14 inches deep. [Note: For locations covered with asphalt, concrete, or gravel surfacing, the field technician drills a 1"- to 1½"-diameter hole through the surfacing to the soils beneath]. The technician then, using a hammer drill with a ½" diameter bit, creates a hole three-feet deep. The hole is then sleeved with a 1"-diameter metal sleeve.
- C. The technician then removes the solid plastic cap from a sampler and replaces it with a Sampling Cap (a plastic cap with a hole covered by screen meshing). The technician inserts the sampler, with the Sampling Cap end facing down, into the hole (see attached figure). The sampler is then covered with an aluminum foil plug and soils for uncapped locations or, for capped locations, an aluminum foil plug and a concrete patch. The sampler's location, time and date of emplacement, and other relevant information are recorded on the Field Deployment Form.
- D. One or more trip blanks are included as part of the quality-control procedures.
- E. Once all the samplers have been deployed, field personnel schedule sampler recovery and depart, taking all other equipment and materials with them.
- F. Field personnel retrieve the samplers at the end of the exposure period. At each location, a field technician withdraws the sampler from its hole, removes the retrieval wire, and wipes the outside of the vial clean using gauze cloth; following removal of the Sampling Cap, the threads of the vial are also cleaned. A solid plastic cap is screwed onto the vial and the sample location number is written on the label. The technician then records sample-point location, date, time, etc. on the Field Deployment Form.
- G. Sampling holes are refilled with soil, sand, or other suitable material. If samplers have been installed through asphalt or concrete, the hole is filled to grade with a plug of cold patch or cement.
- H. Following retrieval, field personnel ship or transport the passive samplers to BEACON's laboratory.

BEACON'S PASSIVE SOIL-GAS SAMPLER

DEPLOYMENT THROUGH SOILS



DEPLOYMENT THROUGH AN ASPHALT/CONCRETE CAP



Attachment 3

Field Deployment Report

Project Information				
Beacon Project No.:	2594			
Site Name:	Circle Court Ground Water Plume Superfund Site			
Site Location:	Willow Park, TX			



Clie	ent Information		
Company Name:	EA Engineering, Science, and Technology, Inc		
Office Location:	Lewisville, TX		
Samples Collected By:	JAS JASON Strong		

FIELD SAMPLE ID	Date Emplaced ル/3/1分 Time Emplaced	Date Retrieved	Sampling Hole Depth (inches)	FIELD NOTES (e.g., asphalt/concrete/gravel, description of sample location, PID/FID readings)
VA8	0855	0955	20	soit nature soil and cla catiche rock
VA7	0901	0954	32	tt n
/A6	0903	0953	22	1)
1A5	0905	0957	32	i h
Ay	0907	0949	27	li li
1/A3	0909	0945	25	i)
·A2	0913	0943	25	1
VA1	0915	0941	29"	N U
VC1	0918	1007	M+15	near home
V B1	0921	1006	15	1,
1B2	0922	1004	32	nature 50.7 and rock
1 B3	0924	1003	14	ner home
1B4	0928	1001	15	N 0
~ CZ	0932	1008	15	K 11
VC3	0934	1669	15	It is

Beacon Project 2594 -- Page 26 of 36

Page _____ of _____

Project Information				
Beacon Project No.:	2594			
Site Name:	Circle Court Ground Water Plume Superfund Site			
Site Location:	Willow Park, TX			



Clie	ent Information				
Company Name:	EA Engineering, Science, and Technology, Inc.				
Office Location:	Lewisville, TX				
Samples Collected By:	JAS Jason Stromp				

FIELD	Date Emplaced	Date Retrieved	Sampling	FIELD NOTES
SAMPLE ID	11/8/17 Time Emplaced	Time Retrieved	Hole Depth (inches)	(e.g., asphalt/concrete/gravel, description of sample location, PID/FID readings)
VCY	0936	1011	23	nation soil and rock
VC4 VC4.5 VC5	0939	1013	15	new home
165	0941	1014	15	1 1 11
VC515	0944	1015	15	1.5 1/
VC6	0946	1016	15	
166.5	0947	1017	15	Ty ()
1C6.5	0952	1102	15	11
VD6.5	0953	1024	15	1. 11
VE6	0956	1059	15	tx 17
VDE5	1001	1025	.15	18 17
DE5.5	1003	1026	15	ix v
05.5	1006	1027	15	15 17
1 D6	1008	1028	15	
VDE6	1発1010	1029	15	17 11
E5	1015	1058	15	PS 0

Beacon Project 2594 -- Page 27 of 36

Page 2 of 5

Project Information				
Beacon Project No.:	2594			
Site Name:	Circle Court Ground Water Plume Superfund Site			
Site Location:	Willow Park, TX			



Clie	ent Information
Company Name:	EA Engineering, Science, and Technology, Inc.
Office Location:	Lewisville, TX
Samples Collected By:	JAS Jasan Skrup

FIELD SAMPLE ID	Date Emplaced Time Emplaced	Date Retrieved Time Retrieved	Sampling Hole Depth (inches)	FIELD NOTES (e.g., asphalt/concrete/gravel, description of sample location, PID/FID readings)
DE4.5	1021	1056	15	new home
VD4.5	1023	1037	15	ty 11
VD4	1025	1034	15	3x 1/
103.5	1027	1036	15	IX. M
VAE3.5	1030	1043	32	natur Soil at Lock
VDF3	1033	1045	32	1/
YE3	1035	1047	13	1)
185	1046	0959	32	Ti Ti
VB6	1048	0958	28	11
187	1050	0957	32	1)
1B8	1052	0957	32	1)
1CB	1053	1021	37	u h
VC7	1055	1018	37	12 /1
V D7	1105	1023	32	II II
VD8	1108	1027	30	Li y

Beacon Project 2594 -- Page 28 of 36

Page 3 of 5

Project Information

Beacon Project No.: 2594
Site Name: Circle Court Ground Water Plume Superfund Site

Site Location: Willow Park, TX



Client Information				
Company Name:	EA Engineering, Science, and Technology, Inc.			
Office Location:	Lewisville, TX			
Samples Collected By:	TAS Jasus Stimo			

FIELD	Date Emplaced	Date Retrieved	Sampling						
SAMPLE ID	11/9/17		Hole Depth	(e.g., asphalt/concrete/gravel, description of sample location, PID/FID reading					
	Time Emplaced	Time Retrieved	(inches)						
VE8	1110	1103	32	nature So.7 and Rock					
~F8	1112	1104	32	ic 11					
VG7	1115	1106	32	11					
VG6	1117	1108	37	VV VI					
VF6	1119	1107	32	11					
VF7	1170	1105	20	· · · · · · · · · · · · · · · · · · ·					
VE7	1173	1100	30	V V					
VF5	1135	1109	32	1/					
165	1150	1115	32	it II					
V64	1153	1117	32	1)					
VF4	1157	1110	32	11					
VE4	1201	1052	15	near home					
VDE4	1204	1054	15	- 1s U					
VE3.5	1209	1043	28	native soft and Rock					
VG3	1217	1/19	32	ne l					

Beacon Project 2594 -- Page 29 of 36

Pı	roject Information
Beacon Project No.:	2594
Site Name:	Circle Court Ground Water Plume Superfund Site
Site Location:	Willow Park, TX



Clie	ent Information
Company Name:	EA Engineering, Science, and Technology, Inc.
Office Location:	Lewisville, TX
Samples Collected By:	JAS Jasu Stry

FIELD	Date Emplaced	Date Retrieved	Sampling Hole Depth	FIELD NOTES				
SAMPLE ID	Time Emplaced	Time Retrieved	(inches)	(e.g., asphalt/concrete/gravel, description of sample location, PID/FID readings)				
1G2	1226	1177	32	native	Soll and Rock			
VG1	1230	1122	32	11	1,			
VF.1	1234	1123	32	15	11			
VF2	1736	1124	32	u	1,			
VF3	1238	1175	32	11	1)			
VEZ.	1741	1127	32	1 <	()			
VE1	1243	1127	32	10	4			
VD1	1748	1128	32	11	i)			
ヘロケ	1752	1130	32	ιt	11			

Attachment 4

LABORATORY PROCEDURES FOR PASSIVE SOIL-GAS SAMPLES

Following are laboratory procedures used with BEACON Passive Soil-Gas Surveys, a screening technology for expedited site investigation. After exposure, adsorbent cartridges from the passive samplers are analyzed using U.S. EPA Method 8260C as a guidance document, a capillary gas chromatographic/mass spectrometric method, modified to accommodate high temperature thermal desorption of the adsorbent cartridges and to meet the objectives of reporting semi-quantitative data. This procedure is summarized as follows:

- A. The adsorbent cartridges are loaded with internal standards and surrogates prior to loading the autosampler with the cartridges. The loaded cartridges are purged in a helium flow. Then the cartridges are thermally desorbed in a helium flow onto a focusing trap. Any analytes in the helium stream are adsorbed onto a focusing trap.
- B. Following trap focusing, the trap is thermally desorbed onto a Rxi-624Sil MS 20m, 0.18 mm ID, 1.00 micron filament thickness capillary column.
- C. The GC/MS is scanned between 35 and 270 Atomic Mass Units (AMU) at 3.12 scans per second.
- D. BFB tuning criteria and the initial five-point calibration procedures are those stated in method SW846-8260C. System performance and calibration check criteria are met prior to analysis of samples. A laboratory method blank is analyzed after the daily standard to determine that the system is contaminant-free.
- E. The instrumentation used for these analyses includes:
 - Agilent 6890-5973a Gas Chromatograph/Mass Spectrometer;
 - Markes Unity thermal desorber;
 - Markes UltrA autosampler; and
 - Markes Mass Flow Controller Modules

Attachment 5

Chain-of-Custody Form

CHAIN-OF-CUSTODY PASSIVE SOIL-GAS SAMPLES

Pı	oject Information]	Clie	ent Information
Beacon Project No.:	2594	BEACON	Company Name:	EA Engineering, Science, and Technology, Inc.
Site Name:	Circle Court Ground Water Plume Superfund Site		Office Location:	Lewisville, TX
Site Location:	Willow Park, TX	SERVICES, INC. 323 Williams Street, Suite D. Bel Air, MD 21014 (800) 878-5510	Samples Submitted By:	Jason Stroup
Analytical Method:	EPA Method 8260C		Contact Phone No.:	214-578-8182
Target Compounds:	Beacon Project Number 2594 Target	Compound List		

Field Sample ID			ments oblem or discrepancy)			
17		Notes		Date	e Time	Initial
A8				11/19	1/12 0955	JAS
AT				11/191	112 0954	JAS
A6				11/19/	12 0953	JAS
A5				11/19/		JAS JAS
AH				11/19/	12 0949	J45
A3				11/19/	112 0945	JAS
42				11/191	112 0943	JAS
A1		· · · · · · · · · · · · · · · · · · ·		11/191		JAS
C1				11/19/	12 /007	JAS
B1				11/19/	12 1006	JAS
Ba				11/19	112 1004	JAS
B3				11/19	112 1003	JAS
B4				11/19	112 1001	JAJ
Ca				11/19	112 1008	JAS
C3				11/19	112 1009	JAS
CY				11/19	112 1011	JAS
C4,5				11/19	110 1013	JAS
C5				11/19	112 1014	JAS
25.5				11/19	1/12 1015	JAS
C6			7	11/19	112 1016	THE
ment of Field Kit to Sit	te — Custody Seal # 17350247		Intact? (Y) N			
Relinquished by:	Date/Time	Courier	Received by	:	Date/Ti	
my Thecho	10-31-2012 / 1700 Hours	FedEx	A Joson	Stroyp	11/2/12	1030
				1		
ment of Field Kit to La	boratory — Custody Seal # /73	50 248	Intact? (V) N			
Relinquished by:	Date/Time	Courier	Received by	:	Date/Ti	me
A	11/19/12/1630	FEDEX	Kenny Tpeach	4.50	11-20-2012 1	1000 Hory

CHAIN-OF-CUSTODY PASSIVE SOIL-GAS SAMPLES

Pı	oject Information		Clie	ent Information
Beacon Project No.:	2594	BEACON	Company Name:	EA Engineering, Science, and Technology, Inc.
Site Name:	Circle Court Ground Water Plume Superfund Site		Office Location:	Lewisville, TX
Site Location:	Willow Park, TX	SERVICES, INC. 323 Williams Street, Suite D. Bel Air, MD 21014 (800) 878-5510	Samples Submitted By:	Jason Stroup
Analytical Method:	EPA Method 8260C	SEC NAMED DECK, GLIO D. DOT MICHAEL (000) OF SEC.	Contact Phone No.:	214-578-8187
Target Compounds:	Beacon Project Number 2594 Target	Compound List		

Field Sample ID			ments oblem or discrepancy)				
±'		Notes		Da	te	Time	Initial
C 6:5				11/19	7/12	1017	JAS
CD6.5				11/19	1/12	1102	TAS
06.5				11/19	112	1024	JAS
E6 DE5				11/19	1/12	1059	JAS
DE5				11/19	1/12	1025	JAS
DE 5.5				11/19	112	1026	JAS
D 5.5	•			11/18	9/12	1027	JAS
D6 Duplicate				11/19	1/2	1028	JAS
DE6				11/10	9/12	1029	JAS
E5				11/19	9/12	1058	JAS
DE4.5 Duplozul				11/1	9/12	1056	JAS
04.5				11/1	9/12	1032	JAS
D4 Ouplicate				11/1	9/12	1034	JAS
03.5				11/	19/12	1036	JAS
DE3.5 Duplicate				11/1	9/12	1043	JAS
DE3				11/1	19/12	1045	JAS
E3	A-1112			11/1	9/12	1047	J48
B5					9/12	0959	JAS
B6				11/1	9/12	0958	JAS
67				11/1	9/12	0957	JAS
Shipment of Field Kit to Site -		247	Intact? (Y) N				
Relinquished by:	Date/Time	Courier	Received by:			Date/Tir	ne
Kenny Ifecto	10-31-2012 / 1700 Hours	FedEx	Josn S	strong	11/4	112 1	0.30
1		2000		1	1 6	7	
Shipment of Field Kit to Labo		17350248	Intact? D N				
Relinquished by:	Date/Time	Courier	Received by:			Date/Tir	
	11/19/12 / 1630	FedEX	Kenny Jacks		11-20	-2012/1	ooo tlous

CHAIN-OF-CUSTODY PASSIVE SOIL-GAS SAMPLES

Pr	oject Information		Client Information			
Beacon Project No.:	2594	BEACON	Company Name:	EA Engineering, Science, and Technology, Inc.		
Site Name:	Circle Court Ground Water Plume Superfund Site		Office Location:	Lewisville, TX		
Site Location:	Willow Park, TX	SERVICES, INC. 323 Williams Street, Suite D. Bel Air, MD 21014 (800) 878-5510	Samples Submitted By:	Jason Stroup		
Analytical Method:	EPA Method 8260C	22 134 134 134 134 134 134 134 134 134 134	Contact Phone No.:	214-578-8187		
Target Compounds:	Beacon Project Number 2594 Target	Compound List				

	Field Sample ID		Comm (only necessary if pro				
i			Notes		Date	Time	Initial
	68				1/19/11	0957	Total
	CB				Viglia	1001	JAS JAS
Ī	67		Manager		1/19/11	1018	TH
	07				11/19/12	1023	JAS
	89				Migli	1022	JAS
	E8				1/19/11	1103	JAT
	Fg			j	119/12	1104	TAP
	F§				1/19/12	1106	THE
	66				1/19/10	1108	JAT
	F6				1/19/12	1107	JAS
	F7				11/19/11	1105	JES
	ET			,	1/19/11	1100	JAS
	F5 Duplicate				1/19/12	1109	JAS
	65				11/19/12	1115	JAS
	Gy Duplicate				11/19/12	1112	JAC JAC
	Fy Dup Is cate				11/19/12	1110	了好
φ[EY				1/19/12	1052	JAS
acc	DEY				1/19/12	1054	JA
ĭ Fi	E3.5				1/19/12	1048	JAC
Beacon Project 2594	63			2	1/119/12	1119	JAI
<u>, </u>	Shipment of Field Kit to Site	- Custody Seal # 17350	247	Intact? (Y) N	7		
<u> </u>	Relinquished by:	Date/Time	Courier	Received by:		Date/Ti	me
1	Kenny Ifeachs	10-31-2012 / 1700 Hours	FedEx	A Town stry	1	12/12	10 30
Page 35 of 36	. 1						
ნ ა ⊦	Shipment of Field Kit to Lab		7350248	Intact? N			
5 c	Relinquished by:	Date/Time	Courier	Received by:		Date/Time	
36	A	11/19/12 //630	Fed EX	Kenny Treacho	11-2	0-2012/	1000 House
L							

CHAIN-OF-CUSTODY PASSIVE SOIL-GAS SAMPLES

Project Information			Client Information			
Beacon Project No.:	2594	BEACON ENVIRONMENTAL SERVICES, INC. 323 Williams Street, Suite D, Bel Air, MD 21014 (800) 878-5510	Company Name:	EA Engineering, Science, and Technology, Inc.		
Site Name:	Circle Court Ground Water Plume Superfund Site		Office Location:	Lewisville, TX		
Site Location:	Willow Park, TX		Samples Submitted By:	Jason Stroup		
Analytical Method:	EPA Method 8260C	2101 (000)	Contact Phone No.:	714-578-B182		
Target Compounds:	Beacon Project Number 2594 Target	Compound List				

Target Compounds:	Beacon Project Number 2594 Target	Compound List			0 0:0	
Field Sample II)		nments coblem or discrepancy)			
		Notes	N.	Date	Time	Initial
Ga			Zinne-mark A	11/19/12	1122	JAS
G1				11/19/12	1122	JAS
F1				11/19/12	1123	TAS
Fa				11/19/12	1124	JAS
F3				11/19/12	1125	TAS
EZ				11/19/12	1127	JAS
E1	,			11/19/12	1127	JAS
Δ1 02				11/19/12	1128	JAS JAS
Da				11/19/12	1130	JAS
				MHATTI		
				ASH1-9/12		
				1		
			*			
Shipment of Field Kit	to Site — Custody Seal # 1735	0247	Intact? (Y) N			
Relinquished by				Date/Time		
Kenny Iflaction		FedEx	Jason St	roup 11/2/12 1030		
11					(
hipment of Field Kit	to Laboratory — Custody Seal #	17350 248	Intact? (Y) N			
Relinquished by: Date/Time		Courier	Received by:		Date/Time	
A	11/19/12/1630	FedEX	Kenny Igrech) 11-	20-2012/	1000 House
0	/				A STATE OF THE STA	