

From: [Garyg Miller](#)
To: lvega@eaest.com
Cc: lvoskov@tceq.state.tx.us; [Rena McClurg](#); [Gustavo Chavarria](#); [Dipanjana Bhattacharya](#)
Subject: Gulfco Monitoring Well Installation - Task Order 0006-RICO-06JZ
Date: 05/07/2007 03:19 PM

Luis,

As we discussed, the Gulfco Respondents are planning to install additional monitoring wells. The monitoring well drilling will be done during the week of 5/21/07, and the well development & ground water sampling will be done approximately 2 weeks later - exact date will be determined later. The well installation is expected to take about one week to complete, but the actual time may vary depending on field conditions. The well installation work is to be done in accordance with PBW's "Groundwater Data" and proposed monitoring wells, dated January 19, 2007, as approved by EPA with modifications (as per the 3/14/07 email sent to you).

Please provide field oversight of the well installation and split sampling for this work.

Regarding the sample splits:

Zone A (shallow) monitoring wells - two ground water sample splits, analysis for VOCs, SVOCs, metals, and pesticides. Please obtain the splits from MW-21 and the new Zone-A well that is adjacent to planned MW-23B.

Zone B (deeper) monitoring wells - one ground water sample split, analysis for VOCs, SVOCs, metals, and pesticides. The Zone B well to be split should be determined following drilling, and should be based on the well with the presence of NAPL or other indications of contamination.

Thanks Luis. Let me know if you have any questions on this.

Gary Miller
Remediation Project Manager
EPA Region 6 - Superfund (6SF-AP)
(214) 665-8318
miller.garyg@epa.gov



9543223