

## **Falcon Refinery - WORK TO BE PERFORMED**

38. The Respondent shall perform, at a minimum, all actions necessary to implement the Order of Work. The actions to be implemented generally include, but are not limited to, the following:

### **a. The Work**

The intent of this action is to remove and dispose of source materials from tanks and other miscellaneous containers, equipment, piping and buildings. This also includes the removal of any source materials in piping associated with transfer of materials to the facility docks or former facility docks. As a result, it may be necessary to demolish or otherwise remove some tanks, piping, equipment, and buildings in order to effectuate this activity. This action may also include the consolidation of materials in onsite tankage for future disposal. If the Respondent elects to consolidate and temporarily store these materials, Respondent must comply with all applicable laws including storage and spill prevention regulations. The work includes:

**i. Asbestos Inspection and Abatement:** The Respondent shall comply with applicable law(s) to address any asbestos and coordinate its handling appropriately with any demolition activities. Therefore, it will be necessary for the Respondent to conduct an asbestos inspection and make appropriate notifications for the conduct of such demolition and asbestos abatement activities as required by applicable law(s).

**ii. Assessment and Removal of Hazardous Substances, or Pollutants or Contaminants:** The Respondent shall conduct tests and properly classify the wastes for appropriate disposal or recycling.

**iii. Decontamination of Containers, Equipment, Piping, and Buildings:** The Respondent shall decontaminate all containers, equipment, piping, and buildings to the extent necessary for the purpose of recycling, reuse, or disposal.

**iv. Removal of Containers, Equipment, Piping, and other Contaminated Items:** The Respondent shall recycle or dispose of containers, equipment, piping, and other potentially contaminated items in accordance with applicable law(s). The metal debris associated with the removal of the containers, equipment, piping, and other items should be recycled to the extent practical.

**V. Consolidation, Removal and Disposal of Grossly Contaminated Soil:** The Respondent shall consolidate and then treat or dispose of visibly contaminated surface soils identified during the conduct or resulting from the conduct of this action.