17804C



# INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT

We make Indiana a cleaner, healthier place to live

Evan Bayh Governor Kathy Prosser Commissioner 105 South Meridian Street P.O. Hox 6015 Indianapolis, Indiana 46206-6015 Telephone 317-232-8603 Environmental Helpling 1-800-451-6027

962490

January 29, 1993

Ms. Deborah Orr Remedial Project Manager HSRL-6J USEPA, Region V, 77 West Jackson Blvd. Chicago, IL 60604

المنظام والمتاهدة والمستعلق سيلاونها فالمتاثر

RE: Main Street Well Field Preliminary Design Report Eastside Activities Elkhart, Indiana

Dear Ms. Orr:

The State has reviewed the above cited document submitted by Geraghty & Miller on behalf of the Eastside respondents. Our review generated the following comments:

## Sec. 2.5 - SVE Pilot Test, Page 12. Paragraph 1

It is stated that the measurements were collected approximatel every 15 minutes, it did not specify for how long. Also Table indicated that the test was conducted from 12:35 to 12:47pm. (12 minutes).

It is not clear how the extraction rates for other areas, i.e. areas 2A, 4A, 5A, 6A were determined. Also an explanation is needed for different extraction rates for each area (i.e. 5 CF for area 4A and 110 CFM for area 2A).

the PRPs should be aware of an "exempt certificate or letter" that must be obtained from the IDEM commissioner prior to the commencement of VES operation (see attached rules).

#### ec. 2.6.1 - Excavation Procedures

low will the excavated area (10' x 25' x 3') be secured? No illing plans (with clean soil) were mentioned or discussed.

Ms. Deborah Orr Page 2

والإشار والمستخار والمستجار والمستجار سياسا فيباس ليباس السنسا أرواني

### Sec. 4.2 - SVE System Configuration

On page 26, it is stated that the combined flow rate for the simulated full-scale SVE system is 300 CFM but on page 29 (SVE pilot study bullet 3) the same figure was mentioned as 368 CFM. Which figure is correct?

#### Table 4

Although the analytical results show low levels of lead and mercury in the soils, the community or public should be cautioned about the soil conditions in order to avoid any direct contact threat during excavation activities in that area.

If you have any questions concerning this letter, please feel free to contact me at AC (317) 243-5130.

Very truly yours,

Prabhakar Kasarabada Project Manager Superfund Section Office of Environmental Response

PK/pw

cc: Fran Metcalf, IDEM Ken Gill, IDEM