

Interim Response Activities

East Jefferson at Belle Isle

***City of
Detroit***

Interim Response Activities


East Jefferson at Belle Isle

***City of
Detroit***



CONSULTANT TEAM

Interim Response Activities
East Jefferson At Belle Isle



CITY OF DETROIT



THE
TRAVERSE
GROUP

- ♦ Project Management (Project Manager - John J. D'Addona, PE)
- ♦ Technical Oversight / Design (Project Technical Leader - Joel W. Parker)
- ♦ Investigations / Remedial Work
- ♦ Work Plans / Reports
- ♦ Project Enhancements

HALEY &
ALDRICH

- ♦ MGP Remedial Design
- ♦ Geotechnical Engineering
- ♦ Ground Modification Methods
- ♦ Seawall Evaluation
- ♦ Contractor Support Services

Leishmore Eng. Services

LES

- ♦ Environmental Construction
- ♦ Heavy Equipment Operation (Excavation, Trucking / Hauling)
- ♦ Waste Coordination / Disposal
- ♦ Laboratory Services
- ♦ Drilling Services





CH2MHILL


- ♦ Engineering Support
- ♦ Cost Estimate Review
- ♦ Peer Review
- ♦ Regulatory Support
- ♦ Constructability Review

Site Background

- Former MGP Operations (*MichCon Parcel*)
- Tire Manufacturing (*Uniroyal Parcel*)
- Ammonia Works (*Shared Parcel*)
- Foundry Operations (*Stove Works Parcel*)



NOTE: THIS DRAWING IS FOR REFERENCE ONLY AND IS NEITHER COMPLETE NOR TO EXACTING SCALE.



A0010022/P2945 DWN: DVS REV: 10/18/00 DVS CHK: EPH

FIGURE 1
REMEDATION PLAN/SITE
EAST JEFFERSON AT BELLE ISLE
DETROIT, MICHIGAN

The City has conducted several previous investigations, which have identified the following:

- Coal Tar
- Free Product, both LNAPL and DNAPL
- Mercury Venting to Surface Water
- Organics (BTEX, PCBs)

Objective:

July 3
Chicago Tribune
Ray Am

Design and Implement Interim Response Activities to Address Potential Threats to Safety, Health, and Environment, while Maximizing Redevelopment Potential of the Site.

Technical Approach

- Focused Feasibility Study (*90 Days*)
- Remedial Design
- Implementation/Engineering Oversight (*End of Year 1*)
- Operation & Maintenance (*Years 2-3*)

Focused Feasibility Study

- General Issues (Security, HASP, PR)
- Work Plans
 - Field Sampling Plan (w/ QA/QC)
 - Data Investigation Work Plan

Focused Feasibility Study

- **Additional Investigation**
 - Geophysical
 - Test Pits
 - Soil Borings/Sampling
 - Soil (Bench Testing)
 - Ground Water (GSI)
 - Tar/Product (Characterization)
 - River (GSI)
 - Seawall Inspection (GSI)
 - Product/Ground Water Recovery Pump Tests (NAPL, Organics)

Remedial Design

Remedial Design will Address:

- Mercury
- Coal Tar
- NAPLs
- Organics Above GSI

Anticipated Key Components Include:

- Excavation of Soil Impacted with Coal Tar to 10'
- Passive Collection Wells - NAPL
 - Including Pumping and Disposal
- Excavation and/or In-Situ Stabilization of Soil Impacted with Coal Tar Below 10'
- Barrier for Residual Coal Tar Below 10' by In-Situ Deep Soil Mixing
- Full-Scale Oxygen Injection System

Implementation/ Engineering Oversight

- Various Management Plans
- Performance Specifications
- Permitting
- Schedule
 - Implemented 1 Year from Notice to Proceed
- O&M will Extend to 2 Years from Date of Installation