

PALO ALTO

WASHINGTON, D.C.

75. file 1.13 Wahler
NEWPORT BEACH

**W.A. WAHLER
& ASSOCIATES**

P.O. BOX 10023 • 1023 CORPORATION WAY, PALO ALTO, CALIFORNIA 94303 • (415) 968-6250

March 17, 1976
Project 0886

Mr. Gerald Sneddon ✓
General Manager
Baker Industries, Corp.
P.O. Box 37
Conda, Idaho 83230

Subject: Reconstruction of the dike embankment near the southwest corner of Gypsum Pond No. 3 and construction of a new water control decant structure.

Dear Mr. Sneddon:

As we discussed with you on March 10, 1976, following our initial field inspection of the Baker waste disposal facilities, we feel that it would be very difficult to positively identify the cause of the recent dike failure near the southwest corner of Gypsum Pond No. 3. We suspect that the high free-water level in the pond was the principal contributing factor and we believe that if a suitable method of controlling and minimizing the free-water level is implemented, the overall stability of the entire dike embankment around Gypsum Pond No. 3 will be substantially improved. In this regard, we basically concur in principle with the decanting method proposed by your staff which essentially consists of constructing a conduit at the foundation level of the dike and providing the capability for periodically raising the upstream decant level as the gypsum tailings and free-water levels increase in the pond. This system should allow an operator to maintain a minimum free-water level, sufficient for the solids to settle out, but will preclude the buildup of unnecessary free-water storage. The proposed method is commonly and successfully used for controlling tailings pond levels by the mining industry throughout the world and, in most cases, has provided a safe and efficient means of operation. Although we have just started work on this project and are not completely familiar with all of the past history and problems at this facility, we have not discovered to date any apparent reasons

FH0028666

Mr. Gerald Sneddon
March 17, 1976
Page 2

why this system cannot be constructed and safely operated by Beker Industries at Soda Springs, provided that good engineering practices are employed in the construction of the facilities. In this regard, we are listing certain aspects of the construction which we consider important and which may require special attention:

Item 1: Due to the low pH of the gypsum tailings water and its tendency to chemically react with the local soils, any seepage from the pond constitutes an undesirable condition because of both environmental effects and possible alteration of engineering properties of the soil embankment and foundation. Therefore, we suggest that any portion of the impervious liner known to have been damaged by the recent dike failure be replaced. It is especially important that a good, lasting seal be accomplished between the impervious lining and the decant conduit.

Item 2: The contact between a conduit and an embankment or a foundation represents one of the more vulnerable areas with regard to the possibility of the occurrence of excessive seepage and piping of the fine-grained soils. We suggest that it may be prudent to assume that a leak could conceivably occur through the impervious liner and, based on this assumption, to design the conduit so that the seepage would be controlled. We, therefore, recommend that seepage cutoff collars be installed at selected intervals around the conduit, and that a stable filter material be placed in conjunction with the collars so as to minimize the possibility of piping along the conduit. It is equally important that special attention be given to the compaction of the material completely surrounding the conduit so that a firm contact is established. Conduit construction must be accomplished on an adequate foundation, carefully prepared to handle the anticipated loading conditions.

Item 3: Finally, for that portion of the dike which is to be reconstructed, we recommend that the dike embankment material be placed and compacted in accordance with acceptable standards such as those provided by the American Society of Testing Materials (ASTM), or by the American Association of State Highway Officials (AASHTO). Continuous inspection should be provided to see that these criteria are met.


Mr. Gerald Sneddon
March 17, 1976
Page 3

In summary, we conclude that there is no apparent reason why Pond No. 3 with an adjustable decant facility cannot be repaired and operated in a safe and efficient manner and at a minimal risk of major slope instability.

If you desire our specialized assistance in the final planning and construction of the repairs to Pond No. 3, please do not hesitate to notify us.

Very truly yours,

W. A. WAHLER & ASSOCIATES



Jack G. Wulff
Chief Engineer

JGW:etc

Enclosure

Copy of letter to:
Mr. Monty Marthus
Environmental Services Division
636 Pershing
Pocatello, Idaho 83201

W.A. WAHLER
& ASSOCIATES

FH0028668

Beker Industries Corp.

Box 37, Conda, Idaho 83230
Telephone: 208/547-4381, TWX 910-978-5768

8a

NO. 4 TAILINGS IMPOUNDMENT

Justification

At the end of the 1978 construction season, the embankments on the existing No. 3 Tailings Impoundment will be 50 feet high and will contain slime storage for one year. During the summer of 1979 these embankments could be raised to their ultimate height of 70 feet at a cost of \$2,500,000 and would yield only one additional year of storage. At that time a new tailings impoundment would have to be constructed.

By constructing No. 4 Tailings Impoundment during 1979 at a cost of \$2,400,000 with three years storage capacity, or 2 more years than building Stage IV on No. 3 Tailings Impoundment at the same cost, excluding the purchase price of the required land which would be required after constructing Stage IV anyway.

Scope of Work

The following work will have to be started during the last quarter of 1978 as indicated.

<u>Start</u>	<u>Complete</u>	<u>Description</u>
9/18/78	10/2/78	Aerial photograph the proposed site.
10/2/78	4/30/79	Acquire land at proposed site.
10/2/78	10/16/78	Perform preliminary land survey for design work.
10/16/78	12/29/78	Geotechnical field and lab tests.
10/16/78	2/26/79	Engineering design work on ditch relocation.

Total monies to be committed during 4th quarter.
(excluding land acquisition) -----\$50,000.





ESTIMATE SHEET

APPROVALS

PLANT MGR. _____

ENGINEERING MGR. _____

PRODUCTION MGR. _____

FH0028670



BEKER INDUSTRIES CORP.
CHARLES F. WHITE PLANT

DATE: 9 / 7 / 78

ESTIMATE SHEET

JOB TITLE: No. 4 Tailings Impoundment - Stage I

APPROVALS

A/E NO.: PROJECT NO.: 78-15-131

PLANT MGR. _____

DRAWING NO. SHEET 1 OF 1

ENGINEERING MGR. _____

PREPARED BY: J.B. Carpita

PRODUCTION MGR. _____

DESCRIPTION	QUANT	UNIT	USEFUL LIFE		TOTAL
			30 yr.	3 yr.	
SITE PREPARATION					
1. Land acquisition	350	Acres	\$650,000		\$650,000
2. Site investigation & soils testing	1	Lot	\$ 45,000		\$ 45,000
3. Engineering & field layout	1	Lot	\$ 35,000		\$ 35,000
4. Fencing	2.5	Miles	\$ 25,000		\$ 25,000
5. Grubbing & Stripping	500,000	Cu.Yd.	\$125,000		\$125,000
6. Access roads	3.0	Miles	\$ 70,000		\$ 70,000
7. Relocating farm ditches	1.5	Miles	\$ 30,000		\$ 30,000
Subtotal			\$980,000		\$980,000
EMBANKMENT CONSTRUCTION					
1. Earthwork (15 ft. high embankments)	400,000	Cu. Yd.		\$865,000	\$865,000
2. Slope Protection	40,000	Tons		\$ 75,000	\$ 75,000
3. Instrumentation	1	Lot		\$ 20,000	\$ 20,000
4. Engineering & inspection	1	Lot		\$ 60,000	\$ 60,000
Subtotal			-0-	\$1,020,000	\$1,020,000
MECHANICAL SYSTEMS					
1. Tailings piping	4,000	L.F.	\$375,000		\$375,000
2. Reclaim piping	6,000	L.F.	\$565,000		\$565,000
3. Pump & Barge modifications	1	Lot	\$ 25,000		\$ 25,000
4. Electrical	1	Lot	\$ 75,000		\$ 75,000
Subtotal			\$1,040,000	-0-	\$1,040,000
TOTAL ESTIMATED COSTS			\$2,020,000	\$1,020,000	\$3,040,000

FH0028671

Beker Industries Corp.

Box 37, Conda, Idaho 83230

Telephone: 208/547-4381, TWX 910-978-5768

NO. 4 TAILINGS IMPOUNDMENT

Justification

At the end of the 1978 construction season, the embankments on the existing No. 3 Tailings Impoundment will be 50 feet high and will contain slime storage for one year. During the summer of 1979 these embankments could be raised to their ultimate height of 70 feet at a cost of \$2,500,000 and would yield only one additional year of storage. At that time a new tailings impoundment would have to be constructed.

By constructing No. 4 Tailings Impoundment during 1979 at a cost of \$2,400,000 with three years storage capacity, or 2 more years than building Stage IV on No. 3 Tailings Impoundment at the same cost, excluding the purchase price of the required land which would be required after constructing Stage IV anyway.

Scope of Work

The following work will have to be started during the last quarter of 1978 as indicated.

<u>Start</u>	<u>Complete</u>	<u>Description</u>
9/18/78	10/2/78	Aerial photograph the proposed site.
10/2/78	4/30/79	Acquire land at proposed site.
10/2/78	10/16/78	Perform preliminary land survey for design work.
10/16/78	12/29/78	Geotechnical field and lab tests.
10/16/78	2/26/79	Engineering design work on ditch relocation.

Total monies to be committed during 4th quarter.
(excluding land acquisition) -----\$50,000.





ESTIMATE SHEET

APPROVALS

PLANT MGR. _____

ENGINEERING MGR. _____

PRODUCTION MGR. _____

FH0028673



BEKER INDUSTRIES CORP.
CHARLES F. WHITE PLANT

DATE: 9 / 7 / 78

ESTIMATE SHEET

JOB TITLE: No. 4 Tailings Impoundment - Stage I

APPROVALS

AFE NO.: PROJECT NO.: 78-15-131

PLANT MGR. _____

DRAWING NO. SHEET 1 OF 1

ENGINEERING MGR. _____


PREPARED BY: J.B. Carpita

PRODUCTION MGR. _____


DESCRIPTION	QUANT	UNIT	USEFUL LIFE		TOTAL
			30 yr.	3 yr.	
SITE PREPARATION					
1. Land acquisition	350	Acres	\$650,000		\$650,000
2. Site investigation & soils testing	1	Lot	\$ 45,000		\$ 45,000
3. Engineering & field layout	1	Lot	\$ 35,000		\$ 35,000
4. Fencing	2.5	Miles	\$ 25,000		\$ 25,000
5. Grubbing & Stripping	500,000	Cu.Yd.	\$125,000		\$125,000
6. Access roads	3.0	Miles	\$ 70,000		\$ 70,000
7. Relocating farm ditches	1.5	Miles	\$ 30,000		\$ 30,000
Subtotal			\$980,000		\$980,000
EMBANKMENT CONSTRUCTION					
1. Earthwork (15 ft. high embankments)	400,000	Cu. Yd.		\$865,000	\$865,000
2. Slope Protection	40,000	Tons		\$ 75,000	\$ 75,000
3. Instrumentation	1	Lot		\$ 20,000	\$ 20,000
4. Engineering & inspection	1	Lot		\$ 60,000	\$ 60,000
Subtotal			-0-	\$1,020,000	\$1,020,000
MECHANICAL SYSTEMS					
1. Tailings piping	4,000	L.F.	\$375,000		\$375,000
2. Reclaim piping	6,000	L.F.	\$565,000		\$565,000
3. Pump & Barge modifications	1	Lot	\$ 25,000		\$ 25,000
4. Electrical	1	Lot	\$ 75,000		\$ 75,000
Subtotal			\$1,040,000	-0-	\$1,040,000
TOTAL ESTIMATED COSTS			\$2,020,000	\$1,020,000	\$3,040,000

FH0028674

PROPOSED LOCATION OF
NO. 4 TAILINGS POND




BEKER BEKER INDUSTRIES CORP.
CHARLES F. WHITE PLANT



TOTAL LIFE - 30 YEARS OR 67.1 MILLION TONS OF ORE
 STAGE I LIFE - 3 YEARS OR 6.8 MILLION TONS OF ORE

NO. 4 TAILINGS IMPOUNDMENT - TYPICAL SECTION

BEKER BEKER INDUSTRIES CORP.
 CHARLES F. WHITE PLANT



THIS GAINING IS THE PROPERTY OF STEEL INDUSTRIES CORPORATION AND IS LENT TO THE MEMBERS FOR NO COMPENSATION. THE USE ONLY, AND IS SUBJECT TO REVOCATION UPON REQUEST AND SHALL NOT BE REPRODUCED, COPIED, LENT OR OTHERWISE USED OR OTHERWISE USED OR INDULGENT, FOR USE FOR ANY PURPOSES OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY LENT.

Beker Industries Corp.
Box 37, Conda, Idaho 83230
Telephone: 208/547-4381, TWX 910-978-5768

NO. 4 TAILINGS IMPOUNDMENT

Justification

At the end of the 1978 construction season, the embankments on the existing No. 3 Tailings Impoundment will be 50 feet high and will contain slime storage for one year. During the summer of 1979 these embankments could be raised to their ultimate height of 70 feet at a cost of \$2,500,000 and would yield only one additional year of storage. At that time a new tailings impoundment would have to be constructed.

By constructing No. 4 Tailings Impoundment during 1979 at a cost of \$2,400,000 with three years storage capacity, or 2 more years than building Stage IV on No. 3 Tailings Impoundment at the same cost, excluding the purchase price of the required land which would be required after constructing Stage IV anyway.

Scope of Work

The following work would have to be completed as indicated to take advantage of the cost savings of constructing No. 4 Tailings Impoundment during 1979.

Required
Completion Date


- | | |
|---------|---|
| 1-1-79 | 1. Acquire approximately 350 acres of land north of existing impoundments. |
| 4-1-79 | 2. Perform soil investigation, engineering design, and field layout of impoundment, and support facilities. |
| 7-1-79 | 3. Clear the land, reroute existing farm ditches, fence property, and construct access roads. |
| 10-1-79 | 4. Construct 15 feet high starter embankments, approximately 400,000 cubic yards, including slope protection and instrumentation to meet Dam Safety regulations. |
| 10-1-79 | 5. Install new tailings line from Wash Plant to southeast corner of No. 4 Tailings Impoundments. |
| 10-1-79 | 6. Install new reclaim water line from northwest corner of No. 4 Tailings Impoundment to existing reclaim water line at No. 5 Well House and use existing reclaim water pump to boost water to ore processing area. |
| 10-1-79 | 7. Modify existing reclaim barge and install new vertical reclaim water pump on the barge to reclaim water from No. 4 Tailings Impoundment, including new 13,800/480 V electrical power line. |

JC/jb




FH0028678

PROPOSED LOCATION OF
NO. 4 TAILINGS POND



BEKER BEKER INDUSTRIES CORP.
CHARLES F. WHITE PLANT



OCT 6, 1978

8131

3-1

1-98



OCT 6, 1978

8131

2-1,

8b-2



OCT. 6, 1978

8131

10-1


86-3

OCT. 6, 1978

8131

11-1





COPIES	PRINT RECORD					APPROVALS					REVISIONS					CDB RECORD					DATE
	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	
THIS DRAWING IS THE PROPERTY OF BAKER INDUSTRIES CORP. AND IS NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF BAKER INDUSTRIES CORP. ANY UNAUTHORIZED REPRODUCTION OR COPIING OF THIS DRAWING IS A VIOLATION OF THE PATENT RIGHTS OF BAKER INDUSTRIES CORP. AND IS SUBJECT TO PROSECUTION.																					

BAKER INDUSTRIES CORP.
 10000 BAKER BLVD. (PHILADELPHIA) 19104
 10000 BAKER BLVD. (PHILADELPHIA) 19104
 10000 BAKER BLVD. (PHILADELPHIA) 19104