



**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Mr. James Filippini  
Mr. Douglas Lamb  
Water Division Compliance Branch  
United States Environmental Protection Agency, Region V  
77 West Jackson Boulevard (WC-15J)  
Chicago, Illinois 60604-3590

September 26, 2016  
PJ/DW

**Subject:** Annual Dock Wall Observation and Repair  
Consent Decree – Case No. 2:96-CV-96-RL-1  
ArcelorMittal Burns Harbor LLC

Dear Messrs. Filippini and Lamb:

Attachment 1 is the summary report of the annual dock wall inspection for 2016. This document summarizes the results of the annual dock wall observation that was conducted on August 23, 30, and September 6, 2016, by Weaver Consultants Group, contractor to ArcelorMittal Burns Harbor, as required by Paragraph 21 of the subject decree.

During the annual observations, twenty five (25) locations were found along the dock wall with discernible discharges of flowing water. Notification regarding these findings was made via e-mail to Ms. Susan Prout (EPA Region V, Office of Regional Counsel) by T. E. Kirk on August 23, and September 7, 2016. Originally, 26 discharges were reported. However, the discharge recorded as #5 did not have a discernable discharge that could be sampled. As a result, no information is available for #5. It has been marked and will be repaired with along with the discernable discharges.

All but one of the locations were found in the coffer dam section of the dock wall. The height above the Lake Michigan level and the estimated flow from each location are noted in Attachment 1.

Samples were obtained from all locations and submitted to a contract analytical laboratory for nitrogen-ammonia analysis. The reports of these analyses are provided in Attachment 2. The results are also summarized in Attachment 1 and used to estimate the amount of ammonia discharged, on a daily basis, from these locations. Digital photographs of each of the locations were also obtained and are provided in Attachment 3.



Repairs have been contracted and are expected to begin by mid-October. Due to heavy boat traffic, an estimated date of completion of repairs is not yet available. Photographs of the locations after repair/sealing will be provided in a separate report.

No one particular cause for the discharges was identified. Because almost all of the discharges were observed along the coffer dam section of the harbor wall and the nitrogen-ammonia concentrations of most of the discharges are well below the concentration of the groundwater being captured by the dewatering well system (i.e., average of 6.7 mg/L for the previous 12 months), it is surmised that these concrete cellular revetments were discharging accumulated stormwater runoff that had inadvertently seeped through the caps of these structures. Therefore, the source of the water is not groundwater that is adequately being controlled by the dewatering well system. Based on the ammonia concentrations and estimated flow rates summarized in Attachment 1, approximately sixty seven one hundredths of a pound per day (0.67 lbs/day) of ammonia is being discharged to the harbor from all 8 locations. Notwithstanding, Burns Harbor has responded as quickly as possible to the identification of the locations in order to timely minimize and/or eliminate any potential impact.

If there are any questions concerning this matter, please contact T. E. Kirk or me at (219) 787-2712.

I certify under penalty of law that I have personally examined and am familiar with the information submitted herein and that I have made a diligent inquiry of those individuals immediately responsible for obtaining the information and that to the best of my knowledge and belief, the information submitted herewith is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Very truly yours,

A handwritten signature in blue ink, appearing to read 'R. A. Maciel'.

R. A. Maciel, Manager  
Environmental Management Department

Attachments

ArcelorMittal Burns Harbor, LLC  
Annual Dock Wall Observation  
Consent Decree – Case No. 2:96-CV-96-RL-1

Attachment 1 – Summary Report of the 2016 Annual Dock Wall Inspection

ArcelorMittal Burns Harbor, LLC  
August 23, 30, and September 6, 2016 Dock Wall Inspection  
Performed by: Weaver Boos Consultants

<b>ID Number</b>	<b>Height Above Water (feet)</b>	<b>Estimated Flow Rate (Liters/minute)</b>	<b>Estimated Flow (Gal/Min)</b>	<b>Ammonia Concentration* (mg/L)</b>	<b>Ammonia Discharge (Pounds/day)</b>	<b>Date of Repair</b>
16-1	5	0.14	0.04	0.66	<0.001	TBD
16-2	3	0.1	0.03	5.4	0.002	TBD
16-3	5	0.08	0.02	2.4	0.001	TBD
16-4	5	0.8	0.02	5.2	0.013	TBD
16-6	2	1.5	0.40	2.7	0.013	TBD
16-7	5	8	2.11	2.4	0.061	TBD
16-8	0.5	11.36	3.00	2.8	0.101	TBD
16-9	5	2.5	0.66	2.5	0.020	TBD
16-10	5	13	3.43	2.2	0.091	TBD
16-11	3.5	2.5	0.66	1	1.008	TBD
16-12	3.5	39	10.30	1.1	0.136	TBD
16-13	3.5	21.5	5.68	1.2	0.082	TBD
16-14	4.5	3.7	0.98	1.3	0.015	TBD
16-15	5	15.14	4.00	0.41	0.020	TBD
16-16	5	0.12	0.03	1.7	0.001	TBD
16-17	4.5	2.28	0.60	1.2	0.009	TBD
16-18	2.5	0.6	0.16	0.25	<0.001	TBD
16-19	2.5	0.28	0.07	0.6	0.001	TBD
16-20	2.5	0.88	0.23	0.45	0.001	TBD
16-21	3.5	0.88	0.23	0.53	0.001	TBD
16-22	5	0.12	0.03	0.33	<0.001	TBD
16-23	3.5	2	0.53	2.7	0.017	TBD
16-24	5	0.24	0.06	1.9	0.001	TBD
16-25	4	3.79	1.00	5.0	0.060	TBD
16-26	4	0.88	0.23	4.8	0.013	TBD

**Total Potential Ammonia Discharge (pounds per day) from all locations: 0.67**

\* Results reported are the larger of the sample and duplicate analysis.

ArcelorMittal Burns Harbor, LLC  
Annual Dock Wall Observation  
Consent Decree – Case No. 2:96-CV-96-RL-1

Attachment 2 – Nitrogen Ammonia Analytical Results



August 30, 2016

Arcelor Mittal USA, Inc.  
250 W US Highway 12  
Burns Harbor, IN 46304-9745

Work Order No.: 16H1697

Re: Dock Wall Inspection

Dear Teri Kirk:

Microbac Laboratories, Inc. - Chicagoland Division received 8 sample(s) on 8/24/2016 9:35:00AM for the analyses presented in the following report as Work Order 16H1697.

The enclosed results were obtained from and are applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report have been reviewed and meet the applicable project specific and certification specific requirements, unless otherwise noted. A qualifications page is included in this report and lists the programs under which Microbac maintains certification.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories.

We appreciate the opportunity to service your analytical needs. If you have any questions, please contact your project manager. For any feedback, please contact Robert Crookston, Managing Director, at [robert.crookston@microbac.com](mailto:robert.crookston@microbac.com).

Sincerely,  
Microbac Laboratories, Inc.

Carey Gadzala  
Project Manager

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

**WORK ORDER SAMPLE SUMMARY****Date:** *Tuesday, August 30, 2016***Client:** Arcelor Mittal USA, Inc.**Project:** Dock Wall Inspection**Lab Order:** 16H1697

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
16H1697-01	16-1		08/23/2016 09:02	8/24/2016 9:35:00AM
16H1697-02	16-2		08/23/2016 09:50	8/24/2016 9:35:00AM
16H1697-03	16-3		08/23/2016 12:26	8/24/2016 9:35:00AM
16H1697-04	16-4		08/23/2016 13:35	8/24/2016 9:35:00AM
16H1697-05	16-1D		08/23/2016 09:02	8/24/2016 9:35:00AM
16H1697-06	16-2D		08/23/2016 09:50	8/24/2016 9:35:00AM
16H1697-07	16-3D		08/23/2016 12:26	8/24/2016 9:35:00AM
16H1697-08	16-4D		08/23/2016 13:35	8/24/2016 9:35:00AM

[Microbac Laboratories, Inc.](#)250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

## Analytical Results

Date: Tuesday, August 30, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H1697-01
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/23/2016 9:02
<b>Client Sample ID:</b>	16-1	<b>Received:</b>	08/24/2016 9:35
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF								
Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	0.64	0.10		mg/L	1	08/29/2016 11:07



## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.

**Client Project:** Dock Wall Inspection

**Client Sample ID:** 16-2

**Sample Description:**

**Matrix:** Aqueous

**Work Order/ID:** 16H1697-02

**Sampled:** 08/23/2016 9:50

**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
<p>Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF</p> <p>Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25</p>								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	5.4	0.10		mg/L	1	08/29/2016 11:12

## Analytical Results

Date: Tuesday, August 30, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H1697-03
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/23/2016 12:26
<b>Client Sample ID:</b>	16-3	<b>Received:</b>	08/24/2016 9:35
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0      Analyst: GRIEFF Prep Method: Aqueous Ammonia Distillation      Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	2.4	0.10		mg/L	1	08/29/2016 11:14

## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.  
**Client Project:** Dock Wall Inspection  
**Client Sample ID:** 16-4  
**Sample Description:**  
**Matrix:** Aqueous

**Work Order/ID:** 16H1697-04  
**Sampled:** 08/23/2016 13:35  
**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	4.8	0.10		mg/L	1	08/29/2016 11:16

## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.  
**Client Project:** Dock Wall Inspection  
**Client Sample ID:** 16-1D  
**Sample Description:**  
**Matrix:** Aqueous

**Work Order/ID:** 16H1697-05  
**Sampled:** 08/23/2016 9:02  
**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	0.66	0.10		mg/L	1	08/29/2016 11:18

## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.

**Client Project:** Dock Wall Inspection

**Client Sample ID:** 16-2D

**Sample Description:**

**Matrix:** Aqueous

**Work Order/ID:** 16H1697-06

**Sampled:** 08/23/2016 9:50

**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
<p>Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF</p> <p>Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25</p>								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	5.1	0.10		mg/L	1	08/29/2016 11:24

## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.  
**Client Project:** Dock Wall Inspection  
**Client Sample ID:** 16-3D  
**Sample Description:**  
**Matrix:** Aqueous

**Work Order/ID:** 16H1697-07  
**Sampled:** 08/23/2016 12:26  
**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0 Analyst: GRIEFF Prep Method: Aqueous Ammonia Distillation Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	2.4	0.10		mg/L	1	08/29/2016 11:26

## Analytical Results

**Date:** Tuesday, August 30, 2016

**Client:** Arcelor Mittal USA, Inc.  
**Client Project:** Dock Wall Inspection  
**Client Sample ID:** 16-4D  
**Sample Description:**  
**Matrix:** Aqueous

**Work Order/ID:** 16H1697-08  
**Sampled:** 08/23/2016 13:35  
**Received:** 08/24/2016 9:35

Analyses	Certs	AT	Result	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0      Analyst: GRIEFF Prep Method: Aqueous Ammonia Distillation      Prep Date/Time: 08/29/2016 08:25								
<b>Nitrogen, Ammonia as N</b>								
Nitrogen, Ammonia (As N)	di	A	5.2	0.10		mg/L	1	08/29/2016 11:28

**FLAGS, FOOTNOTES AND ABBREVIATIONS (as needed)**

B = Detected in the associated method Blank at a concentration above the routine RL  
 b- = Detected in the associated method Blank at a concentration greater than 2.2 times the MDL  
 b\* = Detected in the associated method Blank at a concentration greater than half the RL  
 CFU = Colony forming units  
 D = Dilution performed on sample  
 DF = Dilution Factor  
 g = Gram  
 E = Value above quantitation range  
 H = Analyte was prepared and/or analyzed outside of the analytical method holding time  
 I = Matrix Interference  
 J = Analyte concentration detected between RL and MDL (Metals / Organics)  
 LOD = Limit of Detection  
 LOQ = Limit of Quantitation  
 m3 = Meters cubed  
 MDL = Method Detection Limit  
 mg/Kg = Milligrams per Kilogram (ppm)  
 mg/L = Milligrams per Liter (ppm)  
 NA = Not Analyzed  
 ND = Not Detected at the Reporting Limit (or the Method Detection Limit, if used)  
 NR = Not Recovered  
 R = RPD outside accepted recovery limits  
 RL = Reporting Limit  
 S = Spike recovery outside recovery limits  
 Surr = Surrogate  
 U = Undetected  
 > = Greater than  
 < = Less than  
 % = Percent  
 \* = Result exceeds project specific limits

**ANALYTE TYPES: (AT)**

A,B = Target Analyte  
 I = Internal Standard  
 M = Summation Analyte  
 S = Surrogate  
 T = Tentatively Identified Compound (TIC, concentration estimated)

**QC SAMPLE IDENTIFICATIONS**

BLK = Method Blank	ICSA = Interference Check Standard "A"
DUP = Method Duplicate	ICSAB = Interference Check Standard "AB"
BS = Method Blank Spike	BSD = Method Blank Spike Duplicate
MS = Matrix Spike	MSD = Matrix Spike Duplicate
ICB = Initial Calibration Blank	ICV = Initial Calibration Verification
CCB = Continuing Calibration Blank	CCV = Continuing Calibration Verification
CRL = Client Required Reporting Limit	OPR = Ongoing Precision and Recovery Standard
PDS = Post Digestion Spike	SD = Serial Dilution
QCS = Quality Control Standard	

**CERTIFICATIONS (Certs)**

*Below is a list of certifications maintained by the Microbac Merrillville Laboratory. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. Complete lists of individual analytes pursuant to each certification below are available upon request.*

- <sup>d</sup> Illinois EPA drinking water, wastewater and solid waste analysis (#200064)
- <sup>i</sup> Kansas Dept Health & Env. NELAP (#E-10397)





## COOLER INSPECTION

Client Name: Arcelor Mittal USA, Inc.

Work Order Number: 16H1697

Checklist completed by: 8/24/2016 10:16:00AM | Nicole Rainwater

Date: Tuesday, August 30, 2016

Date/Time Received: 08/24/2016 09:35

Received by: Nicole Rainwater

Reviewed by: 8/24/2016 | KAZ

Carrier Name: Microbac

Cooler ID: Default Cooler

Container/Temp Blank Temperature: 3.5° C

After-Hour Arrival?	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Shipping container/cooler in good condition?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input type="checkbox"/>
Custody seals intact on shipping container/cooler?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
Custody seals intact on sample containers?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
COC present?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient client identification?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient sample collector information?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included a sample description?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC agrees with sample labels?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate matrix?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included date of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included time of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate number of containers?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples in proper container/bottle?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sample containers intact?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sufficient sample volume for indicated test?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
All samples received within holding time?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
If the samples are preserved, are the preservatives identified?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	

If No, adjusted by? \_\_\_\_\_

COC included the requested analyses?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC signed when relinquished and received?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples received on ice?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples properly preserved?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Voa vials for aqueous samples have zero headspace?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	No VOA vials submitted <input checked="" type="checkbox"/>

Cooler Comments: \_\_\_\_\_

ANY "NO" EVALUATION (excluding After-Hour Receipt) REQUIRES CLIENT NOTIFICATION.

Sample ID	Client Sample ID	Comments
16H1697-01	16-1	
16H1697-02	16-2	
16H1697-03	16-3	
16H1697-04	16-4	
16H1697-05	16-1D	
16H1697-06	16-2D	
16H1697-07	16-3D	
16H1697-08	16-4D	

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

**MICROBAC®**

Samples ☐ 250 West 84th Drive  
 Submitted to: Merrillville, IN 46410  
 Tel: 219-769-8378  
 Fax: 219-769-1664

☐ 5713 West 85th Street  
 Indianapolis, IN 46278  
 Tel: 317-872-1375  
 Fax: 317-872-1379

**Chain of Custody Record****Number 136490***Instructions on back*

Client Name <b>ArcelorMittal</b>	Project <b>Dock Wall Inspection</b>	Turnaround Time	Report Type
Address <b>250 West US Hwy 12</b>	Location	<input checked="" type="checkbox"/> Routine (5 to 7 business days)	<input checked="" type="checkbox"/> Results Only
City, State, Zip <b>Burns Harbor, IN</b>	PO #	<input type="checkbox"/> RUSH* (notify lab)	<input type="checkbox"/> Level III <input type="checkbox"/> Level II
Contact <b>Teri Kirk</b>	Compliance Monitoring? <input type="checkbox"/> Yes <input type="checkbox"/> No	(needed by)	<input type="checkbox"/> Level IV <input type="checkbox"/> Level I
Telephone #	(1) Agency/Program		<input type="checkbox"/> EDD
Sampled by (PRINT) <b>Patty Kastro</b>		Sampler Signature <b>Patty Kastro</b>	
Send Report via <input type="checkbox"/> Mail <input type="checkbox"/> Telephone <input type="checkbox"/> Fax (fax #)		Sampler Phone #	
		E-mail (address)	

\* Matrix Types: Soil/Solid (S), Sludge, Oil, Wipe, Drinking Water (DW), Groundwater (GW), Surface Water (SW), Waste Water (WW), Other (specify)

\*\* Preservative Types: (1) HNO<sub>3</sub>, (2) H<sub>2</sub>SO<sub>4</sub>, (3) HCl, (4) NaOH, (5) Zinc Acetate, (6) Methanol, (7) Sodium Bisulfate, (8) Sodium Thiosulfate, (9) Hexane, (U) Unpreserved

Client Sample ID	Matrix*	Grab	Composite	Filtered	Date Collected	Time Collected	No. of Containers	Requested Analyses → Preservative Types ** ↓	Ammonia	For Lab
16-1	GW	✓			8/23/16	0902	1	H2SO4	✓	1641697
16-2	GW	✓			8/23/16	0950	1		✓	-01
16-3	GW	✓			8/23/16	1224	1		✓	-02
16-4	GW	✓			8/23/16	1335	1		✓	-03
16-1D	GW	✗			8/23/16	0902	1		✓	-04
16-2D	GW	✗			8/23/16	0950	1		✓	-05
16-3D	GW	✓			8/23/16	1224	1		✓	-06
16-4D	GW	✓			8/23/16	1335	1		✓	-07
										-08

Possible Hazard Identification ☐ Hazardous ☐ Non-Hazardous ☐ Radioactive Sample Disposition ☒ Dispose as appropriate ☐ Return ☐ Archive

Comments	To be completed by Microbac			
	Temperature Upon Receipt (°C) <b>4.5-1.0=3.5</b>	Relinquished By (signature) <b>Patty Kastro</b>	Date/Time <b>8/23/16 3:17 pm</b>	Received By (signature) <b>[Signature]</b>
	Samples Received on Ice? <b>Yes</b> No N/A	Relinquished By (signature) <b>[Signature]</b>	Date/Time <b>8/24/16 8:00 am</b>	Received By (signature) <b>Ron Dummer</b>
	Custody Seals Intact? <b>Yes</b> No <b>N/A</b>	Relinquished By (signature) <b>Ron Dummer</b>	Date/Time <b>8/24/16 9:35</b>	Received By (signature) <b>Nicole Remato</b>

Page 1 of 1 0935





September 8, 2016

Arcelor Mittal USA, Inc.  
250 W US Highway 12  
Burns Harbor, IN 46304-9745

Work Order No.: 16H2149

Re: Dock Wall Inspection

Dear Teri Kirk:

Microbac Laboratories, Inc. - Chicagoland Division received 20 sample(s) on 8/31/2016 9:40:00AM for the analyses presented in the following report as Work Order 16H2149.

The enclosed results were obtained from and are applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report have been reviewed and meet the applicable project specific and certification specific requirements, unless otherwise noted. A qualifications page is included in this report and lists the programs under which Microbac maintains certification.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories.

We appreciate the opportunity to service your analytical needs. If you have any questions, please contact your project manager. For any feedback, please contact Robert Crookston, Managing Director, at [robert.crookston@microbac.com](mailto:robert.crookston@microbac.com).

Sincerely,  
Microbac Laboratories, Inc.

A handwritten signature in black ink that reads "Carey Gadzala". The signature is fluid and cursive, with the first name "Carey" and last name "Gadzala" clearly distinguishable.

Carey Gadzala  
Project Manager

[Microbac Laboratories, Inc.](http://www.microbac.com)

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

**WORK ORDER SAMPLE SUMMARY****Date:** *Thursday, September 8, 2016***Client:** Arcelor Mittal USA, Inc.**Project:** Dock Wall Inspection**Lab Order:** 16H2149

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
16H2149-01	16-6		08/30/2016 10:05	8/31/2016 9:40:00AM
16H2149-02	16-6D		08/30/2016 10:20	8/31/2016 9:40:00AM
16H2149-03	16-7		08/30/2016 10:35	8/31/2016 9:40:00AM
16H2149-04	16-7D		08/30/2016 10:42	8/31/2016 9:40:00AM
16H2149-05	16-8		08/30/2016 10:55	8/31/2016 9:40:00AM
16H2149-06	16-8D		08/30/2016 11:00	8/31/2016 9:40:00AM
16H2149-07	16-9		08/30/2016 11:20	8/31/2016 9:40:00AM
16H2149-08	16-9D		08/30/2016 11:27	8/31/2016 9:40:00AM
16H2149-09	16-10		08/30/2016 11:47	8/31/2016 9:40:00AM
16H2149-10	16-10D		08/30/2016 11:55	8/31/2016 9:40:00AM
16H2149-11	16-11		08/30/2016 12:06	8/31/2016 9:40:00AM
16H2149-12	16-11D		08/30/2016 12:08	8/31/2016 9:40:00AM
16H2149-13	16-12		08/30/2016 12:22	8/31/2016 9:40:00AM
16H2149-14	16-12D		08/30/2016 12:24	8/31/2016 9:40:00AM
16H2149-15	16-13		08/30/2016 12:30	8/31/2016 9:40:00AM
16H2149-16	16-13D		08/30/2016 12:32	8/31/2016 9:40:00AM
16H2149-17	16-14		08/30/2016 12:42	8/31/2016 9:40:00AM
16H2149-18	16-14D		08/30/2016 12:50	8/31/2016 9:40:00AM
16H2149-19	16-15		08/30/2016 13:05	8/31/2016 9:40:00AM
16H2149-20	16-15D		08/30/2016 13:12	8/31/2016 9:40:00AM

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-01
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 10:05
<b>Client Sample ID:</b>	16-6	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/05/2016 09:05				
Nitrogen, Ammonia (As N)	ei	A	2.9	0.054	0.10		mg/L	1	09/06/2016 11:41

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-02
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 10:20
<b>Client Sample ID:</b>	16-6D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/05/2016 09:05				
Nitrogen, Ammonia (As N)	ei	A	2.7	0.054	0.10		mg/L	1	09/06/2016 11:47



## Analytical Results

Date: Thursday, September 8, 2016

Client: Arcelor Mittal USA, Inc.

Client Project: Dock Wall Inspection

Client Sample ID: 16-7

Sample Description:

Matrix: Aqueous

Work Order/ID: 16H2149-03

Sampled: 08/30/2016 10:35

Received: 08/31/2016 9:40

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/05/2016 09:05				
Nitrogen, Ammonia (As N)	ei	A	2.3	0.054	0.10		mg/L	1	09/06/2016 11:49

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-04
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 10:42
<b>Client Sample ID:</b>	16-7D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.4	0.054	0.10		mg/L	1	09/06/2016 11:51



## Analytical Results

**Date:** Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-05
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 10:55
<b>Client Sample ID:</b>	16-8	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.8	0.054	0.10		mg/L	1	09/06/2016 11:52



## Analytical Results

Date: Thursday, September 8, 2016

Client: Arcelor Mittal USA, Inc.

Client Project: Dock Wall Inspection

Client Sample ID: 16-8D

Sample Description:

Matrix: Aqueous

Work Order/ID: 16H2149-06

Sampled: 08/30/2016 11:00

Received: 08/31/2016 9:40

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.7	0.054	0.10		mg/L	1	09/06/2016 11:58

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-07
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 11:20
<b>Client Sample ID:</b>	16-9	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.2	0.054	0.10		mg/L	1	09/06/2016 12:04

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-08
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 11:27
<b>Client Sample ID:</b>	16-9D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.5	0.054	0.10		mg/L	1	09/06/2016 12:06

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-09
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 11:47
<b>Client Sample ID:</b>	16-10	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.1	0.054	0.10		mg/L	1	09/06/2016 12:08



## Analytical Results

Date: Thursday, September 8, 2016

Client: Arcelor Mittal USA, Inc.

Client Project: Dock Wall Inspection

Client Sample ID: 16-10D

Sample Description:

Matrix: Aqueous

Work Order/ID: 16H2149-10

Sampled: 08/30/2016 11:55

Received: 08/31/2016 9:40

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	2.2	0.054	0.10		mg/L	1	09/06/2016 12:10

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-11
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:06
<b>Client Sample ID:</b>	16-11	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	0.94	0.054	0.10		mg/L	1	09/06/2016 12:12



## Analytical Results

Date: Thursday, September 8, 2016

Client: Arcelor Mittal USA, Inc.

Client Project: Dock Wall Inspection

Client Sample ID: 16-11D

Sample Description:

Matrix: Aqueous

Work Order/ID: 16H2149-12

Sampled: 08/30/2016 12:08

Received: 08/31/2016 9:40

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	1.0	0.054	0.10		mg/L	1	09/06/2016 12:14

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com



## Analytical Results

**Date:** Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-13
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:22
<b>Client Sample ID:</b>	16-12	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	0.91	0.054	0.10		mg/L	1	09/06/2016 12:16

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-14
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:24
<b>Client Sample ID:</b>	16-12D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	1.1	0.054	0.10		mg/L	1	09/06/2016 12:18

## Analytical Results

**Date:** Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-15
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:30
<b>Client Sample ID:</b>	16-13	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	1.0	0.054	0.10		mg/L	1	09/06/2016 12:20

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-16
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:32
<b>Client Sample ID:</b>	16-13D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	1.2	0.054	0.10		mg/L	1	09/06/2016 12:22

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-17
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:42
<b>Client Sample ID:</b>	16-14	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 07:28				
Nitrogen, Ammonia (As N)	ei	A	1.3	0.054	0.10		mg/L	1	09/06/2016 12:28

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-18
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 12:50
<b>Client Sample ID:</b>	16-14D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/06/2016 11:35				
Nitrogen, Ammonia (As N)	ei	A	0.90	0.054	0.10		mg/L	1	09/06/2016 13:01

## Analytical Results

Date: Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-19
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 13:05
<b>Client Sample ID:</b>	16-15	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/07/2016 07:55				
Nitrogen, Ammonia (As N)	ei	A	0.41	0.054	0.10		mg/L	1	09/08/2016 11:26

## Analytical Results

**Date:** Thursday, September 8, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16H2149-20
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	08/30/2016 13:12
<b>Client Sample ID:</b>	16-15D	<b>Received:</b>	08/31/2016 9:40
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/07/2016 07:55				
Nitrogen, Ammonia (As N)	ei	A	0.40	0.054	0.10		mg/L	1	09/08/2016 11:31



**FLAGS, FOOTNOTES AND ABBREVIATIONS (as needed)**

B = Detected in the associated method Blank at a concentration above the routine RL  
 b- = Detected in the associated method Blank at a concentration greater than 2.2 times the MDL  
 b\* = Detected in the associated method Blank at a concentration greater than half the RL  
 CFU = Colony forming units  
 D = Dilution performed on sample  
 DF = Dilution Factor  
 g = Gram  
 E = Value above quantitation range  
 H = Analyte was prepared and/or analyzed outside of the analytical method holding time  
 I = Matrix Interference  
 J = Analyte concentration detected between RL and MDL (Metals / Organics)  
 LOD = Limit of Detection  
 LOQ = Limit of Quantitation  
 m3 = Meters cubed  
 MDL = Method Detection Limit  
 mg/Kg = Milligrams per Kilogram (ppm)  
 mg/L = Milligrams per Liter (ppm)  
 NA = Not Analyzed  
 ND = Not Detected at the Reporting Limit (or the Method Detection Limit, if used)  
 NR = Not Recovered  
 R = RPD outside accepted recovery limits  
 RL = Reporting Limit  
 S = Spike recovery outside recovery limits  
 Surr = Surrogate  
 U = Undetected  
 > = Greater than  
 < = Less than  
 % = Percent  
 \* = Result exceeds project specific limits

**ANALYTE TYPES: (AT)**

A,B = Target Analyte  
 I = Internal Standard  
 M = Summation Analyte  
 S = Surrogate  
 T = Tentatively Identified Compound (TIC, concentration estimated)

**QC SAMPLE IDENTIFICATIONS**

BLK = Method Blank	ICSA = Interference Check Standard "A"
DUP = Method Duplicate	ICSAB = Interference Check Standard "AB"
BS = Method Blank Spike	BSD = Method Blank Spike Duplicate
MS = Matrix Spike	MSD = Matrix Spike Duplicate
ICB = Initial Calibration Blank	ICV = Initial Calibration Verification
CCB = Continuing Calibration Blank	CCV = Continuing Calibration Verification
CRL = Client Required Reporting Limit	OPR = Ongoing Precision and Recovery Standard
PDS = Post Digestion Spike	SD = Serial Dilution
QCS = Quality Control Standard	

**CERTIFICATIONS (Certs)**

*Below is a list of certifications maintained by the Microbac Merrillville Laboratory. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. Complete lists of individual analytes pursuant to each certification below are available upon request.*

- <sup>d</sup> Illinois EPA drinking water, wastewater and solid waste analysis (#200064)
- <sup>i</sup> Kansas Dept Health & Env. NELAP (#E-10397)



## COOLER INSPECTION

Client Name: Arcelor Mittal USA, Inc.

Work Order Number: 16H2149

Checklist completed by: 8/31/2016 10:55:00AM Dave Bryant

Date: Thursday, September 8, 2016

Date/Time Received: 08/31/2016 09:40

Received by: Nicole Rainwater

Reviewed by: 8/31/2016 CAG

Carrier Name: Microbac

Cooler ID: Default Cooler

Container/Temp Blank Temperature: 0.5° C

After-Hour Arrival?	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Shipping container/cooler in good condition?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input type="checkbox"/>
Custody seals intact on shipping container/cooler?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
Custody seals intact on sample containers?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
COC present?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient client identification?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient sample collector information?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included a sample description?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC agrees with sample labels?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate matrix?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included date of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included time of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate number of containers?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples in proper container/bottle?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sample containers intact?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sufficient sample volume for indicated test?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
All samples received within holding time?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
If the samples are preserved, are the preservatives identified?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	

If No, adjusted by? \_\_\_\_\_

COC included the requested analyses?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC signed when relinquished and received?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples received on ice?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples properly preserved?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Voa vials for aqueous samples have zero headspace?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	No VOA vials submitted <input checked="" type="checkbox"/>

Cooler Comments: \_\_\_\_\_

ANY "NO" EVALUATION (excluding After-Hour Receipt) REQUIRES CLIENT NOTIFICATION.

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

Sample ID	Client Sample ID	Comments
16H2149-01	16-6	
16H2149-02	16-6D	
16H2149-03	16-7	
16H2149-04	16-7D	
16H2149-05	16-8	
16H2149-06	16-8D	
16H2149-07	16-9	
16H2149-08	16-9D	
16H2149-09	16-10	
16H2149-10	16-10D	
16H2149-11	16-11	
16H2149-12	16-11D	
16H2149-13	16-12	
16H2149-14	16-12D	
16H2149-15	16-13	
16H2149-16	16-13D	
16H2149-17	16-14	
16H2149-18	16-14D	
16H2149-19	16-15	
16H2149-20	16-15D	

**MICROBAC**

Samples Submitted to: ☒ 250 West 84th Drive  
Merrillville, IN 46410  
Tel: 219-769-8378  
Fax: 219-769-1664

☐ 5713 West 85th Street  
Indianapolis, IN 46278  
Tel: 317-872-1375  
Fax: 317-872-1379

**Chain of Custody Record**

**Number 136081**

Instructions on back

Project <u>Dock Wall Inspection</u>		Turnaround Time	Report Type
Location		<input checked="" type="checkbox"/> Routine (5 to 7 business days)	<input checked="" type="checkbox"/> Results Only <input type="checkbox"/> Level II
PO #		<input type="checkbox"/> RUSH* (notify lab)	<input type="checkbox"/> Level III <input type="checkbox"/> Level III CLP-like
Compliance Monitoring? <input type="checkbox"/> Yes <input type="checkbox"/> No		(needed by)	<input type="checkbox"/> Level IV <input type="checkbox"/> Level IV CLP-like
(1) Agency/Program			<input type="checkbox"/> EDD

(PRINT) David Ekkehl Sampler Signature [Signature] Sampler Phone # 219 808 9099

via ☐ Mail ☐ Telephone ☐ Fax (fax #) ☒ e-mail (address)

\* Matrix Types: Soil/Solid (S), Sludge, Oil, Wipe, Drinking Water (DW), Groundwater (GW), Surface Water (SW), Waste Water (WW), Other (specify)

Preservative Types: (1) HNO<sub>3</sub>, (2) H<sub>2</sub>SO<sub>4</sub>, (3) HCl, (4) NaOH, (5) Zinc Acetate, (6) Methanol, (7) Sodium Bisulfate, (8) Sodium Thiosulfate, (9) Hexane, (U) Unpreserved

Client Sample ID	Matrix*	Grab	Composite	Filtered	Date Collected	Time Collected	No. of Containers	Requested Analyses → Preservative Types ** ↓	For Lab Use Only									
16-6	GW	X			8-30-16	10:05A	1	H <sub>2</sub> SO <sub>4</sub>										16H2149
16-6A						10:26A	1											-01
16-7						10:35A	1											-02
16-7D						10:42A	1											-03
16-8						10:55A	1											-04
16-8D						11:08A	1											-05
16-9						11:20A	1											-06
16-9D						11:27A	1											-07
16-10						11:47A	1											-08
16-10D						11:55A	1											-09
																		-10

Possible Hazard Identification ☐ Hazardous ☐ Non-Hazardous ☐ Radioactive

Sample Disposition ☐ Dispose as appropriate ☐ Return ☐ Archive

Comments	To be completed by Microbac		Relinquished By (signature)				Date/Time		Received By (signature)		Date/Time	
	Temperature Upon Receipt (°C)		10-0.5 = 0.5		[Signature]		8-30-16 2:15P		[Signature]		8/30/16 2:15pm	
	Samples Received on Ice?		Yes No N/A		[Signature]		8/31/16 8:00 am		[Signature]		8/31/16 0800	
	Custody Seals Intact?		Yes No N/A		[Signature]		8/31/16 0940		[Signature]		8/31/16	



Samples Submitted to: 250 West 84th Drive  
Merrillville, IN 46410  
Tel: 219-769-8378  
Fax: 219-769-1664

☐ 5713 West 85th Street  
Indianapolis, IN 46278  
Tel: 317-872-1375  
Fax: 317-872-1379

# Chain of Custody Record

Number **136079**

Instructions on back

Client Name <u>Arcebor Mital Burns Harbor</u>	Project <u>Dock Wall Inspection</u>	Turnaround Time <input checked="" type="checkbox"/> Routine (5 to 7 business days) <input type="checkbox"/> RUSH* (notify lab) _____ (needed by)	Report Type <input checked="" type="checkbox"/> Results Only <input type="checkbox"/> Level III <input type="checkbox"/> Level IV <input type="checkbox"/> EDD <input type="checkbox"/> Level II <input type="checkbox"/> Level III CLP-like <input type="checkbox"/> Level IV CLP-like
Address	Location		
City, State, Zip	PO #		
Contact	Compliance Monitoring? <input type="checkbox"/> Yes <input type="checkbox"/> No		
Telephone #	(1) Agency/Program		

Sampled by (PRINT) David Ecken Sampler Signature David Ecken Sampler Phone # 219 808 9099  
Send Report via ☐ Mail ☐ Telephone ☐ Fax (fax #) \_\_\_\_\_ ☒ e-mail (address) \_\_\_\_\_

\* Matrix Types: Soil/Solid (S), Sludge, Oil, Wipe, Drinking Water (DW), Groundwater (GW), Surface Water (SW), Waste Water (WW), Other (specify)  
\*\* Preservative Types: (1) HNO<sub>3</sub>, (2) H<sub>2</sub>SO<sub>4</sub>, (3) HCl, (4) NaOH, (5) Zinc Acetate, (6) Methanol, (7) Sodium Bisulfate, (8) Sodium Thiosulfate, (9) Hexane, (10) Unpreserved

Client Sample ID	Matrix*	Grab	Composite	Filtered	Date Collected	Time Collected	No. of Containers	Requested Analyses → Preservative Types ** ↓												For Lab Use Only
16-11	GW	X			8/30/16	12:06P	1	H2SO4												16H2149
16-11 D						12:08P	1													- 11
16-12						12:22P	1													- 12
16-12 D						12:24P	1													- 13
16-13						12:30P	1													- 14
16-13 D						12:32P	1													- 15
16-14						12:42P	1													- 16
16-14 D						12:50P	1													- 17
16-15						1:05P	1													- 18
16-15 D						1:12P	1													- 19
																				- 20

Possible Hazard Identification ☐ Hazardous ☐ Non-Hazardous ☐ Radioactive Sample Disposition ☐ Dispose as appropriate ☐ Return ☐ Archive

Comments	To be completed by Microbac				
	Temperature Upon Receipt (°C) <u>10-25-05</u>	Relinquished By (signature) <u>[Signature]</u>	Date/Time <u>8/30/16 2:15P</u>	Received By (signature) <u>[Signature]</u>	Date/Time <u>8/30/16 2:15P</u>
	Samples Received on Ice?	Relinquished By (signature) <u>[Signature]</u>	Date/Time <u>8/31/16 8:00am</u>	Received By (signature) <u>[Signature]</u>	Date/Time <u>8/31/16 0800</u>
	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	Custody Seals Intact?	Relinquished By (signature) <u>[Signature]</u>	Date/Time <u>8/31/16 0940</u>	Received By (signature) <u>[Signature]</u>
Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>					



September 14, 2016

Arcelor Mittal USA, Inc.  
250 W US Highway 12  
Burns Harbor, IN 46304-9745

Work Order No.: 16I0272

Re: Dock Wall Inspection

Dear Teri Kirk:

Microbac Laboratories, Inc. - Chicagoland Division received 22 sample(s) on 9/7/2016 9:33:00AM for the analyses presented in the following report as Work Order 16I0272.

The enclosed results were obtained from and are applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report have been reviewed and meet the applicable project specific and certification specific requirements, unless otherwise noted. A qualifications page is included in this report and lists the programs under which Microbac maintains certification.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories.

We appreciate the opportunity to service your analytical needs. If you have any questions, please contact your project manager. For any feedback, please contact Robert Crookston, Managing Director, at [robert.crookston@microbac.com](mailto:robert.crookston@microbac.com).

Sincerely,  
Microbac Laboratories, Inc.

Carey Gadzala  
Project Manager

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

**WORK ORDER SAMPLE SUMMARY****Date:** Wednesday, September 14, 2016**Client:** Arcelor Mittal USA, Inc.**Project:** Dock Wall Inspection**Lab Order:** 16I0272

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
16I0272-01	16-16		09/06/2016 09:59	9/7/2016 9:33:00AM
16I0272-02	16-16D		09/06/2016 09:59	9/7/2016 9:33:00AM
16I0272-03	16-17		09/06/2016 10:33	9/7/2016 9:33:00AM
16I0272-04	16-17D		09/06/2016 10:33	9/7/2016 9:33:00AM
16I0272-05	16-18		09/06/2016 10:50	9/7/2016 9:33:00AM
16I0272-06	16-18D		09/06/2016 10:50	9/7/2016 9:33:00AM
16I0272-07	16-19		09/06/2016 11:08	9/7/2016 9:33:00AM
16I0272-08	16-19D		09/06/2016 11:08	9/7/2016 9:33:00AM
16I0272-09	16-20		09/06/2016 11:20	9/7/2016 9:33:00AM
16I0272-10	16-20D		09/06/2016 11:20	9/7/2016 9:33:00AM
16I0272-11	16-21		09/06/2016 11:37	9/7/2016 9:33:00AM
16I0272-12	16-21D		09/06/2016 11:37	9/7/2016 9:33:00AM
16I0272-13	16-22		09/06/2016 12:02	9/7/2016 9:33:00AM
16I0272-14	16-22D		09/06/2016 12:02	9/7/2016 9:33:00AM
16I0272-15	16-23		09/06/2016 13:04	9/7/2016 9:33:00AM
16I0272-16	16-23D		09/06/2016 13:04	9/7/2016 9:33:00AM
16I0272-17	16-24		09/06/2016 13:20	9/7/2016 9:33:00AM
16I0272-18	16-24D		09/06/2016 13:20	9/7/2016 9:33:00AM
16I0272-19	16-25		09/06/2016 13:54	9/7/2016 9:33:00AM
16I0272-20	16-25D		09/06/2016 13:54	9/7/2016 9:33:00AM
16I0272-21	16-26		09/06/2016 14:16	9/7/2016 9:33:00AM
16I0272-22	16-26D		09/06/2016 14:16	9/7/2016 9:33:00AM

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | [www.microbac.com](http://www.microbac.com)

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-01
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 9:59
<b>Client Sample ID:</b>	16-16	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/10/2016 07:10				
Nitrogen, Ammonia (As N)	ei	A	1.4	0.054	0.10		mg/L	1	09/13/2016 14:51



## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-02
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 9:59
<b>Client Sample ID:</b>	16-16D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/10/2016 07:10				
Nitrogen, Ammonia (As N)	ei	A	1.7	0.054	0.10		mg/L	1	09/13/2016 14:57



## Analytical Results

Date: Wednesday, September 14, 2016

**Client:** Arcelor Mittal USA, Inc.  
**Client Project:** Dock Wall Inspection  
**Client Sample ID:** 16-17  
**Sample Description:**  
**Matrix:** Aqueous

**Work Order/ID:** 16I0272-03  
**Sampled:** 09/06/2016 10:33  
**Received:** 09/07/2016 9:33

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/10/2016 07:10				
Nitrogen, Ammonia (As N)	ei	A	1.2	0.054	0.10		mg/L	1	09/13/2016 14:59

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-04
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 10:33
<b>Client Sample ID:</b>	16-17D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/10/2016 07:10				
Nitrogen, Ammonia (As N)	ei	A	1.2	0.054	0.10		mg/L	1	09/13/2016 15:01

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-05
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 10:50
<b>Client Sample ID:</b>	16-18	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.24	0.054	0.10		mg/L	1	09/12/2016 15:00

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-06
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 10:50
<b>Client Sample ID:</b>	16-18D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.25	0.054	0.10		mg/L	1	09/12/2016 15:02

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-07
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 11:08
<b>Client Sample ID:</b>	16-19	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.58	0.054	0.10		mg/L	1	09/13/2016 13:41



## Analytical Results

Date: Wednesday, September 14, 2016

Client: Arcelor Mittal USA, Inc.

Client Project: Dock Wall Inspection

Client Sample ID: 16-19D

Sample Description:

Matrix: Aqueous

Work Order/ID: 16I0272-08

Sampled: 09/06/2016 11:08

Received: 09/07/2016 9:33

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.60	0.054	0.10		mg/L	1	09/13/2016 13:43

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-09
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 11:20
<b>Client Sample ID:</b>	16-20	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.45	0.054	0.10		mg/L	1	09/13/2016 13:45



## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-10
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 11:20
<b>Client Sample ID:</b>	16-20D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.41	0.054	0.10		mg/L	1	09/13/2016 13:47

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-11
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 11:37
<b>Client Sample ID:</b>	16-21	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.53	0.054	0.10		mg/L	1	09/13/2016 13:49

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-12
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 11:37
<b>Client Sample ID:</b>	16-21D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.42	0.054	0.10		mg/L	1	09/13/2016 13:51

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-13
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 12:02
<b>Client Sample ID:</b>	16-22	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.33	0.054	0.10		mg/L	1	09/13/2016 13:53

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-14
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 12:02
<b>Client Sample ID:</b>	16-22D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	0.31	0.054	0.10		mg/L	1	09/13/2016 13:55

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-15
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:04
<b>Client Sample ID:</b>	16-23	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	2.7	0.054	0.10		mg/L	1	09/13/2016 13:57

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-16
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:04
<b>Client Sample ID:</b>	16-23D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	2.6	0.054	0.10		mg/L	1	09/13/2016 14:06

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-17
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:20
<b>Client Sample ID:</b>	16-24	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 08:35				
Nitrogen, Ammonia (As N)	ei	A	1.9	0.054	0.10		mg/L	1	09/13/2016 14:08



## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-18
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:20
<b>Client Sample ID:</b>	16-24D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/12/2016 11:25				
Nitrogen, Ammonia (As N)	ei	A	1.5	0.054	0.10		mg/L	1	09/13/2016 14:10

## Analytical Results

Date: Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-19
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:54
<b>Client Sample ID:</b>	16-25	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/13/2016 08:00				
Nitrogen, Ammonia (As N)	ei	A	4.7	0.054	0.10		mg/L	1	09/13/2016 12:59

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-20
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 13:54
<b>Client Sample ID:</b>	16-25D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/13/2016 08:00				
Nitrogen, Ammonia (As N)	ei	A	5.0	0.054	0.10		mg/L	1	09/13/2016 13:01

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-21
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 14:16
<b>Client Sample ID:</b>	16-26	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/13/2016 08:00				
Nitrogen, Ammonia (As N)	ei	A	4.3	0.054	0.10		mg/L	1	09/13/2016 13:03

## Analytical Results

**Date:** Wednesday, September 14, 2016

<b>Client:</b>	Arcelor Mittal USA, Inc.	<b>Work Order/ID:</b>	16I0272-22
<b>Client Project:</b>	Dock Wall Inspection	<b>Sampled:</b>	09/06/2016 14:16
<b>Client Sample ID:</b>	16-26D	<b>Received:</b>	09/07/2016 9:33
<b>Sample Description:</b>			
<b>Matrix:</b>	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
Method: EPA 350.1 Rev 2.0					Analyst: GRIEFF				
Nitrogen, Ammonia as N					Prep Date/Time: 09/13/2016 08:00				
Nitrogen, Ammonia (As N)	ei	A	4.8	0.054	0.10		mg/L	1	09/13/2016 13:05

**FLAGS, FOOTNOTES AND ABBREVIATIONS (as needed)**

B = Detected in the associated method Blank at a concentration above the routine RL  
 b- = Detected in the associated method Blank at a concentration greater than 2.2 times the MDL  
 b\* = Detected in the associated method Blank at a concentration greater than half the RL  
 CFU = Colony forming units  
 D = Dilution performed on sample  
 DF = Dilution Factor  
 g = Gram  
 E = Value above quantitation range  
 H = Analyte was prepared and/or analyzed outside of the analytical method holding time  
 I = Matrix Interference  
 J = Analyte concentration detected between RL and MDL (Metals / Organics)  
 LOD = Limit of Detection  
 LOQ = Limit of Quantitation  
 m3 = Meters cubed  
 MDL = Method Detection Limit  
 mg/Kg = Milligrams per Kilogram (ppm)  
 mg/L = Milligrams per Liter (ppm)  
 NA = Not Analyzed  
 ND = Not Detected at the Reporting Limit (or the Method Detection Limit, if used)  
 NR = Not Recovered  
 R = RPD outside accepted recovery limits  
 RL = Reporting Limit  
 S = Spike recovery outside recovery limits  
 Surr = Surrogate  
 U = Undetected  
 > = Greater than  
 < = Less than  
 % = Percent  
 \* = Result exceeds project specific limits

**ANALYTE TYPES: (AT)**

A,B = Target Analyte  
 I = Internal Standard  
 M = Summation Analyte  
 S = Surrogate  
 T = Tentatively Identified Compound (TIC, concentration estimated)

**QC SAMPLE IDENTIFICATIONS**

BLK = Method Blank	ICSA = Interference Check Standard "A"
DUP = Method Duplicate	ICSAB = Interference Check Standard "AB"
BS = Method Blank Spike	BSD = Method Blank Spike Duplicate
MS = Matrix Spike	MSD = Matrix Spike Duplicate
ICB = Initial Calibration Blank	ICV = Initial Calibration Verification
CCB = Continuing Calibration Blank	CCV = Continuing Calibration Verification
CRL = Client Required Reporting Limit	OPR = Ongoing Precision and Recovery Standard
PDS = Post Digestion Spike	SD = Serial Dilution
QCS = Quality Control Standard	

**CERTIFICATIONS (Certs)**

*Below is a list of certifications maintained by the Microbac Merrillville Laboratory. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. Complete lists of individual analytes pursuant to each certification below are available upon request.*

- <sup>d</sup> Illinois EPA drinking water, wastewater and solid waste analysis (#200064)
- <sup>i</sup> Kansas Dept Health & Env. NELAP (#E-10397)



## COOLER INSPECTION

Client Name: Arcelor Mittal USA, Inc.

Work Order Number: 1610272

Checklist completed by: 9/7/2016 10:38:00AM | Nicole Rainwater

Date: Wednesday, September 14, 2016

Date/Time Received: 09/07/2016 09:33

Received by: Nicole Rainwater

Reviewed by: 9/7/2016 | CAG

Carrier Name: Microbac

Cooler ID: Default Cooler

Container/Temp Blank Temperature: 2.2° C

After-Hour Arrival?	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Shipping container/cooler in good condition?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input type="checkbox"/>
Custody seals intact on shipping container/cooler?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
Custody seals intact on sample containers?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
COC present?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient client identification?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included sufficient sample collector information?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included a sample description?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC agrees with sample labels?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate matrix?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included date of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC included time of collection?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC identified the appropriate number of containers?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples in proper container/bottle?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sample containers intact?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Sufficient sample volume for indicated test?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
All samples received within holding time?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
If the samples are preserved, are the preservatives identified?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	

If No, adjusted by? \_\_\_\_\_

COC included the requested analyses?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
COC signed when relinquished and received?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples received on ice?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Samples properly preserved?	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Voa vials for aqueous samples have zero headspace?	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	No VOA vials submitted <input checked="" type="checkbox"/>

Cooler Comments: \_\_\_\_\_

ANY "NO" EVALUATION (excluding After-Hour Receipt) REQUIRES CLIENT NOTIFICATION.

Microbac Laboratories, Inc.

250 West 84<sup>th</sup> Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

Sample ID	Client Sample ID	Comments
16I0272-01	16-16	
16I0272-02	16-16D	
16I0272-03	16-17	
16I0272-04	16-17D	
16I0272-05	16-18	
16I0272-06	16-18D	
16I0272-07	16-19	
16I0272-08	16-19D	
16I0272-09	16-20	
16I0272-10	16-20D	
16I0272-11	16-21	
16I0272-12	16-21D	
16I0272-13	16-22	
16I0272-14	16-22D	
16I0272-15	16-23	
16I0272-16	16-23D	
16I0272-17	16-24	
16I0272-18	16-24D	
16I0272-19	16-25	
16I0272-20	16-25D	
16I0272-21	16-26	
16I0272-22	16-26D	



160272 Carey Gadzala  
Arceformital - Burns Harbor, IN  
Dock Wall Inspection  
08/07/2016

**MICROBAC** Samples Submitted to: ☐ 250 West 84th Drive Merrillville, IN 46410 Tel: 219-769-8378 Fax: 219-769-1664  
☐ 5713 West 85th Street Indianapolis, IN 46278 Tel: 317-872-1375 Fax: 317-872-1379

**Chain of Custody Record**  
Number **136082**  
Instructions on back

ne Am B4 Project Dockwall Sample Turnaround Time Results Only Report Type Level II  
Location Am B4 ☒ Routine (5 to 7 business days) ☐ Level III ☐ Level III CLP-like  
Zip 46410 ☐ RUSH\* (notify lab) ☐ Level IV ☐ Level IV CLP-like  
Compliance Monitoring? ☐ Yes ☐ No (needed by)  
# 1 (1) Agency/Program Am B4 ☐ EDD  
y (PRINT) Patricia Kastrup Sampler Signature [Signature] Sampler Phone # 219 808 9099  
rt via ☐ Mail ☐ Telephone ☐ Fax (fax #) ☒ e-mail (address)

\* Matrix Types: Soil/Solid (S), Sludge, Oil, Wipe, Drinking Water (DW), Groundwater (GW), Surface Water (SW), Waste Water (WW), Other (specify)  
\* Preservative Types: (1) HNO3, (2) H2SO4, (3) HCl, (4) NaOH, (5) Zinc Acetate, (6) Methanol, (7) Sodium Bisulfate, (8) Sodium Thiosulfate, (9) Hexane, (U) Unpreserved

Client Sample ID	Matrix*	Grab	Composite	Filtered	Date Collected	Time Collected	No. of Containers	Requested Analyses → Preservative Types **	For Lab Use Only									
16-16	GW	✓			9/6	0959	1	H2SO4	✓									1610272
16-16D		✓				0959	1		✓									161026
16-17		✓				1033	1		✓									01
16-17D		✓				1033	1		✓									02
16-18		✓				1050	1		✓									03
16-18D		✓				1050	1		✓									04
16-19		✓				1108	1		✓									05
16-19D		✓				1108	1		✓									06
16-20		✓				1120	1		✓									07
16-20D	GW	✓			9/6	1120	1	H2SO4	✓									08

Possible Hazard Identification ☐ Hazardous ☐ Non-Hazardous ☐ Radioactive Sample Disposition ☐ Dispose as appropriate ☐ Return ☐ Archive

Comments

To be completed by Microbac		Relinquished By (signature)		Received By (signature)	
Temperature Upon Receipt (°C)	2.7-0.5=2.2	[Signature]	9/6/16, 1432	[Signature]	9/6/16 1432
Samples Received on Ice?	Yes No N/A	[Signature]	9/6/16, 1500	[Signature]	9/7/16 7:35
Custody Seals Intact?	Yes No N/A	[Signature]	9/7/16 9:33	[Signature]	9/7/16



Samples Submitted to: ☐ 250 West 84th Drive  
Merrillville, IN 46410  
Tel: 219-769-8378  
Fax: 219-769-1664

☐ 5713 West 85th Street  
Indianapolis, IN 46278  
Tel: 317-872-1375  
Fax: 317-872-1379

# Chain of Custody Record

Number **136084**

Instructions on back

Client Name <b>AMBH</b>	Project <b>Dock Wall Samples</b>	Turnaround Time	Report Type
Address	Location	<input checked="" type="checkbox"/> Routine (5 to 7 business days)	<input checked="" type="checkbox"/> Results Only <input type="checkbox"/> Level II
City, State, Zip	PO #	<input type="checkbox"/> RUSH* (notify lab)	<input type="checkbox"/> Level III <input type="checkbox"/> Level III CLP-like
Contact	Compliance Monitoring? <input type="checkbox"/> Yes <input type="checkbox"/> No	(needed by)	<input type="checkbox"/> Level IV <input type="checkbox"/> Level IV CLP-like
Telephone #	(1) Agency/Program		<input type="checkbox"/> EDD
Sampled by (PRINT) <b>Patricia Kastro</b>	Sampler Signature <b>Patricia Kastro</b>	Sampler Phone # <b>219 808 9099</b>	
Send Report via <input type="checkbox"/> Mail <input type="checkbox"/> Telephone <input type="checkbox"/> Fax (fax #)	<input checked="" type="checkbox"/> e-mail (address)		

\* Matrix Types: Soil/Solid (S), Sludge, Oil, Wipe, Drinking Water (DW), Groundwater (GW), Surface Water (SW), Waste Water (WW), Other (specify)

\*\* Preservative Types: (1) HNO<sub>3</sub>, (2) H<sub>2</sub>SO<sub>4</sub>, (3) HCl, (4) NaOH, (5) Zinc Acetate, (6) Methanol, (7) Sodium Bisulfate, (8) Sodium Thiosulfate, (9) Hexane, (U) Unpreserved

Client Sample ID	Matrix*	Grab	Composite	Filtered	Date Collected	Time Collected	No. of Containers	Requested Analyses	NH <sub>3</sub>										For Lab Use Only
								Preservative Types **											
16-21	GW	✓			9/6	1137		H <sub>2</sub> SO <sub>4</sub>	✓										1610272
16-21 D	↓	✓			↓	1137		↓	✓										-11
16-22	↓	✓			↓	1202		↓	✓										-12
16-22 D	↓	✓			↓	1202		↓	✓										-13
16-23	↓	✓			↓	1304		↓	✓										-14
16-23 D	↓	✓			↓	1304		↓	✓										-15
16-24	↓	✓			↓	1320		↓	✓										-16
16-24 D	↓	✓			↓	1320		↓	✓										-17
16-25	↓	✓			↓	1354		↓	✓										-18
16-25 D	GW	✓			9/6	1354		H <sub>2</sub> SO <sub>4</sub>	✓										-19
																			-20

Possible Hazard Identification ☐ Hazardous ☐ Non-Hazardous ☐ Radioactive


Sample Disposition ☐ Dispose as appropriate ☐ Return ☐ Archive

Comments	To be completed by Microbac			
	Temperature Upon Receipt (°C)	Relinquished By (signature)	Date/Time	Received By (signature)
	27.05-22	<i>[Signature]</i>	9/6/16, 1432 est	<i>[Signature]</i>
	Samples Received on Ice?	Relinquished By (signature)	Date/Time	Received By (signature)
	Yes No N/A	<i>[Signature]</i>	9/6/16, 1500	<i>[Signature]</i>
Custody Seals Intact?	Relinquished By (signature)	Date/Time	Received By (signature)	
Yes No N/A	<i>[Signature]</i>	9/7/16 9:33	<i>[Signature]</i>	



ArcelorMittal Burns Harbor, LLC  
Annual Dock Wall Observation  
Consent Decree – Case No. 2:96-CV-96-RL-1

Attachment 3 – Discharge Location Photographs







Discharge 16-1, August 23, 2016



Discharge 16-2, August 23, 2016





Discharge 16-3, August 23, 2015



Discharge 16-4, August 23, 2016





Discharge 16-6, August 30, 2016



Discharge 16-7, August 30, 2016





Discharge 16-8, August 30, 2016



Discharge 16-9, August 30, 2016





Discharge 16-10, August 30, 2016




Discharges 16-11, 16-12 and 16-13, August 30, 2016





Discharge 16-14, August 30, 2016




Discharge 16-15, August 30, 2016





Discharge 16-16, September 6, 2016



Discharge 16-17, September 6, 2016






Discharge 16-18, September 6, 2016



Discharge 16-19 and 16-20, September 6, 2016





Discharge 16-21, September 6, 2016



Discharge 16-22 September 6, 2016 (labeling above sampling location on ore dock)





Discharge 16-23, September 6, 2016



Discharge 16-24, September 6, 2016





Discharge 16-25, September 6, 2016



Discharge 16-26, September 6, 2016