

Comanche Station Bottom Ash Treatment System Discussion March 18-19, 2021








Groundwater Monitoring Issues/Questions

- Updated table and/or plots with all data collected to date
 - Export from database available
 - More user-friendly table in progress
- Has a statistical method been identified for SSIs?
 - Yes Upper Prediction Limit (UPL)
- BTVs established and/or SSI evaluation completed?
 - Bottom ash pond
 - W-2A background well BTVs calculated
 - SSI for boron in two shallow adjacent colluvial wells
 - No boron SSIs in downgradient/property boundary wells
 - pH SSIs in multiple wells; parameter not unique to bottom ash
 - Landfill
 - MW-3 and MW-5 background data pooled, BTVs calculated
 - No SSIs in downgradient wells
 - 2 SSIs in cross-gradient wells completed in different geologic unit
- Assessment monitoring 1st early April, 2nd mid-May



Upper Prediction Limits for Detection Monitoring for each Appendix III Constituent in Comanche Pond


W-2A as background Well

Туре	Constitue nt	Unit		January 12-14, 2021 DM Sample Event										
			n	BTV ⁴	W-3	W-5	W-5B	W-6	W-4	W-1	W-7	W-9		
Appendix I	Boron	mg/l	8	4.00	0.57	3.8	1.	7.5	2.4	4.1	2.2	1.9		
Appendix I	I Calcium	mg/l	81	657	300	200	480	210	420	420	440	380		
Appendix I	Chloride (a	mg/l	81	897	23	560	110	180	480	760	770	360		
Appendix I	I Fluoride	mg/l	81	578	0.68	<0.5	<0.5	1.7	4.4	3.1	<0.5	<0.5		
Appendix I	II pH (field) (su	81	6.22	7.74	7.26	7.07	7.36	7.68	7.37	6.61	6.87		
Appendix I	I pH (field) (su	81	6.73	7.74	7.26	7.07	7.36	7.68	7.37	6.61	6.87		
Appendix I	I Sulfate (as	mg/l	81	86,791	1300	13000	3600	4800	29000	29000	48000	11000		
Appendix I	I Total Disso	mg/l	81	202,620	2000	16000	5300	6200	NA	42000	69000	16000		

W-11	W-12
1.1	1.3
370	160
350	870
2.7	<0.5
6.89	6.83
6.89	6.83
14000	16000
20000	23000

Upper Prediction Limits for Detection Monitoring for each Appendix III Constituent in Comanche Pond (based on background wells MW-3 and MW-5)																	
	Unit		No. Below MDL	% Below MDL	ProUCL's Best Fit ²	HDK's Recommendations				January 12-14, 2021 DM Sample Event							
Constitue nt		n				Per-Test FPR (a) ¹	No. of Verificatio n Samples	BTV ⁴	Notes	MW-18	MW-28	MW-3	MW-48	MW-S	MW-6	W-11	W-12
Boron	mg/l	18	0	0%	ral; Normal	0.0016	0	6.65		1.5	2.1	2.2	0.49	1.3	2.1	1.1	1.3
Calcium	mg/l	18	0	0%	parametric	0.0001	2	470		120	150	160	510	210	430	370	160
Chloride (a	mg/l	18	0	0%	parametric	0.0001	2	1,800		410	580	360	200	1600	260	350	870
Fluoride	mg/l	18	5	28%	na; Normal	0.0016	0	444		1.8	1.3	<0.5	0.17	<0.5	0.25	2.7	<0.5
pH (field) [su	18	0	0%	al; Normal	0.0016	0	6.32	(*)	6.77	6.81	6.94	6.82	6.9	7.42	6.89	6.83
pH (field) (su	18	0	0%	nal; Normal	0.0016	0	7.35	(*)	6.77	6.81	6.94	6.82	6.9	7.42	6.89	6.83
Sulfate (as	mg/l	18	0	0%	parametric	0.0001	2	42,000		19000	37000	36000	3000	18000	4200	14000	16000
Total Disso	mg/l	18	0	0%	Lognormal	0.0016	0	200,778		25000	44000	51000	5900	24000	6100	20000	23000

Plan/schedule to locate and sample downgradient domestic wells



Plans and timing regarding locating and sampling downgradient domestic wells

- Phased step out approach
 - CCR Rule and technically appropriate
- wells installed in 2020
 - 6 south and east of pond
 - 2 dry, 4 sampled
 - Limited impact in shallow colluvial groundwater adjacent to pond
 - Concentrations less than background in downgradient wells at property line
- Nature and extent is bounded
- Cross-sections from the CCR units to the St. Charles River (N-S)?

Impacts of continued use of pond?

- Anticipate no additional impacts to groundwater
- Pond is 3 acres and has been in service for over 40 years
- Impacts localized in two adjacent shallow wells in colluvium
- No boron SSIs further downgradient of the pond and at property line
- Additional weeks of operation would not exacerbate
- How/when would Xcel model this?
 - Results don't suggest it is needed
 - Recommend we continue to follow the steps of the CCR Rule
 - Mathematical hydrogeologic model would take considerable time

Tracking bottom ash quantities

- Bottom ash total ~ 30,000 tons/year
- Bunker
 - Ash slurry water contains <1% ash solids
 - Captures 75+% of total ash
 - Material is ~ DOT Class 6 road base
 - ~ 60-65% beneficially used, cement
 - 5 days/week; ~ 4 trucks/day
 - ~ 24,000 tons/year, good balance w/% solids in
- South ~ 1/3 pond area
 - Monthly
- North ~ 2/3 pond area
 - Annually
 - Mostly silt and vegetation
- Pond cleanout ~ 7,000 tons/year



Comanche Station Units 1 & 2 Bottom Ash Concrete Bunker (front and side views)




Groundwater Evaluation Summary

- First detection monitoring January 2021
- BTVs calculated as Upper Prediction Limit (UPL)
 - SSIs for boron in two shallow colluvial wells adjacent to pond
 - Impacts at pond localized; boron in downgradient wells less than BTV
 - No SSIs in down-gradient wells at landfill
- Nature and extent limited
- No additional impacts from pond anticipated
- Results support no potential impact to off-site wells

Bottom Ash Treatment System Update


Original System Design Concept

- September 25, 2020 EPA response
 - Parts A and B determined not viable
 - Very early design phase
 - Evaluating pre-packaged treatment systems
 - Initiated treatability study for system design and treatment specifications
 - Anticipated continued use of existing bunker
 - Bunker effluent to be routed to new treatment system
 - Bunker for flow equalization and bulk solids removal
 - Flocculant addition and clarifier tank to settle finer solids
 - Confirmed that the major system components were available
 - Schedule was ambitious, believed we could meet it based on info at that time
 - NPDES permit modification appeared to be longest lead time item



System Design Progression

- 4th quarter 2020 design-build approach
 - Bid pre-packaged treatment system
 - Simple, reliable, performance guarantees, flocculant testing
 - Requires new significantly larger bunker for flow equalization
 - Larger footprint than original system concept; new site higher elevation
 - January 2021 temporary system needed to meet schedule
 - temp system not as 'elegant' as the pre-packaged system; numerous independent components connected to make a 'system'; non-automated
 - Larger footprint than pre-packaged system
 - January 31st ceased non-CCR flows 133 gpm continuous, ~ 200 gpm episodic
 - 2,000 gpm = total system flow rate; diverted non-CCR flows ~ 7%
 - Balance of plant
 - New larger bunker (~5 x existing bunker size)
 - Multiple borings under rail and water supply/return lines, electrical duct bank and local control center, chemical feed system, makeup water tank, thickener, dewatering tanks, high pressure feed pump in plant



Common System Components

- Bottom ash sluice water piping (~800') to treatment location
- Treated effluent discharge piping (~1,000') to the polishing pond
- Water supply piping (~1,000') to the chemical feed building
 - 3 horizontal borings under rail crossing
- High pressure pump added in plant to address increased elevation
- Chemical feed building to mix and distribute coagulant and flocculent
- Zone 4 of bunker to transfer flow between treatment steps
- Electrical duct bank (~400 feet), to new centralized power distribution center to supply 1250 kVA

Temporary and pre-packaged systems status


Temporary

- Major equipment arriving this week
 - Total Clean tank, conveyors, 16 clarifiers, 8 clear wells, 2 bag filter trailers
 - Underflow thickener, dewatering tanks, chemical feed skids, buildings, piping
 - Weather delays deliveries from Denver, site access conditions
- Construction/installation
 - Excavations complete, bldg. foundations done, rebar/concrete in progress, zone 4 bunker floor pour next week, tank foundation ready for concrete,
 - Boring under rail complete; HDPE pipe welding on site in progress; install begins next week
 - High pressure pump in plant to be installed

Prepackaged


- Major equipment on site mid-May
 - Operation date contingent on completion of bunker zones 1-3
 - 3 weeks to install, test, commission
 - Any float in schedule has been consumed


















Schedule for conducting tie-ins

- Temp System bunker zone 4 temp system mid-late April
- Long lead items arrive mid-late May
 - Manufacturing backlog in all market sectors even for common items
 - Specialty valves, actuators, makeup water tank, control panel, pumps
 - Alternative materials, parts, sources to expedite schedule
- Temp System operational mid-June
- Bunker zones 1-3 pre-packaged system
 - Bunker all zones = 175' x 45' x 10'
 - Rebar, sequential concrete cure times, floor, walls
 - Heated enclosure, 3-day cure testing
 - Sealing, leak testing, backfill
- Bunker 1-3 concrete mid June
- Bunker 1-3 electrical early July
- Bunker 1-3 piping late July

Why Have Costs Increased?

- Pre-packaged system
 - September 2020
 - \$885,000 \$1.2 million annual operating cost
 - Pre-design rough estimate
 - January 2021
 - \$2.1 million annual operating cost (\$4.2 for 24 months)
 - more detailed design, contractor bid
 - operating cost includes monthly system rental fees
 - increased labor to operate 24 x 7 x 365
 - 2-person crew on night shift, safety
- Temporary system for 90 days operation ~ \$5 million
- Site prep (foundations, piping, bunker, etc.) costs = ~ \$3 million

Possible Administrative Order on Consent

Does any entity other than Public Service Company of Colorado (PSCo)

- own Comanche Station units 1 and 2? No
- operate Comanche Station units 1 and 2? No
- own the bottom ash impoundment? No

Does any entity other than Public Service Company of Colorado operate the bottom ash impoundment?

- PSCo is the sole operator of bottom ash discharges from the plant to the pond
- PSCo is also the sole entity in control of when bottom ash discharges to the pond will cease
- A PSCo contractor maintains the pond by regularly removing bottom ash from the bunker/pond system

Discussion